

C O R E

HTML5 CANVAS

Graphics, Animation,
and Game Development



DAVID GEARY

Core HTML5 Canvas



This page intentionally left blank

Core HTML5 Canvas

Graphics, Animation, and Game Development

David Geary



Upper Saddle River, NJ • Boston • Indianapolis • San Francisco
New York • Toronto • Montreal • London • Munich • Paris • Madrid
Capetown • Sydney • Tokyo • Singapore • Mexico City

Many of the designations used by manufacturers and sellers to distinguish their products are claimed as trademarks. Where those designations appear in this book, and the publisher was aware of a trademark claim, the designations have been printed with initial capital letters or in all capitals.

The author and publisher have taken care in the preparation of this book, but make no expressed or implied warranty of any kind and assume no responsibility for errors or omissions. No liability is assumed for incidental or consequential damages in connection with or arising out of the use of the information or programs contained herein.

The publisher offers excellent discounts on this book when ordered in quantity for bulk purchases or special sales, which may include electronic versions and/or custom covers and content particular to your business, training goals, marketing focus, and branding interests. For more information, please contact:

U.S. Corporate and Government Sales
(800) 382-3419
corpsales@pearsontechgroup.com

For sales outside the United States, please contact:

International Sales
international@pearson.com

Visit us on the Web: informit.com/ph

Library of Congress Cataloging-in-Publication Data

Geary, David M.

Core HTML5 canvas : graphics, animation, and game development / David Geary.

p. cm.

Includes index.

ISBN 978-0-13-276161-1 (pbk. : alk. paper)

1. HTML (Document markup language) 2. Computer games—Programming. 3. Computer animation. I. Title.

QA76.76.H94C66 2012

006.6'6—dc23

2012006871

Copyright © 2012 David Geary

All rights reserved. Printed in the United States of America. This publication is protected by copyright, and permission must be obtained from the publisher prior to any prohibited reproduction, storage in a retrieval system, or transmission in any form or by any means, electronic, mechanical, photocopying, recording, or likewise. To obtain permission to use material from this work, please submit a written request to Pearson Education, Inc., Permissions Department, One Lake Street, Upper Saddle River, New Jersey 07458, or you may fax your request to (201) 236-3290.

ISBN-13: 978-0-13-276161-1

ISBN-10: 0-13-276161-0

Text printed in the United States on recycled paper at RR Donnelley in Crawfordsville, Indiana.
First printing, May 2012

Contents



<i>Preface</i>	xv
<i>Acknowledgments</i>	xxiii
<i>About the Author</i>	xxv
Chapter 1: Essentials	1
1.1 The canvas Element	1
1.1.1 Canvas Element Size vs. Drawing Surface Size	5
1.1.2 The Canvas API	7
1.2 Canvas Contexts	8
1.2.1 The 2d Context	9
1.2.1.1 The WebGL 3d Context	11
1.2.2 Saving and Restoring Canvas State	11
1.3 Canonical Examples in This Book	12
1.4 Getting Started	14
1.4.1 Specifications	14
1.4.2 Browsers	15
1.4.3 Consoles and Debuggers	16
1.4.4 Performance	18
1.4.4.1 Profiles and Timelines	19
1.4.4.2 jsPerf	20
1.5 Fundamental Drawing Operations	22
1.6 Event Handling	26
1.6.1 Mouse Events	26
1.6.1.1 Translating Mouse Coordinates to Canvas Coordinates	26
1.6.2 Keyboard Events	31
1.6.3 Touch Events	33
1.7 Saving and Restoring the Drawing Surface	33
1.8 Using HTML Elements in a Canvas	36
1.8.1 Invisible HTML Elements	41

1.9	Printing a Canvas	46
1.10	Offscreen Canvases	51
1.11	A Brief Math Primer	53
1.11.1	Solving Algebraic Equations	54
1.11.2	Trigonometry	54
1.11.2.1	Angles: Degrees and Radians	54
1.11.2.2	Sine, Cosine, and Tangent	55
1.11.3	Vectors	56
1.11.3.1	Vector Magnitude	57
1.11.3.2	Unit Vectors	58
1.11.3.3	Adding and Subtracting Vectors	59
1.11.3.4	The Dot Product of Two Vectors	60
1.11.4	Deriving Equations from Units of Measure	62
1.12	Conclusion	64
Chapter 2:	Drawing	65
2.1	The Coordinate System	67
2.2	The Drawing Model	68
2.3	Drawing Rectangles	70
2.4	Colors and Transparency	72
2.5	Gradients and Patterns	76
2.5.1	Gradients	76
2.5.1.1	Linear Gradients	76
2.5.1.2	Radial Gradients	78
2.5.2	Patterns	79
2.6	Shadows	83
2.6.1	Inset Shadows	85
2.7	Paths, Stroking, and Filling	88
2.7.1	Paths and Subpaths	93
2.7.1.1	The Nonzero Winding Rule for Filling Paths	94
2.7.2	Cutouts	95
2.7.2.1	Cutout Shapes	98
2.8	Lines	103
2.8.1	Lines and Pixel Boundaries	104
2.8.2	Drawing a Grid	105

2.8.3	Drawing Axes	107
2.8.4	Rubberband Lines	110
2.8.5	Drawing Dashed Lines	117
2.8.6	Drawing Dashed Lines by Extending CanvasRenderingContext2D	118
2.8.7	Line Caps and Joins	121
2.9	Arcs and Circles	124
2.9.1	The arc() Method	124
2.9.2	Rubberband Circles	126
2.9.3	The arcTo() Method	127
2.9.4	Dials and Gauges	130
2.10	Bézier Curves	137
2.10.1	Quadratic Curves	137
2.10.2	Cubic Curves	141
2.11	Polygons	144
2.11.1	Polygon Objects	147
2.12	Advanced Path Manipulation	150
2.12.1	Dragging Polygons	151
2.12.2	Editing Bézier Curves	158
2.12.3	Scrolling Paths into View	169
2.13	Transformations	170
2.13.1	Translating, Scaling, and Rotating	171
2.13.1.1	Mirroring	173
2.13.2	Custom Transformations	174
2.13.2.1	Algebraic Equations for Transformations	175
2.13.2.2	Using transform() and setTransform()	176
2.13.2.3	Translating, Rotating, and Scaling with transform() and setTransform()	177
2.13.2.4	Shear	179
2.14	Compositing	181
2.14.1	The Compositing Controversy	186
2.15	The Clipping Region	187
2.15.1	Erasing with the Clipping Region	187
2.15.2	Telescoping with the Clipping Region	194
2.16	Conclusion	198

Chapter 3: Text	201
3.1 Stroking and Filling Text	202
3.2 Setting Font Properties	207
3.3 Positioning Text	210
3.3.1 Horizontal and Vertical Positioning	210
3.3.2 Centering Text	214
3.3.3 Measuring Text	215
3.3.4 Labeling Axes	217
3.3.5 Labeling Dials	221
3.3.6 Drawing Text around an Arc	223
3.4 Implementing Text Controls	225
3.4.1 A Text Cursor	225
3.4.1.1 Erasing	228
3.4.1.2 Blinking	230
3.4.2 Editing a Line of Text in a Canvas	232
3.4.3 Paragraphs	238
3.4.3.1 Creating and Initializing a Paragraph	242
3.4.3.2 Positioning the Text Cursor in Response to Mouse Clicks	242
3.4.3.3 Inserting Text	243
3.4.3.4 New Lines	244
3.4.3.5 Backspace	245
3.5 Conclusion	252
Chapter 4: Images and Video	253
4.1 Drawing Images	254
4.1.1 Drawing an Image into a Canvas	255
4.1.2 The drawImage() Method	257
4.2 Scaling Images	259
4.2.1 Drawing Images outside Canvas Boundaries	260
4.3 Drawing a Canvas into a Canvas	266
4.4 Offscreen Canvases	270
4.5 Manipulating Images	274
4.5.1 Accessing Image Data	274
4.5.1.1 ImageData Objects	279

4.5.1.2	Image Data Partial Rendering: <code>putImageData</code> 's Dirty Rectangle	280
4.5.2	Modifying Image Data	283
4.5.2.1	Creating <code>ImageData</code> Objects with <code>createImageData()</code>	285
4.5.2.1.1	The Image Data Array	286
4.5.2.2	Image Data Looping Strategies	292
4.5.2.3	Filtering Images	293
4.5.2.4	Device Pixels vs. CSS Pixels, Redux	295
4.5.2.5	Image Processing Web Workers	299
4.6	Clipping Images	302
4.7	Animating Images	306
4.7.1	Animating with an Offscreen Canvas	309
4.8	Security	312
4.9	Performance	313
4.9.1	<code>drawImage(HTMLImage)</code> vs. <code>drawImage(HTMLCanvas)</code> vs. <code>putImageData()</code>	314
4.9.2	Drawing a Canvas vs. Drawing an Image, into a Canvas; Scaled vs. Unscaled	316
4.9.3	Looping over Image Data	317
4.9.3.1	Avoid Accessing Object Properties in the Loop: Store Properties in Local Variables Instead	317
4.9.3.2	Loop over Every Pixel, Not over Every Pixel Value ..	320
4.9.3.3	Looping Backwards and Bit-Shifting Are Crap Shoots	320
4.9.3.4	Don't Call <code>getImageData()</code> Repeatedly for Small Amounts of Data	321
4.10	A Magnifying Glass	321
4.10.1	Using an Offscreen Canvas	325
4.10.2	Accepting Dropped Images from the File System	326
4.11	Video Processing	328
4.11.1	Video Formats	329
4.11.1.1	Converting Formats	330
4.11.2	Playing Video in a Canvas	331
4.11.3	Processing Videos	333
4.12	Conclusion	337

Chapter 5: Animation	339
5.1 The Animation Loop	340
5.1.1 The requestAnimationFrame() Method: Letting the Browser Set the Frame Rate	343
5.1.1.1 Firefox	345
5.1.1.2 Chrome	346
5.1.2 Internet Explorer	348
5.1.3 A Portable Animation Loop	348
5.2 Calculating Frame Rates	358
5.3 Scheduling Tasks at Alternate Frame Rates	359
5.4 Restoring the Background	360
5.4.1 Clipping	361
5.4.2 Blitting	363
5.5 Double Buffering	364
5.6 Time-Based Motion	367
5.7 Scrolling the Background	370
5.8 Parallax	377
5.9 User Gestures	383
5.10 Timed Animations	385
5.10.1 Stopwatches	385
5.10.2 Animation Timers	389
5.11 Animation Best Practices	390
5.12 Conclusion	391
Chapter 6: Sprites	393
6.1 Sprites Overview	394
6.2 Painters	398
6.2.1 Stroke and Fill Painters	398
6.2.2 Image Painters	404
6.2.3 Sprite Sheet Painters	406
6.3 Sprite Behaviors	411
6.3.1 Combining Behaviors	412
6.3.2 Timed Behaviors	416
6.4 Sprite Animators	417
6.5 A Sprite-Based Animation Loop	424
6.6 Conclusion	425

Chapter 7: Physics	427
7.1 Gravity	428
7.1.1 Falling	428
7.1.2 Projectile Trajectories	432
7.1.3 Pendulums	445
7.2 Warping Time	450
7.3 Time-Warp Functions	456
7.4 Warping Motion	458
7.4.1 Linear Motion: No Acceleration	461
7.4.2 Ease In: Gradually Accelerate	463
7.4.3 Ease Out: Gradually Decelerate	465
7.4.4 Ease In, Then Ease Out	468
7.4.5 Elasticity and Bouncing	469
7.5 Warping Animation	473
7.6 Conclusion	482
Chapter 8: Collision Detection	483
8.1 Bounding Areas	483
8.1.1 Rectangular Bounding Areas	484
8.1.2 Circular Bounding Areas	485
8.2 Bouncing Off Walls	488
8.3 Ray Casting	490
8.3.1 Fine-Tuning	494
8.4 The Separating Axis Theorem (SAT) and Minimum Translation Vector (MTV)	495
8.4.1 Detecting Collisions with the SAT	495
8.4.1.1 Projection Axes	500
8.4.1.2 Projections	503
8.4.1.3 Shapes and Polygons	504
8.4.1.4 Collisions between Polygons	511
8.4.1.5 Circles	516
8.4.1.6 Images and Sprites	521
8.4.2 Reacting to Collisions with the Minimum Translation Vector	526
8.4.2.1 The MTV	526
8.4.2.2 Sticking	531

8.4.2.3	Bouncing	537
8.5	Conclusion	541
Chapter 9: Game Development		543
9.1	A Game Engine	544
9.1.1	The Game Loop	545
9.1.1.1	Pause	551
9.1.1.2	Time-Based Motion	553
9.1.2	Loading Images	554
9.1.3	Multitrack Sound	557
9.1.4	Keyboard Events	558
9.1.5	High Scores	560
9.1.6	The Game Engine Listing	561
9.2	The Ungame	572
9.2.1	The Ungame's HTML	573
9.2.2	The Ungame's Game Loop	576
9.2.3	Loading the Ungame	579
9.2.4	Pausing	581
9.2.4.1	Auto-Pause	583
9.2.5	Key Listeners	584
9.2.6	Game Over and High Scores	585
9.3	A Pinball Game	589
9.3.1	The Game Loop	590
9.3.2	The Ball	593
9.3.3	Gravity and Friction	594
9.3.4	Flipper Motion	595
9.3.5	Handling Keyboard Events	597
9.3.6	Collision Detection	601
9.3.6.1	SAT Collision Detection	601
9.3.6.2	The Dome	609
9.3.6.3	Flipper Collision Detection	611
9.4	Conclusion	614
Chapter 10: Custom Controls		615
10.1	Rounded Rectangles	617
10.2	Progress Bars	625

10.3 Sliders	631
10.4 An Image Panner	643
10.5 Conclusion	655
Chapter 11: Mobile	657
11.1 The Mobile Viewport	659
11.1.1 The viewport Metatag	661
11.2 Media Queries	666
11.2.1 Media Queries and CSS	666
11.2.2 Reacting to Media Changes with JavaScript	668
11.3 Touch Events	671
11.3.1 Touch Event Objects	672
11.3.2 Touch Lists	672
11.3.3 Touch Objects	673
11.3.4 Supporting Both Touch and Mouse Events	674
11.3.5 Pinch and Zoom	675
11.4 iOS5	677
11.4.1 Application Icons and Startup Images	678
11.4.2 Media Queries for iOS5 Application Icons and Startup Images	679
11.4.3 Fullscreen with No Browser Chrome	680
11.4.4 Application Status Bar	681
11.5 A Virtual Keyboard	682
11.5.1 A Canvas-Based Keyboard Implementation	683
11.5.1.1 The Keys	689
11.5.1.2 The Keyboard	693
11.6 Conclusion	701
<i>Index</i>	703

This page intentionally left blank

Preface



In the summer of 2001, after 15 years of developing graphical user interfaces and graphics-intensive applications, I read a best-selling book about implementing web applications by someone I did not know—Jason Hunter—but whom, unbeknownst to me, would soon become a good friend on the No Fluff Just Stuff (NFJS) tour.

When I finished Jason’s Servlets book,¹ I put it in my lap and stared out the window. After years of Smalltalk, C++, and Java, and after writing a passionate 1622 pages for *Graphic Java 2: Swing*,² I thought to myself, *am I really going to implement user interfaces with print statements that generate HTML?* Unfortunately, I was.

From then on, I soldiered on through what I consider the Dark Ages of software development. I was the second Apache Struts committer and I invented the Struts Template Library, which ultimately became the popular Tiles project. I spent more than six years on the JavaServer Faces (JSF) Expert Group, spoke about server-side Java at more than 120 NFJS symposiums and many other conferences, and coauthored a book on JSF.³ I got excited about Google Web Toolkit and Ruby on Rails for a while, but in the end the Dark Ages was mostly concerned with the dull business of presenting forms to users on the client and processing them on the server, and I was never again able to capture that passion that I had for graphics and graphical user interfaces.

In the summer of 2010, with HTML5 beginning its inexorable rise in popularity, I came across an article about Canvas, and I knew salvation was nigh. I immediately dropped everything in my professional life and devoted myself fulltime to write the best Canvas book that I could. From then on, until the book was finalized in March 2012, I was entirely immersed in Canvas and in this book. It’s by far the most fun I’ve ever had writing a book.

Canvas gives you all the graphics horsepower you need to implement everything from word processors to video games. And, although performance varies on specific platforms, in general, Canvas is fast, most notably on iOS5, which

-
1. *Java Servlet Programming*, 2001, by Jason Hunter with William Crawford, published by O’Reilly.
 2. *Graphic Java 2, Volume 2, Swing*, 1999, by David Geary, published by Prentice Hall.
 3. *Core JavaServer™ Faces, Third Edition*, 2010, by David Geary and Cay Horstmann, published by Prentice Hall.

hardware accelerates Canvas in Mobile Safari. Browser vendors have also done a great job adhering to the specification so that well-written Canvas applications run unmodified in any HTML5-compliant browser with only minor incompatibilities.

HTML5 is the Renaissance that comes after the Dark Ages of software development, and Canvas is arguably the most exciting aspect of HTML5. In this book I dive deeply into Canvas and related aspects of HTML5, such as the Animation Timing specification, to implement real-world applications that run across desktop browsers and mobile devices.

Reading This Book

I wrote this book so that in the Zen tradition you can read it without reading.

I write each chapter over the course of months, constantly iterating over material without ever writing a word. During that time I work on outlines, code listings, screenshots, tables, diagrams, itemized lists, notes, tips, and cautions. Those things, which I refer to as scaffolding, are the most important aspects of this book. The words, which I write only at the last possible moment after the scaffolding is complete, are meant to provide context and illustrate highlights of the surrounding scaffolding. Then I iterate over the words, eliminating as many of them as I can.

By focusing on scaffolding and being frugal with words, this book is easy to read without reading. You can skim the material, concentrating on the screenshots, code listings, diagrams, tables, and other scaffolding to learn a great deal of what you need to know on any given topic. Feel free to consider the words as second-class citizens, and, if you wish, consult them only as necessary.

An Overview of This Book

This book has two parts. The first part, which spans the first four chapters of the book and is nearly one half of the book, covers the Canvas API, showing you how to draw shapes and text into a canvas, and draw and manipulate images. The last seven chapters of the book show you how to use that API to implement animations and animated sprites, create physics simulations, detect collisions, and develop video games. The book ends with a chapter on implementing custom controls, such as progress bars, sliders, and image panners, and a chapter that shows you how to create Canvas-based mobile applications.

The first chapter—*Essentials*—introduces the canvas element and shows you how to use it in web applications. The chapter contains a short section on getting

started with HTML5 development in general, briefly covering browsers, consoles, debuggers, profilers, and timelines. The chapter then shows you how to implement Canvas essentials: drawing into a canvas, saving and restoring Canvas parameters and the drawing surface itself, printing a canvas, and an introduction to offscreen canvases. The chapter concludes with a brief math primer covering basic algebra, trigonometry, vector mathematics, and deriving equations from units of measure.

The second chapter—*Drawing*—which is the longest chapter in the book, provides an in-depth examination of drawing with the Canvas API, showing you how to draw lines, arcs, curves, circles, rectangles, and arbitrary polygons in a canvas, and how to fill them with solid colors, gradients, and patterns. The chapter goes beyond the mere mechanics of drawing, however, by showing you how to implement useful, real-world examples of drawing with the Canvas API, such as drawing temporary rubber bands to dynamically create shapes, dragging shapes within a canvas, implementing a simple retained-mode graphics subsystem that keeps track of polygons in a canvas so users can edit them, and using the clipping region to erase shapes without disturbing the Canvas background underneath.

The third chapter—*Text*—shows you how to draw and manipulate text in a canvas. You will see how to stroke and fill text, set font properties, and position text within a canvas. The chapter also shows you how to implement your own text controls in a canvas, complete with blinking text cursors and editable paragraphs.

The fourth chapter—*Images and Video*—focuses on images, image manipulation, and video processing. You'll see how to draw and scale images in a canvas, and you'll learn how to manipulate images by accessing the color components of each pixel. You will also see more uses for the clipping region and how to animate images. The chapter then addresses security and performance considerations, before ending with a section on video processing.

The fifth chapter—*Animation*—shows you how to implement smooth animations with a method named `requestAnimationFrame()` that's defined in a W3C specification titled *Timing control for script-based animations*. You will see how to calculate an animation's frame rate and how to schedule other activities, such as updating an animation's user interface at alternate frame rates. The chapter shows you how to restore the background during an animation with three different strategies and discusses the performance implications of each. The chapter also illustrates how to implement time-based motion, scroll an animation's background, use parallax to create the illusion of 3D, and detect and react to user gestures during an animation. The chapter concludes with a look at timed animations and the implementation of a simple animation timer, followed by a discussion of animation best practices.

The sixth chapter—*Sprites*—shows you how to implement sprites (animated objects) in JavaScript. Sprites have a visual representation, often an image, and you can move them around in a canvas and cycle through a set of images to animate them. Sprites are the fundamental building block upon which games are built.

The seventh chapter—*Physics*—shows you how to simulate physics in your animations, from modeling falling objects and projectile trajectories to swinging pendulums. The chapter also shows you how to warp both time and motion in your animations to simulate real-world movement, such as the acceleration experienced by a sprinter out of the blocks (ease-in effect) or the deceleration of a braking automobile (ease-out).

Another essential aspect of most games is collision detection, so the eighth chapter in the book—*Collision Detection*—is devoted to the science of detecting collisions between sprites. The chapter begins with simple collision detection using bounding boxes and circles, which is easy to implement but not very reliable. Because simple collision detection is not reliable under many circumstances, much of this chapter is devoted to the Separating Axis Theorem, which is one of the best ways to detect collisions between arbitrary polygons in both 2D and 3D; however, the theorem is not for the mathematically faint of heart, so this chapter goes to great lengths to present the theorem in layman terms.

The ninth chapter—*Game Development*—begins with the implementation of a simple but effective game engine that provides support for everything from drawing sprites and maintaining high scores to time-based motion and multitrack sound. The chapter then discusses two games. The first game is a simple Hello World type of game that illustrates how to use the game engine and provides a convenient starting point for a game. It also shows you how to implement common aspects of most games such as asset management, heads-up displays, and a user interface for high scores. The second game is an industrial-strength pinball game that draws on much of the previous material in the book and illustrates complex collision detection in a real-world game.

Many Canvas-based applications require custom controls, so the tenth chapter—*Custom Controls*—teaches you how to implement them. The chapter discusses implementing custom controls in general and then illustrates those techniques with four custom controls: a rounded rectangle, a progress bar, a slider, and an image panner.

The final chapter of this book—*Mobile*—focuses on implementing Canvas-based mobile applications. You'll see how to control the size of your application's viewport so that your application displays properly on mobile devices, and how to account for different screen sizes and orientations with CSS3 media queries.

You'll also see how to make your Canvas-based applications indistinguishable from native applications on iOS5 by making them run fullscreen and fitting them with desktop icons and startup screens. The chapter concludes with the implementation of a keyboard for iOS5 applications that do not receive text through a text field.

Prerequisites

To make effective use of this book you must have more than a passing familiarity with JavaScript, HTML, and CSS. I assume, for example, that you already know how to implement objects with JavaScript's prototypal inheritance, and that you are well versed in web application development in general.

This book also utilizes some mathematics that you may have learned a long time ago and forgotten, such as basic algebra and trigonometry, vector math, and deriving equations from units of measure. At the end of the first chapter you will find a short primer that covers all those topics.

The Book's Code

All the code in this book is copyrighted by the author and is available for use under the license distributed with the code. That license is a modified MIT license that lets you do anything you want with the code, including using it in software that you sell; however, you may not use the code to create educational material, such as books, instructional videos, or presentations. See the license that comes with the code for more details.

When implementing the examples, I made a conscious decision to keep comments in code listings to a bare minimum. Instead, I made the code itself as readable as possible; methods average about five lines of code so they are easy to understand.

I also adhered closely to Douglas Crawford's recommendations in his excellent book *JavaScript, The Good Parts*.⁴ For example, all function-scoped variables are always declared at the top of the function, variables are declared on a line of their own, and I always use `===` and its ilk for equality testing.

Finally, all the code listings in this book are color coded. Function calls are displayed in `blue`, so they stand out from the rest of the listing. As you scan listings, pay particular attention to the `blue` function calls; after all, function calls are the verbs of JavaScript, and those verbs alone reveal most of what you need to know about the inner workings of any particular example.

4. *JavaScript, The Good Parts*, 2008, by Douglas Crawford, published by O'Reilly.

The Future of Canvas and This Book

The HTML5 APIs are constantly evolving, and much of that evolution consists of new features. The Canvas specification is no exception; in fact, this book was just days from going to the printer when the WHATWG Canvas specification was updated to include several new features:

- An `ellipse()` method that creates elliptical paths
- Two methods, `getLineDash()` and `setLineDash()`, and an attribute `lineDashOffset` used for drawing dashed lines
- An expanded `TextMetrics` object that lets you determine the exact bounding box for text
- A `Path` object
- A `CanvasDrawingStyles` object
- Extensive support for hit regions

At that time, no browsers supported the new features, so it was not yet possible to write code to test them.

Prior the March 26, 2012 update to the specification, you could draw arcs and circles with Canvas, but there was no explicit provision for drawing ellipses. Now, in addition to arcs and circles, you can draw ellipses with the new `ellipse()` method of the Canvas 2d context. Likewise, the context now explicitly supports drawing dashed lines.

The `TextMetrics` object initially only reported one metric: the width of a string. However, with the March 26, 2012 update to the specification, you can now determine both the width and height of the rectangle taken up by a string in a canvas. That augmentation of the `TextMetrics` object will make it much easier, and more efficient, to implement Canvas-based text controls.

In addition to ellipses and an improved `TextMetrics` object, the updated specification has also added `Path` and `CanvasDrawingStyles` methods. Prior to the updated specification, there was no explicit mechanism for storing paths or drawing styles. Now, not only are there objects that represent those abstractions, but many of the Canvas 2d context methods have been duplicated to also take a `Path` object. For example, you stroke a context's path by invoking `context.stroke()`, which strokes the *current* path; however, the context now has a method `stroke(Path)` and that method strokes the path you send to the method instead of the context's current path. When you modify a path with `Path` methods such as `addText()`, you can specify a `CanvasDrawingStyle` object, which is used by the path, in this case to add text to the path.

The updated specification contains extensive support for hit regions. A hit region is defined by a path, and you can associate an optional mouse cursor and accessibility parameters, such as an Accessible Rich Internet Application (ARIA) role and a label, with a hit region. A single canvas can have multiple hit regions. Among other things, hit regions will make it easier and more efficient to implement collision detection and improve accessibility.

Finally, both the WHATWG and W3C specifications have included two Canvas context methods for accessibility, so that applications can draw focus rings around the current path, letting users navigate with the keyboard in a Canvas. That functionality was not part of the March 26, 2012 update to the specification, and in fact, has been in the specification for some time; however, while the book was being written, no browser vendors supported the feature, so it is not covered in this book.

As the Canvas specification evolves and browser vendors implement new features, this book will be updated on a regular basis. In the meantime, you can read about new Canvas features and preview the coverage of those features in the next edition of this book, at corehtml5canvas.com.

The Companion Website

This book's companion website is <http://corehtml5canvas.com>, where you can download the book's code, run featured examples from the book, and find other HTML5 and Canvas resources.

This page intentionally left blank

Acknowledgments



Writing books is a team sport, and I was lucky to have great teammates for this book.

I'd like to start by thanking my longtime editor and good friend Greg Doench, who believed wholeheartedly in this book from the moment I proposed it and who gave me the latitude to write the book exactly as I wanted. Greg also oversaw the book from the moment of conception until, and after, it went to print. I couldn't ask for more.

I'm also fortunate that Greg comes with a great team of his own. Julie Nahil did a wonderful job of managing production and keeping everything on track, and Alina Kirsanova took my raw docbook XML and turned it into the beautiful color book you hold in your hands. Alina also did a superb job proofreading, weeding out small errors and inconsistencies.

Once again I was thrilled to have Mary Lou Nohr copy edit this book. Mary Lou is the only copy editor I've had in 15 years of writing books, and she not only makes each book better than I possibly could, but she continues to teach me the craft of writing.

Technical reviewers are vital to the success of any technical book, so I actively recruit reviewers who I think have an appropriate skill set to make significant contributions. For this book I was fortunate to land an excellent group of reviewers who helped me mold, shape, and polish the book's material. First, I'd like to thank Philip Taylor for being one of the most knowledgeable and thorough reviewers that I've ever had. Philip, who has implemented nearly 800 Canvas test cases—see <http://philip.html5.org/tests/canvas/suite/tests>—sent me pages of insightful comments for each chapter that only someone who knows the most intimate Canvas nuances could provide. Philip went way beyond the call of duty and single-handedly made this a much better book.

Next, I'd like to thank Scott Davis at thirstyhead.com, one of the foremost experts in HTML5 and mobile web application development. Scott has spoken at many conferences on HTML5 and mobile development, cofounded the HTML5 Denver Users Group, and taught mobile development to Yahoo! developers. Like Philip, Scott went way beyond the call of duty by offering excellent suggestions in many different areas of the book. I'm deeply indebted to Scott for delaying the publishing of this book for a full three months, while I entirely rewrote nearly a quarter of the book as the result of his scathing review. That rewrite took this book to the next level.

Ilmari Heikkinen, of Runfield fame (<http://fhtr.org/runfield/runfield>), provided some great insights for the Animation, Sprites, Physics, and Collision Detection chapters. Ted Neward, Dion Almaer, Ben Galbraith, Pratik Patel, Doris Chen, Nate Schutta, and Brian Sam-Bodden also provided great review comments.

I'd also like to thank Mathias Bynens, the creator of jsperf.com, for giving me permission to use screenshots from that website.

I would like to acknowledge MJKRZAK for the sprite sheet used in the Physics chapter. That sprite sheet was downloaded from the public domain section of the People's Sprites website. I would also like to thank Ilmari Heikkinen for giving me permission to use his sky image for the parallax example in the Animation chapter. Some images in Sprites chapter are from the popular open source Replica Island game.

Finally, I'd like to thank Hiroko, Gaspé, and Tonka for enduring over the past year and a half while this book utterly consumed my life.

About the Author



David Geary is a prominent author, speaker, and consultant, who began implementing graphics-based applications and interfaces with C and Smalltalk in the 1980s. David taught C++ and Object-Oriented Software Development for eight years at Boeing, and was a software engineer at Sun Microsystems from 1994–1997. He is the author of eight Java books, including two best-selling books on the Java component frameworks, Swing and JavaServer Faces (JSF). David's *Graphic Java 2: Swing* is the all-time best-selling Swing book, and *Core JavaServer™ Faces*, which David wrote with Cay Horstmann, is the best-selling book on JSF.

David is a passionate and prolific public speaker who has spoken at hundreds of conferences world-wide. He spoke on the No Fluff Just Stuff tour for six years, speaking at over 120 symposiums, and he is a three-time JavaOne Rock Star.

In 2011, David and Scott Davis co-founded the HTML5 Denver Meetup group—www.meetup.com/HTML5-Denver-Users-Group—which had grown to over 500 members when this book was published in 2012.

David can be found on Twitter (@davidgeary) and at the companion website for this book, <http://corehtml5canvas.com>.

This page intentionally left blank

Essentials

In 1939, Metro-Goldwyn-Mayer Studios released a film that, according to the American Library of Congress, was destined to become the most watched film in history. *The Wizard of Oz* is the story of a young girl named Dorothy and her dog Toto, who are transported by a violent tornado from Kansas in the central United States to the magical land of Oz.

The film begins in Kansas and is shot in a bland and dreary black-and-white. When Dorothy and Toto arrive in the land of Oz however, the film bursts into vibrant color, and the adventure begins.

For more than a decade, software developers have been implementing bland and dreary web applications that do little more than present bored-to-death users with a seemingly unending sequence of banal forms. Finally, HTML5 lets developers implement exciting desktop-like applications that run in the browser.

In this HTML5 land of Oz, we will use the magical canvas element to do amazing things in a browser. We will implement image panning, as shown in [Figure 1.1](#); an interactive magnifying glass; a paint application that runs in any self-respecting browser and that also runs on an iPad; several animations and games, including an industrial-strength pinball game; image filters; and many other web applications that in another era were almost entirely the realm of Flash.

Let's get started.

1.1 The canvas Element

The canvas element is arguably the single most powerful HTML5 element, although, as you'll see shortly, its real power lies in the Canvas context, which




Figure 1.1 Canvas offers a powerful graphics API

you obtain from the canvas element itself. **Figure 1.2** shows a simple use of the canvas element and its associated context.




Figure 1.2 Hello canvas

The application shown in [Figure 1.2](#) simply displays a string, approximately centered in the canvas itself. The HTML for that application is shown in [Example 1.1](#).

The HTML in [Example 1.1](#) uses a canvas element and specifies an identifier for the element and the element's width and height. Notice the text in the body of the canvas element. That text is known as the *fallback content*, which the browser displays only if it does not support the canvas element.

Besides those two elements, the HTML in [Example 1.1](#) uses CSS to set the application's background color and some attributes for the canvas element itself. By default, a canvas element's background color matches the background color of its parent element, so the CSS sets the canvas element's background color to opaque white to set it apart from the application's light gray background.

The HTML is straightforward and not very interesting. As is typically the case for Canvas-based applications, the interesting part of the application is its JavaScript. The JavaScript code for the application shown in [Figure 1.2](#) is listed in [Example 1.2](#).

Example 1.1 example.html

```
<!DOCTYPE html>
<html>
  <head>
    <title>A Simple Canvas Example</title>

    <style>
      body {
        background: #dddddd;
      }
      #canvas {
        margin: 10px;
        padding: 10px;
        background: #ffffff;
        border: thin inset #aaaaaa;
      }
    </style>
  </head>

  <body>
    <canvas id='canvas' width='600' height='300'>
      Canvas not supported
    </canvas>

    <script src='example.js'></script>
  </body>
</html>
```

Example 1.2 example.js

```
var canvas = document.getElementById('canvas'),
    context = canvas.getContext('2d');

context.font = '38pt Arial';
context.fillStyle = 'cornflowerblue';
context.strokeStyle = 'blue';

context.fillText('Hello Canvas', canvas.width/2 - 150,
               canvas.height/2 + 15);

context.strokeText('Hello Canvas', canvas.width/2 - 150,
                 canvas.height/2 + 15);
```

The JavaScript in [Example 1.2](#) employs a recipe that you will use in your Canvas-based applications:

1. Use `document.getElementById()` to get a reference to a canvas.
2. Call `getContext('2d')` on the canvas to get the graphics context (note: the 'd' in '2d' *must* be lowercase).
3. Use the context to draw in the canvas.

After obtaining a reference to the canvas's context, the JavaScript sets the context's `font`, `fillStyle`, and `strokeStyle` attributes and fills and strokes the text that you see in [Figure 1.2](#). The `fillText()` method fills the characters of the text using `fillStyle`, and `strokeText()` strokes the outline of the characters with `strokeStyle`. The `fillStyle` and `strokeStyle` attributes can be a CSS color, a gradient, or a pattern. We briefly discuss those attributes in Section 1.2.1, "The 2d Context," on p. 9 and take a more in-depth look at both the attributes and methods in Chapter 2.

The `fillText()` and `strokeText()` methods both take three arguments: the text and an (x, y) location within the canvas to display the text. The JavaScript shown in [Example 1.2](#) approximately centers the text with constant values, which is not a good general solution for centering text in a canvas. In Chapter 3, we will look at a better way to center text.

**CAUTION: The suffix px is not valid for canvas width and height**

Although it's widely permitted by browsers that support Canvas, the `px` suffix for the `width` and `height` attributes is not technically allowed by the Canvas specification. The values for those attributes, according to the specification, can only be non-negative integers.

**NOTE: The default canvas size is 300 × 150 screen pixels**

By default, the browser creates canvas elements with a width of 300 pixels and a height of 150 pixels. You can change the size of a canvas element by specifying the width and height attributes.

You can also change the size of a canvas element with CSS attributes; however, as you will see in the next section, changing the width and height of a canvas element may have unwanted consequences.

1.1.1 Canvas Element Size vs. Drawing Surface Size

The application in the preceding section sets the size of the canvas element by setting the element's width and height attributes. You can also use CSS to set the size of a canvas element, as shown in [Example 1.3](#); however, using CSS to size a canvas element is not the same as setting the element's width and height attributes.

Example 1.3 Setting element size and drawing surface size to different values

```
<!DOCTYPE html>
<head>
  <title>Canvas element size: 600 x 300,
    Canvas drawing surface size: 300 x 150</title>
  <style>
    body {
      background: #dddddd;
    }
    #canvas {
      margin: 20px;
      padding: 20px;
      background: #ffffff;
      border: thin inset #aaaaaa;
      width: 600px;
      height: 300px;
    }
  </style>
</head>

<body>
  <canvas id='canvas'>
    Canvas not supported
  </canvas>

  <script src='example.js'></script>
</body>
</html>
```

The difference between using CSS and setting canvas element attributes lies in the fact that *a canvas actually has two sizes*: the size of the element itself and the size of the element's drawing surface.

When you set the element's width and height attributes, you set *both* the element's size and the size of the element's drawing surface; however, when you use CSS to size a canvas element, you set *only* the element's size and not the drawing surface.

By default, both the canvas element's size and the size of its drawing surface is 300 screen pixels wide and 150 screen pixels high. In the listing shown in [Example 1.3](#), which uses CSS to set the canvas element's size, the size of the element is 600 pixels wide and 300 pixels high, but *the size of the drawing surface remains unchanged* at the default value of 300 pixels \times 150 pixels.

And here is where things get interesting because when a canvas element's size does not match the size of its drawing surface, *the browser scales the drawing surface to fit the element*. That effect is illustrated in [Figure 1.3](#).



Figure 1.3 *Top*: element and coordinate system = 600 \times 300; *bottom*: element = 600 \times 300, coordinate system = 300 \times 150

The application shown at the top of [Figure 1.3](#) is the application that we discussed in the preceding section. It sets the canvas element's size with the element's width

and `height` attributes, setting both the element's size and the size of the drawing surface to 600 pixels \times 300 pixels.

The application shown at the bottom of [Figure 1.3](#) is the application whose HTML is shown in [Example 1.3](#). That application is identical to the application in the preceding section, except that it uses CSS to size the canvas element (and has a different title in the window's title bar).

Because the application shown in the bottom screenshot in [Figure 1.3](#) uses CSS to size the canvas element and does not set the element's width or height attributes, the browser scales the drawing surface from 300 pixels \times 150 pixels to 600 pixels \times 300 pixels.



CAUTION: The browser may automatically scale your canvas

It's a good idea to use the canvas element's `width` and `height` attributes to size the element, instead of using CSS. If you use CSS to size the element without also specifying the `width` and `height` attributes of the canvas element, the element size will not match the canvas's drawing surface size, and the browser will scale the latter to fit the former, most likely resulting in surprising and unwanted effects.

1.1.2 The Canvas API

The canvas element does not provide much of an API; in fact, that API offers only two attributes and three methods that are summarized in [Table 1.1](#) and [Table 1.2](#).

Table 1.1 canvas attributes

Attribute	Description	Type	Allowed Values	Default
<code>width</code>	The width of the canvas's <i>drawing surface</i> . By default, the browser makes the canvas element the same size as its drawing surface; however, if you override the element size with CSS, then the browser will <i>scale</i> the drawing surface to fit the element.	non-negative integer	Any valid non-negative integer. You may add a plus sign or whitespace at the beginning, but technically, you cannot add a px suffix.	300

(Continues)

Table 1.1 (Continued)

Attribute	Description	Type	Allowed Values	Default
height	The height of the canvas's drawing surface. The browser may scale the drawing surface to fit the canvas element size. See the width attribute for more information.	non-negative integer	Any valid non-negative integer. You may add a plus sign or whitespace at the beginning, but technically, you cannot add a px suffix.	150

Table 1.2 canvas methods

Method	Description
getContext()	Returns the graphics context associated with the canvas. Each canvas has one context, and each context is associated with one canvas.
toDataURL(type, quality)	Returns a data URL that you can assign to the src property of an img element. The first argument specifies the type of image, such as image/jpeg, or image/png; the latter is the default if you don't specify the first argument. The second argument, which must be a double value from 0 to 1.0, specifies a quality level for JPEG images.
toBlob(callback, type, args...)	Creates a Blob that represents a file containing the canvas's image. The first argument to the method is a function that the browser invokes with a reference to the blob. The second argument specifies the type of image, such as image/png, which is the default value. The final arguments represent a quality level from 0.0 to 1.0 inclusive, for JPEG images. Other arguments will most likely be added to this method in the future to more carefully control image characteristics.

1.2 Canvas Contexts

The canvas element merely serves as a container for a context. The context provides all the graphics horsepower. Although this book focuses exclusively on the 2d context, the Canvas specification embraces other types of contexts as well; for example, a 3d context specification is already well underway. This section looks at the attributes of the 2d context, with a brief nod to the 3d context.

1.2.1 The 2d Context

In your JavaScript code, you will find little use for the canvas element itself, other than occasionally using it to obtain the canvas width or height or a data URL, as discussed in the preceding section. Additionally, you will use the canvas element to obtain a reference to the canvas's context, which provides a capable API for drawing shapes and text, displaying and manipulating images, etc. Indeed, for the rest of this book our focus will mainly be on the 2d context.

Table 1.3 lists all of the 2d context attributes. Other than the canvas attribute, which gives you a reference to the canvas itself, all of the 2d context attributes pertain to drawing operations.

Table 1.3 CanvasRenderingContext2D attributes

Attribute	Brief Description
canvas	Refers to the context's canvas. The most common use of the canvas attribute is to access the width and height of the canvas: <code>context.canvas.width</code> and <code>context.canvas.height</code> , respectively.
fillStyle	Specifies a color, gradient, or pattern that the context subsequently uses to fill shapes.
font	Specifies the font that the context uses when you call <code>fillText()</code> or <code>strokeText()</code> .
globalAlpha	Is the global alpha setting, which must be a number between 0 (fully transparent), and 1.0 (fully opaque). The browser multiplies the alpha value of every pixel you draw by the <code>globalAlpha</code> property, including when you draw images.
globalComposite-Operation	Determines how the browser draws one thing over another. See Section 2.14 for valid values.
lineCap	Specifies how the browser draws the endpoints of a line. You can specify one of the following three values: <code>butt</code> , <code>round</code> , and <code>square</code> . The default value is <code>butt</code> .
lineWidth	Determines the width, in screen pixels, of lines that you draw in a canvas. The value must be a non-negative, non-infinite <code>double</code> value. The default is 1.0.
lineJoin	Specifies how lines are joined when their endpoints meet. Valid values are: <code>bevel</code> , <code>round</code> , and <code>miter</code> . The default value is <code>miter</code> .

(Continues)

Table 1.3 (Continued)

Attribute	Brief Description
<code>miterLimit</code>	Specifies how to draw a miter line join. See Section 2.8.7 for details about this property.
<code>shadowBlur</code>	Determines how the browser spreads out shadow; the higher the number, the more spread out the shadows. The <code>shadowBlur</code> value is not a pixel value, but a value used in a Gaussian blur equation. The value must be a positive, non-infinite <code>double</code> value. The default value is 0.
<code>shadowColor</code>	Specifies the color the browser uses to draw shadows. The value for this property is often specified as partially transparent to let the background show through.
<code>shadowOffsetX</code>	Specifies the horizontal offset, in screen pixels, for shadows.
<code>shadowOffsetY</code>	Specifies the vertical offset, in screen pixels, for shadows.
<code>strokeStyle</code>	Specifies the style used to stroke paths. This value can be a color, gradient, or pattern.
<code>textAlign</code>	Determines horizontal placement of text that you draw with <code>fillText()</code> or <code>strokeText()</code> .
<code>textBaseline</code>	Determines vertical placement of text that you draw with <code>fillText()</code> or <code>strokeText()</code> .

The table gives you an overview of all the 2d context attributes. In Chapter 2, we examine all those attributes on a case-by-case basis.



NOTE: You can extend the 2d context's capabilities

The context associated with each canvas is a powerful graphics engine that supports features such as gradients, image compositing, and animation, but it does have limitations; for example, the context does not provide a method for drawing dashed lines. Because JavaScript is a dynamic language, however, you can add new methods or augment existing methods of the context. See Section 2.8.6, "Drawing Dashed Lines by Extending `CanvasRenderingContext2D`," on p. 118 for more information.

1.2.1.1 The WebGL 3d Context

The Canvas 2d context has a 3d counterpart, known as WebGL, that closely conforms to the OpenGL ES 2.0 API. You can find the WebGL specification, which is maintained by the Khronos Group, at <http://www.khronos.org/registry/webgl/specs/latest/>.

At the time this book was written, browser vendors were just beginning to provide support for WebGL, and there are still some notable platforms, such as iOS4 and IE10, that do not provide support. Nonetheless, a 3d Canvas context is an exciting development that will open the door to all sorts of bleeding edge applications.

1.2.2 Saving and Restoring Canvas State

In Section 1.2.1, “The 2d Context,” on p. 9 we discussed all of the attributes of the Canvas context. You will often set those attributes for drawing operations. Much of the time you will want to *temporarily* set those attributes; for example, you may draw a grid with thin lines in the background and subsequently draw on top of the grid with thicker lines. In that case you would temporarily set the `linewidth` attribute while you draw the grid.

The Canvas API provides two methods, named `save()` and `restore()`, for saving and restoring all the canvas context’s attributes. You use those methods like this:

```
function drawGrid(strokeStyle, fillStyle) {
    controlContext.save(); // Save the context on a stack

    controlContext.fillStyle = fillStyle;
    controlContext.strokeStyle = strokeStyle;

    // Draw the grid...

    controlContext.restore(); // Restore the context from the stack
}
```

The `save()` and `restore()` methods may not seem like a big deal, but after using Canvas for any length of time you will find them indispensable. Those two methods are summarized in [Table 1.4](#).



NOTE: You can nest calls to `save()` and `restore()`

The context’s `save()` method places the current state of the context onto a stack. The corresponding call to `restore()` pops the state from the stack and restores the context’s state accordingly. That means you can nest calls to `save()/restore()`.

Table 1.4 CanvasRenderingContext2D state methods

Method	Description
save()	<p>Pushes the current state of the canvas onto a stack of canvas states. Canvas state includes the current transformation and clipping region and all attributes of the canvas's context, including <code>strokeStyle</code>, <code>fillStyle</code>, <code>globalCompositeOperation</code>, etc.</p> <p>The canvas state does not include the current path or bitmap. You can only reset the path by calling <code>beginPath()</code>, and the bitmap is a property of the canvas, not the context.</p> <p>Note that although the bitmap is a property of the canvas, you access the bitmap through the context (via the context's <code>getImageData()</code> method).</p>
restore()	<p>Pops the top entry off the stack of canvas states. The state that resides at the top of the stack, after the pop occurs, becomes the current state, and the browser must set the canvas state accordingly. Therefore, any changes that you make to the canvas state between <code>save()</code> and <code>restore()</code> method calls persist only until you invoke the <code>restore()</code> method.</p>

**NOTE: Saving and restoring the drawing surface**

This section shows you how to save and restore context state. It's also beneficial to be able to save and restore the drawing surface itself, which we discuss in Section 1.7, "Saving and Restoring the Drawing Surface," on p. 33.

1.3 Canonical Examples in This Book

Many of the examples in this book use the following canonical form:

```

<!-- example.html -->

<!DOCTYPE html>
<html>
  <head>
    <title>Canonical Canvas used in this book</title>

    <style>
      ...
      #canvas {
        ...
      }
    </style>
  </head>

```

```
<body>
  <canvas id='canvas' width='600' height='300'>
    Canvas not supported
  </canvas>

  <script src='example.js'></script>
</body>
</html>

// example.js

var canvas = document.getElementById('canvas'),
    context = canvas.getContext('2d');

// Use the context...
```

The preceding example has one canvas whose ID is `canvas`, and it uses one JavaScript file named `example.js`. That JavaScript file has two variables, one for the canvas and another for the canvas's context. The preceding example uses `document.getElementById()` to obtain a reference to the canvas and gets a reference to the canvas's context.

Most applications in this book that adhere to the preceding canonical form omit the HTML listings in the interests of brevity. Likewise, for inline code listings, meaning listings like the preceding listing that do not have an Example heading, you will often see the variables `canvas` and `context` with no code showing their initialization.

Finally, again in the interests of brevity, not every example in the book is fully listed. Often examples in the book build upon one other, and when they do, you will often see the full listing for the last example and partial listings for the other related examples.



NOTE: A word about User Agents

The Canvas specification refers to the implementor of the canvas element as a *User Agent*, which is often abbreviated to UA. The specification uses that term instead of the word *browser* because canvas elements can be implemented by any piece of software, not just browsers.

This book refers to the implementor of the canvas element as a browser because the term *User Agent*, or worse, the abbreviation UA, can be foreign and confusing to readers.

**NOTE: URLs referenced in this book**

In this book you will occasionally find references to URLs for further reading. Sometimes, if they are readable and not too long, those URLs will be the actual URLs. For unwieldy URLs, this book refers to shortened URLs that may be difficult to remember but are easy to type.

1.4 Getting Started

This section gives you a brief overview of your development environment, from the browsers in which your application will run to the development tools, such as profilers and timelines, that you will use during development. Feel free to skim this section and use it as a reference as necessary.

1.4.1 Specifications

Three specifications are pertinent to this book:

- HTML5 Canvas
- Timing control for script-based animations
- HTML5 video and audio

For historical reasons, there are actually two Canvas specifications that are nearly identical. One of those specifications is maintained by the W3C and can be found at <http://dev.w3.org/html5/spec>; the other specification is maintained by the WHATWG and can be found at <http://bit.ly/qXWjOl>. Furthermore, whereas the Canvas context is included in the WHATWG's specification, the WC3 has a separate specification for the context, at <http://dev.w3.org/html5/2dcontext>.

For a long time, people used `window.setInterval()` or `window.setTimeout()` for web-based animations; however, as you will see in Chapter 5, those methods are not suitable for performance-critical animations. Instead, you should use `window.requestAnimationFrame()`, which is defined in a specification of its own named *Timing control for script-based animations*. You can find that specification at <http://www.w3.org/TR/animation-timing>.

Finally, this book shows you how to incorporate HTML5 video and audio into your Canvas-based applications. HTML5 video and audio are covered in the same specification, which you can find at <http://www.w3.org/TR/html5/video.html>.

1.4.2 Browsers

At the time this book went to press in early 2012, all five major browsers—Chrome, Internet Explorer, Firefox, Opera, and Safari—provided extensive support for HTML5 Canvas. Although there are some minor incompatibilities that mostly stem from different interpretations of the Canvas specification—for example, see Section 2.14.1, “The Compositing Controversy,” on p. 186, which explains incompatibilities for compositing—browser vendors have done an admirable job of both adhering to the specification and providing implementations that perform well.

Chrome, Firefox, Opera, and Safari have all had HTML5 support for some time. Microsoft’s Internet Explorer was a bit late to the game and did not provide extensive support for HTML 5 until IE9. However, Microsoft has done a phenomenal job with Canvas in IE9 and IE10; in fact, as this book went to press, those two browsers had the fastest Canvas implementation from among the five major browsers.

If you are implementing a Canvas-based application and you must support IE6, IE7, or IE8, you have two choices, depicted in [Figure 1.4](#): `explorercanvas`, which




Figure 1.4 `explorercanvas` and Google Chrome Frame for IE6/7/8, from Google

adds Canvas support to those older versions of Internet Explorer, and Google Chrome Frame, which replaces the IE engine with the Google Chrome engine. Both `explorercanvas` and Google Chrome Frame are from Google.

1.4.3 Consoles and Debuggers

All the major browsers that support HTML5 give you access to a console and a debugger. In fact, because browser vendors often borrow ideas from each other, the consoles and debuggers provided by WebKit-based browsers—Firefox, Opera, and IE—are all pretty similar.

Figure 1.5 shows the console and debugger for Safari.




Figure 1.5 The Safari console and debugger

You can write to the console with the `console.log()` method. Just pass that method a string, and it will appear in the console. The debugger is standard debugger fare; you can set breakpoints, watch expressions, examine variables and the call stack, and so on.

A full treatment of the developer tools for various browsers is beyond the scope of this book. For more information about developer tools for Chrome, take a look

at the Chrome Developer Tools documentation, shown in [Figure 1.6](#). Similar documentation is available for other browsers.




Figure 1.6 The Chrome Developer Tools documentation



TIP: Start and stop the profiler programmatically

As you can see from [Figure 1.6](#), you can start profiling in WebKit-based browsers by clicking the filled circle at the bottom of the profiler window.

Controlling the profiler by clicking buttons, however, is often insufficient; for example, you may want to start and stop profiling at specific lines of code. In WebKit-based browsers, you can do that with two methods: `console.profile()` and `console.profileEnd()`. You use them like this:

```
console.profile('Core HTML5 Animation,
               erasing the background');
//...
console.profileEnd();
```

1.4.4 Performance

Most of the time the applications that you implement with Canvas will perform admirably; however, if you are implementing animations or games or if you are implementing Canvas-based applications for mobile devices, you may need to make performance optimizations.

In this section we briefly look at the tools you have at your disposal for discovering performance bottlenecks in your code. To illustrate the use of those tools, we refer to the application shown in [Figure 1.7](#). That animation, which is discussed in [Chapter 5](#), simultaneously animates three filled circles.




Figure 1.7 An animation from Chapter 5

We discuss three tools:

- Profilers
- Timelines
- jsPerf

The first two tools in the preceding list are provided by browsers directly or are offered as add-ons. jsPerf, on the other hand, is a website that lets you create performance tests and make them public. In the sections that follow we will look at profiling and timeline tools available in Chrome and Safari, and then we will take a look at jsPerf.

1.4.4.1 Profiles and Timelines

Profiles and timelines are indispensable for discovering performance bottlenecks in your code. [Figures 1.8](#) and [1.9](#) show a timeline and a profile, respectively, for the animation shown in [Figure 1.7](#).




Figure 1.8 Timelines

Timelines give you a record of significant events that occur in your application, along with details of those events such as their duration and the area of the window they affect. In WebKit-based browsers, such as Chrome and Safari, you can hover the mouse over those events to obtain their associated details, as illustrated in [Figure 1.8](#).

The screenshot shows the Web Inspector's CPU Profiles panel. The table below represents the data visible in the main pane of the profile.

Function	Self	Total	Average	Calls
animate	0.05%	64.58%	0.00%	101
draw	0.03%	64.47%	0.00%	100
stroke	56.41%	56.41%	0.01%	4200
drawBackground (idle)	0.74%	56.31%	0.01%	100
eraseBackground	35.42%	35.42%	35.42%	0
clearRect	0.02%	6.70%	0.00%	100
drawRings	6.68%	6.68%	0.07%	100
drawRings	0.02%	1.42%	0.00%	100
drawRings	0.08%	1.40%	0.00%	300
beginPath	0.18%	0.18%	0.00%	4200
restore	0.08%	0.08%	0.00%	400
moveTo	0.06%	0.06%	0.00%	3900
lineTo	0.06%	0.06%	0.00%	3900
save	0.04%	0.04%	0.00%	400
arc	0.04%	0.04%	0.00%	300
clip	0.03%	0.03%	0.00%	300
update	0.03%	0.03%	0.00%	100
Date	0.01%	0.01%	0.00%	100
monitorProfiling	0.01%	0.01%	0.00%	101
calculateFps	0.00%	0.00%	0.00%	100
toFixed	0.00%	0.00%	0.00%	2
profileEnd	0.00%	0.00%	0.00%	1

Figure 1.9 Profiles


Profilers give you a much more detailed view of how your code performs at the function level. As you can see in [Figure 1.9](#), profiles show you how many times each function in your application is called, and how long those functions take. You can see what percentage of the total execution time is taken up by each function, and you can also discover exactly how many milliseconds each function takes, on average, to execute.

1.4.4.2 jsPerf

jsPerf, shown in [Figure 1.10](#), is a website that lets you create and share JavaScript benchmarks.

You may wonder, for example, what's the most efficient way to loop through pixels in an image that you are processing in a canvas. If you click the "test cases" link, shown at the top of the screenshot in [Figure 1.10](#), jsPerf displays all of the publicly available test cases, as shown in [Figure 1.11](#).

In fact, not only are there many Canvas-related tests at jsperf.com, there is a test case that matches the description in the preceding paragraph, which is highlighted in [Figure 1.11](#). If you click the link for that test case, jsPerf shows you the code for the test case, as shown in [Figure 1.12](#). You can run the test case yourself, and your results will be added to the test case. You can also look at the results for all the different browsers that users have used to run the test case (not shown in [Figure 1.12](#)).



The screenshot shows the jsPerf homepage with the following content:

jsPerf — JavaScript performance playground

What is jsPerf?

jsPerf aims to provide an easy way to create and share [test cases](#), comparing the performance of different JavaScript snippets by running benchmarks. For more information, see [the FAQ](#).

Create a test case

Your details (optional)

Name

Email (won't be displayed; might be used for Gravatar)

URL

Test case details

Title *

Slug *

Test case URL will be `http://jsperf.com/slug`

Published (uncheck if you want to fiddle around before making the page public)

Figure 1.10 jsperf.com homepage




Figure 1.11 Code for a Canvas test case at jsperf.com

Testing in Safari 5.0.1 on Mac OS X 10.6.4		Ops/sec
Test		
property accesses 2d	<pre>for (var y = 0; y < id.height; y++) { for (var x = 0; x < id.width; x++) { var off = (y * id.width + x) * 4; id.data[off] += 10; id.data[off + 1] += 20; id.data[off + 2] += 30; id.data[off + 3] += 40; } }</pre>	ready
property accesses 1d	<pre>for (var i = 0; i < id.data.length; i += 4) { id.data[i] += 10; id.data[i + 1] += 20; id.data[i + 2] += 30; id.data[i + 3] += 40; }</pre>	ready
local variables	<pre>for (var y = 0; y < height; y++) { for (var x = 0; x < width; x++) { var off = (y * width + x) * 4; pixels[off] += 10; pixels[off + 1] += 20;</pre>	ready

Figure 1.12 A test case for looping through image pixels

Now that we're done with the preliminaries, let's look at how to draw into a canvas.

1.5 Fundamental Drawing Operations

In the next chapter we will look closely at drawing in a canvas. For now, however, to familiarize you with the drawing methods that the Canvas API provides, let's begin with the application shown in [Figure 1.13](#), which implements an analog clock.

The clock application, which is listed in [Example 1.4](#), uses the following drawing methods from the Canvas API:

- `arc()`
- `beginPath()`
- `clearRect()`

- `fill()`
- `fillText()`
- `lineTo()`
- `moveTo()`
- `stroke()`




Figure 1.13 A clock

Like Adobe Illustrator and Apple’s Cocoa, Canvas lets you draw shapes by creating invisible paths that you subsequently make visible with calls to `stroke()`, which strokes the outline of the path, or `fill()`, which fills the inside of the path. You begin a path with the `beginPath()` method.

The clock application’s `drawCircle()` method draws the circle representing the clock face by invoking `beginPath()` to begin a path, and subsequently invokes `arc()` to create a circular path. That path is invisible until the application invokes `stroke()`. Likewise, the application’s `drawCenter()` method draws the small filled circle at the center of the clock with a combination of `beginPath()`, `arc()`, and `fill()`.

The application’s `drawNumerals()` method draws the numbers around the face of the clock with the `fillText()` method, which draws filled text in the canvas. Unlike the `arc()` method, `fillText()` does not create a path; instead, `fillText()` immediately renders text in the canvas.

The clock hands are drawn by the application's `drawHand()` method, which uses three methods to draw the lines that represent the clock hands: `moveTo()`, `lineTo()`, and `stroke()`. The `moveTo()` method moves the graphics pen to a specific location in the canvas, `lineTo()` draws an invisible path to the location that you specify, and `stroke()` makes the current path visible.

The application animates the clock with `setInterval()`, which invokes the application's `drawClock()` function once every second. The `drawClock()` function uses `clearRect()` to erase the canvas, and then it redraws the clock.

Example 1.4 A basic clock

```
var canvas = document.getElementById('canvas'),
    context = canvas.getContext('2d'),
    FONT_HEIGHT = 15,
    MARGIN = 35,
    HAND_TRUNCATION = canvas.width/25,
    HOUR_HAND_TRUNCATION = canvas.width/10,
    NUMERAL_SPACING = 20,
    RADIUS = canvas.width/2 - MARGIN,
    HAND_RADIUS = RADIUS + NUMERAL_SPACING;

// Functions.....

function drawCircle() {
    context.beginPath();
    context.arc(canvas.width/2, canvas.height/2,
        RADIUS, 0, Math.PI*2, true);
    context.stroke();
}

function drawNumerals() {
    var numerals = [ 1, 2, 3, 4, 5, 6, 7, 8, 9, 10, 11, 12 ],
        angle = 0,
        numeralWidth = 0;

    numerals.forEach(function(numeral) {
        angle = Math.PI/6 * (numeral-3);
        numeralWidth = context.measureText(numeral).width;
        context.fillText(numeral,
            canvas.width/2 + Math.cos(angle)*(HAND_RADIUS) -
            numeralWidth/2,
            canvas.height/2 + Math.sin(angle)*(HAND_RADIUS) +
            FONT_HEIGHT/3);
    });
}
```

```

function drawCenter() {
    context.beginPath();
    context.arc(canvas.width/2, canvas.height/2, 5, 0, Math.PI*2, true);
    context.fill();
}

function drawHand(loc, isHour) {
    var angle = (Math.PI*2) * (loc/60) - Math.PI/2,
        handRadius = isHour ? RADIUS - HAND_TRUNCATION-HOUR_HAND_TRUNCATION
            : RADIUS - HAND_TRUNCATION;

    context.moveTo(canvas.width/2, canvas.height/2);
    context.lineTo(canvas.width/2 + Math.cos(angle)*handRadius,
        canvas.height/2 + Math.sin(angle)*handRadius);
    context.stroke();
}

function drawHands() {
    var date = new Date,
        hour = date.getHours();

    hour = hour > 12 ? hour - 12 : hour;

    drawHand(hour*5 + (date.getMinutes()/60)*5, true, 0.5);
    drawHand(date.getMinutes(), false, 0.5);
    drawHand(date.getSeconds(), false, 0.2);
}

function drawClock() {
    context.clearRect(0,0,canvas.width,canvas.height);

    drawCircle();
    drawCenter();
    drawHands();
    drawNumerals();
}

// Initialization.....

context.font = FONT_HEIGHT + 'px Arial';
loop = setInterval(drawClock, 1000);

```



NOTE: A closer look at paths, stroking, and filling

The clock example in this section gives you an overview of what it's like to draw into a canvas. In Chapter 2, we will take a closer look at drawing and manipulating shapes in a canvas.

1.6 Event Handling

HTML5 applications are event driven. You register event listeners with HTML elements and implement code that responds to those events. Nearly all Canvas-based applications handle either mouse or touch events—or both—and many applications also handle various events such as keystrokes and drag and drop.

1.6.1 Mouse Events

Detecting mouse events in a canvas is simple enough: You add an event listener to the canvas, and the browser invokes that listener when the event occurs. For example, you can listen to mouse down events, like this:

```
canvas.onmousedown = function (e) {  
    // React to the mouse down event  
};
```

Alternatively, you can use the more generic `addEventListener()` method:

```
canvas.addEventListener('mousedown', function (e) {  
    // React to the mouse down event  
});
```

In addition to `onmousedown`, you can also assign functions to `onmousemove`, `onmouseup`, `onmouseover`, and `onmouseout`.

Assigning a function to `onmousedown`, `onmousemove`, etc., is a little simpler than using `addEventListener()`; however, `addEventListener()` is necessary when you need to attach multiple listeners to a single mouse event.

1.6.1.1 Translating Mouse Coordinates to Canvas Coordinates

The mouse coordinates in the event object that the browser passes to your event listener are *window* coordinates, instead of being relative to the canvas itself.

Most of the time you need to know where mouse events occur relative to the canvas, not the window, so you must convert the coordinates. For example, [Figure 1.14](#) shows a canvas that displays an image known as a sprite sheet. Sprite sheets are a single image that contains several images for an animation. As an animation progresses, you display one image at a time from the sprite sheet, which means that you must know the exact coordinates of each image in the sprite sheet.

The application shown in [Figure 1.14](#) lets you determine the location of each image in a sprite sheet by tracking and displaying mouse coordinates. As the user moves




Figure 1.14 Sprite sheet inspector

the mouse, the application continuously updates the mouse coordinates above the sprite sheet and the guidelines.

The application adds a mousemove listener to the canvas, and subsequently, when the browser invokes that listener, the application converts the mouse coordinates from the window to the canvas, with a `windowToCanvas()` method, like this:

```
function windowToCanvas(canvas, x, y) {
    var bbox = canvas.getBoundingClientRect();

    return { x: x - bbox.left * (canvas.width / bbox.width),
            y: y - bbox.top * (canvas.height / bbox.height)
    };
}

canvas.onmousemove = function (e) {
    var loc = windowToCanvas(canvas, e.clientX, e.clientY);

    drawBackground();
    drawSpritesheet();
    drawGuidelines(loc.x, loc.y);
    updateReadout(loc.x, loc.y);
};
...

```

The `windowToCanvas()` method shown above invokes the canvas's `getBoundingClientRect()` method to obtain the canvas's bounding box relative to the window. The `windowToCanvas()` method then returns an object with `x` and `y` properties that correspond to the mouse location in the canvas.

Notice that not only does `windowToCanvas()` subtract the left and top of the canvas's bounding box from the x and y window coordinates, it also scales those coordinates when the canvas element's size differs from the size of the drawing surface. See Section 1.1.1, "Canvas Element Size vs. Drawing Surface Size," on p. 5 for an explanation of canvas element size versus canvas drawing surface size.

The HTML for the application shown in [Figure 1.14](#) is listed in [Example 1.5](#), and the JavaScript is listed in [Example 1.6](#).

Example 1.5 A sprite sheet inspector: HTML

```
<!DOCTYPE html>
<head>
  <title>Sprite sheets</title>

  <style>
    body {
      background: #dddddd;
    }

    #canvas {
      position: absolute;
      left: 0px;
      top: 20px;
      margin: 20px;
      background: #ffffff;
      border: thin inset rgba(100,150,230,0.5);
      cursor: pointer;
    }

    #readout {
      margin-top: 10px;
      margin-left: 15px;
      color: blue;
    }
  </style>
</head>

<body>
  <div id='readout'></div>

  <canvas id='canvas' width='500' height='250'>
    Canvas not supported
  </canvas>

  <script src='example.js'></script>
</body>
</html>
```

Example 1.6 A sprite sheet inspector: JavaScript

```

var canvas = document.getElementById('canvas'),
    readout = document.getElementById('readout'),
    context = canvas.getContext('2d'),
    spritesheet = new Image();

// Functions.....

function windowToCanvas(canvas, x, y) {
    var bbox = canvas.getBoundingClientRect();
    return { x: x - bbox.left * (canvas.width / bbox.width),
            y: y - bbox.top * (canvas.height / bbox.height)
    };
}

function drawBackground() {
    var VERTICAL_LINE_SPACING = 12,
        i = context.canvas.height;

    context.clearRect(0,0,canvas.width,canvas.height);
    context.strokeStyle = 'lightgray';
    context.lineWidth = 0.5;

    while(i > VERTICAL_LINE_SPACING*4) {
        context.beginPath();
        context.moveTo(0, i);
        context.lineTo(context.canvas.width, i);
        context.stroke();
        i -= VERTICAL_LINE_SPACING;
    }
}

function drawSpritesheet() {
    context.drawImage(spritesheet, 0, 0);
}

function drawGuidelines(x, y) {
    context.strokeStyle = 'rgba(0,0,230,0.8)';
    context.lineWidth = 0.5;
    drawVerticalLine(x);
    drawHorizontalLine(y);
}

function updateReadout(x, y) {
    readout.innerHTML = '(' + x.toFixed(0) + ', ' + y.toFixed(0) + ')';
}

```

(Continues)

Example 1.6 (Continued)

```

function drawHorizontalLine (y) {
    context.beginPath();
    context.moveTo(0,y + 0.5);
    context.lineTo(context.canvas.width, y + 0.5);
    context.stroke();
}

function drawVerticalLine (x) {
    context.beginPath();
    context.moveTo(x + 0.5, 0);
    context.lineTo(x + 0.5, context.canvas.height);
    context.stroke();
}

// Event handlers.....

canvas.onmousemove = function (e) {
    var loc = windowToCanvas(canvas, e.clientX, e.clientY);

    drawBackground();
    drawSpritesheet();
    drawGuidelines(loc.x, loc.y);
    updateReadout(loc.x, loc.y);
};

// Initialization.....

spritesheet.src = 'running-sprite-sheet.png';
spritesheet.onload = function(e) {
    drawSpritesheet();
};

drawBackground();

```

**TIP: x and y vs. clientX and clientY**

In pre-HTML5 days, obtaining window coordinates for mouse events from the event object that the browser passes to your event listeners was a mess. Some browsers stored those coordinates in `x` and `y`, and others stored them in `clientX` and `clientY`. Fortunately, modern browsers that support HTML5 have finally come to agreement, and they all support `clientX` and `clientY`. You can read more about those event properties at http://www.quirksmode.org/js/events_mouse.html.

**TIP: Tell the browser to butt out . . .**

When you listen to mouse events, the browser invokes your listener when the associated event occurs. After you handle the event, the browser also reacts to the event. Much of the time when you handle mouse events in a canvas, you don't want the browser to handle the event after you're done with it because you will end up with unwanted effects, such as the browser selecting other HTML elements or changing the cursor.

Fortunately, the event object comes with a `preventDefault()` method that, as its name suggests, prevents the browser from carrying out its default reaction to the event. Just invoke that method from your event handler, and the browser will no longer interfere with your event handling.

**NOTE: The Canvas context's `drawImage()` method**

The example shown in [Figure 1.14](#) uses the 2d context's `drawImage()` method to draw the sprite sheet. That single method lets you copy all or part of an image stored in one place to another place, and if you wish, you can scale the image along the way.

The sprite sheet application uses `drawImage()` in the simplest possible way: The application draws all of an image, unscaled, that is stored in an `Image` object, into the application's canvas. In the Chapter 4 and throughout the rest of this book, you will see more advanced uses for `drawImage()`.

1.6.2 Keyboard Events

When you press a key in a browser window, the browser generates key events. Those events are targeted at the HTML element that currently has focus. If no element has focus, key events bubble up to the window and document objects.

The canvas element is not a focusable element, and therefore in light of the preceding paragraph, adding key listeners to a canvas is an exercise in futility. Instead, you will add key listeners to either the document or window objects to detect key events.

There are three types of key events:

- `keydown`
- `keypress`
- `keyup`

The keydown and keyup events are low-level events that the browser fires for nearly every keystroke. Note that some keystrokes, such as command sequences, may be *swallowed* by the browser or the operating system; however, most keystrokes make it through to your keydown and keyup event handlers, including keys such as Alt, Esc, and so on.

When a keydown event generates a printable character, the browser fires a keypress event before the inevitable keyup event. If you hold a key that generates a printable character down for an extended period of time, the browser will fire a sequence of keypress events between the keydown and keyup events.

Implementing key listeners is similar to implementing mouse listeners. You can assign a function to the document or window object's onkeydown, onkeyup, or onkeypress variables, or you can call `addEventListener()`, with keydown, keyup, or keypress for the first argument, and a reference to a function for the second argument.

Determining which key was pressed can be complicated, for two reasons. First, there is a huge variety of characters among all the languages of the world. When you must take into consideration the Latin alphabet, Asian ideographic characters, and the many languages of India, just to mention a few, supporting them all is mind boggling.

Second, although browsers and keyboards have been around for a long time, key codes have never been standardized until DOM Level 3, which few browsers currently support. In a word, detecting exactly what key or combination of keys has been pressed is a mess.

However, under most circumstances you can get by with the following two simple strategies:

- For keydown and keyup events, look at the `keyCode` property of the event object that the browser passes to your event listener. In general, for printable characters, those values will be ASCII codes. Notice the *in general* caveat, however. Here is a good website that you can consult for interpreting key codes among different browsers: <http://bit.ly/o3b1L2>. Event objects for key events also contain the following boolean properties:
 - `altKey`
 - `ctrlKey`
 - `metaKey`
 - `shiftKey`

- For keypress events—which browsers fire only for printable characters—you can reliably get that character like this:

```
var key = String.fromCharCode(event.which);
```

In general, unless you are implementing a text control in a canvas, you will handle mouse events much more often than you handle key events. One other common use case for key events, however, is handling keystrokes in games. We discuss that topic in Chapter 9.

1.6.3 Touch Events

With the advent of smart phones and tablet computers, the HTML specification has added support for touch events. See Chapter 11 for more information about handling touch events.

1.7 Saving and Restoring the Drawing Surface

In Section 1.2.2, “Saving and Restoring Canvas State,” on p. 11, you saw how to save and restore a context’s state. Saving and restoring context state lets you make temporary state changes, which is something you will do frequently.

Another essential feature of the Canvas context is the ability to save and restore the drawing surface itself. Saving and restoring the drawing surface lets you draw on the drawing surface temporarily, which is useful for many things, such as rubber bands, guidewires, or annotations. For example, the application shown in [Figure 1.15](#) and discussed in Section 2.13.1, “Translating, Scaling, and Rotating,” on p. 171, lets users interactively create polygons by dragging the mouse.




Figure 1.15 Drawing guidewires

On a mouse down event, the application saves the drawing surface. As the user subsequently drags the mouse, the application continuously restores the drawing surface to what it was when the mouse went down and then draws the polygon and the associated guidewires. When the user releases the mouse, the application restores the drawing surface one last time and draws a final representation of the polygon, without guidewires.

The JavaScript from the application shown in [Figure 1.15](#) that pertains to drawing the guidewires is listed in [Example 1.7](#). See Section 2.11.1, “Polygon Objects,” on p. 147 for a more complete listing of the application.



NOTE: Image manipulation with `getImageData()` and `putImageData()`

The application shown in [Figure 1.15](#) saves and restores the drawing surface with the context's `getImageData()` and `putImageData()` methods. Like `drawImage()`, `getImageData()` and `putImageData()` can be used in a number of different ways; one common use is implementing image filters that get an image's data, manipulate it, and put it back into a canvas. You will see how to implement image filters in Section 4.5.2.3, “Filtering Images,” on p. 293, among other uses for `getImageData()` and `putImageData()`.



NOTE: Immediate-mode graphics

Canvas implements what's known as *immediate-mode graphics*, meaning that it immediately draws whatever you specify in the canvas. Then it immediately forgets what you have just drawn, meaning that canvases do not retain a list of objects to draw. Some graphics systems, such as SVG, do maintain a list of objects to draw. Those graphics systems are referred to as retained-mode graphics.

Immediate-mode graphics, because it does not maintain a list of objects to draw, is more low-level than retained-mode graphics. Immediate-mode graphics is also more flexible because you draw straight to the screen instead of adjusting objects that the graphics system draws for you.

Immediate-mode graphics is more suited to applications, such as paint applications, that do not keep track of what the user has drawn, whereas retained-mode graphics is more suited to applications, such as drawing applications, that let you manipulate graphical objects that you create.

In Section 2.11.1, “Polygon Objects,” on p. 147 you will see how to implement a simple retained-mode graphics system that maintains an array of polygons in a drawing application, which lets users drag those polygons to reposition them.

Example 1.7 Drawing guidewires by saving and restoring the drawing surface

```
var canvas = document.getElementById('canvas'),
    context = canvas.getContext('2d'),
    ...

// Save and restore drawing surface.....

function saveDrawingSurface() {
    drawingSurfaceImageData = context.getImageData(0, 0,
                                                canvas.width,
                                                canvas.height);
}

function restoreDrawingSurface() {
    context.putImageData(drawingSurfaceImageData, 0, 0);
}

// Event handlers.....

canvas.onmousedown = function (e) {
    ...
    saveDrawingSurface();
    ...
};

canvas.onmousemove = function (e) {
    var loc = windowToCanvas(e);

    if (dragging) {
        restoreDrawingSurface();
        ...

        if (guidewires) {
            drawGuidewires(mousedown.x, mousedown.y);
        }
    }
};

canvas.onmouseup = function (e) {
    ...
    restoreDrawingSurface();
};
```

1.8 Using HTML Elements in a Canvas

Canvas is arguably the coolest feature of HTML5, but when you use it to implement web applications, you will rarely use it alone. Most of the time you will combine one or more canvases with other HTML controls so that your users can provide input or otherwise control the application.

To combine other HTML controls with your canvases, you may first be inclined to embed those controls inside your canvas elements, but that won't work, because anything you put in the body of a canvas element is displayed by the browser only if the browser does not support the canvas element.

Because browsers will display either a canvas element or HTML controls that you put inside that element, but not both, you must place your controls outside of your canvas elements.

To make it appear as though HTML controls are inside a canvas, you can use CSS to place the controls above the canvas. The application shown in [Figure 1.16](#) illustrates that effect.




Figure 1.16 HTML elements above a canvas

The application shown in [Figure 1.16](#) animates 100 balls and provides a link to start and stop the animation. That link resides in a DIV element that is partially transparent and floats above the canvas. We refer to that DIV as a *glass pane* because it appears to be a pane of glass floating above the canvas.

The HTML for the application shown in [Figure 1.16](#) is listed in [Example 1.8](#).

Example 1.8 HTML controls in a canvas: HTML

```
<!DOCTYPE html>
<html>
  <head>
    <title>Bouncing Balls</title>

  <style>
    body {
      background: #dddddd;
    }

    #canvas {
      margin-left: 10px;
      margin-top: 10px;
      background: #ffffff;
      border: thin solid #aaaaaa;
    }

    #glasspane {
      position: absolute;
      left: 50px;
      top: 50px;
      padding: 0px 20px 10px 10px;
      background: rgba(0, 0, 0, 0.3);
      border: thin solid rgba(0, 0, 0, 0.6);
      color: #eeeeee;
      font-family: Droid Sans, Arial, Helvetica, sans-serif;
      font-size: 12px;
      cursor: pointer;
      -webkit-box-shadow: rgba(0,0,0,0.5) 5px 5px 20px;
      -moz-box-shadow: rgba(0,0,0,0.5) 5px 5px 20px;
      box-shadow: rgba(0,0,0,0.5) 5px 5px 20px;
    }

    #glasspane h2 {
      font-weight: normal;
    }
  </style>
</html>
```

(Continues)

Example 1.8 (Continued)

```
#glasspane .title {
    font-size: 2em;
    color: rgba(255, 255, 0, 0.8);
}

#glasspane a:hover {
    color: yellow;
}

#glasspane a {
    text-decoration: none;
    color: #cccccc;
    font-size: 3.5em;
}

#glasspane p {
    margin: 10px;
    color: rgba(65, 65, 220, 1.0);
    font-size: 12pt;
    font-family: Palatino, Arial, Helvetica, sans-serif;
}
</style>
</head>

<body>
  <div id='glasspane'>
    <h2 class='title'>Bouncing Balls</h2>

    <p>One hundred balls bouncing</p>

    <a id='startButton'>Start</a>
  </div>

  <canvas id='canvas' width='750' height='500'>
    Canvas not supported
  </canvas>

  <script src='example.js'></script>
</body>
</html>
```

The HTML shown in [Example 1.8](#) uses CSS absolute positioning to make the glass pane appear above the canvas, like this:

```
#canvas {
  margin-left: 10px;
  margin-top: 10px;
  background: #ffffff;
  border: thin solid #aaaaaa;
}

#glasspane {
  position: absolute;
  left: 50px;
  top: 50px;
  ...
}
```

The preceding CSS uses *relative* positioning for the canvas, which is the default for the `position` CSS property, whereas it specifies *absolute* positioning for the glass pane. The CSS specification states that elements with absolute positioning are drawn on top of elements with relative positioning, which is why the glass pane appears above the canvas in [Figure 1.16](#).

If you also change the canvas's positioning to absolute, then the canvas will appear on top of the glass pane, and you won't see the glass pane because the canvas's background is not transparent. In that case, the glass pane is underneath the canvas because the canvas element comes after the glass pane's DIV element. If you switch the order of those elements, then the glass pane will once again appear above the canvas.

So, you have two options to position the glass pane above the canvas: Use relative positioning for the canvas and absolute positioning for the glass pane; or use either relative or absolute positioning for both elements and declare the glass pane's DIV after the canvas element.

A third option is to use either relative or absolute positioning for both elements and manipulate their `z-index` CSS property. The browser draws elements with a higher `z-index` above elements with a lower `z-index`.

In addition to placing HTML controls where you want them to appear, you also need to obtain references to those elements in your JavaScript so that you can access and manipulate their values.

The application shown in [Figure 1.16](#) obtains references to the glass pane and the button that controls the animation and adds event handlers to them, like this:

```
var context = document.getElementById('canvas').getContext('2d'),
    startButton = document.getElementById('startButton'),
    glasspane = document.getElementById('glasspane'),
    paused = false,
    ...

startButton.onclick = function(e) {
    e.preventDefault();
    paused = ! paused;
    startButton.innerHTML = paused ? 'Start' : 'Stop';
};
...

glasspane.onmousedown = function(e) {
    e.preventDefault();
};
```

The preceding JavaScript adds an `onclick` handler to the button that starts or pauses the animation based on the current state of the application, and adds an `onmousedown` event handler to the glass pane to prevent the browser from its default reaction to that mouse click. The `onmousedown` handler prevents the browser from reacting to the event to avoid inadvertent selections.



NOTE: You can implement your own Canvas-based controls

The Canvas specification states that you should prefer built-in HTML controls rather than implementing controls from scratch with the Canvas API, which in general is good advice. Implementing controls from scratch with the Canvas API generally involves a good deal of work, and most of the time it's wise to avoid a good deal of work when there's an easier alternative.

However, in some circumstances it makes sense to implement Canvas-based controls. In Chapter 10, will see both motivations for implementing your own Canvas-based controls and ways to do so.



NOTE: Drawing a grid

The application discussed in this section draws a grid underneath the bouncing balls to emphasize that the floating DIV is indeed floating above the canvas.

In Chapter 2, we discuss how to draw a grid, but for now you can safely forge ahead without knowing grid drawing details.

1.8.1 Invisible HTML Elements

In the preceding section you saw how to combine static HTML controls with a canvas. In this section we explore a more advanced use of HTML controls that involves dynamically modifying the size of a DIV as the user drags the mouse.

Figure 1.17 shows an application that uses a technique known as rubberbanding to select a region of a canvas. That canvas initially displays an image, and when you select a region of that image, the application reacts by zooming into the region that you selected.




Figure 1.17 Implementing rubber bands with a DIV

First, let's take a look at the HTML for the application, which is listed in **Example 1.9**.

Example 1.9 Rubber band with a floating DIV

```
<!DOCTYPE html>
<html>
  <head>
    <title>Rubber bands with layered elements</title>

    <style>
      body {
        background: rgba(100, 145, 250, 0.3);
      }

      #canvas {
        margin-left: 20px;
        margin-right: 0;
        margin-bottom: 20px;
        border: thin solid #aaaaaa;
        cursor: crosshair;
        padding: 0;
      }

      #controls {
        margin: 20px 0px 20px 20px;
      }

      #rubberbandDiv {
        position: absolute;
        border: 3px solid blue;
        cursor: crosshair;
        display: none;
      }

    </style>
  </head>

  <body>
    <div id='controls'>
      <input type='button' id='resetButton' value='Reset' />
    </div>

    <div id='rubberbandDiv'></div>

    <canvas id='canvas' width='800' height='520'>
      Canvas not supported
    </canvas>

    <script src='example.js'></script>
  </body>
</html>
```

The HTML uses a DIV that contains a button. If you click that button, the application draws the entire image as it is displayed when the application starts.

The application uses a second DIV for the rubber band. That DIV is empty, and its CSS `display` attribute is set to `none`, which makes it initially invisible. When you start dragging the mouse, the application makes that second DIV visible, which shows the DIV's border. As you continue dragging the mouse, the application continuously resizes the DIV to produce the illusion of a rubber band, as shown in [Figure 1.17](#).

The JavaScript for the application shown in [Figure 1.17](#) is listed in [Example 1.10](#).

Example 1.10 Rubber bands with a DIV

```
var canvas = document.getElementById('canvas'),
    context = canvas.getContext('2d'),
    rubberbandDiv = document.getElementById('rubberbandDiv'),
    resetButton = document.getElementById('resetButton'),
    image = new Image(),
    mousedown = {},
    rubberbandRectangle = {},
    dragging = false;

// Functions.....

function rubberbandStart(x, y) {
    mousedown.x = x;
    mousedown.y = y;

    rubberbandRectangle.left = mousedown.x;
    rubberbandRectangle.top = mousedown.y;

    moveRubberbandDiv();
    showRubberbandDiv();

    dragging = true;
}

function rubberbandStretch(x, y) {
    rubberbandRectangle.left = x < mousedown.x ? x : mousedown.x;
    rubberbandRectangle.top = y < mousedown.y ? y : mousedown.y;

    rubberbandRectangle.width = Math.abs(x - mousedown.x),
    rubberbandRectangle.height = Math.abs(y - mousedown.y);

    moveRubberbandDiv();
    resizeRubberbandDiv();
}
```

(Continues)

Example 1.10 (Continued)

```
function rubberbandEnd() {
    var bbox = canvas.getBoundingClientRect();

    try {
        context.drawImage(canvas,
            rubberbandRectangle.left - bbox.left,
            rubberbandRectangle.top - bbox.top,
            rubberbandRectangle.width,
            rubberbandRectangle.height,
            0, 0, canvas.width, canvas.height);
    }
    catch (e) {
        // Suppress error message when mouse is released
        // outside the canvas
    }

    resetRubberbandRectangle();

    rubberbandDiv.style.width = 0;
    rubberbandDiv.style.height = 0;

    hideRubberbandDiv();

    dragging = false;
}

function moveRubberbandDiv() {
    rubberbandDiv.style.top = rubberbandRectangle.top + 'px';
    rubberbandDiv.style.left = rubberbandRectangle.left + 'px';
}

function resizeRubberbandDiv() {
    rubberbandDiv.style.width = rubberbandRectangle.width + 'px';
    rubberbandDiv.style.height = rubberbandRectangle.height + 'px';
}

function showRubberbandDiv() {
    rubberbandDiv.style.display = 'inline';
}

function hideRubberbandDiv() {
    rubberbandDiv.style.display = 'none';
}

function resetRubberbandRectangle() {
    rubberbandRectangle = { top: 0, left: 0, width: 0, height: 0 };
}
```

```
// Event handlers.....

canvas.onmousedown = function (e) {
    var x = e.clientX,
        y = e.clientY;

    e.preventDefault();
    rubberbandStart(x, y);
};

window.onmousemove = function (e) {
    var x = e.clientX,
        y = e.clientY;

    e.preventDefault();
    if (dragging) {
        rubberbandStretch(x, y);
    }
};

window.onmouseup = function (e) {
    e.preventDefault();
    rubberbandEnd();
};

image.onload = function () {
    context.drawImage(image, 0, 0, canvas.width, canvas.height);
};

resetButton.onclick = function(e) {
    context.clearRect(0, 0, context.canvas.width,
                     context.canvas.height);
    context.drawImage(image, 0, 0, canvas.width, canvas.height);
};

// Initialization.....

image.src = 'curved-road.png';
```

Again, we're getting ahead of ourselves a little bit by using the `drawImage()` method to both draw and zoom in on the image. In Section 4.1, "Drawing Images," on p. 254, we will look closely at that method, and we will also see an alternative way to implement rubber bands that involves manipulating the image's pixels to draw the rubber band itself.

For now, however, our focus is on the rubberband DIV and how the code manipulates that DIV as the user drags the mouse.

The `onmousedown` event handler for the canvas invokes the `rubberbandStart()` method, which moves the DIV's upper left-hand corner to the mouse down location and makes the DIV visible. Because the rubberband DIV's CSS `position` attribute is `absolute`, the coordinates for the DIV's upper left-hand corner must be specified in window coordinates, and not as coordinates relative to the canvas.

If the user is dragging the mouse, the `onmousemove` event handler invokes `rubberbandStretch()`, which moves and resizes the rubberband DIV.

When the user releases the mouse, the `onmouseup` event handler invokes `rubberbandEnd()`, which draws the scaled image and shrinks and hides the rubberband DIV.

Finally, notice that all three mouse event handlers invoke `preventDefault()` on the event object they are passed. As discussed in Section 1.6.1.1, "Translating Mouse Coordinates to Canvas Coordinates," on p. 26, that call prevents the browser from reacting to the mouse events. If you remove those calls to `preventDefault()`, the browser will try to select elements on the page, which produces undesired effects if the user drags the mouse outside of the canvas.

1.9 Printing a Canvas

It's often convenient to let users of your application access a canvas as an image. For example, if you implement a paint application, such as the one discussed in Chapter 2, users will expect to be able to print their paintings.

By default, although every canvas is a bitmap, it is not an HTML `img` element, and therefore users cannot, for example, right-click a canvas and save it to disk, nor can they drag a canvas to their desktop to print later on. The fact that a canvas is not an image is illustrated by the popup menu shown in [Figure 1.18](#).

Fortunately, the Canvas API provides a method—`toDataURL()`—that returns a reference to a data URL for a given canvas. You can subsequently set the `src` attribute of an `img` element equal to that data URL to create an image of your canvas.

In Section 1.5, "Fundamental Drawing Operations," on p. 22, you saw how to implement an analog clock with the Canvas API. [Figure 1.19](#) shows a modified version of that application that lets you take a snapshot of the clock and display it as an image, as described above. As you can see from [Figure 1.19](#), when you right-click on the ensuing image, you can save the image to disk, and because the clock image shown in the bottom screenshot is an `img` element, you can also drag the image to your desktop.




Figure 1.18 The right-click menu for a canvas

The application shown in [Figure 1.19](#) implements a common use case for printing a canvas: It provides a control—in this case, the Take snapshot button—that lets users take a snapshot of the canvas. The application displays that snapshot as an image, so users can right-click the image and save it to disk. Subsequently, when the user clicks the Return to Canvas button, the application replaces the image with the original canvas. Here’s a recipe for that use case:

In your HTML page:

- Add an invisible image to the page, and give the image an `id`, but no `src`.
- Use CSS to position and size the image to exactly overlap your canvas.
- Add a control to the page for taking a snapshot.

In your JavaScript:

- Get a reference to the invisible image.
- Get a reference to the snapshot control.
- When the user activates the control to take a snapshot:
 1. Invoke `toDataURL()` to get a data URL.
 2. Assign the data URL to the invisible image’s `src` attribute.
 3. Make the image visible and the canvas invisible.

- When the user activates the control to return to the Canvas:
 1. Make the canvas visible and the image invisible.
 2. Redraw the canvas as needed.

Let's see how to translate that recipe to code. [Example 1.11](#) lists the HTML for the application shown in [Figure 1.19](#), and [Example 1.12](#) lists the application's JavaScript.




Figure 1.19 Using `toDataURL()`

Example 1.11 Using `toDataURL()` to print a canvas: HTML

```
<!DOCTYPE html>
<head>
  <title>Clock</title>

  <style>
    body {
      background: #dddddd;
    }

    #canvas {
      position: absolute;
      left: 10px;
      top: 1.5em;
      margin: 20px;
      border: thin solid #aaaaaa;
    }

    #snapshotImageElement {
      position: absolute;
      left: 10px;
      top: 1.5em;
      margin: 20px;
      border: thin solid #aaaaaa;
    }
  </style>
</head>

<body>
  <div id='controls'>
    <input id='snapshotButton' type='button' value='Take snapshot' />
  </div>

  <img id='snapshotImageElement' />

  <canvas id='canvas' width='400' height='400'>
    Canvas not supported
  </canvas>

  <script src='example.js'></script>
</body>
</html>
```

Example 1.12 Using `toDataURL()` to print a canvas: JavaScript

```

var canvas = document.getElementById('canvas'),
    context = canvas.getContext('2d'),
    snapshotButton = document.getElementById('snapshotButton'),
    snapshotImageElement =
        document.getElementById('snapshotImageElement'),
    loop;

// Clock drawing functions are omitted from this listing
// in the interests of brevity. See Example 1.4 on p. 24
// for a complete listing of those methods.

// Event handlers.....

snapshotButton.onclick = function (e) {
    var dataUrl;

    if (snapshotButton.value === 'Take snapshot') {
        dataUrl = canvas.toDataURL();
        clearInterval(loop);
        snapshotImageElement.src = dataUrl;
        snapshotImageElement.style.display = 'inline';
        canvas.style.display = 'none';
        snapshotButton.value = 'Return to Canvas';
    }
    else {
        canvas.style.display = 'inline';
        snapshotImageElement.style.display = 'none';
        loop = setInterval(drawClock, 1000);
        snapshotButton.value = 'Take snapshot';
    }
};

// Initialization.....

context.font = FONT_HEIGHT + 'px Arial';
loop = setInterval(drawClock, 1000);

```

The application accesses the canvas and `img` elements and uses CSS absolute positioning to overlap the two elements. When the user clicks the Take snapshot button, the application obtains a data URL from the canvas and assigns it to the `src` attribute of the image. Then it shows the image, hides the canvas, and sets the text of the button to Return to Canvas.

When the user clicks the Return to Canvas button, the application hides the image, displays the canvas, and returns the text of the button to Take snapshot.

**NOTE: Canvas blobs**

As this book was being written, the Canvas specification added a `toBlob()` method, so you can, among other things, save a canvas as a file. When the book went to press, no browsers supported that method.

1.10 Offscreen Canvases

Another essential Canvas feature is the ability to create and manipulate offscreen canvases. For example, you can, in most cases, considerably boost your performance by storing backgrounds in one or more offscreen canvases and copying parts of those offscreen canvases onscreen.

Another use case for offscreen canvases is the clock that we discussed in the preceding section. Although that application shows you how to implement a general solution that requires user interaction to switch from canvas to image, a clock is a better candidate for an application that does that switching behind the scenes without user intervention.

An updated version of the clock application is shown in [Figure 1.20](#). Once a second, the application draws the clock into the offscreen canvas and assigns the




Figure 1.20 Using an offscreen canvas for an image clock

canvas's data URL to the `src` attribute of an image. The result is an animated image that reflects the offscreen canvas. See Section 1.9, "Printing a Canvas," on p. 46 for more information on canvas data URLs.

The HTML for the application shown in [Figure 1.20](#) is listed in [Example 1.13](#).

Example 1.13 An image clock: HTML

```
<!DOCTYPE html>
<head>
  <title>Image Clock</title>

  <style>
    body {
      background: #dddddd;
    }

    #canvas {
      display: none;
    }

    #snapshotImageElement {
      position: absolute;
      left: 10px;
      margin: 20px;
      border: thin solid #aaaaaa;
    }
  </style>
</head>

<body>
  <img id='snapshotImageElement' />

  <canvas id='canvas' width='400' height='400'>
    Canvas not supported
  </canvas>

  <script src='example.js'></script>
</body>
</html>
```

Notice the CSS for the canvas in the HTML—the canvas is invisible because its `display` attribute is set to `none`. That invisibility makes it an *offscreen* canvas. You can also programmatically create an offscreen canvas, like this: `var offscreen = document.createElement('canvas');`

The JavaScript pertinent to the offscreen canvas for the application shown in [Figure 1.20](#) is listed in [Example 1.14](#).

Example 1.14 The image clock: JavaScript (excerpt)

```
// Some declarations and functions omitted for brevity.
// See Section 1.9 on p. 46 for a complete listing of
// the clock.

var canvas = document.getElementById('canvas'),
    context = canvas.getContext('2d'),
    ...

// Functions.....

function updateClockImage() {
    snapshotImageElement.src = canvas.toDataURL();
}

function drawClock() {
    context.clearRect(0, 0, canvas.width, canvas.height);

    context.save();

    context.fillStyle = 'rgba(255,255,255,0.8)';
    context.fillRect(0, 0, canvas.width, canvas.height);

    drawCircle();
    drawCenter();
    drawHands();

    context.restore();

    drawNumerals();

    updateClockImage();
}
...
```

1.11 A Brief Math Primer

To do anything interesting with Canvas, you need a good understanding of basic mathematics, especially working with algebraic equations, trigonometry, and vectors. It also helps, for more complex applications like video games, to be able to derive equations, given units of measure.

Feel free to skim this section if you're comfortable with basic algebra and trigonometry and you can make your way to pixels/frame given pixels/second and milliseconds/frame. Otherwise, spending time in this section will prove fruitful throughout the rest of this book.

Let's get started with solving algebraic equations and trigonometry, and then we'll look at vectors and deriving equations from units of measure.

1.11.1 Solving Algebraic Equations

For any algebraic equation, such as $(10x + 5) \times 2 = 110$, you can do the following, and the equation will still be true:

- Add any real number to both sides
- Subtract any real number from both sides
- Multiply any real number by both sides
- Divide both sides by any real number
- Multiply or divide one or both sides by 1

For example, for $(10x + 5) \times 2 = 110$, you can solve the equation by dividing both sides by 2, to get: $10x + 5 = 55$; then you can subtract 5 from both sides to get: $10x = 50$; and finally, you can solve for x by dividing both sides by 10: $x = 5$.

The last rule above may seem rather odd. Why would you want to multiply or divide one or both sides of an equation by 1? In Section 1.11.4, "Deriving Equations from Units of Measure," on p. 62, where we derive equations from units of measure, we will find a good use for that simple rule.

1.11.2 Trigonometry

Even the simplest uses of Canvas require a rudimentary understanding of trigonometry; for example, in the next chapter you will see how to draw polygons, which requires an understanding of sine and cosine. Let's begin with a short discussion of angles, followed by a look at right triangles.

1.11.2.1 Angles: Degrees and Radians

All the functions in the Canvas API that deal with angles require you to specify angles in radians. The same is true for the JavaScript functions `Math.sin()`, `Math.cos()`, and `Math.tan()`. Most people think of angles in terms of degrees, so you need to know how to convert from degrees to radians.

180 degrees is equal to π radians. To convert from degrees to radians, you can create an algebraic equation for that relationship, as shown in [Equation 1.1](#).

$$180 \text{ degrees} = \pi \text{ radians}$$

[Equation 1.1](#) Degrees and radians

Solving [Equation 1.1](#) for radians, and then degrees, results in [Equations 1.2](#) and [1.3](#).

$$\text{radians} = (\pi / 180) \times \text{degrees}$$

[Equation 1.2](#) Degrees to radians

$$\text{degrees} = (180 / \pi) \times \text{radians}$$

[Equation 1.3](#) Radians to degrees

π is roughly equal to 3.14, so, for example, 45 degrees is equal to $(3.14 / 180) \times 45$ radians, which works out to 0.7853.


1.11.2.2 Sine, Cosine, and Tangent

To make effective use of Canvas, you must have a basic understanding of sin, cos, and tan, so if you're not already familiar with [Figure 1.21](#), you should commit it to memory.

$$\cos(\theta) = \text{adjacent} / \text{hypotenuse}$$

$$\sin(\theta) = \text{opposite} / \text{hypotenuse}$$

$$\tan(\theta) = \text{opposite} / \text{adjacent}$$



[Figure 1.21](#) Sine, cosine, and tangent

You can also think of sine and cosine in terms of the X and Y coordinates of a circle, as illustrated in [Figure 1.22](#).

Given the radius of a circle and a counterclockwise angle from 0 degrees, you can calculate the corresponding X and Y coordinates on the circumference of the circle by multiplying the radius times the cosine of the angle, and multiplying the radius by the sine of the angle, respectively.




Figure 1.22 Radius, x, and y



NOTE: Soak a toe, ah!

One of many ways to remember how to derive sine, cosine, and tangent from a right triangle: SOHCAHTOA. SOH stands for sine, opposite, hypotenuse; CAH stands for cosine, adjacent, hypotenuse; and TOA is tangent, opposite, adjacent.

1.11.3 Vectors

The two-dimensional vectors that we use in this book encapsulate two values: direction and magnitude; they are used to express all sorts of physical characteristics, such as forces and motion.

In Chapter 8, “Collision Detection,” we make extensive use of vectors, so in this section we discuss the fundamentals of vector mathematics. If you’re not interested in implementing collision detection, you can safely skip this section.

Near the end of Chapter 8 we explore how to react to a collision between two polygons by bouncing one polygon off another, as illustrated in [Figure 1.23](#).

In [Figure 1.23](#), the top polygon is moving toward the bottom polygon, and the two polygons are about to collide. The top polygon’s incoming velocity and outgoing velocity are both modeled with vectors. The edge of the bottom




Figure 1.23 Using vectors to bounce one polygon off another

polygon with which the top polygon is about to collide is also modeled as a vector, known as an edge vector.

Feel free to skip ahead to Chapter 8 if you can't wait to find out how to calculate the outgoing velocity, given the incoming velocity and two points on the edge of the bottom polygon. If you're not familiar with basic vector math, however, you might want to read through this section before moving to Chapter 8.

1.11.3.1 Vector Magnitude

Although two-dimensional vectors model two quantities—magnitude and direction—it's often useful to calculate one or the other, given a vector. You can use the Pythagorean theorem, which you may recall from math class in school (or alternatively, from the movie *The Wizard of Oz*), to calculate a vector's magnitude, as illustrated in [Figure 1.24](#).

The Pythagorean theorem states that the hypotenuse of any right triangle is equal to the square root of the squares of the other two sides, which is a lot easier to understand if you look at [Figure 1.24](#). The corresponding JavaScript looks like this:

```
var vectorMagnitude = Math.sqrt(Math.pow(vector.x, 2) +  
                                Math.pow(vector.y, 2));
```

The preceding snippet of JavaScript shows how to calculate the magnitude of a vector referenced by a variable named `vector`.

Now that you know how to calculate a vector's magnitude, let's look at how you can calculate a vector's other quantity, direction.




Figure 1.24 Calculating a vector's magnitude

1.11.3.2 Unit Vectors

Vector math often requires what's known as a unit vector. Unit vectors, which indicate direction only, are illustrated in Figure 1.25.




Figure 1.25 A unit vector

Unit vectors are so named because their magnitude is always 1 unit. To calculate a unit vector given a vector with an arbitrary magnitude, you need to strip away the magnitude, leaving behind only the direction. Here's how you do that in JavaScript:

```
var vectorMagnitude = Math.sqrt(Math.pow(vector.x, 2) +
                                Math.pow(vector.y, 2)),
    unitVector = new Vector();

    unitVector.x = vector.x / vectorMagnitude;
    unitVector.y = vector.y / vectorMagnitude;
```

The preceding code listing, given a vector named `vector`, first calculates the magnitude of the vector as you saw in the preceding section. The code then creates a new vector—see Chapter 8 for a listing of a `Vector` object—and sets that unit

vector's X and Y values to the corresponding values of the original vector, divided by the vector's magnitude.

Now that you've seen how to calculate the two components of any two-dimensional vector, let's see how you combine vectors.

1.11.3.3 Adding and Subtracting Vectors

It's often useful to add or subtract vectors. For example, if you have two forces acting on a body, you can sum two vectors representing those forces together to calculate a single force. Likewise, subtracting one positional vector from another yields the edge between the two vectors.

Figure 1.26 shows how to add vectors, given two vectors named A and B.




Figure 1.26 Adding vectors

Adding vectors is simple: You just add the components of the vector together, as shown in the following code listing:

```
var vectorSum = new Vector();  
  
vectorSum.x = vectorOne.x + vectorTwo.x;  
vectorSum.y = vectorOne.y + vectorTwo.y;
```

Subtracting vectors is also simple: you subtract the components of the vector, as shown in the following code listing:

```
var vectorSubtraction = new Vector();

vectorSubtraction.x = vectorOne.x - vectorTwo.x;
vectorSubtraction.y = vectorOne.y - vectorTwo.y;
```

Figure 1.27 shows how subtracting one vector from another yields a third vector whose direction is coincident with the edge between the two vectors. In Figure 1.27, the vectors $A-B$ and $B-A$ are parallel to each other and are also parallel to the edge vector between vectors A and B .




Figure 1.27 Subtracting vectors

Now that you know how to add and subtract vectors and, more importantly, what it means to do that, let's take a look at one more vector quantity: the dot product.

1.11.3.4 The Dot Product of Two Vectors

To calculate the dot product of two vectors you multiply the components of each vector by each other, and sum the values. Here is how you calculate the dot product for two two-dimensional vectors:

```
var dotProduct = vectorOne.x * vectorTwo.x + vectorOne.y * vectorTwo.y;
```

Calculating the dot product between two vectors is easy; however, understanding what a dot product means is not so intuitive. First, notice that unlike the result of adding or subtracting two vectors, the dot product is not a vector—it's what engineers refer to as a *scalar*, which means that it's simply a number. To understand what that number means, study Figure 1.28.




Figure 1.28 A positive dot product

The dot product of the two vectors in Figure 1.28 is 528. The significance of that number, however, is not so much its magnitude but the fact that it's greater than zero. That means that the two vectors point in roughly the same direction.

Now look at Figure 1.29, where the dot product of the two vectors is -528 . Because that value is less than zero, we can surmise that the two vectors point in roughly different directions.




Figure 1.29 A negative dot product

The ability to determine whether or not two vectors point in roughly the same direction can be critical to how you react to collisions between objects. If a moving object collides with a stationary object and you want the moving object to bounce off the stationary object, you need to make sure that the moving object bounces *away* from the stationary object, and not toward the stationary object's center. Using the dot product of two vectors, you can do exactly that, as you'll see in Chapter 8.

That's pretty much all you need to know about vectors to implement collision detection, so let's move on to the last section in this brief math primer and see how to derive the equations from units of measure.

1.11.4 Deriving Equations from Units of Measure

As you will see in Chapter 5, motion in an animation should be time based, because the rate at which an object moves should not change with an animation's frame rate. Time-based motion is especially important for multiplayer games; after all, you don't want a game to progress more quickly for players with more powerful computers.

To implement time-based motion, we specify velocity in this book in terms of pixels per second. To calculate how many pixels to move an object for the current animation frame, therefore, we have two pieces of information: the object's velocity in *pixels per second*, and the current frame rate of the animation in *milliseconds per frame*. What we need to calculate is the number of *pixels per frame* to move any given object. To do that, we must derive an equation that has pixels per frame on the left side of the equation, and pixels per second (the object's velocity) and milliseconds per frame (the current frame rate) on the right of the equation, as shown in [Equation 1.4](#).

$$\frac{\text{pixels}}{\text{frame}} \neq \frac{X \text{ ms}}{\text{frame}} \times \frac{Y \text{ pixels}}{\text{second}}$$

[Equation 1.4](#) Deriving an equation for time-based motion, part I

In this *inequality*, X represents the animation's frame rate in milliseconds/frame, and Y is the object's velocity in pixels/second. As that inequality suggests, however, you cannot just multiply milliseconds/frame times pixels/second, because you end up with a nonsensical milliseconds-pixels/frame-seconds. So what do you do?

Recall the last rule we discussed in Section 1.11.1, "Solving Algebraic Equations," on p. 54 for solving algebraic equations: You can multiply or divide one or both sides of an equation by 1. Because of that rule, and because one second is equal

to 1000 ms, and therefore 1 second / 1000 ms is equal to 1, we can multiply the right side of the equation by that fraction, as shown in [Equation 1.5](#).

$$\frac{\text{pixels}}{\text{frame}} = \frac{X \text{ ms}}{\text{frame}} \times \frac{1 \text{ second}}{1000 \text{ ms}} \times \frac{Y \text{ pixels}}{\text{second}}$$

[Equation 1.5](#) Deriving an equation for time-based motion, part 2

And now we are ready to move in for the kill because when you multiply two fractions together, *a unit of measure in the numerator of one fraction cancels out the same unit of measure in the denominator of the other fraction*. In our case, we cancel units of measure as shown in [Equation 1.6](#).

$$\frac{\text{pixels}}{\text{frame}} = \frac{X \cancel{\text{ms}}}{\text{frame}} \times \frac{1 \cancel{\text{second}}}{1000 \cancel{\text{ms}}} \times \frac{Y \text{ pixels}}{\cancel{\text{second}}}$$

[Equation 1.6](#) Deriving an equation for time-based motion, part 3

Canceling those units of measure results in [Equation 1.7](#).

$$\frac{\text{pixels}}{\text{frame}} = \frac{X}{\text{frame}} \times \frac{Y \text{ pixels}}{1000}$$

[Equation 1.7](#) Deriving an equation for time-based motion, part 4

Carrying out the multiplication results in the simplified equation, shown in [Equation 1.8](#).

$$\frac{\text{pixels}}{\text{frame}} = \frac{X \times Y}{1000}$$

X = frame rate in ms/frame

Y = velocity in pixels/second

[Equation 1.8](#) Deriving an equation for time-based motion, part 5

Whenever you derive an equation, you should plug some simple numbers into your equation to see if the equation makes sense. In this case, if an object is moving at 100 pixels per second, and the frame rate is 500 ms per frame, you can easily figure out, without any equations at all, that the object should move 50 pixels in that 1/2 second.

Plugging those numbers into [Equation 1.8](#) results in $500 \times 100 / 1000$, which equals 50, so it appears that we have a valid equation for any velocity and any frame rate.

In general, to derive an equation from variables with known units of measure, follow these steps:

1. Start with an inequality, where the result is on the left, and the other variables are on the right.
2. Given the units of measure on both sides of the equation, multiply the right side of the equation by one or more fractions, each equal to 1, whose units of measure cancel out the units of measure on the right side of the equation to yield the units of measure on the left side of the equation.
3. Cancel out the units of measure on the right side of the equation.
4. Multiply the fractions on the right side of the equation.
5. Plug simple values whose result you can easily verify into the equation to make sure the equation yields the expected value.

1.12 Conclusion

This chapter introduced you to the canvas element and its associated 2d context, and illustrated some essential features of that context, such as the difference between canvas element size and the size of the canvas's drawing surface.

From there we had a quick overview of your development environment, including browsers, consoles and debuggers, and performance tools.

Then we looked at the essentials of using a canvas, including fundamental drawing operations, event handling, saving and restoring the drawing surface, using HTML elements with a canvas, printing canvases, and using offscreen canvases. You will see the use of those essential features many times throughout this book, and you will use them yourself as you write Canvas-based applications.

Finally, we ended this chapter with a brief math primer, which you can consult as needed as you read the rest of the book.

In the next chapter we take a deep-dive into drawing in a canvas. In that chapter you will learn about the Canvas drawing API, and you'll see how to put that API to good use by implementing most of the features of a capable paint application.

Index

Numbers

3d

- Canvas context, 11
 - simulating with parallax, 377–378
- 3D Monster Maze game, 359

A

acceleration. *See* ease in

- add() method (Vector), 501–502
- addChangeListener() method (Slider), 636, 642
- addCirclePath() function (cutouts example), 99–103
- addColorStop() method (CanvasGradient), 77–79
- addEventListener() method (window), 26, 32, 671
- addListener() method
 - of Game object, 544, 558–560, 598–601
 - of Keyboard object, 700
- addLine() method (Paragraph), 239, 242
- addOuterRectanglePath() function (cutouts example), 99–103
- addRectanglePath() function (cutouts example), 99–103
- addSprite() method (Game), 544
- addTrianglePath() function (cutouts example), 99–103
- Adobe Illustrator, 23
 - bézier curves in, 137
 - paths in, 89
- advance() method (SpriteSheetPainter), 407
- air resistance, 461
- algebraic equations, 54, 175–176
- Alt key, 32, 672
- altKey browser attribute, 32, 672
- Android
 - home screen icons on, 677
 - layout viewport on, 661
- angles, 54–55

- animate() function, 195, 332, 353–354, 360, 410
 - locking up browser with, 341
 - time parameter of, 348, 350
- animate() method (Game), 550–551
- animation frames
 - dropping, 368
 - ending, 544–546, 550
 - number of pixels to move objects for.
 - See* time-based motion
 - starting, 544–546, 550
- animation loop, 340–357, 416
 - implementing, 544
 - portable. *See* requestNextAnimationFrame()
 - sprite-based, 424
- animation timers, 389–390, 429
 - for warping time, 595
 - starting, 416
- animations, 14, 306–312, 339–391
 - allocating memory during, 390–391
 - best practices for, 390–391
 - callback for, 421–423
 - completion percentage of, 454
 - Flash-based, 339
 - linear vs. nonlinear, 423
 - performance of, 18–22, 366, 390–391, 404
 - period of, 421
 - separating updating and drawing in, 390
 - time-based, 345
 - timed, 385–390
 - warping, 473–482
- AnimationTimer object, 389–390, 450–456
 - getElapsedTime() method, 386, 389, 451, 454–455, 464, 475
 - isOver() method, 389–390
 - isRunning() method, 386
 - makeBounce() method, 457
 - makeEaseIn() method, 456–457
 - makeEaseInOut() method, 457

- AnimationTimer object (*cont.*)
 - makeEaseOut() method, 457
 - makeElastic() method, 457
 - makeLinear() method, 457
 - reset() method, 386
- Animator.js library, 394
- anti-aliasing, 107
- appendTo() method
 - for custom controls, 616–617
 - of Keyboard object, 700
 - of Slider object, 619, 624–625, 628
- Apple, 329–330
- Apple’s Cocoa graphics system, 23
 - bézier curves in, 137
 - paths in, 89
- apple-mobile-web-app-status-bar-style
 - metatag, 681
- apple-touch-icon-precomposed link, 678
- applications
 - desktop vs. mobile, 657–659, 671
 - fullscreen mode of, 677, 680–681
 - home screen icon of, 677–680
 - native, 677
 - splash screen of, 677–680
 - status bar of, 681–682
- applyFrictionAndGravity() method
 - (Pinball), 594–595
- arc() method (Canvas context), 22–23, 91–92, 95–103, 124–125, 130, 136, 361
 - optional argument of, 127
- arcs, 124–136
 - direction of, 99–100, 124, 127
 - drawing, 91–92
 - for text placement, 223–225
- arcTo() method (Canvas context), 127–130
- ArrayBuffer object, 291
- aspect-ratio media feature, 667
- audio. *See* sound
- auto-pause, 583–584
- axes, 495–525
 - direction of, 503
- B**
- background, 360–364
 - blitting from offscreen, 360–361, 363–364, 367, 390
 - canvas for, 574
 - clipping to damaged areas, 360–364, 390
 - color of, 3
 - erasing, 360–361, 364–367
 - painting, 546, 592
 - redrawing, 360–361
 - restoring, 71, 322
 - scrolling, 265, 370–377, 577–579
 - scrollBackground() function, 577–579
- Backspace key, 232, 237–241, 245–251
- backspace() method (Paragraph), 239–241, 245–251
- ballMover object, 593–594
 - execute() method, 594
- ballWillHitLedge() function (bounding areas example), 485
- beginPath() method (Canvas context), 12, 22–23, 91–94, 100, 103, 110, 125, 136, 361
- behaviors, 394–395, 411–417
 - combining, 412–415
 - execute() method, 394, 411–417, 431, 459, 473, 475, 594
 - timed, 416–417
- Bespin text editor, 252
- bézier curves, 137–143
 - cubic, 141–143
 - cursorInControlPoint() function, 162
 - cursorInEndPoint() function, 162
 - drawing, 158–159
 - editing, 158–169
 - for rounded corners, 138–139
 - quadratic, 137–141
- Bézier, Pierre, 137
- bezierCurveTo() method (Canvas context), 141–143
- bit-shifting, 317, 320
- blinkCursor() function (blinking cursor example), 230–231, 243
- blitting, 360–361, 363–364, 367, 390
- blushing (in animations), 450
- bomb exploding application, 417–423
- bounce() function (pinball game), 539, 604, 609
- bouncing, 459, 469, 471–472, 537–541
 - after collisions between objects, 606
 - and velocity, 609

- handleEdgeCollisions() function, 488–489
 - off stationary objects, 62, 488–489
- bounding areas, 483–488
 - accuracy of, 494
 - ballWithHitLedge() function, 485
 - circular, 485–488
 - rectangular, 484–485
- bounding volumes, 483
- brieflyShowTryAgainImage() method (Pinball), 592
- browsers, 13, 15–16
 - backfilling functionality into, 350
 - clamping in, 342, 583
 - composition operations in, 85, 186–187
 - custom controls in, 615
 - desktop, 660
 - domains in, 313
 - double buffering in, 366–367, 390–391
 - executing JavaScript in, 299–301, 340
 - fallback content for, 3
 - FileSystem API support in, 326
 - font string values in, 210
 - garbage collecting in, 391
 - ignoring content outside canvas in, 265
 - image loading in, 256
 - line height in, 208, 210
 - locking up with animate(), 341
 - maximum width of text in, 205
 - mobile, 659–666
 - no scrolling into view in, 169
 - px units in, 4
 - reacting to events in, 31, 111
 - scaling canvas in, 6–8
 - scrolling in, 675
 - setting frame rate in, 343–348
 - shadows in, 85
 - sound formats in, 557–558
 - SVG support in, 74
 - touch events in, 672
 - video formats in, 329–330
 - WebKit-based, 16–17, 19, 85
 - web-safe fonts in, 209
 - window coordinates in, 26, 30–31, 46, 111, 673
 - window focus of, 583
 - z-index of elements in, 39
- bucket game, 485–487, 490–494
 - isBallInBucket() method, 486–487, 493–494
- C**
- CAD (computer-aided design systems), 150
- call() method (Function), 551
- cancelRequestAnimationFrame() method (window), 344–345
- canPlay...() methods (Game), 557–558
- canPlaySound() method (Game), 544
- canvas element (HTML), 1–8
 - background color of, 3
 - dir attribute, 211
 - drawing:
 - into canvas, 253, 258, 266–270, 314–317, 325–326
 - into itself, 266, 270, 274, 316–317, 322, 324–325
 - outside boundaries of, 260–266, 370–377
 - erasing, 24
 - getContext() method, 4, 8
 - hardware acceleration for, 659
 - inappropriate uses of, 266
 - offscreen, 51–53, 266, 270–274, 302, 325–326, 628
 - and performance, 274
 - blitting from, 360–361, 363–364, 367, 390
 - created programmatically, 52
 - for double buffering, 365
 - invisibility of, 52
 - onscreen, 628
 - opacity of, 646, 650
 - playing video in, 331–333
 - printing, 46–51
 - saving, 51
 - scaling, 270–272, 316–317, 324–325
 - size of, 4–8, 28
 - changing, 646, 650, 668–670
 - default, 5–6, 67, 272
 - in CSS, 5–7
 - state of, 12
 - using HTML elements in, 36–46
 - width and height attributes, 7

- Canvas context, 9–11
 - arc() method, 22–23, 91–92, 95–103, 124–125, 127, 130, 136, 361
 - arcTo() method, 127–130
 - beginPath() method, 12, 22–23, 91–94, 100, 103, 110, 125, 136, 361
 - bezierCurveTo() method, 141–143
 - canvas attribute, 9
 - clearRect() method, 22, 24, 70–71, 188
 - clip() method, 87, 187–197, 302
 - closePath() method, 91–92, 511
 - createImageData() method, 254, 285–286
 - createLinearGradient() method, 76–79
 - createPattern() method, 80–83
 - createRadialGradient() method, 78–79
 - drawImage() method, 253–258, 266, 270, 276, 282, 312–315, 322–324, 328, 332, 407
 - extending, 10, 118–120, 129
 - fill() method, 23, 77, 91–92, 94–95, 148, 398
 - fillRect() method, 88
 - fillStyle attribute, 4, 9, 12, 72–75, 91–92, 136
 - fillText() method, 4, 9–10, 23, 88, 201, 210–211, 215, 222, 237, 266
 - font attribute, 9
 - getImageData() method, 12, 34, 228–230, 253, 274–301, 306, 309, 313, 317, 321–322
 - globalAlpha attribute, 9, 69, 75, 256, 282, 306–312
 - globalCompositeOperation attribute, 9, 12, 181–187, 282
 - lineCap attribute, 9, 121, 123
 - lineJoin attribute, 9, 70–72, 122–123
 - lineTo() method, 23–24, 99, 103–104, 110, 144
 - linewidth attribute, 9, 11, 71–72, 91, 103–104, 123
 - measureText() method, 201, 216–217, 227–228, 237
 - miterLimit attribute, 10, 72, 122–124
 - moveTo() method, 23–24, 99, 103–104, 110, 118–119, 125, 144
 - pointInPath() method, 151
 - putImageData() method, 34, 229, 253, 274–301, 314, 322
 - quadraticCurveTo() method, 138–141
 - rect() function, 91–94, 99–100, 361
 - restore() method, 11–12, 85, 136, 185, 194, 197
 - rotate() method, 172–175, 225
 - roundedRect() extension function, 128–129
 - save() method, 11–12, 85, 136, 185, 194, 197, 361
 - scale() method, 172–175
 - scrollPathIntoView() method, 169–170
 - setClip() method, 324–325
 - setTransform() method, 174–181
 - shadowBlur attribute, 10, 83–85, 88
 - shadowColor attribute, 10, 83–85, 88
 - shadowOffsetX and shadowOffsetY attributes, 10, 83–88
 - stroke() method, 23–24, 91–94, 103, 110, 148, 398, 603
 - strokeRect() method, 88, 170
 - strokeStyle attribute, 4, 10, 12, 72–75, 91–92, 136
 - strokeText() method, 4, 9–10, 88, 201–207, 210, 215, 237
 - textAlign attribute, 10, 136, 201–202, 210–215, 220–221
 - textBaseline attribute, 10, 136, 201–202, 210–215, 220–221
 - toBlob() method, 8, 51
 - toDataURL() method, 8, 46–51, 313
 - transform() method, 174–181
 - translate() method, 170–175, 225
- Canvas specification. *See HTML5 Canvas specification*
- CanvasGradient object, 77–79
 - addColorStop() method, 77–79
- CanvasPattern object, 81
- CanvasRenderingContext2D object. *See Canvas context*
- captureCanvasPixels() function (rubber bands example), 285
- captureRubberbandPixels() function (rubber bands example), 276, 280–281

- caret, 233, 239
- cell phones
 - performance of, 280
 - touch events in, 67
- changedTouches browser attribute, 672
- checkboxes, 137
- checkMTVAxisDirection() function
 - (pinball game), 608
- Chrome browser, 15
 - composition operations in, 186–187
 - cross-domain images in, 313
 - documentation for, 17
 - FileSystem API support in, 326
 - looping backwards in, 320
 - maximum width of text in, 205
 - requestAnimationFrame() in, 344, 346–348
 - time bug in, 348, 350
 - timelines in, 19
 - video formats in, 329
- circles, 124–136
 - axes for, 516
 - colliding with polygons, 516–521
 - drawing, 92
 - MTV for, 530
 - rubberband, 126–127
- circular text, 223–225
 - drawCircularText() function, 224
- clamping, 342
- clearHighScores() method (Game), 544, 560–561
- clearInterval() method (window), 231
- clearRect() method (Canvas context), 22, 24, 70–71, 188
- clearScreen() method (Game), 550
- clientX and clientY browser attributes, 30, 673
- clip() method (Canvas context), 87, 187–197, 302, 361
- clipping region, 187–197
 - and drawing images, 256, 302
 - applying filters with, 302
 - compositing shadows into, 69
 - default size of, 71, 187
 - draw() method, 362–363
 - drawDiscBackground() function, 363
 - erasing with, 187–194
 - for background areas, 360–364, 390
 - setting, 322, 324
 - telescoping with, 194–197
- clobbering, 121
- clock application, 22–25, 398–404
 - drawCenter() function, 23
 - drawCircle() function, 23
 - drawClock() function, 24
 - drawNumerals() function, 23
 - making snapshots of, 46–51
 - using offscreen canvases for, 51–53
- closePath() method (Canvas context), 91–92, 511
- collidesWith() method (Shape), 504–508, 518–520, 529–530, 532, 604
- collision detection, 56, 483–541, 546, 592, 601–614
 - a posteriori, 485–488, 601, 610
 - a priori, 485, 488
 - and clamping, 583
 - and velocity, 461
 - between ball and:
 - flippers, 604, 611–614
 - triangles, 609–611
 - detectCollisions() function, 512, 532
 - displacement vector for, 594
 - separation after, 488, 526–541, 609
 - techniques:
 - bounding areas, 483–485
 - circular bounding areas, 485–488
 - ray casting, 490–494
 - SAT, 495–541
- color media feature, 667
- color picker application, 631–643
- color wheel, 75
- color-index media feature, 667
- colors, 72–75
 - changing at edges, 296
 - CSS strings for, 74
 - inverting, 293
 - lookup table for, 667
 - names for, 74
- Command design pattern (sprites), 394, 412
- Commodore Amiga computer, 393

- compositing, 181–187
 - and shadows, 85
 - controversy of, 186–187
 - global vs. local, 187
 - operations for, 69, 181–187, 256
- console object, 16
 - log() method, 16
 - profile() function, 17
 - profileEnd() function, 17
- contentEditable attribute (HTML5), 252
- contexts, 8–12
 - 2d. *See* Canvas context
 - 3d, 11
- controls
 - checkboxes, 137
 - custom. *See* custom controls
 - input element, 252, 615
 - textarea element, 252
- coordinate system
 - canvas vs. window, 26, 30–31, 46, 111, 674–675
 - origin of, 67, 170
 - rotating, 171–173, 176
 - scaling, 173–176
 - transforming, 67–68, 170–181
 - translating, 26–31, 171–175, 222
 - windowToCanvas() function, 27–28, 111, 195, 674–675
- copyCanvasPixels() function (rubber bands example), 285–286
- COREHTML5 object, 615–616, 624, 689
- cos() method (Math), 54, 445–446
- cosine, 55–56, 445
- createCanvas() method
 - (RoundedRectangle), 617
- createDOMElement() method (custom controls), 617
- createDomePolygons() method (Pinball), 609–611
- createImageData() method (Canvas context), 254, 285–286
- createLinearGradient() method (Canvas context), 76–79
- createPath() method (Shape), 148, 172, 511
- createPattern() method (Canvas context), 80–83
- createPolygonPath() function (polygon example), 147
- createRadialGradient() method (Canvas context), 78–79
- CRTs (cathode ray tubes), 75
- CSS (Cascading Style Sheets)
 - absolute positioning in, 39, 46, 50
 - changing canvas size with, 668
 - color strings in, 74, 77, 88
 - font strings in, 207, 210
 - pixels in, 279–283, 295–299
 - selecting with media queries, 666–668
 - shadows in, 390
 - tweening in, 458
- Ctrl key, 237, 672
- ctrlKey browser attribute, 32, 672
- cursor, 225–231
 - blinkCursor() function, 230–231
 - blinking, 230–231
 - erasing, 228–230
 - moving, 242–243
 - positioning, 215–216, 232–237
- cursorInControlPoint() function (bézier curves example), 162
- cursorInEndPoint() function (bézier curves example), 162
- custom controls, 40, 615–655, 693–700
 - appending to HTML elements, 616–617
 - composite, 626
 - draw() method, 616
 - erase() method, 617
 - floating, 181
 - for text, 225–252
 - image panner, 643–655
 - positioning with CSS, 36
 - progress bars, 579, 625–630
 - rounded rectangles, 617–625
 - sliders, 631–643
 - virtual keyboard, 682–700
- Cut the Rope game, 427
- cutouts, 95–103, 136
 - addCirclePath() function, 99–103
 - addOuterRectanglePath() function, 99–103
 - addRectanglePath() function, 99–103
 - addTrianglePath() function, 99–103

- D**
- dashed lines, 10, 117–121
 - dashedLineTo() function, 118–120
 - drawDashedLine() function, 118
 - de Casteljau, Paul, 137
 - debuggers, 16
 - and double buffering, 366
 - deceleration. *See* ease out
 - degrees, 54–55
 - depth perception, 377
 - detectCollisions() function (collision detection), 512, 532, 592, 604
 - detectFlipperCollision() function (pinball game), 604, 611–614
 - device-aspect-ratio media feature, 667
 - device-height
 - content attribute (viewport), 665
 - media feature, 667
 - devices
 - grid-based, 668
 - mobile. *See* mobile devices
 - orientation of, 666–670
 - and layout viewport, 663–664
 - pixels in, 279–283, 295–299, 668
 - device-width
 - content attribute (viewport), 664–665
 - media feature, 667, 679–680
 - dials
 - annotating polygons with, 171
 - drawDial() function, 131
 - drawing, 130–136
 - labeling, 221–223
 - didThrow() function (user gestures example), 384
 - dir attribute (canvas), 211
 - dirty rectangles, 280–283
 - display context attribute, 52
 - DIV element (HTML), 37–46
 - document object
 - getElementById() method, 4, 13
 - DOM Level 3, 32
 - domElement browser property, 616–617
 - dot product, 60–62, 501, 608
 - dotProduct() method (Vector), 501–502
 - double buffering, 364–367, 390–391
 - Drag and Drop API, 326
 - drawArrow() function (mirroring example), 139, 173
 - drawCenter() function (clock application), 23
 - drawCircle() function (clock application), 23
 - drawCircularText() function (circular text example), 224–225
 - drawClock() function (clock application), 24
 - drawCollisionShapes() method (Game), 603
 - drawConnectors() function (sunglasses example), 302
 - drawDashedLine() function (dashed lines example), 118
 - drawDial() function (dials example), 131
 - drawDiscBackground() function (clipping animations example), 363
 - drawGrid() function (grid drawing example), 105–107
 - drawImage() method (Canvas context), 31, 45, 253–258, 266, 270, 312–315, 328
 - and global settings, 282
 - and origin-clean flag, 312
 - five-argument version of, 257–258, 332
 - nine-argument version of, 257–258, 276, 322–324, 407
 - drawing, 22–25, 65–199
 - immediate vs. retained, 34, 147
 - outside canvas boundaries, 260–266, 370–377
 - scaling context during development for, 173
 - separated from updating, 390
 - temporarily, 228
 - using rubber bands for, 65
 - drawing surface
 - saving/restoring, 12, 33–35, 115, 228
 - size of, 5–8, 28
 - default, 6–8
 - in CSS, 5–7
 - drawLenses() function (sunglasses example), 302
 - drawMagnifyingGlass() function (magnifying glass example), 322–324

- drawNumerals() function (clock application), 23
 - drawRubberbandShape() function (rubber bands example), 116, 126–127, 147–148
 - drawScaled() function (watermarks example), 272–274
 - drawText() function (text positioning example), 185, 212–214
 - drawWatermark() function (watermarks example), 266–270
 - drawWire() function (sunglasses example), 302
 - drifting clouds, 370–377
 - dropping frames, 368
- E**
- ease in, 451, 456–458, 463–465, 595
 - ease in/out, 458, 468–469
 - ease out, 458, 465–467, 595
 - edge detection, 296
 - edge() method (Vector), 502
 - elapsed time, 386, 433, 452
 - elastic motion, 469, 471
 - electromagnetic force, 428
 - em square, 211, 214
 - embossing filter, 295–299
 - emboss() function, 296–298
 - enablePrivilege() function (PrivilegeManager), 313
 - endAnimate() method (Game), 544–546, 550, 553, 590, 592
 - endless loops, 340
 - Enter key, 238, 241, 244–245
 - eraseMagnifyingGlass() function (magnifying glass example), 322
 - erasing
 - entire background, 360–361, 364–367
 - paragraphs, 244
 - text, 228–230, 239, 245–251
 - with clipping region, 187–194
 - Esc key, 32
 - event handlers, 26–33
 - onchange, 202, 619, 636, 650
 - onclick, 40, 353, 423, 627
 - onkeydown, 31–32, 241
 - onkeypress, 31–33, 237, 241
 - onkeyup, 31–32
 - onload, 256
 - onmessage, 301–302
 - onmousedown, 26, 40, 46, 111–115, 151, 195, 241
 - onmousemove, 26–27, 46, 115, 151, 162, 171, 185, 194, 280, 322, 642
 - onmouseout, 26
 - onmouseover, 26
 - onmouseup, 26, 46, 642
 - preventDefault() function, 31, 46, 111, 675
 - execute() method (behavior), 394, 411–417, 431, 459, 473, 475, 594
 - explorercanvas, 15–16
 - explosionAnimator sprite animator, 423
- F**
- fallback content, 3
 - falling, 427–431, 436
 - FileSystem API, 326–328
 - fill() method (Canvas context), 23, 77, 91–92, 94–95, 148, 398
 - fillColor context attribute, 226
 - filling, 88–103
 - and shadows, 84
 - text, 201–207
 - with gradients/patterns, 75, 205–207
 - fillKnob() method (Slider), 642
 - fillRect() method (Canvas context), 88
 - fillStyle context attribute, 4, 9, 12, 72–75, 91–92, 136
 - fillText() method (Canvas context), 4, 9–10, 23, 88, 201, 210–211, 215, 222, 237, 266
 - optional argument of, 204–205
 - filters, 293–295
 - black-and-white, 293–295
 - embossing, 295–299
 - negative, 293–294
 - sunglasses, 299–301
 - fireChangeEvent() method (Slider), 642
 - Firefox, 15
 - clamping in, 342
 - composition operations in, 186–187
 - console and debugger for, 16
 - cross-domain images in, 313
 - frame rate bug in, 346, 350

- looping backwards in, 320
 - maximum width of text in, 205
 - requestAnimationFrame() in, 344–346, 350
 - shadows in, 85
 - video formats in, 329–330
 - fireKeyEvent() method (Keyboard), 700
 - Flash, 328, 339
 - tweening in, 458
 - flippers (pinball game), 595–597
 - Flyweight design pattern (sprites), 394, 404
 - font context attribute, 4, 9, 201, 207–210, 226
 - font-family context attribute, 208–209
 - fonts
 - em square of, 211, 214
 - height of, 228
 - properties of, 207–210
 - web-safe, 209
 - font-size context attribute, 208
 - font-style context attribute, 207–208
 - font-variant context attribute, 207–208
 - font-weight context attribute, 207–208
 - fps() method (Game), 544
 - frame rate, 544
 - calculating, 358–359
 - clamping, 583
 - for tasks, 359–360
 - setting, 343–348, 544
 - updating, 546, 550
 - friction, 432, 461, 592, 594–595
 - fuseBurningAnimator sprite animator, 423
- G**
- Game object, 544–572
 - addKeyListener() method, 544, 558–560, 598–601
 - addSprite() method, 544
 - animate() method, 550–551
 - canPlay...() methods, 557–558
 - canPlaySound() method, 544
 - clearHighScore() method, 544, 560–561
 - clearScreen() method, 550
 - drawCollisionShapes() method, 603
 - endAnimate() method, 544–546, 550, 553, 590, 592
 - fps() method, 544
 - getHighScore() method, 544, 560–561
 - getImage() method, 554
 - getSprite() method, 544
 - loadImages() method, 554–557
 - paintOverSprites() and paintUnderSprites() methods, 544–546, 550, 576–577, 590–592
 - paintSprites() method, 550
 - pixelsPerFrame() method, 544, 553, 594
 - playSound() method, 544, 557–558
 - queueImage() method, 554–557
 - setHighScore() method, 544, 560–561
 - start() method, 544, 550–551
 - startAnimate() method, 544–546, 550, 553, 590–592, 594, 604
 - tick() method, 550
 - togglePaused() method, 544, 546, 551–553, 582, 600
 - updateFrameRate() method, 550
 - updateSprites() method, 550
 - game engine, 544–572
 - adding sprites to, 544
 - full listing of, 561–572
 - game loop, 544
 - Game Over toast, 585–589
 - game time, 544
 - setting, 544, 546
 - updating, 550
 - games, 543–614
 - 3D Monster Maze, 359
 - auto-pause in, 583–584
 - Bucket, 432–444, 485–487, 490–494
 - Cut the Rope, 427
 - heads-up display in, 433, 436–437, 585–589
 - multiplayer, 62, 367
 - naming, 545
 - Pac-Man, 495
 - pausing, 544–546, 551–553
 - performance of, 18–22, 404
 - Pinball, 589–614
 - Replica Island, 394
 - scoreboard in, 433, 436–437, 585–589
 - Sonic the Hedgehog, 427
 - starting, 550, 554
 - Ungame, 572–589

- Gaussian blur, 10, 88
 - getAxes() method (Shape), 504–511, 516
 - getBoundingClientRect() method (window), 27
 - getContext() method (Canvas), 4, 8
 - getElapsedTime() method (AnimationTimer), 386, 389, 451, 454–455, 464, 475
 - getElementById() method (document), 4, 13
 - getHeight() method
 - of TextCursor object, 226
 - of TextLine object, 233
 - getHighScores() method (Game), 544, 560–561
 - getImage() method (Game), 554
 - getImageData() method (Canvas context), 12, 34, 228–230, 253, 274–301, 306, 309, 322
 - and origin-clean flag, 313
 - calling repeatedly, 317, 321
 - slowness of, 280
 - getMagnitude() method (Vector), 501–502
 - getPoints() method (Polygon), 148
 - getPolygonPointClosestToCircle() function (polygon example), 519
 - getPolygonPoints() function (polygon example), 147
 - getSprite() method (Game), 544
 - getWidth() method (TextLine), 216, 233
 - glass pane, 37–40
 - globalAlpha context attribute, 9, 69, 75, 256
 - and putImageData(), 282
 - fading images with, 306–312
 - globalCompositeOperation context attribute, 9, 12, 181–187
 - and putImageData(), 282
 - Google, 16, 328–329
 - Google Chrome Frame, 15–16
 - GPS positioning, 659
 - gradients, 76–79
 - and performance, 391
 - color stops in, 77–79
 - for stroke or fill, 75, 205–207
 - linear, 76–78, 205
 - radial, 78–79
 - graph axes
 - drawing, 107–110
 - labeling, 217–220
 - gravity, 427–450, 592, 594–595
 - and nonlinear systems, 445–450
 - applied to vertical velocity, 433
 - constant of, 428, 431
 - grid, 11
 - drawGrid() function, 105–107
 - drawing, 40, 105–107
 - grid media feature, 668
 - guidewires
 - annotating polygons with, 171
 - drawing, 433
 - temporary drawing surface for, 33–35
 - turning on/off, 162
 - gyroscopes, 659
- ## H
- H.264 video format, 329
 - handleEdgeCollisions() function (bouncing off walls example), 488–489
 - hardware acceleration, 659
 - heads-up display, 433, 436–437, 585–589
 - height
 - content attribute (viewport), 665
 - context attribute, 4–8
 - media feature, 667
 - hideKeyboard() function (keyboard example), 689
 - high scores, 436–437, 545, 560–561, 585–589
 - HSL (hue/saturation/lightness), 74–75
 - hsl() color definition (CSS), 74
 - HSLA (hue/saturation/lightness/alpha), 74
 - hsla() color definition (CSS), 74
 - HTML elements
 - appending custom controls to, 616–617
 - canvas. *See* canvas element
 - DIV, 37–46
 - img, 8, 46, 50
 - input, 252, 615
 - invisible, 41–46
 - meta, 661–666, 681
 - output, 266
 - source, 329
 - span, 279

- standard controls in, 615
 - textarea, 252
 - using in canvas, 36–46
 - video, 329, 331–333
 - HTML5 Canvas* specification, 14
 - best practices of, 252
 - constantly evolving, 121
 - drawing unloaded images in, 256
 - glyph rendering in, 237
 - immediate-mode graphics of, 34, 147
 - no explicit support for animation in, 339
 - rectangles with zero width or height in, 276
 - text width in, 217
 - uses for canvas element in, 266
 - vs. native applications, 659, 677
 - HTML5 video and audio* specification, 14
 - HTMLCanvasElement object, 258
 - HTMLImageElement object, 258
 - HTMLVideoElement object, 258, 329
- I**
- icons
 - floating, 181
 - selected, 83
 - identifiedTouch() method (TouchList), 672
 - identifier browser attribute, 673
 - image data
 - accessing, 274–283
 - arrays of, 286–291, 295
 - blank, 254
 - looping over, 292, 317–320
 - modifying, 283–285, 301–302
 - partial rendering, 280–283
 - updating, 276
 - image painters, 398, 404–406, 594
 - image loading policy of, 406
 - image panner application, 643–655
 - ImageData object, 254, 280–283
 - creating, 285–286
 - ImagePainter object
 - draw() method, 406
 - images, 253–327
 - animating, 306–312
 - centering, 260–266
 - clipping, 302–306
 - colliding, 521–525
 - cross-domain, 312–313
 - dragging from desktop, 326–328
 - drawing, 69, 253–258, 314–317
 - fading, 306–312
 - filtering, 293–295, 306–312
 - loading, 255–256, 406, 554–557, 579–581
 - failed, 554
 - manipulating, 274–301
 - and performance, 298–301
 - scaling, 258–265, 316–317
 - security risks of, 312–313
 - startup. *See* applications, splash screens of
 - zooming into, 41–46
 - img element (HTML), 8, 46, 50
 - initial-scale content attribute (viewport), 665–666
 - input element (HTML), 252, 615
 - insert() method
 - of Paragraph object, 239, 241, 243–244
 - of TextLine object, 233
 - Internet Explorer
 - console and debugger for, 16
 - HTML5 support in, 15
 - maximum width of text in, 205
 - older versions of, 15–16
 - requestAnimationFrame() in, 344, 348
 - video formats in, 329
 - WebGL support in, 11
 - invisible ink, 92
 - iOS4, no WebGL support in, 11
 - iOS5, 677–682
 - fullscreen mode on, 677, 680–681
 - hardware acceleration for Canvas in, 659
 - home screen icons on, 677–680
 - splash screens on, 677–680
 - status bars on, 681–682
 - title bar on, 657
 - iPad
 - device orientation on, 667–670
 - home screen icons on, 680–681
 - layout viewport on, 661–663, 666
 - looping backwards on, 320
 - title bar on, 657
 - virtual keyboard on, 682–700

iPhone, 663
 isBallInBucket() method (bucket game),
 486–487, 493–494
 isOver() method (AnimationTimer),
 389–390
 isPointInside() method (Paragraph), 238
 isRunning() method (AnimationTimer),
 386

J

JavaScript
 benchmarks in, 20–22
 call() method, 551
 changing canvas size with, 668–670
 executed on main thread, 299–301, 340
 key codes in, 560
 loops in:
 backward, 317, 320
 endless, 340
 opaque objects in, 81
 self variable, 551
 self-executing functions in, 349
 this variable, 550–551
 JPEG image format, 8
 JSON (JavaScript Object Notation), 560
 jsPerf, 19–22, 317–319

K

Key object, 689–692
 key codes, 32
 key events, 31–33, 237, 544, 558–560,
 597–601
 firing, 700
 keydown, 31–32, 241
 keypress, 31–33, 237, 241
 keyup, 31–32
 throttling, 600
 key listeners, 234–237, 584, 598–601
 adding, 558–560, 700
 Keyboard object, 689, 693–700
 addKeyListener() method, 700
 appendTo() method, 700
 draw() method, 690, 700
 fireKeyEvent() method, 700
 mouseDownOrTouchStart() method, 700
 resize() method, 700
 keyboard, virtual. *See* virtual keyboard

keyCode browser property, 32
 Khronos Group, 11

L

length property (TouchList), 672–673
 lighting effect, 642
 lineCap context attribute, 9, 121, 123
 line-height context attribute, 208, 210
 lineJoin context attribute, 9, 70–72,
 122–123
 lines, 103–123
 dashed, 10, 117–121
 endpoints of, 9, 121
 joins of, 122–124
 width of, 9, 11, 104–105
 lineTo() method (Canvas context), 23–24,
 99, 103–104, 110, 144
 lineWidth context attribute, 9, 11, 71–72,
 91, 103–104, 123
 loadImages() method (Game), 554–557
 lob behavior, 433
 local storage, 545, 560–561
 local variables, 317–320
 log() method (console), 16

M

Mac OS X, 657
 magnifying glass application, 253–254,
 321–328
 drag and drop in, 326–328
 drawMagnifyingGlass() function,
 322–324
 eraseMagnifyingGlass() function, 322
 home screen icon of, 678
 orientation of, 668–670
 pinch and zoom in, 675–677
 splash screen of, 679
 throwing in, 383–385
 using offscreen canvas in, 270, 325–326
 makeBounce() method (AnimationTimer),
 457
 makeEaseIn() method (AnimationTimer),
 456–457
 makeEaseInOut() method
 (AnimationTimer), 457
 makeEaseOut() method (AnimationTimer),
 457

- makeElastic() method (AnimationTimer), 457
- makeLinear() method (AnimationTimer), 457
- matchMedia() method (window), 669
- Math object
 - cos() function, 54, 445–446
 - sin() function, 54, 446
 - tan() function, 54
- mathematics, 53–64
 - algebraic equations, 54, 175–176
 - angles, degrees, radians, 54–55
 - Pythagorean theorem, 57, 487
 - scalars, 60
 - trigonometry, 54–56, 145, 176, 221–223, 445, 468
 - vectors, 56–62
- max-device-width. *See* device-width
- maximum-scale content attribute (viewport), 665–666
- measureText() method (Canvas context), 201, 216–217, 227–228, 237
- media features, 667–668
- media queries, 666–670
 - changing canvas size with, 668
 - for icons and splash screens, 679–680
- @media CSS annotation, 666–668
- meta element (HTML), 661–666, 681
- Meta key, 237, 672
- metaKey browser attribute, 32, 672
- metaprogramming, 121
- min-device-width. *See* device-width
- minimum-scale content attribute (viewport), 665
- minimumTranslationVector() method (Shape), 527–529
- mirroring, 173
 - drawArrow() function, 139, 173
- miterLimit context attribute, 10, 72, 122–124
- mobile devices, 657–701
 - battery life of, 583
 - performance of, 18–22
 - pinch and zoom in, 675–677
 - scrolling into view in, 170
 - touch events in, 67
- monitors, 668
 - refresh rate of, 367
- monkey patching, 121
- monochrome media feature, 668
- motion
 - bouncing, 459, 469, 471–472
 - ease in, 451, 456–458, 463–465, 595
 - ease in/out, 458, 468–469
 - ease out, 458, 465–467, 595
 - elastic, 459, 469, 471
 - harmonic, 427
 - linear, 453, 458, 461–463
 - nonlinear, 427, 445, 458–473, 595–597
 - running in place, 411–417
 - time-based, 62–64, 350, 358–359, 367–370, 390–391, 416–417
 - warping, 458–473
- mouse events, 26–31, 671
 - mousedown, 26, 40, 46, 111–115, 151, 195, 241, 642, 694
 - mousemove, 26–27, 46, 115, 151, 162, 171, 185, 194, 280, 322, 642
 - mouseout, 26
 - mouseover, 26
 - mouseup, 26, 46, 642
 - supporting together with touch events, 674–675, 684, 694
 - translating to canvas coordinates, 26, 30–31, 46, 111, 195, 674–675
- mouseDownOrTouchStart() method (Keyboard), 700
- move() method (Shape), 148, 150
- moveCursor() method
 - of Paragraph object, 242–243
 - of TextCursor object, 228
- moveCursorCloseTo() method (Paragraph), 238, 241, 243
- moveTo() method (Canvas context), 23–24, 99, 103–104, 110, 125, 144
 - position last passed to, 118–119
- Mozilla, 329
- mozkitRequestAnimationFrame() method (window), 344–346, 350
- MPEG-4 video format, 329
- msCancelAnimationFrame() method (window), 344, 348

- msRequestAnimationFrame() method (window), 344, 348
- MTV (minimum translation vector), 526–541
 - sticking with, 531–537
- N**
- namespaces, 616, 689
- native applications, 659
- newline() method (Paragraph), 239–241, 244–245
- Newtonian mechanics, 461
- nextVideoFrame() function (video processing example), 333
- Nokia, 329–330
- nonlinear systems, 445–473
- nonzero winding rule, 94–95
- normal() method (Vector), 502–503
- normalize() method (Vector), 502
- nuclear force, 428
- O**
- Ogg Theora video format, 329–330
- onkeydown() method (window), 241
- onkeypress() method (window), 237, 241
- onmousedown() method (window), 241
- ontouchstart browser property, 671
- OpenGL ES 2.0 API, 11
- Opera, 15
 - arc() method in, 127
 - composition operations in, 186–187
 - console and debugger for, 16
 - shadows in, 85
 - video formats in, 329
- orientation media feature, 667, 679–680
- origin-clean flag (Canvas), 312–313
- output element (HTML), 266
- P**
- Pac-Man game, 495
- pageX and pageY browser attributes, 673
- paint application, 65–67
 - eraser in, 86
 - hideKeyboard() function, 689
 - home screen icon of, 678
 - icons in, 83, 179–181
 - rubber bands in, 110–116
 - showKeyboard() function, 689
 - virtual keyboard for, 682–700
- paint() method (Sprite), 394–398, 404
- paintOverSprites() method (Game), 544–546, 550, 576–577, 590
- paintSprites() method (Game), 550
- paintUnderSprites() method (Game), 544–546, 550, 576–577, 590–592
- Paragraph object, 238–252
 - addLine() method, 239, 242
 - backspace() method, 239–241, 245–251
 - insert() method, 239, 241, 243–244
 - isPointInside() method, 238
 - moveCursor() method, 242–243
 - moveCursorCloseTo() method, 238, 241, 243
 - newline() method, 239–241, 244–245
- paragraphs, 238–252
 - creating, 242
 - erasing, 244
 - inserting text into, 243–244
- parallax, 377–382, 579
 - draw() method, 379
- patent issues, 329–330
- paths, 88–103
 - arc, 89
 - circular, 23
 - closed, 89, 91–92, 511
 - current, 93, 256
 - direction of, 92, 99–100
 - drawing, 91
 - filling, 84, 94–95
 - manipulating, 150–170
 - open, 89, 91–92
 - rectangular, 89
 - resetting, 12
 - scrolling into view, 169–170
 - self-intersecting, 94–95
 - stroking, 10, 84
 - subpaths of, 92–94
- patterns, 79–83
 - creating, 81
 - for stroke or fill, 75, 205–207
 - repeating, 80–83
- Paused toast, 600

- pendulums, 427
 - nonlinear motion of, 445–450
 - weight of, 445
- percentComplete browser property, 628
- performance, 18–22, 313–321, 390–391
 - and double buffering, 366
 - and getImageData(), 280
 - and gradients, 391
 - and image manipulations, 298–301
 - and number of objects, 404
 - and offscreen canvases, 274
 - and shadows, 88, 390–391
 - bottlenecks of, 20–22
 - for drawing canvas into itself vs. from offscreen canvas, 326
 - monitoring, 390–391
- perpendicular() method (Vector), 502–503
- physics, 427–482
- pinball game, 589–614
 - bounce() function, 609
 - collision detection for, 601–614
 - detectCollisions() function, 592, 604
 - flipper motion in, 595–597
 - game loop of, 590–593
 - key events for, 597–601
 - pausing, 600
 - separate() function, 609
 - See also* game engine
- Pinball object
 - applyFrictionAndGravity() method, 594–595
 - bounce() function, 604
 - brieflyShowTryAgainImage() method, 592
 - checkMTVAxisDirection() function, 608
 - createDomePolygons() method, 609–611
 - detectFlipperCollision() function, 604, 611–614
 - updateLeftFlipper() method, 592
 - updateRightFlipper() method, 592
- pinch and zoom, 675–677
- pixels
 - boundaries of, 104–105
 - capturing, 280–283
 - clearing, 71
 - CSS vs. device, 279–283, 295–299
 - density of, 668
 - edge detection for, 296
 - looping over, 317, 320
 - manipulating, 253, 274–301
 - modifying transparency of, 283–285
 - scaling, 325
 - to move, per animation frame. *See* time-based motion
- pixelsPerFrame() method (Game), 544, 553, 594
- playSound() method (Game), 544, 557–558
- pointInPath() method (Canvas context), 151
- polyfill method. *See* requestNextAnimationFrame()
- Polygon object, 147–150
 - arrays of, 151–157
 - createPath() method, 511
 - getPoints() method, 148
 - move() method, 150
- polygons, 144–150
 - closed paths for, 511
 - colliding, 601–609
 - polygonCollidesWithCircle() function, 519
 - polygonsCollide() function, 500
 - with circles, 516–521
 - with polygons, 56, 495, 500, 504–516, 526
 - concave vs. convex, 495
 - createPolygonPath() function, 147
 - dragging, 34, 151–157
 - drawing, 33–35, 144–147
 - getPolygonPoints() function, 147
 - manipulating, 147–150
 - rotating, 151, 171–172
- polymorphism, 350
- Porter-Duff operators, 181
- power curves, 464–465, 467
- preventDefault() function (Event), 31, 46, 111, 675
- PrivilegeManager object
 - enablePrivilege() function, 313
- profile() function (console), 17
- profileEnd() function (console), 17

- profilers, 20–22, 390–391
 - starting/stopping, 17
 - progress bars, 579, 625–630
 - Progressbar object
 - draw() method, 628
 - projectile trajectories, 427, 432–444
 - applying gravity to, 433
 - vs. falling, 436
 - Projection object
 - project() function, 504–511
 - prototype() method, 504
 - projections, 495–525
 - overlapping, 503–504, 527
 - separation on, 527
 - putImageData() method (Canvas context), 34, 229, 253, 274–301, 314, 322
 - and global settings, 282
 - seven-argument version of, 280–283
 - putSunglassesOn() function (sunglasses example), 301
 - px units, 4, 7–8
 - Pythagorean theorem, 57, 487, 501
- Q**
- quadraticCurveTo() method (Canvas context), 138–141
 - queueImage() method (Game), 554–557
- R**
- radians, 54–55
 - radioactive decay, 428
 - ray casting, 490–494, 601, 604, 611–614
 - accuracy of, 494
 - intersection of lines for, 492
 - rect() method (Canvas context), 91–94, 99–100, 361
 - rectangles
 - direction of, 99–100
 - drawing, 91
 - rounded, 71–72, 128, 138–139, 390, 617–625
 - appending to HTML elements, 624
 - resizing, 624
 - with square corners, 70
 - with zero width or height, 276
 - Replica Island game, 394
 - requestAnimationFrame() method
 - (window), 14, 342–345, 348, 360, 390, 437, 544, 583
 - browser-specific implementations of, 344–348
 - requestNextAnimationFrame() method
 - (window), 331–333, 349–357, 388, 404, 421, 437, 532, 544, 546, 550–551, 626
 - reset() method (AnimationTimer), 386
 - resize() method
 - for custom controls, 617
 - of Keyboard object, 700
 - of RoundedRectangle object, 624–625
 - resolution media feature, 668
 - restore() method (Canvas context), 11–12, 85, 136, 185, 194, 197
 - restoreRubberbandPixels() function (rubber bands example), 280–281
 - RGB (red/green/blue), 74–75
 - rgb() color definition (CSS), 74
 - RGBA (red/green/blue/alpha), 74
 - rgba() color definition (CSS), 74
 - rotate() method (Canvas context), 172–175, 225
 - rotating
 - after translating, 225
 - coordinate system, 171–173, 176
 - polygons, 151, 171–172
 - text, 177–179
 - roundedRect() function (rounded rectangles example), 128–129
 - RoundedRectangle object
 - draw() method, 625
 - resize() method, 624–625
 - rubber bands, 110–116
 - bounding box of, 275
 - captureCanvasPixels() function, 285
 - captureRubberbandPixels() function, 276, 280–281
 - circular, 126–127
 - copyCanvasPixels() function, 285–286
 - drawRubberbandShape() function, 116, 126–127, 147–148
 - erasing, 115
 - for interactive drawing, 65
 - modifying transparency with, 283–285

- restoreRubberbandPixels() function, 280–281
 - rubberbandEnd() function, 46, 276
 - rubberbandStart() function, 46
 - rubberbandStretch() function, 46, 276
 - selecting with, 274–283
 - temporary drawing surface for, 33
 - zooming with, 41–46
- S**
- Safari, 15
 - composition operations in, 186–187
 - console and debugger for, 16
 - layout viewport on, 666
 - looping backwards in, 320
 - maximum width of text in, 205
 - timelines in, 19
 - video formats in, 329
 - SAT (separating axis theorem), 495–541, 601–609
 - for circles, 516–521
 - for images and sprites, 521–525
 - for polygons, 504–516
 - not for small fast objects, 611
 - pseudocode for, 499–500
 - using MTV for, 526–541
 - save() method (Canvas context), 11–12, 85, 136, 185, 194, 197, 361
 - scalars, 60
 - scale() method (Canvas context), 172–175
 - scaling
 - canvas, 270–272, 316–317
 - coordinate system, 173–176
 - during development, 173
 - images, 258–265
 - text, 177–179
 - video frames, 331
 - scan media feature, 668
 - screen
 - clearing, 544, 546, 550, 579
 - height of, 667
 - width of, 659, 666–667
 - screenX and screenY browser attributes, 673
 - scrollBackground() method (background scrolling example), 577–579
 - scrollPathIntoView() method (Canvas context), 169–170
 - security, 312–313
 - SECURITY_ERR exception, 313
 - self variable (JavaScript), 551
 - separate() function (separating colliding shapes example), 530–531, 609
 - separationOnAxes() method (Shape), 504–508, 527
 - setClip() method (Canvas context), 324–325
 - setHighScore() method (Game), 544, 560–561
 - setInterval() method (window), 14, 24, 306, 341–343, 390
 - setTimeout() method (window), 14, 341–343, 349–350, 390, 551, 579
 - clamping, 342
 - setTransform() method (Canvas context), 174–181
 - shadowBlur context attribute, 10, 83–85, 88
 - shadowColor context attribute, 10, 83–85, 88
 - undefined, 85
 - shadowOffsetX and shadowOffsetY context attributes, 10, 83–88
 - shadows, 83–88
 - and performance, 88, 390–391
 - applying to text, 202
 - color of, 10
 - enabling, 69, 185
 - partially transparent colors for, 85
 - settings for, 69, 256
 - spreading out, 10
 - turning on/off, 85
 - with negative offset, 85–87
 - Shape
 - collidesWith() method, 504–508, 518–520, 529–530, 532, 604
 - createPath() method, 148, 172
 - getAxes() method, 504–511, 516
 - minimumTranslationVector() method, 527–529
 - move() method, 148
 - separationOnAxes() method, 504–508, 527

- shear, 179–181
 - Shift key, 672, 694
 - shiftKey browser attribute, 32, 672
 - showKeyboard() function (keyboard example), 689
 - sin() method (Math), 54, 446
 - Sinclair ZX81 computer, 359
 - sine, 55–56, 468
 - Slider object, 634, 636
 - addChangeListener() method, 636, 642
 - appendTo() method, 619, 624–625, 628
 - fireChangeEvent() method, 642
 - sliders, 173, 325, 631–643
 - fillKnob() method, 642
 - smart phones, 33
 - social network, 312
 - Sonic the Hedgehog game, 427
 - sound
 - formats of, 557–558
 - multitrack, 544, 557–558
 - source element (HTML), 329
 - span element (HTML), 279
 - springs, 427
 - Sprite object, 394–397
 - paint() method, 394–398, 404
 - properties of, 395
 - update() method, 394, 411, 416–417, 553
 - sprite sheets, 26–30
 - painters for, 398, 406–410, 476
 - SpriteAnimator object, 419–423
 - start() method, 419–421
 - sprites, 393–425, 431
 - adding to game engine, 544
 - animating, 417–423
 - colliding, 521–525
 - creating, 397, 594
 - painters for, 394–395, 397–410, 419, 421
 - advancing, 407, 410
 - decoupling from, 394
 - painting, 394, 424
 - under/over, 544–546, 550, 576, 577
 - updating, 424, 544–546, 550
 - SpriteSheetPainter object
 - advance() method, 407
 - src HTML attribute, 8, 46
 - start() method
 - of Game object, 544, 550–551
 - of SpriteAnimator object, 419–421
 - of Stopwatch object, 385
 - startAnimate() method (Game), 544–546, 550, 553, 590–592, 594, 604
 - stick() function (sticking with MTV example), 532–537
 - sticking, 531–537
 - Stopwatch object
 - start() method, 385
 - stop() method, 385
 - stopwatches, 385–388
 - Strategy design pattern (sprites), 394, 398
 - stroke and fill painters, 398–404
 - stroke() method (Canvas context), 23–24, 91–94, 103, 110, 148, 398, 603
 - strokeRect() method (Canvas context), 88
 - simplifying by translating the origin, 170
 - strokeStyle context attribute, 4, 10, 12, 72–75, 91–92, 136
 - strokeText() method (Canvas context), 4, 9–10, 88, 201–207, 210, 215, 237
 - optional argument of, 204–205
 - stroking, 88–103
 - and shadows, 84
 - text, 201–207
 - with gradients/patterns, 75, 205–207
 - subtract() method (Vector), 501–502
 - sunglasses application, 299–306
 - drawConnectors() function, 302
 - drawLenses() function, 302
 - drawWire() function, 302
 - putSunglassesOn() function, 301
 - SVG (Scalable Vector Graphics)
 - color names in, 74
 - list of objects in, 34
 - paths in, 89
 - swing behavior, 445–446
- T**
- tablet computers, 33
 - performance of, 280
 - touch events in, 67
 - tan() method (Math), 54

- tangent, 55–56
 - target browser attribute, 673
 - target-densityDpi content attribute (viewport), 665
 - targetTouches browser attribute, 672
 - telescoping animation, 194–197
 - Texas Instruments 9918(A) video display processor, 393
 - text, 201–252
 - applying shadows to, 202
 - centering, 3–4, 214–215
 - drawing around arc, 223–225
 - editing, 232–237, 252
 - erasing, 239, 245–251
 - filling, 84, 201–207
 - font properties of, 201, 207–210
 - inserting, 239, 243–244
 - maximum width of, 204–205
 - measuring, 201, 215–216, 227–228
 - new lines in, 244–245
 - paragraphs of, 238–252
 - positioning, 136, 201, 210–225
 - drawText() function, 212–214
 - rotating, 177–179
 - scaling, 177–179, 205
 - stroking, 84, 201–207
 - textAlign context attribute, 10, 136, 201–202, 210–215, 220–221
 - textarea element (HTML), 252
 - textBaseline context attribute, 10, 136, 201–202, 210–215, 220–221
 - TextCursor object, 225–231
 - erase() method, 228–230
 - getHeight() method, 226
 - moveCursor() method, 228
 - TextLine object, 232–238, 242
 - draw() method, 233
 - erase() method, 233, 237, 244
 - getHeight() method, 233
 - getWidth() method, 216, 233
 - insert() method, 233
 - TextMetrics object, 216–217
 - this variable (JavaScript), 550–551
 - tick() method (Game), 550
 - time
 - elapsed, 386, 433, 452
 - warping, 390, 427, 450–456, 595
 - time-based motion, 62–64, 350, 358–359, 367–370, 390–391, 416–417, 544, 553, 594
 - timelines, 19, 390–391
 - Timing control for script-based animations specification, 14, 344
 - toasts, 573
 - Game Over, 585–589
 - Paused, 600
 - Try Again, 592
 - toBlob() method (Canvas context), 8, 51
 - toDataURL() method (Canvas context), 8, 46–51
 - and origin-clean flag, 313
 - togglePaused() method (Game), 544, 546, 551–553, 582–583, 600
 - touch events, 33, 67, 671–677
 - supporting together with mouse events, 674–675, 684, 694
 - touchcancel, 671–672
 - touchend, 671–672
 - touchmove, 671–672, 675
 - touchstart, 671–672, 675, 694
 - touch objects, 673
 - touches browser attribute, 672
 - TouchList object, 672
 - identifiedTouch() method, 672
 - length property, 672
 - transform() method (Canvas context), 174–181
 - translate() method (Canvas context), 170–175, 225, 372
 - translating
 - before rotating, 225
 - coordinate system, 171–175
 - translucent overlays, 625
 - transparency, 9, 72–75
 - trigonometry, 54–56, 145, 445, 468
 - for positioning circular text, 221–223
 - for rotating, 176
 - Try Again toast, 592
 - tty terminals, 668
 - TypedArray object, 291
- ## U
- UA (User Agents), 13
 - Uint8ClampedArray object, 291

- ungame, 572–589
 - game loop of, 576–579
 - loading, 579–581
 - pausing, 581–584
 - See also* game engine
 - units of measure, 62–64, 431
 - update() method (Sprite), 350, 394, 411, 416–417, 553
 - updateFrameRate() method (Game), 550
 - updateLeftFlipper() method (Pinball), 592
 - updateRightFlipper() method (Pinball), 592
 - updateSprites() method (Game), 550
 - user gestures, 383–385
 - didThrow() function, 384
 - user-scalable content attribute (viewport), 665
- V**
- Vector object
 - add() method, 501–502
 - dotProduct() method, 501–502
 - edge() method, 502
 - getMagnitude() method, 501–502
 - normal() method, 502–503
 - normalize() method, 502
 - perpendicular() method, 502–503
 - subtract() method, 501–502
 - vectors, 56–62
 - adding, 59–60
 - direction of, 58–59
 - displacement, 594, 604
 - dot product of, 60–62, 501, 608
 - edge, 57, 60, 500
 - edge normal, 500
 - magnitude of, 57, 501–503
 - multiplicating, 501
 - normalized. *See* vectors, unit
 - perpendicular, 503
 - reflecting, 537–541
 - subtracting, 59–60, 501
 - unit, 58–59, 503, 530, 606
 - velocity
 - and air resistance, 461
 - and collisions, 461, 530
 - and current frame rate, 62
 - and friction, 461, 595
 - clamping, 609
 - constant vs. nonlinear, 463–469
 - for bouncing, 537–541, 609
 - initial, 436
 - limiting, for small objects, 487
 - vertical, 428–432, 595
 - applying gravity to, 433
 - video element (HTML), 328–329
 - invisible, 331–333
 - videos, 328–337
 - formats of, 329–330
 - frames of, 328–337
 - drawing into canvas, 253, 258, 328
 - scaling, 331
 - playing in canvas, 331–333
 - processing, 333–337
 - nextVideoFrame() function, 333
 - viewport metatag, 661–666
 - device-height attribute, 665
 - device-width attribute, 664–665
 - height attribute, 665
 - initial-scale attribute, 665–666
 - maximum-scale attribute, 665–666
 - minimum-scale attribute, 665
 - target-densityDpi attribute, 665
 - user-scalable attribute, 665
 - width attribute, 665
 - viewports
 - draggable, 644
 - height of, 667
 - layout, 661
 - set to device-width, 664
 - mobile, 659–666
 - scaling, 661–666
 - visible, 661
 - width of, 667
 - hardcoded, 663
 - virtual keyboard, 682–700
 - hideKeyboard() function, 689
 - resizing, 684–685, 700
 - showKeyboard() function, 689
 - translucent, 685, 694
 - visibility of, 689
 - VP8 video format, 329

W

W3C (World Wide Web Consortium), 14

warping

animation, 473–482

motion, 458–473

time, 390, 427, 450–456, 595

with functions, 454–458

watermarks, 266–274

drawScaled() function, 272–274

drawWatermark() function, 266–270

web browsers. *See* browsers

web workers, 299–301

WebGL 3d context, 11

webkitCancelAnimationFrame() method
(window), 344, 347

webkitRequestAnimationFrame() method
(window), 344, 346–348, 350

WebM video format, 329

WHATWG (Web Hypertext Application
Technology Working Group), 14, 252

while loop (JavaScript), 340

width

content attribute (viewport), 665

context attribute, 4–7

media feature, 667

window object

cancelAnimationFrame()
method, 344–345

clearInterval() method, 231

getBoundingClientRect() method, 27

matchMedia() method, 669

mozkitRequestAnimationFrame()
method, 344–346, 350

msCancelAnimationFrame() method,
344, 348

msRequestAnimationFrame() method,
344, 348

onkeydown() method, 241

onkeypress() method, 237, 241

onmousedown() method, 241

requestAnimationFrame() method, 14,
342–348, 360, 390, 437, 544, 583

requestNextAnimationFrame() method,
331–333, 349–357, 388, 404, 421, 437,
532, 544, 546, 550–551, 626

setInterval() method, 14, 24, 306,
341–343, 390

setTimeout() method, 14, 341–343,
349–350, 390, 551, 579

webkitCancelAnimationFrame()
method, 344, 347

webkitRequestAnimationFrame()
method, 344, 346–348, 350

windowToCanvas() function (translating
coordinates example), 27–28, 111, 195,
674–675

Worker object

onmessage() method, 301–302

X

x browser attribute, 30

Y

y browser attribute, 30

YouTube, 328

Z

z-index property (CSS), 39

zooming in, with rubber bands, 41–46