Structural Masonry Designers' Manual

W. G. Curtin, G. Shaw, J. K. Beck
and **W. A. Bray**

Third Edition revised by

David Easterbrook

Blackwell
Science

Curtins
consulting

Structural Masonry Designers' Manual

Structural Masonry Designers' Manual

W. G. Curtin, G. Shaw, J. K. Beck
and **W. A. Bray**

Third Edition revised by

David Easterbrook

Blackwell
Science

Curtins
consulting

© 2006 Estate of W.G. Curtin, G. Shaw, J.K. Beck, W.A. Bray and D. Easterbrook

Editorial offices:
Blackwell Science Ltd, 9600 Garsington Road, Oxford OX4 2DQ, UK
Tel: +44 (0) 1865 776868
Blackwell Publishing Inc., 350 Main Street, Malden, MA 02148-5020, USA
Tel: +1 781 388 8250
Blackwell Science Asia Pty, 550 Swanston Street, Carlton, Victoria 3053, Australia
Tel: +61 (0)3 8359 1011

The right of the Author to be identified as the Author of this Work has been asserted in accordance with the Copyright, Designs and Patents Act 1988.

All rights reserved. No part of this publication may be reproduced, stored in a retrieval system, or transmitted, in any form or by any means, electronic, mechanical, photocopying, recording or otherwise, except as permitted by the UK Copyright, Designs and Patents Act 1988, without the prior permission of the publisher.

First published in Great Britain by
Grananda Publishing Ltd 1982
Reprinted 1982
Second edition published by
Blackwell Scientific Publications 1987
Reprinted 1989, 1991
Second edition (revised) published by
Blackwell Science 1995
Reprinted 1997, 1999

ISBN-10: 0-632-05612-6
ISBN-13: 978-0-632-05612-5

Library of Congress Cataloging-in-Publication Data

Structural masonry designers' manual / W.G. Curtin . . . [et al.].— 3rd ed. / rev. by David Easterbrook.
p. cm.
Includes index.
ISBN-13: 978-0-632-05612-5 (hardback : alk. paper)
ISBN-10: 0-632-05612-6 (hardback : alk. paper) 1. Masonry—Handbooks, manuals, etc. 2. Structural design—Handbooks, manuals, etc. I. Curtin, W. G. (William George) II. Easterbrook, David.

TA670.S725 2006
693'.1—dc22

2005024960

A catalogue record for this title is available from the British Library

Set in 9/12pt Palatino
by Graphicraft Ltd., Hong Kong
Printed and bound in Singapore
by Fabulous Printers Pte Ltd

The publisher's policy is to use permanent paper from mills that operate a sustainable forestry policy, and which has been manufactured from pulp processed using acid-free and elementary chlorine-free practices. Furthermore, the publisher ensures that the text paper and cover board used have met acceptable environmental accreditation standards.

For further information on Blackwell Publishing, visit our website:
www.blackwellpublishing.com

Contents

Preface to the Third Edition x

Acknowledgements xi

The Authors xii

Notation xiii

1 Introduction 1
- 1.1 Present structural forms 1
- 1.2 Examples of structural layout suiting masonry 2
- 1.3 Reinforced and post-tensioned masonry 2
- 1.4 Arches and vaults 2
- 1.5 The robustness of masonry structures 2
- 1.6 Prefabrication 3
- 1.7 Future tradesmen 3
- 1.8 Engineering education 3

2 Advantages and disadvantages of structural masonry 4
- 2.1 Advantages 4
  - 2.1.1 Cost 4
  - 2.1.2 Speed of erection 4
  - 2.1.3 Aesthetics 4
  - 2.1.4 Durability 5
  - 2.1.5 Sound insulation 5
  - 2.1.6 Thermal insulation 5
  - 2.1.7 Fire resistance and accidental damage 5
  - 2.1.8 Capital and current energy requirements 6
  - 2.1.9 Resistance to movement 6
  - 2.1.10 Repair and maintenance 6
  - 2.1.11 Ease of combination with other materials 7
  - 2.1.12 Availability of materials and labour 7
  - 2.1.13 Recyclability 7
- 2.2 Disadvantages 7
  - 2.2.1 Lack of education in masonry 7
  - 2.2.2 Increase in obstructed area over steel and reinforced concrete 7
  - 2.2.3 Problems with some isolated details 7
  - 2.2.4 Foundations 8
  - 2.2.5 Large openings 8
  - 2.2.6 Beams and slabs 8
  - 2.2.7 Control joints 8
  - 2.2.8 Health and safety considerations 8

3 Design philosophy 10
- 3.1 Strength of material 10
- 3.2 Exploitation of cross-section 10
- 3.3 Exploitation of essential building elements 13

4 Limit state design 16

5 Basis of design (1): Vertical loading 18
- 5.1 Compressive strength of masonry 18
- 5.2 Characteristic strength and characteristic load 18
- 5.3 Partial safety factors for loads, γ_f 20
- 5.4 Characteristic compressive strength of masonry, f_k 20
  - 5.4.1 Brickwork 22
  - 5.4.2 Blockwork 23
  - 5.4.3 Natural stone masonry and random rubble masonry 25
  - 5.4.4 Alternative construction techniques 26
- 5.5 Partial safety factors for material strength, γ_m 27
  - 5.5.1 Manufacturing control (BS 5628, clause 27.2.1) 27
  - 5.5.2 Construction control 27
- 5.6 Slenderness ratio 28
- 5.7 Horizontal and vertical lateral supports 28
  - 5.7.1 Methods of compliance: Walls – horizontal lateral supports 29
  - 5.7.2 Methods of compliance: Walls – vertical lateral supports 32
- 5.8 Effective height or length: Walls 32
- 5.9 Effective thickness of walls 34
  - 5.9.1 Solid walls 34
  - 5.9.2 Cavity walls 34
- 5.10 Loadbearing capacity reduction factor, β 35
- 5.11 Design compressive strength of a wall 36
- 5.12 Columns 36
  - 5.12.1 Slenderness ratio: Columns 36
  - 5.12.2 Columns formed by openings 37
  - 5.12.3 Design strength 38
  - 5.12.4 Columns or walls of small plan area 39
- 5.13 Eccentric loading 39
- 5.14 Combined effect of slenderness and eccentricity of load 40
  - 5.14.1 Walls 40
  - 5.14.2 Columns 41
- 5.15 Concentrated loads 43

6 Basis of design (2): Lateral loading – tensile and shear strength 47
6.1 Direct tensile stress 48
6.2 Characteristic flexural strength (tensile) of masonry, f_{kx} 48
6.2.1 Orthogonal ratio 49
6.3 Moments of resistance: General 51
6.3.1 Moments of resistance: uncracked sections 51
6.3.2 Moments of resistance: Cracked sections 53
6.4 Cavity Walls 54
6.4.1 Vertical twist ties 55
6.4.2 Double-triangle and wire butterfly ties 56
6.4.3 Selection of ties 56
6.4.4 Double-lead (collar-jointed) walls 57
6.4.5 Grouted cavity walls 57
6.4.6 Differing orthogonal ratios 57
6.5 Effective eccentricity method of design 57
6.6 Arch method of design 58
6.6.1 Vertical arching 58
6.6.2 Vertical arching: Return walls 60
6.6.3 Horizontal arching 60
6.7 Free-standing walls 62
6.7.1 General 62
6.7.2 Design bending moments 62
6.7.3 Design moment of resistance 63
6.8 Retaining walls 63
6.9 Panel walls 63
6.9.1 Limiting dimensions 63
6.9.2 Design methods 64
6.9.3 Design bending moment 64
6.9.4 Design moments of resistance 68
6.9.5 Design of ties 68
6.10 Propped cantilever wall design 69
6.10.1 Geometric and other sections in shear 70
6.11 Eccentricity of loading in plane of wall 70
6.11.1 Design of walls loaded eccentrically in the plane of the wall 71
6.12 Walls subjected to shear forces 71
6.12.1 Characteristic and design shear strength 71
6.12.2 Resistance to shear 72

7 Strapping, propping and tying of loadbearing masonry 73
7.1 Structural action 74
7.2 Horizontal movement 76
7.3 Shear keying between wall and floors 77
7.4 Holding down roofs subject to upward forces 77
7.5 Areas of concern 77
7.6 Other factors influencing the details of connections 78
7.7 Illustrated examples of strapping and tying 80
7.8 Design examples: Straps and ties for a three-storey masonry building 89

8 Stability, accidental damage and progressive collapse 94
8.1 Progressive collapse 94
8.2 Stability 96
8.3 Accidental forces (BS 5628, clause 20) 98
8.4 During construction 99
8.5 Extent of damage 99
8.6 Design for accidental damage 100
8.6.1 Partial safety factors 100
8.6.2 Methods (options) of checking 101
8.6.3 Loadbearing elements 101
8.6.4 Protected member 103
8.6.5 General notes 109

9 Structural elements and forms 110
9.1 Structural elements 110
9.1.1 Single-leaf walls 110
9.1.2 Double-leaf collar-jointed walls 110
9.1.3 Double-leaf cavity walls 110
9.1.4 Double-leaf grouted cavity walls 110
9.1.5 Faced walls 111
9.1.6 Veneered walls 111
9.1.7 Walls with improved section modulus 111
9.1.8 Reinforced walls 113
9.1.9 Post-tensioned walls 114
9.1.10 Columns 114
9.1.11 Arches 115
9.1.12 Circular and elliptical tube construction 116
9.1.13 Composite construction 116
9.1.14 Horizontally reinforced masonry 116
9.2 Structural forms 116
9.2.1 Chimneys 116
9.2.2 Crosswall construction 118
9.2.3 Cellular construction 119
9.2.4 Column and plate floor construction 119
9.2.5 Combined forms of construction 120
9.2.6 Diaphragm wall and plate roof construction 121
9.2.7 Fin wall and plate roof construction 121
9.2.8 Miscellaneous wall and plate roof construction 121
9.2.9 Spine wall construction 121
9.2.10 Arch and buttressed construction 122
9.2.11 Compression tube construction 123

10 Design of masonry elements (1): Vertically loaded 124
10.1 Principle of design 124
10.2 Estimation of element size required 124
10.3 Sequence of design 124
10.4 Design of solid walls 124
10.5 Design of cavity walls 130
10.5.1 Ungrouted cavity walls 130
10.5.2 Grouted cavity walls 132
10.5.3 Double-leaf (or collar-jointed) walls 134

10.6 Design of walls with stiffening piers 134
10.7 Masonry columns 136
10.8 Diaphragm walls 138
10.9 Concentrated loads 140

11 Design of masonry elements (2): Combined bending and axial loading 142
11.1 Method of design 142

12 Design of single-storey buildings 173
12.1 Design considerations 173
12.2 Design procedure 177

13 Fin and diaphragm walls in tall single-storey buildings 178
13.1 Comparison of fin and diaphragm walls 179
13.2 Design and construction details 180
13.3 Architectural design and detailing 181
13.3.1 Services 182
13.3.2 Sound and thermal insulation 183
13.3.3 Damp proof courses and membranes 183
13.3.4 Cavity cleaning 183
13.4 Structural detailing 183
13.4.1 Foundations 184
13.4.2 Joints 184
13.4.3 Wall openings 185
13.4.4 Construction of capping beam 185
13.4.5 Temporary propping and scaffolding 185
13.5 Structural design: General 186
13.5.1 Design principles: Propped cantilever 186
13.5.2 Calculate design loadings 187
13.5.3 Consider levels of critical stresses 188
13.5.4 Design bending moments 188
13.5.5 Stability moment of resistance, MR_s 190
13.5.6 Shear lag 190
13.5.7 Principal tensile stress 190
13.6 Design symbols: Fin and diaphragm walls 191
13.7 Fin walls: Structural design considerations 191
13.7.1 Interaction between leaves 191
13.7.2 Spacing of fins 191
13.7.3 Size of fins 192
13.7.4 Effective section and trial section 192
13.8 Example 1: Fin wall 193
13.8.1 Design problem 193
13.8.2 Design approach 194
13.8.3 Characteristic loads 194
13.8.4 Design loads 194
13.8.5 Design cases (as shown in Figure 13.42) 194
13.8.6 Deflection of roof wind girder 194
13.8.7 Effective flange width for T profile 196
13.8.8 Spacing of fins 196
13.8.9 Trial section 196
13.8.10 Consider propped cantilever action 197
13.8.11 Stability moment of resistance 197
13.8.12 Allowable flexural compressive stresses, p_{ubc}, taking into account slenderness, β, and material, γ_m 197
13.8.13 Calculate MR_s and compare with M_b 199
13.8.14 Bending moment diagrams 200
13.8.15 Consider stresses at level of M_w 200
13.8.16 Design flexural stress at M_w levels 201
13.8.17 Consider fins and deflected roof prop 202
13.9 Diaphragm wall: Structural design considerations 202
13.9.1 Determination of rib centres, B_r 202
13.9.2 Depth of diaphragm wall and properties of sections 204
13.9.3 Shear stress coefficient, K_1 205
13.9.4 Trial section coefficients, K_2 and Z 206
13.10 Example 2: Diaphragm wall 207
13.10.1 Design problem 207
13.10.2 Characteristic and design loads 207
13.10.3 Select trial section 208
13.10.4 Determine wind and moment MR_s at base 208
13.10.5 Consider stress at level M_w 209
13.10.6 Consider diaphragm with deflected roof prop 210
13.10.7 Calculate shear stress 211
13.10.8 Stability of transverse shear walls 211
13.10.9 Summary 211
13.11 Other applications 211

14 Design of multi-storey structures 214
14.1 Structural forms 214
14.1.1 Stability 215
14.1.2 External walls 215
14.1.3 Provision for services 216
14.1.4 Movement joints 216
14.1.5 Vertical alignment of loadbearing walls 217
14.1.6 Foundations 218
14.1.7 Flexibility 218
14.1.8 Concrete roof slab/Loadbearing wall connections 218
14.1.9 Accidental damage 218
14.1.10 Choice of brick, block and mortar strengths 219
14.2 Crosswall construction 219
14.2.1 Stability 219
14.2.2 External cladding panel walls 220
14.2.3 Design for wind 221
14.2.4 Openings in walls 222
14.2.5 Typical applications 222

14.2.6 Elevational treatment of crosswall structures 224
14.2.7 Podiums 224
14.3 Spine construction 224
14.3.1 Lateral stability 225
14.3.2 Accidental damage 226
14.4 Cellular construction 226
14.4.1 Comparison with crosswall construction 227
14.4.2 Envelope (cladding) area 227
14.4.3 Robustness 227
14.4.4 Flexibility 227
14.4.5 Height of structure 227
14.4.6 Masonry stresses 227
14.4.7 Foundations 228
14.5 Column structures 228
14.5.1 Advantages 228
14.5.2 Cross-sectional shape 228
14.5.3 Size 229
14.6 Design procedure 229
14.7 Example 1: Hotel bedrooms, six floors 229
14.7.1 Characteristic loads 229
14.7.2 Design of internal crosswalls 231
14.7.3 Partial safety factor for material strength (Table 4, BS 5628 – see Table 5.11) 232
14.7.4 Choice of brick in the two design cases, at ground floor level 232
14.7.5 Choice of brick in the two design cases, at third flood level 232
14.7.6 Design of gable cavity walls to resist lateral loads due to wind 232
14.7.7 Uplift on roof 232
14.7.8 Design of wall 232
14.7.9 Calculation of design wall moment 233
14.7.10 Resistance moment of wall (Figure 14.46) 233
14.7.11 Overall stability check 233
14.7.12 Eccentricity of loading 235
14.7.13 Accidental damage 235
14.8 Example 2: Four-storey school building 236
14.8.1 Characteristic loads 237
14.8.2 Design of wall at ground floor level 237
14.9 Example 3: Four-storey office block 238
14.9.1 Column structure for four-storey office block 238
14.9.2 Characteristic loads 239
14.9.3 Design of brick columns 239
14.9.4 Loading on column P 239

15 Reinforced and post-tensioned masonry 243
15.1 General 244
15.1.1 Design theory 244
15.1.2 Comparison with concrete 244
15.1.3 Applications 245
15.1.4 Prestressing 246
15.1.5 Methods of reinforcing walls 246
15.1.6 Composite construction 247
15.1.7 Economics 247
15.1.8 Corrosion of reinforcement and prestressing steel 247
15.1.9 Cover to reinforcement and prestressing steel 248
15.1.10 Cover 248
15.2 Choice of system 249
15.3 Design of reinforced brickwork 250
15.3.1 Partial factors of safety 250
15.3.2 Strength of materials 251
15.3.3 Design for bending: Reinforced masonry 251
15.3.4 Lateral stability of beams 251
15.3.5 Design formula for bending: Moments of resistance for reinforced masonry 252
15.3.6 Design formula: Shear stress 255
15.3.7 Shear reinforcement 255
15.3.8 Design formula: Local bond 256
15.3.9 Characteristic anchorage bond strength, f_b 256
15.3.10 Design for axial loading 256
15.4 Example 1: Design of reinforced brick beam 257
15.5 Example 2: Alternative design for reinforced brick beam 259
15.6 Example 3: Reinforced brick retaining wall 261
15.7 Example 4: Column design 262
15.8 Design of post-tensioned brickwork 263
15.8.1 General 263
15.8.2 Post-tensioned masonry: Design for flexure 265
15.8.3 Design strengths 266
15.8.4 Steel stresses 267
15.8.5 Asymmetrical sections 267
15.8.6 Losses of post-tensioning force 268
15.8.7 Bearing stresses 269
15.8.8 Deflection 269
15.8.9 Partial safety factor on post-tensioning force 269
15.9 Example 5: High cavity wall with wind loading 269
15.9.1 Capacity reduction factor, β 270
15.9.2 Characteristic strengths 270
15.9.3 Design strengths (after losses) 271
15.9.4 Section modulus of wall 271
15.9.5 Design method 271
15.9.6 Calculation of required post-tensioning force 271
15.9.7 Consider compressive stresses: After losses 272
15.9.8 Consider compressive stresses: Before losses 274
15.9.9 Design of post-tensioning rods 274

15.10 Example 6: Post-tensioned fin wall 275
15.10.1 Design procedure 275
15.10.2 Design post-tensioning force and eccentricity 276
15.10.3 Characteristic strengths 277
15.10.4 Loadings 277
15.10.5 Design bending moments 278
15.10.6 Theoretical flexural tensile stresses 278
15.10.7 Calculations of P and e 278
15.10.8 Spread of post-tensioning force 279
15.10.9 Characteristic post-tensioning force P_k 279
15.10.10 Capacity reduction factors, β 279
15.10.11 Check combined compressive stresses 279
15.10.12 Design flexural compressive strengths of wall: After losses 282
15.10.13 Check overall stability of wall 282
15.10.14 Design of post-tensioning Rods 284
15.11 Example 7: Post-tensioned brick diaphragm retaining wall 284
15.11.1 Design procedure 284
15.11.2 Design loads 285
15.11.3 Trial section 286
15.11.4 Calculate theoretical flexural tensile stresses 289
15.11.5 Minimum required post-tensioning force based on bending stresses 289
15.11.6 Characteristic post-tensioning force, P_k 289
15.11.7 Capacity reduction factors 289
15.11.8 Check combined compressive stresses 290
15.11.9 Check shear between leaf and cross-rib 291
15.11.10 Design of post-tensioning rods 293

16 Arches 294
16.1 General design 294
16.1.1 Linear arch 295
16.1.2 Trial sections 296
16.1.3 Mathematical analysis 297
16.2 Design procedures 299
16.3 Design examples 299
16.3.1 Example 1: Footbridge arch 299
16.3.2 Example 2: Segmental arch carrying traffic loading 301
16.3.3 Example 3: Repeat Example 2 using a pointed arch 304

Appendix 1 Materials 307
A1.0 Introduction 307
A1.1 Clay masonry units (clay bricks) 307
A1.1.1 Sizes 307
A1.1.2 Classification 307
A1.1.3 Strength and durability 308
A1.1.4 Testing 309
A1.2 Calcium silicate units (bricks) 309
A1.3 Concrete bricks 310
A1.4 Stone units (stonework) 310
A1.5 Concrete units (blocks and bricks) 310
A1.5.1 Sizes 310
A1.5.2 Classification 310
A1.5.3 Density 310
A1.5.4 Form 310
A1.5.5 Strength 310
A1.5.6 Durability 310
A1.6 Mortars 311
A1.6.1 Constituents 311
A1.6.2 Choice of mortar 312
A1.6.3 Proportioning and mixing 312
A1.6.4 Testing 312

Appendix 2 Components 314
A2.1 Wall ties 314
A2.2 Damp proof courses 314
A2.3 Fixings 314
A2.4 Brick bonds 315

Appendix 3 Movement joints 317
A3.1 Movement due to thermal expansion and contraction 318
A3.2 Movement due to moisture 318
A3.2.1 Fired clay units 318
A3.2.2 Concrete and calcium silicate units 319
A3.3 Movement due to chemical interaction of materials (sulphate attack) 320
A3.4 Differential movement with dissimilar materials and members 320
A3.5 Foundation settlement 321
A3.6 Movement of joints and accommodation of movement 322
A3.7 Jointing materials and typical details 323
A3.8 Mortars in assisting movement control 323

Appendix 4 Provision for services 324

Index 327

Preface to the Third Edition

The original Structural Masonry Designers' Manual was viewed by many in the industry as a seminal reference for structural engineers designing masonry structures. The authors were founding members and directors of Curtins Consulting Engineers, a civil engineering consultancy practice, which was synonymous with the innovative and creative use of structural masonry in the latter part of the last century (1970s onwards). Both Bill Curtin and Gerry Shaw were educated in the old way which consisted of working by day and studying by night. This engendered a passion for their subject, which is evident in the previous editions of this book.

Gerry Shaw was until his tragic death a Visiting Professor in The Principles of Engineering Design at the University of Plymouth. The updated manual takes nothing away from the enthusiastic approach to masonry design evidenced by the Curtins' authors in the previous editions. Their pragmatic and practical approach to masonry design is retained in its fullness.

The new revision reflects changes in the industry with respect to health and safety, as well as Building Regulation requirements for heat loss, noise transmission and disproportionate collapse rules. The recent amendments to BS 5628 Parts 1, 2 and 3 are also included.

One major change is the transition from British specifications for materials to European Standard specifications. European specifications are based on performance criteria rather than prescriptive criteria and this will require structural engineers to be more aware of the materials that they specify.

Many changes have taken place in masonry construction since the last edition of the book was published. Many of these changes are quite rightly related to health and safety issues, which now appear to influence both the structural form and the choice of material. The current shortage of skilled labour within the construction industry further affects the design decisions made by structural engineers. However, innovative work in the use of structural masonry is still in evidence in structural engineering design.

The format of the book has remained unchanged since it is meant to be a discussion of process, both theoretical and practical, rather than a series of calculation sheets without explanation. The drawings have been updated, but have also been produced in an illustrative format rather than a technical drawing format. This is intended to aid the reader in the understanding of the principles.

Acknowledgements

We appreciate the help given by many friends in the construction industry, design professions and organisations. We learnt much from discussions (and sometimes, arguments) on site, in design team meetings and in the drawing office. To list all who helped would be impossible – to list none would be churlish. Below, in alphabetical order, are some of the organisations and individuals to whom we owe thanks:

Brick Development Association
British Standards Institution
Building Research Establishment
Cement and Concrete Association
} for general assistance

Professor Heyman for permission to quote from his book, *Equilibrium of Shell Structures*.

Mr J. Korff, Deputy Structural Engineer, GLC, for advice on accidental damage.

Mr W. Sharp, County Structural Engineer, Landcashire County Council, for particular help on strapping and tying.

Acknowledgements are also due to the BCRA for permission to quote from their SP93 'Strapping & Tying', which was largely based on information supplied by Lancashire County Council's structural engineer and W. G. Curtin and Partners.

Extracts from BS 5628 1985 and 1992 are reproduced by permission of BSI. Complete copies can be obtained from them at Linford Wood, Milton Keynes MK14 6LE.

Finally, the authors are grateful to the Institution of Structural Engineers for giving their permission to reproduce extracts from the Profile of Dr Bill Curtin, the original and full version of which was published in *The Structural Engineer*, **69** (21), 1991.

The Authors

W. G. Curtin was the founder of Curtins Consulting Engineers plc, a highly respected civil and structural engineering consultancy. He was a member of the Institution of Structural Engineers Science and Research Committee, of numerous CIRIA committees and the Code of Practice Committee for Structural Masonry, and of the Structural Engineering and Building Board of the Institution of Civil Engineers. His experience embraced over 50 years of designing, building, supervising and researching including masonry structures. For this he was awarded the Henry Adams Bronze Medal (twice) and the Oscar Faber Diploma by the Institution of Structural Engineers.

G. Shaw was a director of Curtins with around 40 years' experience in the building industry including more than 30 years as a consulting engineer. He was continuously involved with innovative developments in structural masonry with direct responsibility for numerous important masonry structures, including the world's first prestressed masonry box girder footbridges. He was also involved in research working closely with the University of Plymouth and the Building Research Establishment and was a member of EPSRC Built Environment College. He was co-author of a number of design notes and major text books including *Structural Foundation Designers' Manual* and *Structural Masonry Detailing*.

J. K. Beck, a former director of Curtins, is an engineer with many years' experience at home and abroad. Among the many structural masonry projects he has designed and supervised is, probably, the tallest slender crosswall structure in Europe. He served on the Institution of Structural Engineers ad hoc committee on Design of Masonry Structures and was co-author of *Structural Masonry Detailing*.

W. A. Bray joined Curtins in 1977. He was a group leader responsible for the design and supervision of many masonry structures including the world's first post-tensioned diaphragm wall structure. He later left the practice to follow another career path, via contracting.

Dave Easterbrook is a chartered engineer who has worked in local authority and consultancy for 13 years before joining The School of Civil and Structural Engineering at the University of Plymouth in 1991. He lectures in structural design and his research is focused on structural masonry. He worked in conjunction with the late Gerry Shaw of Curtins on the construction of the first prestressed masonry flat arch structures built at Tring, Herts, and alongside Gerry in his role as a Professor in the principles of engineering design at Plymouth. He is a member of The Institution of Structural Engineers' Codes Panel.

Notation

A	cross-sectional area
A_s	cross-sectional area of primary reinforcing steel
A_{sc}	area of compressive reinforcement
A_{sv}	area of shear reinforcement
a	depth of stress block or shear span
a_v	shear span (distance from support to concentrated load)
B	width of bearing under a concentrated load
B_r	centre-to-centre of cross-ribs in diaphragm wall
BM	bending moment
b	width of section
b_c	breadth of compression face
b_r	clear dimension between diaphragm cross-ribs
C	compressive force
C_c	total compressive force
C_s	compressive force in reinforcement
C_{pe}	wind, external pressure coefficient
C_{pi}	wind, internal pressure coefficient
D	overall depth of diaphragm wall section or depth of arch
Dia	diameter of reinforcing bar
d	effective depth to tensile reinforcement and depth of cavity (void) in diaphragm wall
d_n	depth to neutral axis
d_2	depth to compression reinforcement
E	Young's modulus of elasticity
E_m	modulus of elasticity of masonry
E_u	nominal earth and water load
e	eccentricity
e_a	additional eccentricity due to deflection in wall
e_{ef}	effective eccentricity
e_m	the larger of e_x and e_t
e_{max}	maximum eccentricity that can be practically accommodated in section
e_t	total design eccentricity at approximately mid-height of wall
e_x	eccentricity at top of wall
F_k	characteristic load
F_m	average of the maximum loads carried by two test panels
F_t	tie force
F_b, f_b	characteristic anchorage bond strength
f_{bs}	characteristic local bond strength
f_c	design axial stress due to minimum vertical load
f_k	characteristic compressive strength of masonry
f_{ki}	characteristic compressive strength of masonry at age when post-tensioning force is applied
f_{kx}	characteristic flexural strength (tensile) of masonry
f_{kxpar}	value of f_{kx} when plane of failure is parallel to bed joints
f_{kxperp}	value of f_{kx} when plane of failure is perpendicular to bed joints
f_t	theoretical flexural tensile stress or flange thickness
f_{uac}	design axial compressive stress
f_{ubc}	flexural compressive stress at design load
f_{ubt}	flexural tensile stress at design load
f_v	characteristic shear strength of masonry
f_w	flange width
f_y	characteristic tensile strength of steel
G_k	characteristic dead load
g_A	design vertical load per unit area
g_B	design load per unit area due to loads acting at right angles to the bed joints
g_d	design vertical dead load per unit area
H_z	thrust at crown of arch
h	clear height of wall or column between lateral supports
h_a	clear height of wall between concrete surfaces or other construction capable of providing adequate resistance to rotation across the full thickness of the wall
h_{ef}	effective height or length of wall or column
h_L	clear height of wall to point of application of lateral load
I	second moment of area/moment of inertia
I_{na}	second moment of area about neutral axis
K	stiffness coefficient
K_a	constant term relating design strengths of steel and masonry
K_1	shear stress coefficient for diaphragm walls
K_2	trial section stability moment coefficient for diaphragm walls
k	multiplication factor for lateral strength of axially loaded walls
k_1	$\frac{1-\sin\theta}{1+\sin\theta}$ from Rankine's formula for retained materials
L	length
L_a	a span in accidental damage design
L_{ef}, l_{ef}	effective length
L_f	spacing of fins, centre-to-centre
l_a	lever arm
M, M_A	applied design bending moment
M_a	design bending moment at base of wall
M_d	design moment of resistance
MR	moment of resistance
MR_s	stability moment of resistance
M_{rb}	moment of resistance of a balanced section
M_{rs}	moment of tensile resistance
M_w	design bending moment in height of wall

N design vertical axial load
N_b design vertical axial strength at balanced condition
N_d design vertical axial strength
N_0 design vertical axial strength when loaded on the centroidal axis
N_s number of storeys in building
NA neutral axis
n axial load per unit length of wall, available to resist arch thrust
n_w design vertical load per unit length of wall
P design post-tensioning force
P_k characteristic post-tensioning force
P_{lim} acceptance limit for compressive strength of units
P_0 specified compressive strength of units
P_u mean compressive strength of units
p_{ubc} allowable flexural compressive stress
p_{ubt} allowable flexural tensile stress
Q constant term for design flexural strength of masonry in compression or radius of arch curve
Q_k characteristic superimposed load
q dynamic wind pressure
q_{lat} design lateral strength per unit area
q_1 design horizontal pressure at any depth (from retained material)
R radius of arch
r ratio of area of reinforcement to area of section or width of flat metal shear connector or radius of gyration
r_d projection of rib (or fin) beyond flange (in a T profile)
r_t rib (or fin) thickness (in a T profile)
s vertical spacing of flat metal shear connectors
S clear span of arch
SR slenderness ratio
S_d section depth
S_n strain constant
S_v spacing of link reinforcement
T total tensile force or thickness of diaphragm leaf or flange
t thickness of wall (or depth of section)
t_{ef} effective thickness of wall
t_f thickness of flange
t_p thickness of a pier
t_r thickness of a cross-rib in a diaphragm wall
t_w width of masonry section in vertical shear
u thickness of flat metal shear connector
UDL uniformly distributed load
V, v shear force
v_h design vertical shear stress on masonry section
W, w axial load
W own weight of effective area of fin wall per metre height
W_k characteristic wind load
W_{k1} design wind pressure, windward wall
W_{k2} design wind pressure, leeward wall
W_{k3} design wind pressure uplift (on roof)
w_s width of stress block
x_n depth to neutral axis from top of beam
Y_1 fin dimension, neutral axis to end of fin
Y_2 fin dimension, neutral axis to flange face
Y_u deflection of test wall in mid-height region
Z section modulus
Z_1 minimum section modulus of fin
Z_2 maximum section modulus of fin
z lever arm
α bending moment coefficient for laterally loaded panels
β capacity reduction factor
γ_f partial safety factor for loads
γ_m partial safety factor for materials
γ_{mb} partial safety factor for bond between reinforcement and mortar or grout
γ_{mm} partial safety factor for compressive strength of masonry
γ_{ms} partial safety factor for steel reinforcement
γ_{mv} partial safety factor for masonry in shear
δ deflection
δL short linear measurement
ε strain in reinforcement
μ orthogonal ratio
ρ density
Σu sum of the perimeters of the tensile reinforcement
Ψ_m reduction factor for strength of mortar
ψ_u unit reduction factor
Ω trial section coefficient for fin walls

1 Introduction

The use of masonry as the major structural material in house-building has maintained its market share but the use in multi-storey structures has been eclipsed by the greater use of steel and concrete frames often clad in materials other than masonry. This is a pity but has been brought about primarily by changes in health and safety regulations relating to working practices and the shortage of skilled bricklayers.

It is well known that brickwork forms an attractive cladding and that both brickwork and blockwork are durable sustainable materials with good base thermal and acoustic insulation and excellent fire resistance. Both can be more economic and faster to build if designed and detailed by a knowledgeable structural engineer. In their highly stressed, slender, modern forms, current masonry structures have no resemblance to previous thick masonry structures.

1.1 Present Structural Forms

The two most common forms of multi-storey masonry construction are crosswall and cellular construction (see Figures 14.13 and 14.37) – which can show as much as 10% reduction in overall construction costs and time, compared with other materials. Crosswalls are extensively used in school classroom blocks where one brick thick walls have been spaced at about 7 m centres. In halls of residence, hotel bedroom blocks and similar applications, half brick thick walls have been used spaced at about 3 m centres. These walls are not only space dividers and the base for acoustic barriers, but also form the structure and completely eliminate the need for columns and beams.

One of the reasons for the speed of erection mentioned earlier, is illustrated in Figure 1.1, which demonstrates the essential simplicity of brickwork and blockwork structures. A further reason is to be found in the fact that there is a continuous 'follow on' of other trades. Several contractors have successfully used the 'spiral' method to speed construction, shown in Figure 1.2, and this is described in some detail in Chapter 9 (see Figure 9.29).

Useful and economical though they are for a range of applications, both crosswall and cellular construction demand repetitive floor plans and are therefore not suited to buildings where the floor plans vary or where large flexible open spaces are required.



Figure 1.1 Speed of erection compared with steel and concrete



Figure 1.2 Sequence of masonry construction

1.2 Examples of Structural Layout Suiting Masonry

The masonry 'spine wall' (see Figure 14.36) can be used for office blocks, where precast prestressed concrete floor units can span up to 8 m onto the corridor walls or spine. Current thinking in office layout is that the depth of space from a window should be 6 m maximum for natural daylight to be enjoyed by the user. Coupled with energy costs for lighting and air-conditioning costs, this form of layout has its advantages. Masonry structures also have a naturally high thermal mass aiding natural ventilation and reducing the need for air-conditioning.

Large spaces in multi-storey structures can be achieved using columns of high strength bricks or blocks supporting concrete floors. Single-storey wide-span structures such as sports halls can be achieved by using cavity walls stiffened with brick piers, diaphragm walls and fin walls. Each of these forms provides the structure, the cladding, the base insulation and can be erected by the main contractor using one trade only.

Pier-stiffened cavity walls are economical up to 5 m in height but, above that, diaphragm and fin walls are more suitable. The diaphragm wall (see Figure 13.1) has proved very satisfactory in a number of sports halls, gymnasia, swimming pools, factories, a church, a theatre, and several mass retaining walls designed by the authors' practice.

A diaphragm wall consists of two half-brick leaves separated by a wide cavity stiffened by brick cross-ribs. The structural action is of a series of I or box sections. The cladding function is performed by the outer leaf, the insulation by and within the cavity, and the lining by the inner leaf. Many such buildings have been constructed in the north-west of England in varying weather conditions. They have suffered no distress and above all require little maintenance. Their design was chosen on its economic advantage.

The fin wall (see Figure 13.41), which acts structurally as a series of connected T sections, has been found to be highly efficient for tall single-storey structures, and could well be found useful for multi-storey work – particularly for the column warehouse-type structure. The dramatic visual effect of fin walls can be pleasing. Fin walls readily lend themselves to post-tensioning. Both post-tensioned brick fins and diaphragm walls have been built up to 10 m high and, with the results of diaphragm wall research, it is evident that post-tensioned fins and diaphragms could be built to an even greater height.

Engineers will probably be interested in the simplicity of diaphragm and fin wall design, contractors will welcome the elimination of sub-contractors and suppliers, and architects will welcome the wide choice of architectural treatments. Clients are likely to be pleased with good-looking buildings with lower heating costs, and which are durable and maintenance-free. Some cladding manufacturers proudly guarantee their products for a twenty-year life. Masonry can be guaranteed for a lot longer life and frequently its appearance improves with age.

1.3 Reinforced and Post-tensioned Masonry

Brickwork and blockwork, like concrete, have high compressive strength but relatively low tensile resistance. So, as with concrete, reinforcing and post-tensioning can be used to carry or relieve the tensile stresses. Reinforced brickwork has been used in India and Japan since the First World War and in America since the Second World War. In Britain reinforced and prestressed masonry is also used by structural engineers for structures such as retaining walls, tanks and footbridges.

The authors' practice was one of the earlier pioneers of post-tensioned masonry, particularly in low-rise structures such as schools and libraries where lateral wind loading produces excessive bending moments for traditional plain masonry. More recently the authors' practice used a synthetic rope 'Parafil' as the prestressing tendon in a footbridge design.

Current health and safety requirements, which limit the weight of any item that one person can regularly lift manually to 20 kg, have led blockwork manufacturers to produce a greater range of dense concrete blocks with voids. These voids can be used to include reinforcing bars for a reinforced masonry structure.

1.4 Arches and Vaults

Whole life costs, sustainability issues and aesthetics have led to a renewed interest in older structural forms, particularly the arch. Several highway arch bridges have been built for spans up to 15 m, producing an aesthetically pleasing form which requires little or no maintenance. The authors' practice was instrumental in the construction of two prestressed flat arch pedestrian footbridges at Tring, Herts in 1995. The arches were constructed vertically on site, prestressed and then lifted into place using a crane. This is a good example of prefabrication (see section 1.6).

1.5 The Robustness of Masonry Structures

Robustness is a requirement that all structural engineers must consider in their design work. It was previously implied in many structures which had a cellular form and in which elements were automatically tied to each other as a result of construction practice. The partial collapse of a

block of flats at Ronan Point in 1968 led to a change in Part A of The Building Regulations, which required structural engineers working on certain buildings to consider disproportionate collapse in their design. The requirement of clients and architects for lighter structures with cladding systems and open-plan layouts has led to further amendments to the The Building Regulations, Part A. The revised rules specify tying requirements and the building types which must now be designed to meet these rules. Careful design and consideration of these rules should not adversely affect the choice of masonry as a structural material.

1.6 Prefabrication

The recent initiatives in the construction industry such as Latham, Egan and the current 'Best Practice' initiative have made construction professionals think more about the whole practice of building procurement rather than just the specific requirement of each discipline. Construction is looked upon as a manufacturing process rather than an ad hoc process. There is a drive for the use of more prefabricated elements produced under factory conditions with greater quality control. The structural steelwork industry and the precast concrete industry already provide this facility.

The Construction Design and Management (CDM) Regulations impose a duty of care upon a structural engineer to consider the safe construction and maintenance of any design proposal. Linking this requirement with the fact that the majority of fatalities in the construction industry are as a result of falling from height then the choice of structure ought to limit the time any person is working at height. Prefabrication is one way of achieving this. Many multistorey structures are being clad using prefabricated panels of many materials such as glass, steel sheeting, pvc panels, to the detriment of masonry, which is a more sustainable material. Precast masonry panels have been used on structures in the past but this is reducing with the insulation requirements specified in Part E of The Building Regulations. This is a pity since masonry has an aesthetic quality which improves with age.

1.7 Future Tradesmen

There is currently a deficit of 5% in qualified brick and block layers within the industry. This is expected to increase to 7% in the short term. Construction's answer may be to use the factory produced panels described above.

1.8 Engineering Education

At the beginning of the Victorian era, bricks were the main civil and structural engineering materials. Sir Marc Brunel used reinforced brick rings for the shafts of the Blackwall Tunnel. His son, Isambard Kingdom Brunel, used brick arches of over 100 ft span to bridge the Thames at Maidenhead. Stephenson carried out research into the compressive strength of brickwork when he was designing and building the Conway Bridge. Jesse Hartley made extensive use of structural brickwork in the construction of the superb Albert Dock in Liverpool, and Telford did the same in the elegant modernised St Katherine's Dock in London. The Victorians used bricks to retain canal and railway cutting embankments, for aqueducts, tunnels and sewer linings, deep manholes and inspection chambers, road foundations, bridges, warehouses, cotton mills, factories, railway stations, churches, houses – every conceivable type of building and engineering structure.

However, the advent of steel and reinforced concrete, with their superior tensile and bending strength, marked the decline of structural brickwork. Engineers adopted the new materials with great enthusiasm and, since the end of the nineteenth century, the decrease in the use of structural brickwork has been so sharp that few, if any, engineering graduates can truely design in the material.

Many university civil engineering courses do not teach structural masonry as part of structural design studies. However as long as graduates are competent in their understanding of stress, bending theory, slenderness ratio, reinforced and prestressed material theory and other structural engineering principles, along with an awareness of construction details that will affect behaviour such as effective length of struts, then the detailed design should be learnt in practice. Undergraduate civil engineering programmes are being required to deliver a much broader curriculum than in the past and as a result few graduates can immediately design masonry structures. The graduates however should be able to produce preliminary designs for a masonry structure, based on structural engineering principles.

Using masonry as a solution to a design problem will require the masonry industry from suppliers, structural engineers and contractors to rethink their approach to design and construction and to see the many opportunities that structural masonry offers clients, users and the general public.

2 Advantages and Disadvantages of Structural Masonry

The durability of masonry when used correctly is excellent. However, as with other materials, the proper use of masonry requires an understanding of its physical characteristics, its strengths and weaknesses, the methods of construction and the availability of various shapes and textures, together with relative costs. The advantages which follow are based on the proper use of masonry.

2.1 Advantages

2.1.1 Cost

It is notoriously difficult to obtain accurate and comprehensive costs for building elements – let alone completed buildings. Too often, costs reflect the current state of the building market, and nearly always provide only the cost of erecting the building, and not the long-term cost of the building over its life.

The argument that masonry structures are labour intensive compared with steel or concrete, and are therefore, uneconomical in a high wage situation, is not borne out by the facts. The experience of the authors' practice has always been that where a masonry structure is appropriate, it has inevitably been cheaper than the other structural alternatives.

The authors have found as follows:

(1) In steel and concrete frame structures, masonry or other materials are used to form partitions, staircases and corridor walls, etc. In so many instances, if these partition and other walls are designed in loadbearing masonry they can be made to carry the loads and dispense with the need for columns and beams.
(2) The general contractor can usually erect a masonry structure, whereas steel and some other materials normally require specialist sub-contractors. Experience has shown that generally the less the amount of work put out to sub-contractors, the lower are the construction costs – always assuming, of course, that the job is within the overall capability of the main contractor. With masonry structures, not only is the number of sub-contractors reduced, but there is also a reduction in the number of site operations, trades and materials. The possibility of delays while awaiting fabrication is also overcome.
(3) Masonry buildings tend to be faster to erect, resulting in lower site overhead costs.
(4) The maintenance costs of masonry are minimal.
(5) A high degree of fire protection, thermal and sound insulation, exposure protection, etc., is readily available within masonry buildings. Adding additional material such as cavity insulation and board finishes to the structure provide the additional properties needed to meet the current regulations.

The best way to determine the differences for a particular building is to design and cost compare an appropriate structure using the various structural possibilities, including masonry, ensuring that the most economical scheme has been chosen for each material.

2.1.2 Speed of Erection

This, as was noted in the Introduction (section 1.1), is one of the main advantages of masonry construction. Unfortunately, it tends to be underrated principally due, it would seem, to the widely held though erroneous assumption that because the prefabricated frame of a building can be erected to a high level in a short time, this must result in an early completion of the whole project. Frequently though, a steel frame suddenly appears on a site, rapidly rises to roof level, and then stands rusting away waiting for the follow-on trades to work their way through the building. Ignoring the fabrication time, it is true, of course, that a steel frame has a short site erection time. On the other hand, it should be appreciated that no other construction work can take place during the erection period. This is not the case with masonry structures, where other trades can quickly follow on thus achieving a faster overall construction time for the whole building.

A masonry wall can easily be built in two days, and support a floor load soon after. Compare this with an insitu reinforced concrete column where the time taken to fix reinforcement, erect shuttering, cast concrete, cure, prop, and then strike the shutter is often more than a week.

In conclusion, it is worth pointing out that the speed of masonry construction is achieved without the same planning constraints that limit the application of system building.

2.1.3 Aesthetics

This should be mentioned, even though this aspect of building is not usually considered as being within the province of engineers. Certainly, many engineering courses do not bother to teach it.

The aesthetic appeal of a building is a complex amalgam of many factors: form, massing, scale, elevational treatment, colour, texture, etc. Masonry provides the human scale, is available in a vast range of colours and textures, and, due to the small module size of bricks and blocks, is extremely

flexible in application in that it can be used to form a great variety of shapes and sizes of walls, piers, arches, domes, chimneys, etc. Masonry structures tend to wear well and mellow with time. In our climatic and environmental conditions, many other materials perform conspicuously less well.

2.1.4 Durability

The excellent durability of masonry is obviously a great advantage. Many historic buildings and engineering structures provide living proof of this quality. It must be emphasised again, however, that this considerable functional and environmental benefit applies only to properly designed masonry (see section 2.2, Disadvantages). Provided that masonry structures are designed and built with competence and care, they should last much longer than their required life.

2.1.5 Sound Insulation

The majority of noise introduction is by airborne sound, and the best defence against this traditionally is mass – the heavier the partition, the less the noise transmitted through it. It is an added bonus if the mass structure is not too rigid. Brickwork and blockwork provides the mass without too much rigidity. However there are many lightweight wall systems also available, which perform better than the same thickness of masonry. Typical sound insulation values for a range of brick walls are given in Table 2.1.

2.1.6 Thermal Insulation

The good thermal properties of cavity walls have long been recognised and, more recently, have become critical in the attempts to conserve energy. Cavity walls and diaphragm walls can easily be insulated within the void to provide further improved thermal values. However, care is required in both the choice of external leaf which must resist rain penetration, insulation material and the details employed. Thermal insulation values for some typical masonry walls are shown in Table 2.2.

2.1.7 Fire Resistance and Accidental Damage

Charles II was no fool to insist on brick and stone buildings after the Great Fire of London in 1666. The Victorians lit fires in their mills and warehouses, yet these were surprisingly free from being burnt down. In the bombing of the Second World War, brick structures suffered less damage than steel or concrete buildings – which fact provides evidence of not only the high fire resistance of masonry structures, but also of their inherent capacity to resist accidental damage (see Chapter 8).

Brickwork and blockwork are incombustible and could not start or spread a fire. Masonry is rarely seriously damaged in fire; it does not buckle like steel, spall like reinforced concrete or burn like timber. The Building Regulations 2004,

Table 2.1 Typical sound insulation values of masonry walls

Material and construction	Thickness (mm)	Weight (kg/m^2)	Approximate sound reduction index (dB)
Brick wall plastered both sides with a minimum of 12.5 mm thick of plaster	215	415	49.5
Brick wall plastered both sides with a minimum of 12.5 mm thick of plaster	102.5	220	46
Type A concrete block. Wall plastered both sides with a minimum of 12.5 mm thick of plaster	180	340	47
Cavity wall with outer leaf of brick not less than 100 mm thick and inner leaf of 90 mm thick solid Type A concrete. Wall plastered both faces with a minimum of 12.5 mm thick of plaster	250 (including 50 mm cavity)	380	53

Table 2.2 Typical thermal insulation values of masonry walls

Construction and materials	Minimum thickness (mm)	'*U*' values external walls (W/m^2 K)
Single leaf of bricks of clay, concrete or sand–lime	327.5	1.5
Single leaf of bricks of clay, concrete or sand–lime	215	2.0
Single leaf of Type A concrete blocks	190	2.6
Single leaf of Type A concrete blocks	90	3.0
Single leaf of Type B concrete blocks	100	2.9
Cavity walls with outer leaf of bricks or blocks of clay, concrete or sand–lime not less than 100 mm thick and		
(a) inner leaf of Type A concrete blocks	100	1.7
(b) inner leaf of bricks of clay, concrete or sand–lime	100	1.5

Notes: All walls are unplastered. All materials have a 5% moisture content.

Table 2.3 Typical fire resistance values of masonry walls

Construction and materials	Minimum thickness (mm)	Notional period of fire resistance (h)
Bricks of clay, concrete or sand–lime	100	2
Solid or hollow concrete blocks of Class 1 aggregate	100	2
Solid concrete blocks of Class 2 aggregate	100	2
Hollow concrete blocks, one cell in wall thickness of Class 1 aggregate	100	2
Cavity wall with outer leaf of bricks or blocks of clay, concrete or sand–lime not less than 100 mm thick and		
(a) inner leaf of bricks or blocks of clay, concrete or sand–lime	100	4
(b) inner leaf of solid or hollow concrete bricks or blocks of Class 1 aggregate	100	4

Notes: All walls are unplastered. All walls are loadbearing. In the case of the cavity wall, the load is assumed to be on both leaves.

Schedule 8, give the following fire resistance values for masonry shown in Table 2.3.

2.1.8 Capital and Current Energy Requirements

The staggering increase in oil prices during the 1970s concentrated world attention on the energy crisis. It seems probable that the world will exhaust its fossil fuels by the middle of the 21st century, or soon after, by which time we can only hope that man's ingenuity will have learnt how to extract energy from other renewable sources such as waves, the sun and wind.

Over half the energy used in Britain and other western countries goes into the construction and running of buildings. Cars, by comparison, consume a relatively insignificant quantity of fuel. Of the total consumed by buildings, 10–15% is used in constructing buildings (capital energy) and the remainder in running buildings (current energy). Masonry buildings in conjunction with concrete floors provide most of the thermal mass of the building helping keep them warm in winter and cool in summer. The bulk of the current energy goes in heating and smaller amounts in lighting, operating lifts, etc. It has been shown in a number of studies that brick structures require the lowest capital and current energy.

2.1.9 Resistance to Movement

In Britain we live in a substantially brick-built environment, and it may certainly be claimed that loadbearing brickwork structures have been subjected to the most intensive full-scale testing, over a longer period, than any other present-day building material. The results are impressive, readily visible but, unfortunately, not very well documented.

Wartime damage, mining settlement, earthquake movement and demolition have taught engineers a great deal about the behaviour of brickwork when subjected to large deformations. Buildings can often be seen undergoing demolition, or in areas severely affected by mining, containing deformations and cantilevered projections which would be extremely difficult to justify by calculation. Observations of such cases can teach us a great deal about the use of masonry where deformation is expected, and the part which mortar strength plays in controlling the cracking of masonry under such severe conditions.

It is essential when using masonry not to use a mortar which is too strong, relative to the strength of the brick or block used in the wall. The mortar joints should always be the weak link, in order to retain any cracking within the numerous bed and perpendicular joints between bricks or blocks. A correct relationship between the mortar and the brick or block strengths will result in the total effects of the movement being distributed amongst numerous fine cracks. Such cracks are largely concealed and can be easily pointed over without becoming unsightly (see Appendices 2 and 3).

Had the partially collapsed Ronan Point tower block been built in loadbearing masonry, it is unlikely that the disproportionate collapse requirements in the Building Regulations would exist. Ronan Point was a tower block constructed in the 1960s using a prefabricated system of building. The floors and supporting walls were joined together using a jointing system specifically for this type of construction. A gas explosion in a flat on one of the upper floors led to the supporting walls being destroyed and the floor collapsing on to the floor below. This resulted in that floor also collapsing and so on until the whole of one corner of the tower block had collapsed. The joints were considered adequate for design wind loading but not robust for accidental damage such as the gas explosion. Progressive collapse would not have occurred if brickwork or blockwork had been the major structural material, and damage would have been reduced. Current disproportionate collapse regulations have evolved since then and the current disproportionate collapse regulations can be accommodated by the designer of masonry buildings, and this is dealt with in more detail in Chapter 8.

2.1.10 Repair and Maintenance

Properly designed masonry requires little or no maintenance and is extremely economical in terms of maintenance costs. With reference to its use in areas of possible high deformation, such as mining areas, a well-designed building will contain the majority of damage within the mortar and movement joints, and repointing of the masonry will repair most of the defects.

2.1.11 Ease of Combination with other Materials

The main structural quality of masonry is its ability to resist compression forces. However, this does not prevent its use in locations where bending and tension conditions have to be resisted. In most situations, sufficient precompression exists to prevent tension occurring, and in areas where this is not the case, post tensioning, reinforcing or composite action can be used to provide the combined use of masonry with high-tensile resisting materials to overcome the problem of high-tensile stresses. This is dealt with in more detail in Chapter 15.

The ability of masonry to act compositely with other materials has long been known, but not fully exploited by engineers. Demolition and building contractors continually take advantage of brickwork's true abilities, based on their experience, and it is unfortunate that many engineers are, if anything, lagging behind the more practical man.

2.1.12 Availability of Materials and Labour

The normal module size of bricks and blocks and the ready availability of their raw materials means that they can be mass produced in many locations and stocked in standard sizes. Modern transportation and packaging enable speedy delivery of bulk supplies of bricks and blocks, and reduce the number damaged in transit to a minimum. Similarly, the materials used in mortar are available in many locations and are easily transported.

Being a well-established trade, skilled bricklayers are normally available in most areas. Early discussions with the tradesmen on the site regarding the structural requirements will result in a proper understanding of the constructional and engineering needs. The inspection of completed work can be made immediately – an advantage over concrete which only tends to reveal its defects when the shutters are struck.

2.1.13 Recyclability

Masonry units can be recycled for future use in new construction, or crushed and used for hardcore/fill material in new construction. Masonry units can be expected to perform well for at least 60 years if not longer and therefore care needs to be exercised if using reclaimed units. Reclaimed units can be affected by sulphates, be flawed as a result of the reclamation process, be of variable strength and have a variable appearance. The cost of reclaimed units is only slightly lower than the cost of new units, since the reclamation process is costly. The use of reclaimed units on new construction is therefore limited.

2.2 Disadvantages

2.2.1 Lack of Education in Masonry

This was referred to in section 1.8. However, there seems justification for mentioning it again, since it must be regarded as a genuine disadvantage at the present time.

The many uses to which masonry can be put, the wide range of materials and material behaviour, and the great strides forward in the structural use of masonry, require the backing of a good sound education to prevent misuse and to ensure the maximum economy and efficiency in design and construction. Unfortunately, education has been lagging behind in developments, and this has left the construction industry in a situation where it cannot fully exploit masonry's capabilities until it is geared up to the techniques and applications.

This essential gearing up applies as much to an attitude of mind as to anything else. Industry must get rid of the attitude that masonry is an old-fashioned out of date material, and encourage modern philosophy.

Running parallel to a new philosophy must be a willingness to learn from the past. The advantage of durability, for example, must not be taken for granted, since no material is proof against poor design or bad workmanship. Consider the case of a parapet wall, badly built with absorbent masonry, inadequate mortar and no protective coping. Such a wall will become saturated and suffer from frost damage during the first severe winter. Yet the experienced designer can design a suitable wall which will survive its intended life without trouble. The durability of masonry depends on the quality of design and construction, and these, in turn, depend upon suitably educated and experienced designers and construction operatives.

2.2.2 Increase in Obstructed Area over Steel and Reinforced Concrete

Although masonry units can be obtained with extremely high crushing strengths, the design compressive strengths of masonry walls are generally lower than for steel or reinforced concrete. It follows, therefore, that for a particular loading condition, masonry will require a greater cross-sectional area.

In locations where large unobstructed areas are required, this can create problems which might make masonry unacceptable. It should be noted, however, that careful design and detailing can frequently produce an acceptable and economical scheme for many applications, and masonry should not be completely ignored for buildings requiring large unobstructed areas (see Chapter 9).

2.2.3 Problems with some Isolated Details

Like many other materials, masonry can give rise to problems in the achievement of satisfactory isolated details. For example, fair-faced masonry often creates local detailing difficulties (see Figure 2.1). These apparently minor problems require care and forethought if a satisfactory result is to be achieved. In the case of detail (a), differential movement of the two leaves must be allowed for if the brick face to the slab is to remain (see Appendix 3). In the case of detail (b), reinforced brickwork or a suitably combined lintel can overcome the problem and, in the case of (c), bricks manufactured to tight tolerances can be obtained, and these should be specified.



Figure 2.1 Vertical cross-sections

2.2.4 Foundations

Since one of masonry's main advantages over concrete is that it does not require expensive shuttering, it follows that in situations where shuttering is reduced to a small percentage of the cost, the competitive use of concrete comes into its own. Foundations come into this category, and masonry will generally be found inferior to concrete in situations where the soffit and sides of the excavations form, in effect, the majority if not all of the shuttered faces.

2.2.5 Large Openings

In situations where large openings are to be formed and a level soffit is required, reinforced concrete or steel beams are generally found to be the most economical means of support. They can be combined with the composite action of any masonry above and unless fair-faced masonry is a particular requirement for the soffit of the support, they will usually provide a more economical solution than the masonry alternative.

It must be pointed out, however, that where the soffit can be in the form of an arch, and where the horizontal reactions from such a form can be accommodated, masonry may prove more economical (see Figure 2.2).

2.2.6 Beams and Slabs

The use of masonry in situations where the dead weight of the material is the major portion of the load, and where a level soffit support is required, can often be uneconomical, and most beam and slab situations fall into this category.

The merits of masonry should nevertheless be considered for each individual scheme, taking into account recent changes in material costs and construction methods, and from this point of view, situations may well arise where the use of reinforced or post-tensioned masonry can be exploited.

2.2.7 Control Joints

In some forms of masonry construction, the need for relatively close spacing of the control joints necessary to prevent cracking from the effects of shrinkage and/or expansion can be difficult to accommodate, due to structural, visual and other constraints (see Figure 2.3). It should be remembered, however, that masonry is often required for partition walls when an independent structure is employed, and the introduction of a frame in a different material can often cause an even greater problem from differential movement.

2.2.8 Health and Safety Considerations

Figures produced by the Health and Safety Executive show that the majority of fatal accidents on construction sites



Figure 2.2 Masonry over opening



Figure 2.3 Plans on walls showing unacceptable control joints

arise from persons falling from height or persons being hit by objects falling from a height.

The Construction Design and Management (CDM) Regulations impose a requirement on engineers to design structures which can safely be constructed and maintained. This requirement applies to all aspects of the structure. The engineer therefore has to consider whether there is a safer option for a proposed building than one using masonry, remembering that masonry construction involves persons working at height for longer periods than say for prefabricated elements such as proprietary cladding systems and steelwork frames. There is also the added hazard of masonry units falling from a height during construction. The requirement for mortar to be transported to the upper floors of a building during construction also adds to the hazard of items falling from a height.

The third most common cause of accidents is tripping, and the use of masonry units on construction sites can pose a tripping hazard.

Regulations on manual lifting of objects now limit the maximum weight that is permissible for one person to lift to 20 kg. This limit is therefore restrictive to larger masonry units such as traditional concrete blocks greater than 100 mm thick. Concrete block manufacturers have overcome this problem by producing hollow block units, but this requires filling the voids in most cases, which increases the construction time at height.

3 Design Philosophy



Figure 3.1 High axial load versus low axial load

The main underlying aim should always be to keep the solutions simple, to see that the construction methods and the effects of the design upon them are carefully considered, and to ensure that the design is based upon masonry as a material in its own right, and not simply as a variation on the design of concrete structures.

3.1 Strength of Material

To exploit the structural potential of any material, it is essential to understand its strengths and weaknesses. Masonry is strong in compression and weak in tension and, in order to use the material economically, engineers must exploit the strength and overcome the weakness.

Consider the critical loading conditions for the material, two examples of which are indicated in Figure 3.1. Condition A is a masonry wall at a cross-section where only a small downward load, *W*, exists at a time when a large uplift force, *U*, is applied. Condition B is a masonry wall at a cross-section where only a small downward load, *W*, exists at a time when a large bending moment, *M*, is applied. In both cases the resulting stress in part or whole of the cross-sections will be tensile and, therefore, critical to a simple masonry form.

Consider next the further critical loading condition indicated in Figure 3.2. Condition C is a slender masonry wall subjected to a large axial load. In this case, the load which the wall can carry is severely restricted by the wall's tendency to buckle, and the condition is therefore critical to the proper exploitation of the material.

3.2 Exploitation of Cross-section

In the case of condition A (Figure 3.1), there are a number of methods of solving the problem. One is to increase the dead loading above the level considered. This can often be achieved by changing the construction, for example, roof structures can often be changed to a heavier form, but it is



Figure 3.2 Slender wall



Figure 3.3 Typical strapping details



Figure 3.4 Post tensioning application

important to check that this results in the most economical overall cost.

Alternatively, strapping or tying the elements, to which the uplift is applied, down to a level where sufficient dead weight exists to satisfy the safety requirements can be considered (see Figure 3.3 for typical roof strapping details). The use of concrete capping beams and/or post tensioning rods can also be used to 'anchor' down these forces (see Figure 3.4).

In the case of condition B (Figure 3.1), there are a number of engineering approaches which can produce different but competitive solutions. For example, consider the stress at the cross-section. It is made up of two components, W/A and M/Z where:

W = axial load
A = area of cross-section
M = applied bending moment
Z = section modulus.

Let the stress be f, then:

$$f = \frac{W}{A} \pm \frac{M}{Z}$$

It can be seen that to exploit the material, compressive stresses rather than the tensile stresses are required, i.e. a higher value of W/A than M/Z.

Assume that W and M are fixed values, then it is desirable to have a large Z value relative to the area A of the cross-section, i.e. a large Z/A ratio. This can be achieved by positioning the material to produce an increased section modulus for a similar area, e.g. diaphragm, fin wall or other geometrical section (see Figure 3.5). This, when compared with, say, a normal cavity wall gives increased Z/A ratios (see comparison in Table 3.1). It can be seen that with little increase in area, above the area of a normal cavity wall construction, massive increases in section modulus and hence Z/A ratio can be achieved. It should be noted that the sections being considered are all simple sections designed to take into account the method of construction and material being used – essential factors if real economy is to be achieved.

Considering again the two components of the stress make-up, i.e. W/A and M/Z, it can be seen that another method of increasing the value W/A would be to artificially increase W. The old method of doing this would be to add mass by increasing the amount of masonry, i.e. thickening the wall. However, an increase in the value of W can also be achieved by post-tensioning (see Figure 3.6).

This method produces extra compressive stresses in the brickwork which must then be cancelled out before any tension can be developed, thereby helping to keep the brick stresses at an acceptable level. Again the post-tensioning is kept simple by using large diameter rods rather than cables and applying the force by means of a simple threaded rod and nut bearing on to an endplate. The force is then applied, to the required value, by tightening the nut to the specified torque (see Figure 3.6).

Table 3.1 Comparison of properties of various wall types

Wall	Area, A (m^2)	Section modulus $Z \times 10^{-3}$ (m^3) (minimum value for fin wall)	$\frac{Z}{A}$	Proportional increase in area	Proportional increase in $\frac{Z}{A}$
260 mm cavity wall	0.205	3.50	0.017	1.0	1.0
Diaphragm wall	0.245	52.49	0.214	1.2	12.6
Fin wall	0.307	26.40	0.086	1.5	5.1

Notes: Assuming fin centres at 3.0 $m^c/_c$ and Z value of effective fin only is used. Values relate to the equivalent of 1 m length of each wall type.



Figure 3.5 Shape to achieve best section



Figure 3.6 Prestressed section

Now consider condition C – axial loading (Figure 3.2). The ability of the wall to support vertical loading is restricted by its tendency to buckle, and again there are a number of ways of overcoming the problem. The most obvious is to thicken up the wall, but in many situations this is not the most economical solution and the engineer should consider other possibilities.

The stiffness of the section depends on the ratio of:

$$\frac{\text{effective height or length}}{\text{effective thickness}}$$

or

$$\frac{\text{effective height or length}}{\text{radius of gyration}}$$

i.e. L/t or L/r, depending on how the slenderness ratio or section properties are expressed. As in all struts, the greater the slenderness ratio the weaker the strut, and it is advisable in exploiting the material to reduce the slenderness ratio whenever economically possible. There are two ways, therefore, of reducing this factor. One is to improve the effective thickness or radius of gyration, and again this can be achieved by using a diaphragm or fin form (see Figure 3.5).

Alternatively, a reduction in effective length would have a similar effect and extra restraint from essential building elements should be considered. For example, if a substantial suspended ceiling or a ceiling which could be economically braced to provide restraint were in the close vicinity of the wall, then extra restraint could be provided assuming



Figure 3.7 Restraint by suspended ceiling

that the sequence of construction and sequence of loading are coordinated (see Figure 3.7). This would reduce the effective height. A further consideration would be to make use of a reduced effective length in plan, possibly by changes in the construction of intersecting partitions etc. (see plan in Figure 3.7).

These solution can often be achieved much more economically than by increasing the thickness of the wall. The above solutions bring in the exploitation of essential building elements which can also help the conditions previously considered as explained below.

3.3 Exploitation of Essential Building Elements

Consider again condition B and the two components W/A and M/Z. It has already been shown that improving Z relative to A and/or increasing W reduces the tensile stresses, but a further possibility would be to reduce the applied bending moment M. This condition now brings into consideration the overall building stability and how best to exploit the building elements to produce the most economical structure. For example, consider the simple plan shape of the single-storey sports hall building which has an open plan and simple flat roof, shown in Figure 3.8. Assume that a uniformly distributed wind loading in kN/m^2 is applied in the direction of arrow A. The walls could be designed as pure cantilevers, with a maximum bending moment of $wL^2/2$. Assume that this was the condition at the cross-section considered under condition A in Figure 3.1.

Methods of exploiting the materials at the cross-sections only have so far been considered. For economical solutions, there is a need to exploit all essential building elements. In the building shown in Figure 3.8, it can be seen that the walls best able to resist the wind forces from the direction of the arrow A are the end walls X and Y. In addition, by inspecting the section in Figure 3.8, it can be seen that the roof element, if suitably stiff and adequately fixed, could prop the tops of the walls to which the wind is applied and span as a horizontal girder (or plate) between walls X and Y, transferring its loading as a reaction to the tops of these walls. Walls which resist such reactions are often termed 'shear walls'.

Consider again the applied bending moments in the outside wall, which is now propped at roof level, and it will be found that the maximum bending moment is $wL^2/8$ which is $^1/_4$ of the previous value (see Figure 3.9).

This exploitation of essential elements applies to all building forms, particularly when considering wind forces and restraint conditions. Take the case of a multi-storey building subject to wind forces. Again, the elements on which the wind is directly applied are usually the outer cladding walls, which have their weakest axis at right angles to the wind direction (see Figure 3.10). It can been seen that the



Figure 3.8 Typical sports hall



Figure 3.9 Bending moment diagram



Figure 3.10 Plan of building subject to wind load



Figure 3.11 Composite reaction between ground beam and wall

walls best able to resist these forces are the internal crosswalls, the gable walls and the vertical shafts forming the stairs and lifts. In addition, it can be seen that the floor and roof elements could be economically designed to act as horizontal girders spanning between theses vertical wall elements and reducing the bending moments on the outer cladding walls to a minimum.

The advantage of using masonry for these forms of construction is that while they provide the essential cladding and dividing walls, they can also act as the structure – thus changing elements which would normally be required to be supported on a structural frame into the supporting elements. Moreover, the load from a structural masonry form tends to be more uniformly distributed and, therefore, at foundation level, there is less need to spread the load to reduce the bearing pressure. This makes for economies where strip, pad or raft foundations are employed.

In cases where a piled, or pier and beam, foundation must be used, masonry can also produce advantages since composite action between the ground beam and the masonry can reduce greatly the sizes of foundation beams required (see Figure 3.11). The ground beam is designed taking into account the interaction between the masonry and the reinforced concrete (rc), which gives the beam a greatly increased lever arm over that of the rc beam acting alone.

Taking a broader view of the approach to design, it is important that engineers are involved in the architectural



Figure 3.12 Plan configurations

and planning design layout and proposals at the earliest opportunity. For example, in the case of multi-storey buildings the stiffness of the structure and the distribution of bending stresses depend greatly on the overall layout of the building. In a similar manner to the exploitation of the wall section, the overall plan of a building can often be designed to satisfy both the architectural requirements and provide a high Z/A ratio to resist wind forces.

The use of 'T', 'L' and other plan configurations, can greatly enhance masonry's lateral load resistance (see Figure 3.12), as can the positioning of stairs and lift shafts.

While, from a structural point of view, the ideal layout for multi-storey structures should repeat on every floor, it is not, as some engineers think, essential if loadbearing masonry is to be used. In the same way that a concrete framed structure contains beams to pick up walls over, the masonry structure can also accommodate beams supporting loadbearing masonry above. While it should always be the designer's aim to provide repetitive plans for loadbearing walls, the masonry structure can still prove competitive for more flexible layouts.

For some buildings, the plan layout at ground floor level has to be varied from the upper floors – there is often a need for a much more open plan at this level, requiring minimum intrusion from the structural supports. Many engineers would, under such circumstances, rule out loadbearing masonry completely and introduce a framed solution for the whole structure. In practice, however, a podium construction can often be adopted combining, say, a reinforced concrete frame up to first floor level and loadbearing masonry structure from first to roof (see Figure 3.13). This form of construction has proved very economical for many schemes designed by the authors' practice.

The approach of many engineers to the problem of multi-storey structures is to first consider the most suitable locations for column supports and the most economical material with which to frame up the building. All too frequently, they fail to realise the possibilities of a loadbearing masonry solution.

From the authors' experience, loadbearing masonry is so economical and competitive that this should be considered first before contemplating a concrete or steel frame solution. But, as was stated at the very beginning of this chapter, it is essential that the proposals are kept simple and practical, and based on the use of masonry as a structural



Figure 3.13 Podium construction

material in its own right. This, after all, is no different from the requirements for other forms of construction. Steel and concrete frames behave differently from masonry, are constructed differently and should be designed differently.

For example, concrete and masonry are similar to the extent that they are both strong in compression and weak in tension. Nevertheless, this provides no grounds for supposing that a similar design approach may be adopted. The two materials are very different:

(a) Concrete tends to shrink, whereas some masonry tends to expand.
(b) Concrete is easily reinforced or pre-tensioned, while masonry is more easily post-tensioned.
(c) Thin prestressing tendons are usually required for concrete, whereas large diameter post-tensioning rods are more suitable for masonry.
(d) Concrete behaves similarly in all directions, whereas masonry behaves differently according to the direction of the stress to the bedding planes.

The variations are enormous. Hence, the design approach must be completely different. In particular, it is important not to overlook the methods of construction, since these constitute a major difference. The authors recommend that unless the reader has a good knowledge of building construction, he or she should do further reading of reliable construction text-books.

More detailed information relating to many aspects of this chapter is covered under appropriate headings in subsequent chapters of this book.

4 Limit State Design

At the design stage of a structure, it is not possible to predict accurately the loadings which will act on the structure during its planned life. Nor is it possible to define precisely the behaviour of a structure under these loadings, or to predict with certainty the strength of the materials which combine to form the structure. It is necessary, therefore, for the engineer to introduce factors of safety to be used for any given load and material. It is necessary to first define the meaning of the word 'satisfactory' when related to the use of the structure.

Obviously, one criterion for the design of the building is that it should not fall down, but there are other conditions which need to be examined. The structure should be readily useable by the occupants, as well as visually acceptable in the long term as well as the short. It should not excessively deflect or crack, and should be sufficiently durable to maintain its initial condition. There are other criteria which may be applicable to certain structures including, for example, resistance to fire, explosion, impact and vibration.

In the past, there have been two basic methods of applying a factor of safety to the design of structures. Both methods have involved the introduction of a single factor to cover all the uncertainties mentioned above, in order to ensure the stability and safety of the structure. The first method, and the one commonly used in the past, is permissible stress design. This involves determining the ultimate stresses for the materials involved, and dividing these by a factor of safety to arrive at a permissible or working stress. The second is the load-factor method which involves multiplying the working loads by a factor of safety and using the ultimate stress of the materials.

Both these techniques have their faults. The former is based on elastic stresses, and is not strictly applicable to plastic or semi-plastic materials such as masonry. The latter is applied to loads and does not take into account variations in materials. Both have the disadvantage of applying one factor of safety to cover all conditions of materials, loading, workmanship, and use of structure, thus preventing adjustments where one item is, perhaps, of a higher or lower standard than normal.

Limit state design is an attempt to consider each item more closely so as to enable a more accurate factor of safety to be applied in the design, and depends upon the case being considered. This is achieved by breaking down the overall factor of safety used in the design into its various components, and then placing a specific factor – known as a 'partial factor of safety' – on that component for a given condition. It is thus possible to build up an overall, or 'global', factor of safety from these individual factors.

The global factor of safety may be divided into two groups:

Group 1 The factor of safety to be applied to the materials and to the workmanship used in the construction of the structure.

Group 2 The factor of safety to be applied to the loads in the overall structure and the consequences of failure.

Group 1

The factor of safety for materials and workmanship will be based on the probability of the material failing to reach its expected strength. In reinforced concrete, for example, there are two basic components. One is steel, which is manufactured in a factory with a high degree of control over its production, and the probability of an inferior piece of steel is moderately low. However concrete is made from natural materials which are mixed together on site, or at a batching plant, where the degree of control is relatively reduced. In addition, the placing of the concrete will affect its overall strength and, since this is done by unskilled or semi-skilled labour, the degree of control is further reduced.

The materials used in basic structural masonry are: (a) the structural units which are manufactured from natural clays or concrete or stone, and (b) mortar which is made up of cement, sand, water and a plasticiser – usually lime. The quality control of the structural units could be likened to that of steel, with controlled sampling of the product from the production line. It is also possible to check the strength of a randomly selected unit, or group of units, by means of load tests which will give a reasonable indication of the strength of the units actually used. This is an advantage over concrete in that the method of testing concrete is to manufacture a cube which may not be cured in the same manner as the actual concrete used on site. Masonry units are, therefore, products over which there is reasonable control and some limit to the probability of failure.

Mortar presents a different problem. Although it is manufactured from similar materials to concrete, on many sites there is less control over the mixing of the ingredients, which is generally done in smaller batches than concrete, and there is only limited control over the placing of mortar. Therefore, there is a greater probability of failure. However on larger sites, where the contractor is able to establish a good site organisation, and material testing does not become disproportionately expensive, it is possible to exercise a higher degree of control over the production of masonry. Thus it is

advantageous to vary this partial factor of safety on the design of brickwork from site to site. It becomes necessary, therefore, to assess at an early stage the degree of quality control to be expected on site, and thus the partial factor to be used.

Group 2

The second group of factors is applied to the loadings to be used in the design of the structure. These factors are introduced to take account of inaccuracies in the assumed design loading, errors in the design of the structure, constructional tolerances and the consequences of failure. The dead weight of the structure may be determined reasonably accurately, but the superimposed loading is much more difficult. It is also not possible to predict accurately the probability of overloading of the superimposed load, and it is therefore necessary to use a higher factor of safety for superimposed loading than dead loading.

It is also advantageous to adjust the factors of safety for different combinations of loadings. It is unlikely, for example, that overloading of the dead, superimposed and wind loads would all occur simultaneously, and thus the factors are adjusted for various combinations of loading.

The assumptions and theories used in the design of the structure will not precisely fit the way in which the building acts. Similarly, inaccuracies during the construction of the structure will vary the actual conditions from those assumed in the design. The consequences of failure of the structure vary considerably, depending upon the type, use and location of the building. For example, the effects of failure of a shopping centre or a grandstand are quite different from those of site temporary works such as shuttering to a concrete beam.

It is thus possible to build up an overall factor of safety from those in Group 1, which are applied to the materials, and those from Group 2, which are applied to the loading used in the design of the structure. However, it is also necessary to vary safety factors depending upon the condition being investigated and designed. When checking the ultimate failure of a structure, it is obviously necessary to use a higher factor of safety than when checking the deflection of a beam. Thus the partial factors of safety must be adjusted according to the limit state being considered. The following examples should illustrate the point. Consider the following two cases: in each case the partial factors of safety are indicative and not taken from any specific British Standard Code of Practice.

Example 1

A skip of loose bricks is to be hoisted over a busy shopping street. The skip weighs 1 kN and can carry approximately 5 kN of bricks, and is to be suspended from a steel rope of ultimate tensile stress 260 N/mm^2. Since the rope is of mild steel, and to be used in town, it may be assumed that high-quality steel is available and the partial factor of safety in this material may be taken as 1.15. (Reinforced concrete design to BS 8110 has a factor of safety for steel reinforcement bars of 1.05.)

The skip is to be filled with loose bricks and could easily be overloaded and, as it passes over a busy shopping street, the consequences of failure could be serious. The partial factor of safety on the loading should therefore be taken as 1.4 of its dead load, which is not likely to be increased, and 1.8 on the live load which is liable to increase. Thus:

$$\text{Design loading} = (1 \times 1.4) + (5 \times 1.8) = 10.4 \text{ kN}$$

$$\text{Design steel stress} = \frac{260}{1.15} = 226 \text{ N/mm}^2$$

$$\text{Area of rope} = \frac{10.4 \times 10^3}{226} = 46.0 \text{ mm}^2$$

Example 2

This is a similar problem to Example 1, but with the bricks in pre-packed units of actual weight 5 kN and passing over a non-navigable river. High quality steel is not available. So an increased material factor of safety of 1.5 should be used.

The bricks are in pre-packed units of known weight and overloading is less probable. In addition, the consequences of failure are not serious, merely the loss of the bricks. The partial factor of safety on the loading should be taken as 1.3 on the dead load and 1.5 on the live load. Thus:

$$\text{Design loading} = (1 \times 1.3) + (5 \times 1.5) = 8.8 \text{ kN}$$

$$\text{Design steel stress} = \frac{260}{1.5} = 173 \text{ N/mm}^2$$

$$\text{Area of rope} = \frac{8.8 \times 10^3}{173} = 51 \text{ mm}^2$$

The factors used in masonry are explained further in Chapters 5 and 6.

5 Basis of Design (1): Vertical Loading

This and the succeeding chapter provide a basic design method based on limit state principles, and explanations of the requirements of BS 5628 as they relate to actual design. In later chapters, detailed examples will be given of the design of elements and complete structures. It will be seen from these examples that BS 5628 does not have universal application or provide a solution to all problems, and that the basis of design set out here must be extended to solve the less straightforward problems.

As a structural material, masonry is required to resist direct compression, bending stresses and shear stresses. Masonry is strongest in compression, and this characteristic will be the starting point in establishing the basis of design. Consideration will first be given to walls and columns acting in compression.

In the introduction to limit state principles (Chapter 4), it was shown that the aim of the design process is to ensure that the design strength of the particular element under consideration is greater than, or equal to, the design load the element is required to resist. The design strength of an element is a function of the characteristic strength of the masonry and the relevant partial factors of safety on the materials. This is expressed mathematically as $f(f_k/\gamma_m)$. The design load to be resisted is a function of the characteristic load and the partial factors of safety applicable to loads. This is expressed mathematically as $f(\gamma_f F_k)$.

Thus the aim of the design process may be expressed by the formula:

$$f\left(\frac{f_k}{\gamma_m}\right) \geq f(\gamma_f F_k)$$

where

f_k = characteristic compressive strength of masonry
γ_m = partial factor of safety on materials
F_k = characteristic loading
γ_f = partial factor of safety for load
f is a mathematical function involving the symbols in parentheses.

5.1 Compressive Strength of Masonry

A wall or column carrying a compressive load behaves like any other strut, and its loadbearing capacity depends on the compressive strength of the materials, the cross-sectional area and the geometrical properties as expressed by the slenderness ratio (see Figure 5.1).

The compressive strength of a wall depends on the strength of the units used, the bricks or blocks, and the mortar. The assessment of the combined strength of these elements will also be affected by the degree of quality control exercised in manufacture and construction. The slenderness ratio, in turn, depends upon the effective height (or length, as will be seen later) and the effective thickness of the wall or column.



Figure 5.1 Factors affecting the compressive strength of masonry

5.2 Characteristic Strength and Characteristic Load

The terms 'characteristic strength' and 'characteristic load' have already been used. These occur frequently in limit state design, and should be explained. They derive from the statistical methods used to analyse a number of different results.

If, when considering the compressive strength of a number of bricks, the values of compressive strength are plotted graphically against the number of bricks reaching each specified strength, then a distribution curve is obtained (see Figure 5.2). This graph shows most of the results to be close to one particular value, with a fewer number of results (samples) at greater or lower strengths. If a sufficiently large sample is taken, then the distribution curve can be approximated to the 'normal' or Gaussian distribution (see



Figure 5.2 Plot of brick strength



Figure 5.3 Gaussian distribution



Figure 5.4 Probability of brickwork strength

Figure 5.3). The peak of this curve corresponds to the 'mean' strength of the samples, and the area beneath the curve (defined as unity) represents probability. The area under the curve to the left of the vertical line, at any value of compressive strength, represents the probability that any result will have a strength less than that being considered. Figure 5.4 shows that the probability of any brick or block having a strength of less than x is 0.05, i.e. 1 in 20 of the bricks or blocks will have a strength less than x.

The 'standard deviation' of a set of results is the term used to quantify how narrow a range the results cover. Standard deviation, is defined mathematically as:

$$\sigma = \sqrt{\left(\frac{\Sigma(\bar{x} - x_n)^2}{n-1}\right)}$$

i.e. it is the square root of the sum of all the differences between each result and the mean, multiplied by itself and divided by the number of differences. The values of standard deviation may be plotted on the normal distribution curve (see Figure 5.5).

Thus to obtain a value of strength above which a certain proportion of the results will probably lie, it is only necessary to take the mean strength and add or subtract



Figure 5.5 Normal distribution curve

a certain fraction of the standard deviation. Therefore, if it is required that not more than 1 in 20 of the results should fail, in order to achieve a required factor of safety, then the strength corresponding to this value can be defined in terms of:

$$(\text{mean strength}) - K \times (\text{standard deviation})$$

where K is the relevant factor corresponding to the 1 in 20 limit, which is 1.64 from published probability tables.

The value of the strength so obtained is termed the *characteristic strength*.

$$\text{Characteristic strength} = (\text{mean strength}) - 1.64 \times (\text{standard deviation})$$

Similarly, the values of flexural and shear strength may be obtained.

The characteristic strength of masonry in compression, shear, tension, etc., as defined in BS 5628, is the value of strength below which the probability of test results failing is not more than 5%, i.e. 1 in 20. Note however that BS EN 771, Part 1 allows for the use of category II units, which do not meet this requirement (see Appendix A).

Ideally, the dead and imposed loadings should be based on similar statistical concepts. At present, however, insufficient data are available to express loads in statistical terms. In practice, the values given in appropriate British Standards are used as follows:

(a) ***Characteristic dead load***, G_k. The weight of the structure complete with finishes, fixtures and permanent partitions. This is taken as being equal to the dead load, as defined and calculated in accordance with BS 6399: Part 1.
(b) ***Characteristic imposed load***, Q_k. The imposed load as defined in and calculated in accordance with BS 6399: Part 1.
(c) ***Characteristic wind load***, W_k. The wind load calculated in accordance with BS 6399: Part 2: 1997.

The characteristic load, as defined in BS 5628, is ideally the load which has a probability of not more than 5% of being exceeded where the load acts unfavourably, that is, for example, if the load were likely to cause overstressing. Where the load may be providing stability, e.g. restraining a cantilever beam, it is acting favourably and it is defined as the load which has a probability of at least 95% of being exceeded (see BS 5628, clause 22).

(d) ***Nominal earth and water load***, E_u. The worst credible earth and water lateral loads should be obtained in accordance with BS 8002. Other lateral loads used other than worst credible earth and water lateral load should be obtained in accordance with current practice.

5.3 Partial Safety Factors for Loads, γ_f

Inaccuracies are likely to arise in practice due to errors in design assumptions, errors in calculations, the effect of construction tolerances, possible load increases and unusual stress redistribution. Such errors are taken into account by applying a partial factor of safety, γ_f, to the characteristic loads, so that:

$$\text{Design load} = \text{characteristic load} \times \text{partial factor of safety}$$
$$= G_k \times \gamma_f + Q_k\gamma_f + W_k \times \gamma_f$$

where

G_k = characteristic dead load
Q_k = characteristic imposed load
W_k = characteristic wind load.

The partial factors applied to each type of loading vary according to the accuracy of the estimation of that loading. For example, the characteristic dead load may be assessed more accurately than the characteristic imposed loading. This is reflected in the 1.4 partial safety factor applied to the dead load, and the 1.6 factor applied to the imposed loading. However, it should be noted that where the imposed loading may be more accurately assessed, e.g. a water-retaining structure, it would be reasonable to adjust the partial safety factor.

The partial factor of safety takes into account the importance of the limit state being considered, the accuracy of the estimate of the loadings and the probability of the load combination. It does not account for gross errors in design calculations or faulty construction.

The partial factors of safety given in BS 5628, Part 1 are shown in Table 5.1.

Example 1

The characteristic loads (from BS 6399) for a floor used for offices are:

(a) characteristic dead load, $G_k = 3.0\ \text{kN/m}^2$
(b) characteristic imposed load, $Q_k = 2.5\ \text{kN/m}^2$ (offices for general use)

Determine the design load.

$$\text{Design load} = G_k\gamma_f + Q_k\gamma_f$$
$$= (3.0 \times 1.4) + (2.5 \times 1.6)$$
$$= 4.2 + 4.0$$
$$= 8.2\ \text{kN/m}^2$$

Loads on walls from uniform continuous floor and roof slabs are normally calculated on the assumption that the beams and slabs are simply supported by the walls. However, the structural designer should check that this is a satisfactory assumption.

5.4 Characteristic Compressive Strength of Masonry, f_k

The characteristic compressive strength of masonry depends upon:

(a) the characteristic strength of the masonry unit
(b) mortar designation
(c) the shape of the unit
(d) whether the work is bonded or unbonded
(e) thickness of the mortar joints
(f) the standard of workmanship.

(a) Units

Typical characteristic strengths of masonry units are given in Table 5.2. The specification for masonry units BS EN 771, Part 1 is performance based and therefore does not provide characteristic strengths, although it does not prohibit the use of standard strengths in member nations (see Appendix A). BS EN 771 specifies units in terms of materials

Table 5.1 Partial factors of safety on loadings for various load combinations (BS 5628, clause 22)

Loaded combination	Limit state – ultimate			
	Dead	Imposed	Wind	Earth and water
Dead and imposed	$1.4G_k$ or $0.9G_k$	$1.6Q_k$		$1.2E_u^a$
Dead and wind	$1.4G_k$ or $0.9G_k$		the larger of $1.4W_k$ or $0.015G_k$	$1.4E_u^a$
Dead and wind – freestanding walls and laterally loaded panels whose removal would in no way affect the stability of the remaining structure	$1.4G_k$ or $0.9G_k$		the larger of $1.2W_k$ or $0.015G_k$	
Dead, imposed and wind	$1.2G_k$	$1.2Q_k$	the larger of $1.2W_k$ or $0.015G_k$	$1.2E_u^a$

[a] The authors would add a note of caution when using these specific partial safety factors applied to earth pressures. Earth pressures are the most difficult loads to predict and these values should only be used where there is a high degree of confidence in the calculated earth pressures.

Table 5.2 Compressive strength of masonry units

	Compressive strength of unit (N/mm^2)			
	Bricks	Blocks		
Typically available values	5.0	2.8	↑	Typical structural units
	10.0	3.5		
	15.0	5.0		
	20.0	7.0		
	27.5	10.0	↓	
	35.0	15.0	↑	Blocks of these strengths may not be readily available
	50.0	20.0		
	70.0	35.0	↓	
	100.0			

Table 5.3 Requirements for mortar (BS 5628, Part 1)

	Mortar designation	Type of mortar (proportion by volume)			Mean compressive strength at 28 days (N/mm^2)	
		Cement : lime : sand	Masonry : cement : sand	Cement : sand with plasticizer	Preliminary (laboratory) tests	Site tests
↑ Increasing strength / ↓ Increasing ability to accommodate movements, e.g. due to settlement, temperature and moisture changes	(i)	1 : 0 to 1/4 : 3	–	–	16.0	11.0
	(ii)	1 : 1/2 : 4 to 4 1/2	1 : 2 1/2 to 3 1/2	1 : 3 to 4	6.5	4.5
	(iii)	1 : 1 : 5 to 6	1 : 4 to 5	1 : 5 to 6	3.6	2.5
	(iv)	1 : 2 : 8 to 9	1 : 5 1/2 to 6 1/2	1 : 7 to 8	1.5	1.0
		Increasing resistance to frost attack during construction →				
		Improvement in bond and consequent resistance to rain penetration ←				

Note: Direction of change in properties is shown by the arrows

rather than as brick or block, e.g. clay unit or aggregate concrete masonry unit. This conflicts with BS 5628 which still refers to brick and block units.

(b) Mortar

The designated grades of mortar given in BS 5628, Table 1, are provided in Table 5.3.

(c) Unit Shape

It has been found by experiment that, for a given unit strength, the larger the individual units which comprise the wall or column under consideration, the higher the strength of the resulting construction. This is reasonable when it is realised that the joints in properly designed masonry should be the weakest point of any construction, and the larger the units the fewer the number of mortar joints.

(d) Bond

The values quoted in the tables which follow (Tables 5.4, 5.5, 5.6 and 5.7), based on BS 5628, Table 2, are for 'normally bonded masonry'. This is taken to mean stretcher bond for single-leaf walls, and Flemish or other equivalent bond for greater than single-leaf walls. It would appear that, provided one of the established bond patterns is adopted, variations in bond have little effect on the comparative strength of the wall or column.

(e) Joint Thickness

The main structural role of the mortar in masonry construction is to provide a bedding between the units to ensure the uniform transfer of compressive stress. As stated previously, the mortar joint is the weakest element of masonry construction. Generally, the thicker the joints, the weaker the resulting structure. The conventional joint thickness is 10 mm. Reasonable variations on this thickness will not usually be critical but thicknesses in excess of 13 mm are generally unacceptable. However, the evenness and line of the mortar joints provide a good guide to the quality of workmanship and, in the case of face work, are of aesthetic importance.

(f) Standard of Workmanship

This, perhaps, is the most important factor to be considered because it can affect all the items listed previously. Control of the unit manufacture, under factory conditions, may be fairly sophisticated, but control of workmanship on site is far more difficult. Account is taken of the possible variations in workmanship in the partial factors of safety. This will be discussed later in this chapter.

5.4.1 Brickwork

Table 5.4 gives the characteristic compressive strength, f_k, of normally bonded brickwork constructed with standard format bricks. The values quoted are for walls constructed under laboratory conditions, tested at an age of 28 days under axial compression in such a manner that the effects of slenderness (see later) may be neglected. Linear interpolation within the table is permitted, and Figure 5.6(a) may be used for this purpose.

Where solid walls or the loaded inner leaf of a cavity wall are constructed in standard bricks with a thickness equal to the width of a single brick, the values of f_k obtained from Table 5.4 may be multiplied by 1.15. These enhanced values of f_k for so-called narrow brickwork have been computed and are given in Table 5.5. This increase is based on

Table 5.4 Characteristic compressive strength of masonry, f_k: standard format bricks (BS 5628, Table 2(a))

Mortar designation	Compressive strength of unit (N/mm^2)								
	5	10	15	20	27.5	35	50	70	100
(i)	2.5	4.4	6.0	7.4	9.2	11.4	15.0	19.2	24.0
(ii)	2.5	4.2	5.3	6.4	7.9	9.4	12.2	15.1	18.2
(iii)	2.5	4.1	5.0	5.8	7.1	8.5	10.6	13.1	15.5
(iv)	2.2	3.5	4.4	5.2	6.2	7.3	9.0	10.8	12.7

Table 5.5 Characteristic compressive strength of masonry, f_k: narrow walls – standard format bricks (i.e. 1.15 × Table 5.4 values)

Mortar designation	Compressive strength of unit (N/mm^2)								
	5	10	15	20	27.5	35	50	70	100
(i)	2.9	5.0	6.9	8.5	10.6	13.1	17.3	22.1	27.0
(ii)	2.9	4.8	6.1	7.4	9.1	10.8	14.0	17.4	20.9
(iii)	2.9	4.7	5.8	6.7	8.2	9.8	12.2	15.1	17.8
(iv)	2.5	4.0	5.0	6.0	7.1	8.4	10.4	12.4	14.6

Table 5.6 Characteristic compressive strength of masonry, f_k: narrow walls – modular bricks

Mortar designation	Compressive strength of unit (N/mm^2)								
	5	10	15	20	27.5	35	50	70	100
(i)	3.1	5.5	7.5	9.3	11.5	14.3	18.8	24.0	30.0
(ii)	3.1	5.3	6.6	8.0	9.9	11.8	15.3	18.9	22.8
(iii)	3.1	5.1	6.3	7.3	8.9	10.6	13.3	16.4	19.4
(iv)	2.8	4.4	5.5	6.5	7.8	9.1	11.3	13.5	15.9

Table 5.7 Characteristic compressive strength of masonry, f_k: modular bricks

Mortar designation	Compressive strength of unit (N/mm^2)								
	5	10	15	20	27.5	35	50	70	100
(i)	2.8	4.8	6.6	8.1	10.1	12.5	15.5	21.1	26.4
(ii)	2.8	4.6	5.8	7.0	8.7	10.3	13.4	16.0	20.0
(iii)	2.8	4.5	5.5	6.4	7.8	9.4	11.7	14.4	17.0
(iv)	2.4	3.9	4.8	5.7	6.8	8.0	9.9	11.9	14.0



Figure 5.6(a) Characteristic compressive strength, f_k, of brick masonry (see Table 5.4)

experimental results and relates to the absence of a vertical mortar joint parallel with the face within the thickness of the wall.

Interpolation for classes of loadbearing bricks not shown on the graph may be used for average crushing strengths intermediate between those given on the graph.

With walls constructed in modular bricks (see Appendix 1), the values of f_k from Table 5.4 may be multiplied by 1.25 for narrow walls, as noted above, and 1.10 for a greater thickness of wall. The Code quotes these values as being applicable only for 90 mm wide and 90 mm high modular bricks complying with the requirements of BS 6073: Part 1, or as detailed in DD 34 or DD 59. These enhanced values of f_k for modular bricks have been computed and are given in Tables 5.6 and 5.7.

These standards have now been replaced by BS EN 771, Part 1, which is a performance specification. Designers should check with manufacturers if the units meet the requirements of the previous standards.

Where bricks are used which do not comply with the standard format or modular requirements, the values of f_k should be obtained from wall tests carried out in accordance with the procedures given in BS 5628.

Guidance on the choice of appropriate mortars is given in Appendix 1.

Example 2

Determine the characteristic compressive strength of brickwork constructed with standard format bricks of unit compressive strength 15 N/mm^2 and a 1 : 1 : 6 mortar.

From Table 5.3, the mortar designation is (iii) and referring to Table 5.4 the characteristic compressive strength $f_k = 5.0$ N/mm^2.

5.4.2 Blockwork

When a wall is constructed in blockwork, the increased size of the units means that there are fewer joints than an equivalent wall built with bricks of the standard format. As the joints are generally the weakest part of a wall, a reduction in the number of joints per unit length or height of wall results in an increased compressive strength for a given strength of unit and mortar. The characteristic compressive strength of blockwork thus depends more on the shape factor of the units, that is the ratio of unit height to least horizontal dimension (see Figure 5.7).

The compressive strength also varies depending on whether the units are solid or hollow (see Appendix 1).

Values for the characteristic compressive strength of walls constructed with blocks having a shape factor of 0.6 are given in Table 5.8. Values for hollow block walls with a shape factor between 2.0 and 4.0 are given in Table 5.9, and for solid block walls with similar shape factors in Table 5.10. Linear interpolation within the tables is permitted, and Figures 5.6(b) and 5.6(c) may be used for this purpose.

For values of f_k with units of shape factors between 0.6 and 2.0, interpolation should be made between Tables 5.8 and 5.10 depending on whether solid or hollow blocks are being used.

When hollow blocks are used and completely filled with insitu concrete with a compressive strength, at the appropriate age, of not less than that of the blocks, they should be treated as solid blocks as noted above. The compressive

Table 5.8 Characteristic compressive strength of masonry, f_k: blocks having a ratio of height to least horizontal dimension of 0.6 (BS 5628, Table 2(b))

Mortar designation	Compressive strength of unit (N/mm^2)							
	2.8	3.5	5.0	7.0	10	15	20	≥35
(i)	1.4	1.7	2.5	3.4	4.4	6.0	7.4	11.4
(ii)	1.4	1.7	2.5	3.2	4.2	5.3	6.4	9.4
(iii)	1.4	1.7	2.5	3.2	4.1	5.0	5.8	8.5
(iv)	1.4	1.7	2.2	2.8	3.5	4.4	5.2	7.3

Table 5.9 Characteristic compressive strength of masonry, f_k: hollow blocks having a ratio of height to least horizontal dimension of between 2.0 and 4.0 (BS 5628, Table 2(c))

Mortar designation	Compressive strength of unit (N/mm^2)							
	2.8	3.5	5.0	7.0	10	15	20	≥35
(i)	2.8	3.5	5.0	5.7	6.1	6.8	7.5	11.4
(ii)	2.8	3.5	5.0	5.5	5.7	6.1	6.5	9.4
(iii)	2.8	3.5	5.0	5.4	5.5	5.7	5.9	8.5
(iv)	2.8	3.5	4.4	4.8	4.9	5.1	5.3	7.3

Table 5.10 Characteristic compressive strength of masonry, f_k: solid concrete blocks having a ratio of height to least horizontal dimension of between 2.0 and 4.0 (BS 5628, Table 2(d))

Mortar designation	Compressive strength of unit (N/mm^2)							
	2.8	3.5	5.0	7.0	10	15	20	≥35
(i)	2.8	3.5	5.0	6.8	8.8	12.0	14.8	22.8
(ii)	2.8	3.5	5.0	6.4	8.4	10.6	12.8	18.8
(iii)	2.8	3.5	5.0	6.4	8.2	10.0	11.6	17.0
(iv)	2.8	3.5	4.4	5.6	7.0	8.8	10.4	14.6



Figure 5.6(b) Characteristic comporessive strength, f_k, of block masonry constructed of blocks having a ratio of height to least horizontal dimension of 0.6 (see Table 5.8)



Figure 5.6(c) Characteristic compressive strength, f_k, of block masonry constructed of hollow blocks having a ratio of height to least horizontal dimension between 2.0 and 4.0 (see Table 5.9)

strength of the hollow block should be based on the net area of the block and not the gross area. It will be seen in Appendix 1, dealing with materials, that the compressive strength of blocks is based on the gross area of the block for blocks tested in accordance with BS EN 772, Part 1.

Example 3

Determine the characteristic compressive strength, f_k, of a wall constructed in hollow blocks (as shown in Figure 5.8) of compressive strength 7 N/mm^2, if the blocks are filled with concrete having a 28 day compressive strength equal to that of the blocks and a mortar designation (iii) is used.

Strength of infill concrete:

Unit strength 7 N/mm^2 based on gross area
which in terms of crushing load per block

$$= \text{crushing strength} \times \text{gross area} \times \frac{1}{10^3}$$

$$= \frac{7 \times 80\,000}{10^3} = 560 \text{ kN}$$

Therefore,

crushing strength of unit based on net area

$$= \frac{\text{load} \times 10^3}{\text{net area}}$$

$$= \frac{560 \times 10^3}{50\,000} = 11.2 \text{ N/mm}^2$$

Therefore strength of concrete >11.2 N/mm^2, say, grade 15 mix to BS 8110. The infilled block thus becomes equivalent to an 11.2 N/mm^2 solid unit for purposes of determining the f_k value.

$$\text{Shape factor of unit} = \frac{\text{height}}{\text{least horizontal equation}}$$

$$= \frac{200}{200} = 1$$

The value of f_k is then obtained by interpolation between Tables 5.8 and 5.10.

Assuming a 10 N/mm^2 unit for simplicity, from Table 5.8, f_k = 4.1 N/mm^2; for mortar designation (iii) (shape factor 0.6) and from Table 5.9, f_k = 8.2 N/mm^2; for mortar designation (iii) (shape factor 2.0–4.0), therefore for a shape factor of 1,

$$f_k = 4.1 + \frac{(8.2 - 4.1) \times (1.0 - 0.6)}{(2.0 - 0.6)}$$

$$= 5.3 \text{ N/mm}^2$$

5.4.3 Natural Stone Masonry and Random Rubble Masonry

BS 5628 recommends that natural stone masonry should be designed on the basis of solid concrete blocks of an equivalent compressive strength. Construction with natural stone masonry of a massive type with large well-dressed stones and relatively thin joints has a compressive strength more closely related to the intrinsic strength of the stone. Working stresses in excess of the maximum value quoted in the previous tables may be allowed in massive stone masonry, as described, provided the designer is satisfied



Figure 5.7 Unit dimension ratios



Figure 5.8 Hollow unit example



Figure 5.9 Brick on-end construction



Figure 5.10 Shell bedding

that the properties of the stone and the method of wall construction warrant the increase.

As a guide, the Code suggests that the characteristic strength of random rubble masonry may be taken as being 75% of the corresponding strength of natural stone masonry built with similar materials. However, the structural design of stone masonry and random rubble walling requires great care, and designers should obtain detailed information on the particular design and construction methods for the type of wall being considered before attempting any detailed analysis.

5.4.4 Alternative Construction Techniques

The values for characteristic compressive strength quoted in the previous sections were for bonded masonry and thus do not necessarily apply where the method of construction varies from 'normal'.

For aesthetic or other reasons, structural units may be laid other than on their normal bed faces, e.g. brick-on-edge or brick-on-end construction. The characteristic compressive strength in such an instance is obtained from the tables quoted, but using the compressive strength of the unit as determined for the appropriate direction.

With reference to Figure 5.9, the characteristic strength of masonry for brick-on-end construction as in (A) is determined from Table 5.4 using the compressive strength of the unit obtained by testing the bricks as shown in (B).

As explained in Appendix 1, the compressive strength of hollow blocks and perforated bricks is determined by dividing the load at failure by the gross plan area of the unit. This is done so that the calculation of the strength of walls of solid and hollow units may be carried out in an identical manner, i.e. load × plan area of wall. However, where walls are constructed of hollow units, and sometimes when using perforated bricks, the units are laid with mortar on the two outer edges of the bed face only. This is termed shell bedding (see Figure 5.10).

In walls constructed in this way, the characteristic compressive strength should be obtained in the normal manner, but the design strength of the wall should be reduced by the ratio of the bedded area to the gross area of the block (see Figure 5.11). The design strength of the wall is thus equal to the f_k obtained from Tables 5.8, 5.9, 5.10, as appropriate, multiplied by a factor equal to the bedded area divided by the gross area. Thus the characteristic compressive strength of the shell bedded wall

$$= f_k \frac{2L \times t}{L \times b}$$

where f_k = characteristic compressive stress determined in accordance with section 5.1.



Figure 5.11 Bedded area to gross area

5.5 Partial Safety Factors for Material Strength, γ_m

The degree of care exercised in the control of the manufacture of the units and in the construction of the masonry affects the design strength of the wall, column, etc. The characteristic strength of masonry has to be divided by a partial safety factor to obtain the *design* strength. The partial safety factor depends on the degree of quality control on manufacture and construction. The factor also depends on whether the masonry is subject to compression loading or lateral loading. BS 5628 recognises two categories of control, namely 'normal' and 'special'.

5.5.1 Manufacturing Control (BS 5628, clause 27.2.1)

(a) Normal Category

This category is used when the supplier can meet the compressive strength requirements of the appropriate British Standard.

(b) Special Category

This category is used when suppliers can meet a specified strength limit (known as the 'acceptance limit') when not more than 2.5% (as opposed to the 5% in section 5.2) of the test results will fall below the acceptance limit, and also when the supplier's quality control scheme can satisfy the buyer that the acceptance limit is consistently met. This may be assumed where the unit manufacturer complies with the following two quality control procedures:

(a) The units supplied are to have a specified strength limit termed the 'acceptance limit' for compressive strength, such that the average compressive strength of a sample of units from any consignment selected and tested in accordance with the appropriate British Standard Specification has a probability of not more than 2.5% of being below this acceptance limit. Thus for any particular unit, the specified strength limit, i.e. the 'acceptance limit', may be set for example at 7 N/mm^2. Therefore, in any sample of these units, the strength must only have a 1 in 40 chance of falling below this acceptance limit.
(b) A quality control scheme must be operated to show that the requirements of (a) are consistently satisfied. The results of the quality control scheme should be made available to the purchaser or his representative, i.e. the designer.

5.5.2 Construction Control

(a) Normal Category

This category is assumed in design when the construction complies with the workmanship recommendations given in Annex A of BS 5628: Part 3, 2001 (which incorporates BS 8000–3 2001) or BS 8000, and the work is appropriately supervised and inspected.

(b) Special Category

This category is assumed in design when the requirements for normal category are complied with and in addition:

(a) The specification, supervision and control ensure that the construction is compatible with the use of the appropriate partial safety factors given in Table 5.11. This means in prestressed work that similar care in

Table 5.11 Partial factors of safety on materials (BS 5628, Table 4a and 4b)

γ_m for compression

		Category of construction control	
		Special	Normal
Category of manufacturing control	Special	2.5	3.1
	Normal	2.8	3.5

γ_m for flexure

		Category of construction control	
		Special	Normal
Category of manufacturing control	Special	2.5	3.0

specification, supervision, control and inspection is given to structural masonry as to high-grade concrete.

(b) Preliminary and regular mortar compressive strength tests in accordance with Appendix A of BS 5628 show that the mortar complies consistently with the strength requirements of Table 5.3.

The partial safety factors on material strength are tabulated in Table 5.11. These values do not vary for ultimate or serviceability limit state design, but may vary when considering the effects of misuse or accident (see Chapter 8).

Example 4

Determine the *design* strength of the brickwork in Example 2 (section 5.4.1) if the manufacturing and construction controls are normal category.

$$\text{Design strength} = \frac{f_k\ (\text{characteristic compressive strength})}{\gamma_m (\text{partial safety factor for materials})}$$

(γ_m is for compression)

$$= \frac{5.0}{3.5}\ \text{N/mm}^2$$

$$= 1.43\ \text{N/mm}^2$$

Example 5

Determine the design strength of the brickwork in Example 2 (section 5.4.1), the manufacturing control is normal and the construction control is special category.

$$\text{Design strength} = \frac{5.0}{2.8}\ \text{N/mm}^2$$

(γ_m is for compression)

$$= 1.78\ \text{N/mm}^2$$

5.6 Slenderness Ratio

Slender masonry walls and columns under compressive loading are likely to buckle in the same way as concrete, steel or timber columns in compression. It is therefore, necessary to determine the masonry wall's or column's slenderness ratio in order to relate a failure in buckling to the compressive load-carrying capacity of a wall or column.

The slenderness ratio (SR) of masonry walls or columns is defined in BS 5628 as:

$$\frac{\text{effective height (or length)}}{\text{effective thickness}} = \frac{h_{ef} \quad \text{or} \quad l_{ef}}{t_{ef}}$$

(The term 'effective' is dealt with later.) The effective length should be used where this gives the lesser SR.

Example 6

A wall has an effective height of 2.25 m and an effective thickness of 102.5 mm. Determine its SR.

$$\text{SR} = \frac{\text{effective height}}{\text{effective thickness}}$$

$$= \frac{2250}{102.5} = 22$$

This concept is satisfactory for walls and other sections which are rectangular on plan. However, it is difficult to apply to other geometrical configurations. The Code gives no guidance for such instances, but, for diaphragm and fin walls, guidance is given in the relevant sections of this book.

The slenderness ratio is a measure of the tendency of a member under compressive loading to fail by buckling before failure by crushing occurs. The greater the slenderness ratio, the greater the tendency for the member to fail by buckling, and thus the lower the loadbearing capacity of the member.

BS 5628 (clause 28.1) generally limits the slenderness ratio to not greater than 27. However, in the case of walls less than 90 mm thick in buildings of more than two storeys, this value should not exceed 20. This exception to the general rule should be interpreted as meaning thin walls which are *continuous* for more than two storeys.

5.7 Horizontal and Vertical Lateral Supports

The effective heights and effective lengths used to determine the slenderness ratio of an element are determined from the actual height or length, which is then modified, depending on the restraint conditions, i.e. the manner in which the member is restrained from buckling by adjacent members. The support provided by adjacent members will generally be at right angles to the member and is thus termed a 'lateral' support. In the case of the slenderness ratio being determined from the effective height, the lateral supports (such as floors and roofs) at right angles to the member are acting in a horizontal plane, and are thus termed horizontal lateral supports.

In the case of the slenderness ratio being determined from the effective length, the lateral support at right angles to the member are acting in a vertical plane, and are thus termed vertical lateral supports, as illustrated in Figure 5.12.

To be considered as a lateral support for the purposes of assessing the effective height, or length, the lateral support should be capable of transmitting to the supporting structure (i.e. the walls or other elements providing lateral stability to the structure as a whole) the sum of the following forces:

(a) the simple static reactions to the total applied design horizontal forces at the line of lateral support, and

(b) 2.5% of the total design vertical load (dead plus imposed) that the wall, or other element, is designed to carry at the line of lateral support.

Example 7

For the wall shown in Figure 5.13, determine the loading on the support at mid-height for this to be considered as a horizontal lateral support. (It is assumed in this example, but unlikely in practice, that the foundation and roof over are incapable of providing horizontal lateral support.)



Figure 5.12 Buckling restraints



Figure 5.13 Restraint example

Horizontal lateral support must be capable of resisting:

(a) simple static reactions, i.e.

$$1.2W_k \times h = 1.2W_k h \text{ kN/m}$$

plus

(b) $2^1/_2$% of total design vertical load, i.e.

$$\frac{2.5}{100} \times (1.2G_k + 1.2Q_k + \text{self-weight of wall from A to B}) \text{ kN/m}$$

Note:

(i) The wind loading is capable of reversal, and thus in practice, both a prop and a tie are required. The dead load and imposed load are also reversible.
(ii) The loading on the prop from the wind must be transferred via floors, walls, etc., to the foundations.

5.7.1 Methods of Compliance: Walls – Horizontal Lateral Supports

There are many methods of providing horizontal lateral supports, some are given in BS 5628 and will be described later. The Code separates several forms of support which are defined as providing 'enhanced' resistance to lateral movement. The remainder only provide 'simple' resistance to lateral movement. The details suggested in the Code for simple restraint are given in Figure 5.14. Those details providing 'enhanced' restraint are defined as follows and illustrated in Figure 5.15:

(a) Floors or roofs of any form of construction which span on to the wall, or other element, from both sides at the same level.



Figure 5.14(a) Timber floor bearing directly on to wall



Figure 5.14(b) Timber floor using typical joist hanger



Figure 5.14(c) Timber floor using nailed or bolted joist hangers acting as a tie



Figure 5.14(d) Typical joist hanger as tie: nailed form



Figure 5.14(e) Typical joist hanger as tie: bolted form



Figure 5.14(f) Insitu concrete floor abutting external cavity wall



Figure 5.14(g) Beam and pot floor abutting external cavity wall



Figure 5.14(h) Precast units abutting external cavity wall



Figure 5.14(j) Timber floor abutting external cavity wall



Figure 5.14(k) Timber floor using double joist hanger acting as tie



Figure 5.14(l) Timber floor using typical joist hanger



Figure 5.14(m) Timber floor abutting internal wall



Figure 5.14(n) Insitu floor abutting internal wall



Figure 5.14(p) Beam and pot floor abutting internal wall



Figure 5.14(q) Precast units abutting internal wall



Figure 5.15 Details providing 'enhanced' resistance

(b) An insitu concrete floor or roof, or a precast concrete floor or roof, giving equivalent restraint, irrespective of the direction of span, having a bearing of at least one half the thickness of the wall, or other element, or 90 mm, whichever is greater.
(c) For houses of not more than three storeys, a timber floor spanning on to a wall from one side only, but having a bearing of not less than 90 mm. The Code does not state explicitly in this clause that metal restraint straps are required in this situation, but this is implied and certainly recommended by the authors.

It should be emphasised that, when considering the above conditions, the restraining member, i.e. floor or roof construction, must be capable of resisting the required loading given in section 5.7, and transmitting the static reactions to other members providing the overall stability. This is particularly important in the case of timber trussed rafters. It is also essential that the straps and ties are able to transmit the restraint loads from the wall into the floor or roof structure.

The requirement that a precast concrete floor, or roof, should provide restraint equivalent to that of an insitu slab, needs careful detailing, especially if a 'beam and pot' construction is to be adopted without a structural screed. The precast units must be capable of resisting the required loading and transferring the forces back to the stabilising walls.

5.7.2 Methods of Compliance: Walls – Vertical Lateral Supports

Vertical lateral supports are, as with horizontal lateral supports, classed as those providing simple resistance and those providing enhanced resistance. Such vertical supports must be capable of resisting the forces defined in (a) and (b) of section 5.7, and also of transmitting the static reactions to suitable foundations. Once again, the Code gives 'rule of thumb' details, and allows that, in other cases, suitable lateral supports may be confirmed by calculation. There appear to be no criteria, however, for verifying that a support is in fact an enhanced support within the terms of the Code. The Code requirements are illustrated in Figures 5.16 and 5.17 and defined as follows:

(a) Simple resistance may be assumed where an intersecting or return wall, not less than the thickness of the supported wall, extends from the intersection at least ten times the thickness of the supported wall, and is connected to it by metal anchors (ties) designed to resist the assumed lateral forces (i.e. simple static reactions and 2.5% of the vertical load, as defined previously). The Code also stipulates that the ties should be evenly distributed throughout the height, at not more than 300 mm centres. In the case of cavity wall construction, the thickness of the intersecting or return wall should be not less than the thickness of the loadbearing leaf, and should extend from the intersection at least ten times the thickness of the loadbearing leaf. If both leaves are loadbearing, then it is reasonable to assume that the construction is adequate if the requirements are met for one leaf only, or for the thicker leaf if different thicknesses are used.



Figure 5.16 Simple vertical lateral supports



Figure 5.17 Vertical lateral supports providing 'enhanced' resistance

(b) Enhanced resistance may be assumed where an intersecting or return wall is properly bonded to the supported wall or leaf of a cavity wall. Thickness and length requirements are as (a) above.

On the basis of this and later Code requirements, it would appear that enhanced resistance to lateral movement may be assumed where calculation verifies that a restraint provides the equivalent rotational resistance, or continuity, as would properly bonded construction.

5.8 Effective Height or Length: Walls

As stated in section 5.7 the effective height or length, used in the determination of the slenderness ratio of an element, is based on the actual height or length which is modified depending on the restraint conditions. Examples of simple and enhanced restraints have been given in the previous section, and the effective height or length may be determined



Figure 5.18 Examples of effective heights for walls

in accordance with BS 5628 from the actual height or length as follows.

The effective height is equal to either

(a) 0.75 times the clear distance between horizontal lateral supports which provide enhanced resistance to lateral movement, or
(b) the clear distance between horizontal lateral supports which provide simple resistance to lateral movement (see Figure 5.18).

Effective length is equal to either

(a) 0.75 times the clear distance between vertical lateral supports which provide enhanced resistance to lateral movement (see Figure 5.19(a)), or
(b) twice the distance between a vertical lateral support which provides enhanced resistance to lateral movement, and a free edge (Figure 5.19(b)), or



Figure 5.19(a) Typical condition (a), supports providing enhanced resistance to lateral movement



Figure 5.19(b) Typical condition (b), support providing enhanced resistance to lateral movement and a free edge

(c) the clear distance between vertical lateral supports which provide simple resistance to lateral movement (Figure 5.19(c)), or
(d) 2.5 times the distance between a vertical lateral support which provides simple resistance to lateral movement, and a free edge (see Figure 5.19 (d)).



Figure 5.19(c) Typical condition (c), supports providing simple resistance to lateral movement



Figure 5.19(d) Typical condition (d), support providing simple resistance to lateral movement



Figure 5.20 Slenderness example

Example 8

Determine the slenderness ratio for the wall as shown in Figure 5.20, assuming $t_{ef} = 102.5$ mm.

$$\text{Slenderness ratio, SR} = \text{lesser of } \frac{h_{ef}}{t_{ef}} \quad \text{and} \quad \frac{l_{ef}}{t_{ef}}$$

The concrete floor provides enhanced lateral restraint. Therefore:

$$h_{ef} = 0.75h = 0.75 \times 2.8 = 2.1 \text{ m}$$
$$t_{ef} = 102.5 \text{ mm}$$

Therefore, based on effective height, SR = 2100 /102.5 = 20.5.

$$l_{ef} = L = 2.4 \quad \text{based on condition (c)}$$

Therefore, based on effective length, SR = 2400/102.5 = 23.4

Therefore, use lesser SR = 20.5.

5.9 Effective Thickness of Walls

5.9.1 Solid Walls

For a solid wall not stiffened by intersecting or return walls, the effective thickness is equal to the actual thickness. Where a solid wall is stiffened by piers, the effective thickness, t_{ef}, is increased by an amount depending on the stiffening effect of the piers, i.e. their size and spacing.

$$t_{ef} = t \times K$$

where

t = the actual thickness of the solid wall
K = the appropriate stiffness factor, as given in Table 5.12.

Table 5.12 (BS 5628, Table 5)

Ratio of pier spacing (centre to centre) to pier width	Ratio: $\frac{\text{pier thickness}}{\text{wall thickness}} = \frac{t_p}{t}$ 1	2	3
6	1.0	1.4	2.0
10	1.0	1.2	1.4
20	1.0	1.0	1.0

Note: Linear interpolation is permissible, but not extrapolation



Figure 5.21 Effective thickness example

Example 9

Determine the effective thickness of the wall shown in Figure 5.21.

$$\frac{\text{Pier spacing c/c}}{\text{Pier width}} = \frac{3000}{215} = 13.95$$

$$\frac{\text{Pier thickness } (t_p)}{\text{Wall thickness } (t)} = \frac{317.5}{102.5} = 3.09$$

From Table 5.12, K lies between 1.4 and 1.0.
By interpolation

$$K = 1.24$$

Thus

$$t_{ef} = 1.24 \times 102.5 = 127 \text{ mm}$$

Where a solid wall is stiffened by intersecting walls, the stiffening coefficient as obtained from Table 5.12 may be used to calculate the effective thickness, in the same way as for a wall stiffened by piers. For the purposes of calculating the effective thickness, the intersecting walls are assumed to be equivalent to piers whose widths are equal to the thickness of the intersecting walls, and of thickness equal to three times the thickness of the stiffened wall (see Figure 5.22).



Figure 5.22 Solid wall stiffening effective thickness example

Example 10

Determine the effective thickness of the wall shown in Figure 5.22.

$$\frac{\text{Equivalent pier spacing}}{\text{Equivalent pier width}} = \frac{4000}{215} = 18.6$$

$$\frac{\text{Equivalent pier thickness}}{\text{Wall thickness}} = \frac{3 \times 102.5}{102.5} = 3$$

(note this value will be 3 in all cases)

5.9.2 Cavity Walls

The addition of another leaf of masonry, joined only with ties to a solid wall, will obviously reduce the tendency of the solid wall to buckle, whether only one or both of the leaves are loadbearing. However, two leaves of masonry separated by a cavity will not produce a wall of equal stiffness to that formed by properly bonding the two leaves together. The effective thicknesses of a cavity wall is thus taken to be two-thirds of the sum of the thickness of the two leaves. Where one of the leaves is thicker than the other,

the value for the effective thickness may (on that basis) be less than that of the thicker leaf alone and, in this case, the effective thickness of the cavity wall should be taken as the actual thickness of the thicker leaf.



Figure 5.23 Cavity wall thickness example

Example 11

Determine the effective thickness of the cavity wall shown in Figure 5.23.

Actual thickness of leaves = 327.5 mm and 102.5 mm

$$\text{Effective thickness of combined leaves} = {}^{2}/_{3}(327.5 + 102.5) = 286.7 \text{ mm}$$

But this combined effective thickness is less than the actual thickness of the thicker leaf alone.

Thus, for SR calculation, $t_{ef} = 327.5$ mm.

Where one of the leaves of a cavity wall is stiffened by piers, the effective thickness of this leaf should be calculated as described in section 5.9.1. The effective thickness of the cavity wall is then determined, as set out above, using the increased value for the effective thickness of the leaf stiffened with piers.



Figure 5.24 Cavity wall thickness with piers example

Example 12

Determine the effective thickness of the cavity wall shown in Figure 5.24.

From Example 9, the effective thickness of the leaf with piers is $t_{ef} = 127$ mm.

Thus the effective thickness of the cavity wall = ${}^{2}/_{3}(127 + 102.5) = 153$ mm.

5.10 Loadbearing Capacity Reduction Factor, β

In section 5.6, the tendency of structural materials to buckle under compressive loading was considered, and methods for determining the slenderness ratio for various types of wall were given in subsequent sections. The slenderness ratio is a measurement of how slender a wall is, which in turn, is a measure of the tendency to buckle when subjected to compressive loading. The higher the wall's tendency to buckle, the lower the potential strength of the wall, since it will fail by buckling before failing due to crushing of the units or joints.



Figure 5.25 Slenderness ratio example

Table 5.13 Capacity reduction factor (BS 5628, Table 7, part only)

Slenderness ratio h_{ef}/t_{ef}	β
0	1.00
6	1.00
8	1.00
10	0.97
12	0.93
14	0.89
16	0.83
18	0.77
20	0.70
22	0.62
24	0.53
26	0.45
27	0.40

Even if the characteristic strengths of the masonry in walls 1 and 2 in Figure 5.25 are equal, wall 2 will still have the higher loadbearing capacity as it is less likely to buckle than wall 1.

The design strength of a wall or column must therefore be reduced by a factor, termed the capacity reduction factor β, depending on the slenderness ratio of the wall or column. Values for β are given in BS 5628 and reproduced in Table 5.13.

It should be noted that these values for β which are, in fact, maximum or worst case values, are strictly correct only for the central fifth of the member. Over the remaining height of the member, β varies between this value and unity at restraints (see BS 5628, Appendix B).

5.11 Design Compressive Strength of a Wall

Having determined the characteristic strength of masonry, f_k, the relevant partial factor of safety for materials, γ_m, and the capacity reduction factor, β, the design strength of a wall may now be calculated. The design compressive strength is given by the product of the capacity reduction factor and the characteristic compressive strength divided by the partial safety factor for materials. This may be expressed as follows: $\beta f_k/\gamma_m$, which will give the strength as a force per unit area of wall. The design strength per unit length of wall is thus given by the formula:

$$\text{design strength per unit length} = \frac{\beta t f_k}{\gamma_m}$$

which is the expression given in BS 5628 (clause 32.2.1), where

β = capacity reduction factor (see section 5.10),
f_k = characteristic strength of masonry (see section 5.4),
γ_m = relevant partial safety factor on materials (see section 5.5),
t = actual thickness of wall.

Example 13

A wall has an effective height of 2.25 m and an effective thickness of 102.5 mm (Example 6). The brick strength is 15 N/mm^2 and the mortar mix is 1 : 1 : 6 (Examples 2 and 4). The manufacturing control is normal and the construction controls are special.

Determine: (a) the design strength of the wall,
(b) the loadbearing capacity of the wall.

$$\frac{f_k}{\gamma_m} = 1.78 \text{ N/mm}^2 \quad \text{(Example 5)}$$

$$\beta = 0.62 \quad \text{(Example 6 and Table 5.13)}$$

$$\text{Design strength} = \frac{\beta f_k}{\gamma_m}$$
$$= 0.62 \times 1.78$$
$$= 1.10 \text{ N/mm}^2$$

$$\text{Design load} = \text{stress} \times \text{area}$$
$$= 1.10 \times 102.5 \times 1 \text{ N/mm run}$$
$$= 112.75 \text{ kN/m run}$$

Example 14

Determine the loadbearing capacity of the wall given in Example 13, when both the manufacturing and construction controls are normal.

$$\frac{f_k}{\gamma_m} = 1.43 \text{ N/mm}^2 \quad \text{(Example 4)}$$

$$\text{Design strength} = \frac{\beta f_k}{\gamma_m}$$
$$= 0.62 \times 1.43$$
$$= 0.88 \text{ N/mm}^2$$

$$\text{Design load} = 0.88 \times 102.5$$
$$= 90.20 \text{ kN/m run}$$



Figure 5.26 Column slenderness example

5.12 Columns

In terms of loadbearing masonry subject to axial compressive loading, a column is only a special case in the design of walls. A column is defined in BS 5628 as an isolated vertical loadbearing member whose width is not more than four times its thickness (see Figure 5.26).

5.12.1 Slenderness Ratio: Columns

As an isolated member, a column does not gain from the lateral support provided in the longitudinal direction by the adjacent elements of a wall. The slenderness ratio of a column must, therefore, be checked in two directions, and the worst case used to determine the design strength.

The effective height of a column is defined as the distance between lateral supports, or twice the actual height in respect of a direction in which lateral support is not provided. This is illustrated in Figure 5.27 and Table 5.14.



Figure 5.27 Effective height examples

Table 5.14

End condition		Type of restraint	Effective height, h_{ef}
Column restrained at least against lateral movement top and bottom		Floor or roof of any construction spanning onto column from both sides at the same level	*h* in respect of both axes
		Concrete floor or roof, irrespective of direction of span, which has a bearing of at least $^2/_3$ *t* but not less than 90 mm	*h* in respect of both axes
Column restrained against lateral movement at top and bottom by at least two ties 30 × 5 mm min. at not more than 1.25 m centres		No bearing or bearing less than case above Floor or roof or any construction irrespective of direction of span	*h* in respect of minor axis 2*h* in respect of major axis



Figure 5.28 Effective thickness examples

The effective thickness of a solid column is equal to the actual thickness, *t*, relative to the direction being considered. The effective thickness of a cavity column, perpendicular to the cavity, is taken as two-thirds of the sum of the leaf thicknesses, or the actual thickness of the thicker leaf, whichever is the greater. In the other direction, the effective thickness is equal to the plan length of each leaf (see Figure 5.28). As in the case of walls, the slenderness ratio of a column about either axis is restricted to not more than 27.

In respect of isolated columns, the Code does not specifically provide for any reduction in the effective height if enhanced lateral supports are provided. It would seem reasonable, however, at least in the case of an insitu concrete roof or floor slab, or precast concrete slab providing equivalent restraint, that enhanced lateral support may be assumed and the effective height modified accordingly. A similar assumption may be made in certain cases of 'floors or roofs of any form of construction which span onto the column from both sides at the same level'. However, for this to be valid, the floor or roof construction must have sufficient rigidity perpendicular to the span to provide resistance to the assumed forces as noted in section 5.7. The effective height of a column may also be taken as 0.75 times the clear distance between lateral supports which provide enhanced resistance to lateral movement, as shown in Figure 5.27. This, though, does not comply with BS 5628 and should be used with caution.

5.12.2 Columns Formed by Openings

Most walls contain a door, window or some other form of opening and these are often close together so that a section of the wall between the adjacent openings becomes very narrow. In cases where this section of walling is by definition a column, i.e. width not more than four times its thickness, the effective height relative to an axis perpendicular to the wall will, due to the reduced restraint offered by the remaining section of wall, be less than that of a completely isolated member but greater than that of a continuous wall.

This is illustrated in Figure 5.29, from which it can be seen that for consideration of slenderness relative to an axis x–x, the effective height of the column formed by the openings will be greater than for the wall, but less than for the isolated member. The assessment of the effective height will vary depending on the size of columns, etc. Thus each case should be considered separately. A conservative approach would be to treat such a section as an isolated column. BS 5628 gives two general recommendations for the assessment of the effective height as follows:

(a) Where simple resistance to lateral movement of the wall containing the column is provided, the effective height should be taken as the distance between supports.
(b) Where enhanced resistance to lateral movement of the wall containing the column is provided, the effective height should be taken as 0.75 times the distance between the supports plus 0.25 times the height of the taller of the two openings.



Figure 5.29 Columns formed by openings



Figure 5.30 Effective height of column formed by openings of differing height



Figure 5.31 Example of no lateral restraint provided to columns formed by openings

This is illustrated in Figure 5.30 and means that if one of the openings is full height, the effective height will again be equal to the distance between lateral restraints. It is important to note that, even if the wall containing the column is provided with adequate restraint, the column itself may not be, particularly if both the openings continue up to the level of the lateral restraints (see Figure 5.31).



Figure 5.32 Wall details for Example 15 plan

Example 15

Determine in accordance with BS 5628, the slenderness ratio of the column formed by openings in the wall shown in Figure 5.32.

Effective heights:

$$h_{ef/xx} = 0.75 \times 3000 + 0.25 \times 2400$$
$$= 2850$$
$$h_{ef/yy} = 3000$$

Effective thicknesses:

$$t_{ef/xx} = 327.5$$
$$t_{ef/yy} = 215$$

Slenderness ratios:

$$SR_{xx} = \frac{2850}{327.5} = 8.7$$

$$SR_{yy} = \frac{3000}{215} = 13.9$$

Thus the slenderness ratio for the column is 13.9 as this is the worst case.

5.12.3 Design Strength

The design compressive strength of a column is given by the product of the capacity reduction factor, the column area and the characteristic compressive strength of masonry, divided by the relevant partial safety factor for materials. This may be expressed as follows:

$$\beta\, bt\, \frac{f_k}{\gamma_m}$$

where

b = width of column
t = depth of column.

Therefore

bt = cross-sectional area,
β = capacity reduction factor (see section 5.10),
f_k = characteristic compressive strength (see section 5.4),
γ_m = partial factor of safety for materials (see section 5.5).

(See also section 5.12.4.)

Example 16

Determine the design compressive strength of a column, 440 mm × 440 mm, 4.4 m clear height between concrete floors giving enhanced lateral restraint. The bricks have a compressive strength of 35 N/mm^2, and the mortar is designation (ii). The manufacturing and construction controls are normal. Section 5.12.1 suggests that a value of h_{ef} of 0.75h can be adopted for columns with enhanced lateral restraint, subject to use with caution. This example therefore assumes $h_{ef} = 1h$.

$$\text{Slenderness ratio} = \frac{h_{ef}}{t_{ef}} = \frac{4400}{440} = 10$$

Therefore $\beta = 0.97$.

Characteristic compressive strength of masonry:

$f_k = 9.4\ \text{N/mm}^2$ (see section 5.12.4),
$\gamma_m = 3.5$

Therefore

$$\text{design strength} = 0.97 \times 440 \times 440 \times \frac{9.5}{3.5} \times 10^{-3}$$

$$= 509\ \text{kN}$$

(This example and Example 15 have ignored the 'small plan area' effect and the answers are not strictly correct since the characteristic compressive stresses should have been modified using a factor described in section 5.12.4.)

5.12.4 Columns or Walls of Small Plan Area

In a member whose plan area is relatively small, the number of individual units available to support the loading is less than in the case of a wall. A wall may consist of, say, 50 units, of which some will be of greater compressive strength than others, and some of lesser compressive strength, with a reasonable spread of values about the mean value. A column may be required to support a similar load per unit area, but may consist of only, say, four units on plan. If all the four units in the column are of similar strength, which may be comparatively low, the effect on the design strength of the column would be greater than if four units in the wall were of a similarly low strength. The probability of low strength units being present in the wall or the column is the same, but the effect on the column strength is greater. It is necessary, therefore, to adjust the design strength of a column or wall of small plan area, to ensure that the probability of failure is similar to that of a normal wall. Logically, this should be achieved by adjusting the partial factor of safety for materials. The Code provides for a modification factor to be applied to the characteristic strength. The recommendation given in BS 5628 applies to walls or columns whose horizontal cross-sectional area is less than 0.2 m^2, and states that the characteristic compressive strength should be multiplied by a factor given by the following formula:

$$(0.7 + 1.5A)$$

where A = horizontal cross-sectional area of the column or wall in m^2.



Figure 5.33 Column details for Example 17

Example 17

Determine the design strength of the column shown in Figure 5.33, constructed with 20 N/mm^2 units in mortar designation (iv), normal construction and materials control.

Capacity reduction factor:
Slenderness ratios,

$$h_{ef/yy} = h_{ef/xx} = 4600$$

$$t_{ef/xx} = 327.5,\ \text{SR}_{xx} = \frac{4600}{327.5} = 14$$

$$t_{ef/yy} = 215,\ \text{SR}_{yy} = \frac{4600}{215} = 21$$

Therefore $\beta = 0.66$ (Table 5.13).

Characteristic compressive strength:

20 N/mm^2 units, therefore $f_k = 5.2$ N/mm^2 in mortar designation (iv).

But, plan area = 0.3275 × 0.215 = 0.07 m^2, i.e. < 0.2 m^2, therefore modification factor applies.

$$\text{Modification factor} = 0.70 + 1.5 \times 0.07$$
$$= 0.805$$

Modified characteristic compressive strength

$$= 0.805 \times 5.2\ \text{N/mm}^2$$

Partial factor of safety:

Controls normal, $\gamma_m = 3.5$

Therefore

$$\text{Design strength} = \frac{\beta \times A \times f_k}{\gamma_m}$$

$$= \frac{0.66 \times 0.07 \times 10^6 \times 0.805 \times 5.2 \times 10^{-3}}{3.5}$$

$$= 55\ \text{kN}$$

5.13 Eccentric Loading

When considering a member subject to compressive loading, it is unlikely that the loading will ever be truly applied concentrically. In most instances, the load will be applied at some eccentricity to the centroid of the member, whether



Figure 5.34 Eccentricity of single slab bearing onto wall



Figure 5.35 Eccentricity of continuous slab bearing onto wall

due to construction tolerances, varying imposed loads on adjacent floor spans or other causes. Generally, in the absence of evidence to the contrary, it is assumed that the load transmitted to a wall by a single floor or roof acts at one-third of the length of bearing from the loaded face. The most common cause is bending in the beam or floor or roof being supported. That is, as if a triangular stress distribution is assumed under the bearing (see Figure 5.34).

Where a uniform floor is continuous over a wall, the Code recommends that each span of the floor should be taken as being supported individually, on half the total bearing area (see Figure 5.35).

Previous versions of the Code stated that where loads are supported at a distance from the face of the wall, as where joist hangers or continuous bearers are used, the load should be assumed to be applied at a distance of 25 mm from the face of the wall (see Figure 5.36). The 1992 issue of BS 5628: Part 1 suggests that, for the load condition shown in Figure 5.36, the application of the load should be taken at the face of the wall. As joist hangers seldom fit precisely the authors consider that the eccentricity shown in Figure 5.36 should continue to be used in design.

The eccentricity has a maximum value, e_x, just under the applied load, and the member must be designed to resist the extra stresses incurred due to this eccentricity. But, the effect of the eccentricity may be assumed to decrease down the height of the member, until its effect is zero at the bottom of the member. Thus the vertical load on a member may be considered as being axial (concentric) immediately above a lateral support (see Figure 5.37).

In the case of walls, it is not necessary to consider the effects of eccentricity where e_x is less than $0.05t$.



Figure 5.36 Eccentricity of single timber joist supported in joist holder



Figure 5.37 Variation of eccentricity in the height of a wall

5.14 Combined Effect of Slenderness and Eccentricity of Load

It was seen in section 5.10, that the loadbearing capacity of a member was reduced due to the effects of slenderness on the tendency of the member to buckle. The application of an eccentric load will further increase the tendency of the wall to buckle, and thus reduce the load-carrying capacity of the member. This reduction is catered for by reduced values of β, the capacity reduction factor, depending on the ratio of the eccentricity, e_x, to the member thickness.

5.14.1 Walls

Values of the capacity reduction factor, β, for walls are given in Table 5.15 for values of eccentricity, e_x, from 0 to $0.3t$, where t is the thickness of the wall. The values from Table 5.13 are included in this table. Intermediate values may be obtained by linear interpolation between slenderness ratios and eccentricities. As stated in section 5.10, these values of β are maximum values and are strictly only correct for the central fifth of the member (see also section 5.14.2).

Example 18

Determine from Table 5.15 the value of β when $h_{ef}/t_{ef} = 16$, for the wall shown in Figure 5.38.

Table 5.15 Capacity reduction factor β (BS 5628, Table 7)

Slenderness ratio, h_{ef}/t_{ef}	Eccentricity at top of wall, e_x			
	Up to $0.05t$ [a]	$0.1t$	$0.2t$	$0.3t$
0	1.00	0.88	0.66	0.44
6	1.00	0.88	0.66	0.44
8	1.00	0.88	0.66	0.44
10	0.97	0.88	0.66	0.44
12	0.93	0.87	0.66	0.44
14	0.89	0.83	0.66	0.44
16	0.83	0.77	0.64	0.44
18	0.77	0.70	0.57	0.44
20	0.70	0.64	0.51	0.37
22	0.62	0.56	0.43	0.30
24	0.53	0.47	0.34	
26	0.45	0.38		
27	0.40	0.33		

[a] It is not necessary to consider the effects of eccentricities up to and including $0.05t$

Notes: Linear interpolation between eccentricities and slenderness ratios is permitted.
The derivation of β is given in Appendix B of BS 5628.



Figure 5.38 Wall details for Example 18

$$e_x = \frac{215}{2} - \frac{150}{3} = 57.5$$

Thus, in terms of t,

$$e_x = \frac{57.5}{215}t = 0.27t$$

When $e_x = 0.2t, \beta = 0.64$
$e_x = 0.3t, \beta = 0.44$

Therefore for

$$e_x = 0.27t, \beta = 0.58$$

5.14.2 Columns

Because the application of loading to a column may be eccentric relative to two axes, as compared with a wall where the eccentricity is generally related only to an axis in the plane parallel with the centre line, the treatment of eccentricity for columns is necessarily more involved (see Figure 5.39).

The Code defines eccentricity as relative to the major or minor axis of the column. The major axis being defined as the principal axis, about which the member has the larger moment of inertia. The minor axis being perpendicular to the major axis (see Figure 5.40).

The dimensions of the section are then taken as being b for the side perpendicular to the major axis and t perpendicular to the minor axis. The values of the capacity reduction factor, β, for columns are determined in accordance with BS 5628 as follows:



Figure 5.39 Eccentricity for masonry columns



Figure 5.40 Axes for eccentricity in masonry columns



Figure 5.41 Nominal eccentricity about both axes of a masonry column

Case 1: Nominal Eccentricity Both Axes

When the eccentricities about major and minor axes at the top of the column are less than $0.05b$ and $0.05t$ respectively, β is taken from the range of values given in Table 5.15 for e_x up to $0.05t$, with the slenderness ratio based on the value of t_{ef} appropriate to the minor axes (see Figure 5.41).

Case 2: Nominal Eccentricity – Major Axis Eccentric about Minor Axis

When the eccentricities about the major and minor axes are less than $0.05b$ but greater than $0.05t$ respectively, β is taken from Table 5.15 using the values of eccentricity and slenderness ratio appropriate to the minor axis (see Figure 5.42).

Case 3: Nominal Eccentricity – Minor Axis, Eccentric about Major Axis

When the eccentricities about the major and minor axes are greater than $0.05b$ but less than $0.05t$ respectively, β is taken from Table 5.15 using the value of eccentricity appropriate to the major axis and the value of slenderness ratio appropriate to the minor axis (see Figure 5.43).

Case 4: Eccentricity about Both Axes Greater Than Nominal

For columns, the value of β may be calculated for each axis and the minimum design capacity calculated. This method has a more general application and may be used to determine β for any member at any position. The values given in Table 5.15 are strictly only appropriate for the mid-height region of a member and, in some instances, the determination of β may be required at other points.



Figure 5.42 Eccentricity about minor axis and nominal eccentricity about major axis



Figure 5.43 Eccentricity about major axis and nominal eccentricity about minor axis

When the eccentricities about major and minor axes are greater than $0.05b$ and $0.05t$ respectively, β is calculated by deriving additional eccentricities and substituting in the appropriate formula as described in the next pragraph (based on BS 5628, Appendix B).

The eccentricity of applied loading is assumed to vary from e_x at the point of application to zero above the lateral support (see Figure 5.37), and an additional eccentricity considered to allow for slenderness effects, i.e. the tendency of the member to buckle. This additional eccentricity, e_a, is considered to vary linearly from zero at the lateral supports to a value over the central fifth of the member height given by the formula:

$$e_a = t\left[\frac{1}{2400}\left(\frac{h_{ef}}{t_{ef}}\right)^2 - 0.015\right]$$

where

t_{ef} = effective thickness of member
h_{ef} = effective height (see Figure 5.44).

The total design eccentricity, e_t, for calculation of the capacity reduction factor is given by the sum of e_x and e_a at the point being considered. When considering the mid-height section, where e_a is maximum, the maximum value of e_t will be:

$$e_t = 0.6e_x + e_a \quad \text{at mid-height}$$



Figure 5.44 Variation of e_a and e_x over height of member

When considering the top of the member, e_a will be zero and e_x at a maximum. Thus e_t will be equal to e_x

$$e_t = e_x \quad \text{at top of member}$$

For design eccentricities e_m of 0 to 0.05, the design vertical load capacity of a member is given by:

$$\beta t \frac{f_k}{\gamma_m}$$

where

e_m = larger of e_x and e_t
$\beta = 1$.

The ultimate stress block for an eccentrically loaded section is then assumed to be as given in Figure 5.45, from which the design vertical loading may be seen to be equal to the area of the stress block multiplied by the design stress, that is,

$$2\left(\frac{t}{2} - e_m\right) \times \frac{1.1\, f_k \text{ per unit length}}{\gamma_m}$$

Which may be expressed as follows:

$$\frac{1.1\left(1 - \frac{2e_m}{t}\right) t f_k}{\gamma_m}$$

or

$$\frac{\beta t f_k}{\gamma_m}$$



Figure 5.45 Stress block for eccentrically loaded section

where

$$\beta = 1.1\left(1 - \frac{2e_m}{t}\right)$$

f_k = characteristic strength of masonry
γ_m = partial factor of safety on materials
e_m = the larger of e_x, and e_t, but not less than $0.05t$.

5.15 Concentrated Loads

The design compressive stress locally at the bearing of a concentrated load may be greater than the general level of stress within the body of a wall or other member. Such relatively higher stress concentrations occur only over a small area, and are rapidly reduced by dispersion within the body of the member. Typical examples of such concentrated loads are beam bearings which are usually either rigid in themselves, e.g. deep concrete beams, or are provided with spreaders, e.g. padstones. The distribution of stress under such bearings varies according to the particular details being adopted, and various methods are available for analysing the distribution. BS 5628, clause 34, considers that, in general, the concentrated load may be assumed to be uniformly distributed over the area of the bearing and dispersed in two planes within a zone contained by lines extending downward at 45° from the edges of the loaded area (see Figure 5.46). This, however, tends to conflict with the recommendation in the Code that, when considering the eccentricity of applied loading the load may be assumed to act at one third of the depth of the bearing area from the loaded face (see section 5.13). Each case



Figure 5.46 Load dispersal through masonry under a concentrated load



Figure 5.47 Stress distributions under concentrated loads

should, therefore, be considered separately – the rigidity of the beam, lintel, etc. being an important factor. Also, the bearing detail may be such that the load can be applied uniformly (see Figure 5.47).

Table 5.16

Bearing type	Design local compressive stress in masonry
1	$1.25 \frac{f_k}{\gamma_m}$
2	$1.5 \frac{f_k}{\gamma_m}$
3	$2.0 \frac{f_k}{\gamma_m}$

The design local compressive stresses recommended in the Code vary according to the type of bearing being considered. Three types are considered, being designated as types 1, 2 and 3 respectively. Types 1 and 2 are defined in terms of bearing area in relation to the thickness of the member. Type 3 bearing is for the special case of a spreader beam designed in accordance with the elastic theory, located at the end of a wall and spanning in its plane. For this type of bearing, the local stress is not uniformly distributed, but may be calculated from elastic theory. The appropriate design local compressive stresses for all three types are given in Table 5.16, and each type is illustrated in Figure 5.48.



Figure 5.48 (a–c) Concentrated loads: types of bearing (BS 5628, Figure 4). (*Note:* Although the figure shows bearings with a minimum bearing of 50 mm, the authors do not recommend using such a small bearing length.)



Figure 5.49 Concentrated load dispersal and distributed load combination

The Code requires that where concentrated loads are applied to a member, not only should the applied stresses be checked in the immediate area of the concentrated load, but also the stresses at a distance of $0.4h_b$ below the bearing, where h_b is the height of the bearing relative to the lower support. The applied stresses in the immediate area of the concentrated load will be equal to the sum of the design applied stress due to the concentrated load and the distributed design applied stress existing within the member at that position (see Figure 5.49). The total combined stress must be less than or equal to the design local compressive stress from Table 5.16.

Referring to Figure 5.49,

Total stress at x–x

$$= \frac{\text{design reaction at end of beam}}{\text{bearing area}}$$

$$+ \frac{\text{design load from floor and brickwork above x–x}}{\text{area of wall}}$$

i.e. local concentrated stress + uniformly distributed stress

≤ design local compressive stress from Table 5.16.

The total applied stress at a distance of $0.4h_b$ below the bearing will be equal to the sum of the design applied stress due to the concentrated load, reduced from its maximum value due to an assumed dispersion at 45°, and the distributed design applied stress existing within the member at $0.4h_b$ below the bearing. The total combined stress must be less



Figure 5.50 Concentrated load dispersal configuration

than, or equal to, the design strength of the member calculated in accordance with sections 5.11 and 5.12 for walls and columns respectively (see Figures 5.50 and 5.51).

Referring to Figure 5.50,
Total stress at y–y

$$= \frac{\text{design reaction at end of beam}}{(\text{bearing width} + 0.8h_b) \times \text{thickness of wall}}$$

$$+ \frac{\text{design load from floor and brickwork above y–y}}{\text{area of wall}}$$

$$\leq \frac{\beta f_k}{\gamma_m}$$

It should be noted that, the value of β, the capacity reduction factor, should be that for the position under consideration (see Figure 5.35 and BS 5628, Appendix B). The design strength of the wall may also require checking at other locations, e.g. mid-height which may not coincide with $0.4h_b$ below the bearing. It is also possible that such concentrated loads may provide a degree of horizontal lateral restraint to a member and thus reduce the height between supports to be considered in determining the effective height.



Figure 5.51 (BS 5628, Figure 5)

6 Basis of Design (2): Lateral Loading – Tensile and Shear Strength

Having dealt with walls and columns acting in compression, i.e. supporting vertical loads only, resistance to lateral loads must now be considered. In the walls of a house, for example, in addition to supporting the vertical loads from the roof and floors, masonry is also subject to the pressure of the wind against the outside walls and must, therefore, be designed to resist the resulting tensile bending stresses and shear stresses, as well as the compressive stresses.

When a wall supports a uniformly distributed concentric vertical axial load, every part of the wall is assumed to be subjected to an equal compressive stress at any particular cross-section. When a wall supports a lateral loading, and bends or flexes, the stress at any particular cross-section may vary from being compressive at one face to being tensile at the other face – unless the wall is cracked (see Figure 6.1). As the resulting tensile stress is due to flexure of the wall, it is termed the flexural tensile stress.

When axial loading and lateral loading are combined, the resultant stresses in an uncracked wall, or other geometric section under consideration, are those given by the combination of the stress due to the vertical load (a uniform compressive stress) and the lateral load, i.e. a stress varying from a maximum compressive stress on one face to a maximum flexural stress on the other. Depending on the relative values of the vertical load and the bending moment due to the lateral load, the wall may be subject to entirely compressive stress, as shown in Figure 6.2, case 1, or both compressive and tensile stress, case 2.

If the tensile stresses which develop exceed the tensile resistance of the wall – or other section being considered – the section will crack. Cracking will also occur where no tensile resistance can be developed due, for instance, to the inclusion of a damp proof course (dpc). The applied loading is then resisted purely by compression within the section, as shown in Figure 6.2, case 3. The stress diagrams illustrated are for compressive stresses within the elastic range. Stress diagrams appropriate to conditions approaching the ultimate limit state will be dealt with later in this chapter.

Because of the self-weight of masonry, all walls are subject to some vertical loading. In case 1 (Figure 6.2) the compressive strength of the wall will govern the design of – in this instance – an external wall in the lower storey of a multi-storey building where the vertical loading due to the roof, floors and walls is large, and the bending moment due to the wind pressure is comparatively small.

In case 2, the tensile strength of the wall must be considered in addition to the compressive strength, for example, an external wall in an upper storey of a multi-storey building where the vertical loading from the roof is small, or non-existent due to wind uplift forces, and the wind pressure is at its maximum. As masonry is comparatively weak in tension, it is usually the tensile stress that governs the design in this situation.

In case 3, the tensile strength, if any, of the wall has been exceeded, the section has cracked, and higher compressive stresses have resulted over a reduced area of the section. Thus in this case, the compressive stress governs the design. This example is typical of the external walls of lightly loaded structures, and all laterally loaded members which include a damp proof membrane incapable of transferring tensile stresses across the joint. Some engineering bricks employed as dpcs are capable of transferring tensile stresses, but reliance on this must be given careful consideration by the designer.



Figure 6.1 Stress blocks under vertical and horizontal loading



Figure 6.2 Combination of stresses under vertical and horizontal loading

6.1 Direct Tensile Stress

Tensile stresses due to bending are termed flexural tensile stresses in order to distinguish them from the tensile stresses due to the application of a direct tensile force such as that resulting from wind uplift. In view of masonry's comparative weakness in tension, and the many other factors involved, such as workmanship, etc., it is considered unwise to place any reliance on its direct tensile strength.

Nevertheless, BS 5628 does enable designers, at their own discretion, to allow limited direct tensile stresses in two instances. The first is when suction forces arising from wind loads are transmitted to masonry walls. However, some form of restraint straps are generally necessary, and it is always advisable to provide some positive anchorage to eliminate the direct tensile stresses which can develop. The second case where direct tensile stresses may be allowed is when considering the probable effects of misuse or accidental damage (see Chapter 8).

6.2 Characteristic Flexural Strength (Tensile) of Masonry, f_{kx}

Masonry is a brittle material and its resistance to flexural tension depends on the type of masonry unit, the mortar grade and, most importantly, the bond between the mortar and the unit. The correct type of unit and mortar grade can readily be specified.

Much research has been undertaken into the mechanism of the bond between masonry units and mortar. It has been found under laboratory conditions that, when clay bricks are being used, the strength of the bond varies according to their water absorption properties. Thus for clay bricks, BS 5628 provides characteristic flexural strength values for various ranges of water absorption (see Table 6.1). Nevertheless, achieving a good bond between bricks and mortar still depends to a large extent on the degree of skill and care taken during construction.

Failure to provide adequate temporary propping against wind or lateral pressure, or inadequate curing during construction may result in cracks occurring at a critical section which may invalidate any design assumptions based on flexural tensile resistance. This is not to say that masonry cannot be designed to resist flexural tensile stresses, but the designer's judgement of what is safe and reasonable is crucial, and should be even more critical than when considering other types of loading resistance.

Flexural tension should only be relied on at a dpc if the material has been proved by tests to permit the joint to transmit tension, or if the dpc consists of bricks in accordance with BS 743. Care must also be taken to ensure that the dpc is properly bedded in mortar, since a test on a bonded dpc is useless, if, on site, the dpc is laid dry.

Masonry is not isotropic, i.e. it does not have similar properties in all directions, and, therefore, does not provide the same resistance to bending in both directions. For example, a square wall panel of masonry with only vertical supports on each side will provide a greater resistance to bending due to lateral loading than if only horizontal supports were provided at the top and bottom (see Figure 6.3).

This difference in strength, however, is reduced by the effect of the self-weight of the wall, which will tend to reduce the



Figure 6.3 Failure planes of laterally loaded masonry wall panels

flexural tensile stresses developed – as was explained at the beginning of this chapter. As the height of a wall is increased, the compressive stress due to the self-weight of the masonry will also increase. The combination of this increased stress and the flexural tensile stresses will mean that, if the vertical loading is significant, the wall could resist a greater lateral loading when spanning between top and bottom supports, e.g. referring to Figure 6.3, wall B, than when spanning between vertical supports at each side, e.g. wall A.

Any other dead or permanent imposed loadings will similarly increase the compressive stress in the wall and improve its resistance to bending, provided that the compressive stresses are within allowable limits. This dead loading is often termed the 'pre-load' on the wall.

Thus masonry subject to little or no vertical loading tends to be stronger when spanning horizontally than when spanning vertically. On the other hand, walls which are subject to large vertical loading tend to be stronger when spanning vertically than when spanning horizontally.

Values for the characteristic flexural tensile strength, f_{kx}, both perpendicular and parallel to the bed joints are given in Table 6.1. These values take no account of any pre-load in the wall.

6.2.1 Orthogonal Ratio

As previously explained, masonry is not isotropic and the ratio of the resistance to bending when spanning vertically and horizontally is defined as the orthogonal ratio, μ. It is used primarily for the calculation of bending moments in panel wall design. However, it is considered here because of its relationship to characteristic flexural strength.

The orthogonal ratio, as defined in BS 5628, is the ratio of the values of the respective characteristic flexural strengths when spanning vertically and horizontally. This may be expressed as follows:

$$\text{orthogonal ratio, } \mu = \frac{f_{kx/par}}{f_{kx/perp}}$$

where

$f_{kx/par}$ = characteristic flexural strength parallel to bed joints

$f_{kx/perp}$ = characteristic flexural strength perpendicular to bed joints.

Example 1

Determine the orthogonal ratio, μ, for clay bricks having a water absorption of 9%, laid in mortar designation (ii), when no significant vertical load exists within the panel.

From Table 6.1, the bricks are in the range 7–12% for water absorption.

Thus

$$f_{kx/par} = 0.4\ \text{N/mm}^2$$

and

$$f_{kx/perp} = 1.1\ \text{N/mm}^2$$

Therefore

$$\mu = \frac{0.4}{1.1} = 0.36$$

The effect of any vertical loading in the member will tend to increase its resistance to bending when spanning vertically, and thus must be taken into account when determining the orthogonal ratio. The stress due to the design vertical load – which may only be the self-weight of the panel – is therefore added to the characteristic strength parallel to the bed joints, and the sum of these two stresses is used to determine the appropriate value of the orthogonal ratio. This may be expressed as follows:

$$\text{orthogonal ratio, } \mu = \frac{f_{kx/par} + g_d}{f_{kx/perp}}$$

where g_d = compressive stress due to the design vertical load in N/mm^2.

The Code recommends that the design vertical load should be modified by multiplying the partial safety factor on materials γ_m. This produces the expression:

$$\mu = \frac{f_{kx/par} + \gamma_m g_d}{f_{kx/perp}}$$

It should be noted that the value of γ_f used in calculating the design vertical load (i.e. $\gamma_f G_k$) should be 0.9, since the vertical load is beneficial in terms of flexural stregth.

Example 2

Determine the orthogonal ratio, μ, at mid-height for the wall illustrated in Figure 6.4, constructed of the bricks and mortar described in Example 1 of density, $\rho = 20\ \text{kN/m}^3$.

Table 6.1 Characteristic flexural strength of masonry, f_{kx}, N/mm^2 (BS 5628, Table 3)

	Plane of failure parallel to bed joints			Plane of failure perpendicular to bed joints		
Mortar designation	(i)	(ii) and (iii)	(iv)	(i)	(ii) and (iii)	(iv)
Clay bricks having a water absorption						
less than 7%	0.7	0.5	0.4	2.0	1.5	1.2
between 7% and 12%	0.5	0.4	0.35	1.5	1.1	1.0
over 12%	0.4	0.3	0.25	1.1	0.9	0.8
Calcium silicate bricks		0.3	0.2		0.9	0.6
Concrete bricks		0.3	0.2		0.9	0.6
Concrete blocks (solid or hollow) of compressive strength (N/mm^2)						
2.8, 3.5, 7.0 used in walls of thickness[a] up to 100 mm	0.25		0.2		0.40 0.45 0.60	0.4 0.4 0.5
2.8, 3.5, 7.0 used in walls of thickness[a] 250 mm	0.15		0.1		0.25 0.25 0.35	0.2 0.2 0.3
10.5, 14.0 and over used in walls of any thickness[a]	0.25		0.2		0.75 0.90[b]	0.6 0.7

[a] The thickness should be taken to be the thickness of the wall, for a single-leaf wall, or the thickness of the leaf, for a cavity wall

[b] When used with flexural strength in parallel direction, assume the orthogonal ratio $\mu = 0.3$

Note: Linear interpolation between entries in Table 6.1 is permitted for: (a) concrete block walls of thickness between 100 mm and 250 mm; (b) concrete blocks of compressive strength between 2.8 N/mm^2 and 7.0 N/mm^2 in a wall of given thickness.



Figure 6.4 Wall details for Example 2

Characteristic vertical load, G_k, at mid-height

$$= \text{thickness} \times \frac{\text{height}}{2} \times \text{density/unit length}$$

$$= 0.215 \times \frac{2.4}{2} \times 20$$

$$= 5.16 \text{ kN/m}$$

Design vertical load at mid-height

= partial safety factor on loads × characteristic load
$= \gamma_f \times G_k$
$= 0.9 \times 5.16$ (from Table 5.1, $\gamma_f = 0.9$, i.e. minimum vertical load)
$= 4.6$ kN/m run

Design vertical stress per m length, g_d

$$= \frac{\text{design vertical load}}{\text{area}}$$

$$= \frac{4.6 \times 10^3}{215 \times 10^3}$$

$$= 0.02 \text{ N/mm}^2$$

This value of g_d is modified by γ_m, which in this case is taken as 3.0 for normal category of control for flexure. Therefore

$$\mu = \frac{(0.4 + 0.02 \times 3)}{1.1}$$

$$= 0.418$$

If the effect of the vertical load G_k is ignored then μ would have been 0.36. The benefit of vertical load is significant in multi-storey structures.

6.3 Moments of Resistance: General

With the exception of panel wall design, the topic of lateral loading is not considered to any great extent in BS 5628. However, the application of structural masonry is not limited only to vertical loadbearing elements and cladding panels to structural frames. Design methods should cover all applications of masonry.

The section which follows is based on principles laid down in the Code. These principles have been abstracted, and produced in the form given in the Code, as they have more general application than in their original context.

The effects of lateral loading on masonry members were discussed at the beginning of this chapter. The three cases considered were as follows:

(1) Entire section in compression – design governed by compressive strength requirements.
(2) Limited tensile stresses developing – design generally governed by tensile stress requirements, compressive stresses to be checked (particularly for geometric profile sections).
(3) Section cracked, or no tensile resistance due to presence of dpc unable to transmit tension – design governed by compressive stresses.

6.3.1 Moments of Resistance: Uncracked Sections

At sections where flexural tension can develop, that is uncracked sections and those where continuity is not broken by the inclusion of a dpc unable to transfer tensile stresses, the design moment of resistance is given by the product of the design stress which can develop in the section and the section modulus. When considering the moment of resistance to bending about a vertical axis, i.e. a member spanning horizontally, the design stress will simply be the characteristic flexural strength perpendicular to the bed joints, divided by the appropriate partial safety factor for materials. Thus for members spanning horizontally, the design moment of resistance, MR, may be expressed as follows:

$$\mathrm{MR} = \frac{f_{\mathrm{kx/perp}}}{\gamma_{\mathrm{m}}} \times Z \quad \text{(uncracked section)}$$

where

$f_{\mathrm{kx/perp}}$ = characteristic flexural strength perpendicular to bed joints (see Table 6.1)
γ_{m} = partial factor of safety for materials (see Table 5.11)
Z = elastic section modulus.

It should be noted that the section modulus for hollow blocks should be based on the geometric properties of the unit, i.e. Z based on the net area of the section, not the gross area (see Figure 5.8).

When considering geometric sections (spanning vertically) other than a rectangle section, e.g. diaphragms or fins, the outstanding length of flange from the face of the rib or fin should be taken as follows:

(a) 4 × effective thickness of wall forming the flange, when the flange is unrestrained;
(b) 6 × effective thickness of wall forming the flange when the wall is continuous.

In no case should this distance be more than half the distance between ribs or fins. This consideration affects the assessment of the section modulus, and also the other geometric properties of the section. The requirements are discussed further in Chapter 13 which deals with diaphragm and fin walls.

When considering the moment of resistance to bending about a horizontal axis, i.e. a member spanning vertically, the design stress which may be developed is the sum of the design tensile strength parallel to the bed joints and the stress due to the design vertical loading. Thus for members spanning vertically, the design moment of resistance based on tensile stresses, MR, may be expressed as follows:

$$\mathrm{MR} = \left(\frac{f_{\mathrm{kx/perp}}}{\gamma_{\mathrm{m}}} + g_{\mathrm{d}} \right) Z \quad \text{(uncracked section)}$$

(see Figure 6.5)



Figure 6.5 Design moment of resistance of laterally loaded masonry wall panels



Figure 6.6 Wall details for Example 3

where

$f_{kx/par}$ = characteristic flexural stress parallel to bed joints (see Table 6.1)
γ_m = partial factor of safety for materials (see Table 5.11)
g_d = design vertical stress due to dead loads, i.e. $\gamma_f G_k$/area
Z = elastic section modulus.

Example 3

Determine the type of brick required, laid in mortar designation (ii), for the wall shown in Figure 6.6, assuming $\gamma_m = 2.5$, and density, $\rho = 18$ kN/m^3, if the wall is subject to a lateral characteristic wind load of 0.8 kN/m^2 and is only supported along the top and bottom edges. Assume special category of control for construction.

Consider 1 m length of wall:

Characteristic wind load, $W_k = 0.8$ kN per m height

Design wind load = $\gamma_r W_k = 1.4 \times 0.8 = 1.12$ kN per m height

Total design wind load = $1.12 \times 3 = 3.36$ kN

Therefore, applied moment,

$$\text{maximum at base} = 3.36 \times 3/8 = 1.26 \text{ kN m}$$

(For the purposes of this example, the wall is treated as a propped cantilever.)

$$\text{MR} > \text{applied moment}$$

but

$$\text{MR} = \left(\frac{f_{kx/par}}{\gamma_m} + g_d\right) Z$$

Therefore

$$1.26 < \left(\frac{f_{kx/par}}{\gamma_m} + g_d\right) Z$$

Thus to calculate $f_{kx/par}$ required, substitute $\gamma_m = 2.5$ (special category of control flexure)

$$g_d = \frac{\gamma_f G_k + \gamma_f \rho \times h \times t \times \text{unit length}}{t \times \text{unit length}}$$

$$= \frac{0.9 \times 2 \times 10^3 + 0.9 \times 18 \times 10^3 \times 3 \times 0.215 \times 1}{215 \times 10^3}$$

$$= \frac{12\,249}{215 \times 10^3} = 0.057 \text{ N/mm}^2 \text{ per metre length of wall}$$

and

$$Z = \frac{10^3 \times 215^2}{6} = 7.7 \times 10^6 \text{ mm}^3 \text{ per metre length of wall}$$

Hence

$$f_{kx/par} > \left(\frac{1.26 \times 10^6}{7.7 \times 10^6} - 0.057\right) \times 2.5$$

$$> 0.267 \text{ N/mm}^2$$

From Table 6.1, with mortar designation (ii), any clay bricks would be suitable. The brick strength must also be checked for compressive stresses, as explained in Chapter 5.

The maximum design compression stress will occur at the base, and will be equal to the sum of the design compressive stress due to the axial load and the maximum design compressive stress due to bending. The required design compressive strength of the brickwork must be equal to or exceed this stress. This may be expressed as follows:

$$\begin{pmatrix}\text{design compressive strength of brickwork required (see Chapter 5, section 5.10)}\end{pmatrix} > \begin{pmatrix}\text{design compressive stress due to axial load}\end{pmatrix} + \begin{pmatrix}\text{maximum design compressive stress due to bending}\end{pmatrix}$$

$$\text{i.e. } \frac{f_k \text{ required}}{\gamma_m} > \frac{g_d}{\beta} + \frac{M_A}{Z \times \beta}$$

where

f_k = characteristic design compressive stress required
$\gamma_m = 2.5$
$g_d = 0.057$ N/mm^2
$M_A = 1.26$ kNm
$Z = 7.7 \times 10^6$ mm^3
β = capacity reduction factor at base level, obtained as follows:

$$\text{slenderness ratio} = \frac{0.75 \times 3000}{215} = 10.5$$

eccentricity at base = zero (see Figure 5.44)

Thus $\beta = 0.96$ (see Table 5.15).

Hence

$$f_k \text{ required} \geq \left(\frac{g_d}{\beta} + \frac{M_A}{Z \times \beta}\right)\gamma_m$$

$$\geq \left(\frac{0.057}{0.96} + \frac{1.26 \times 10^6}{7.7 \times 10^6 \times 0.96}\right) 2.5$$

$$\geq 0.57 \text{ N/mm}^2$$



Figure 6.7 Stability moment of cracked section

From Table 5.4 any unit with a compressive strength of 5 N/mm^2 or more, laid in mortar designation (ii), will provide a characteristic compressive strength greater than 0.56 N/mm^2.

6.3.2 Moments of Resistance: Cracked Sections

At sections where flexural tension cannot be developed, e.g. where the section is already cracked, or where a dpc unable to transmit tensile stresses is provided, the design moment of resistance to lateral loading is provided solely by the self-weight of the member and any net dead load about the appropriate lever arm. This stability moment must, therefore, be sufficient to resist the applied overturning moment due to the lateral loading, and the compressive stresses will govern the design.

This action is illustrated in Figure 6.7. Under the action of the applied moment, M_A, the section is tending to overturn about the pivot, which, for the present, is assumed to be a 'knife-edge' support. The tendency to overturning is resisted, and stability is provided, by the action of the concentric vertical axial loading about its lever arm, i.e. about X, which is equal to approximately half the thickness of the section in this instance. This may be expressed as follows:

$$M_A \leq P \times \frac{t}{2}$$

The necessary factors of safety, etc., must, of course, be included – but basically this is the principle involved.

The assumption of a 'knife-edge' support, that is to say non-yielding points of contact, is not correct when dealing with masonry. The compressive stresses at the edge X would be infinitely large. This would cause some local crushing of units or mortar, or squeezing of the damp proof membrane, if one is present, and increase the contact area. The actual width of this contact area, and actual stress distribution over it, is complex. In order to simplify the design analysis, an equivalent stress block is assumed. In BS 5628, a rectangular stress block is assumed, the value of the compressive strength being taken as the characteristic compressive strength of masonry divided by the partial factor of safety. Where this stress block is actually shown in the Code (Appendix B), the compressive strength is increased by



Figure 6.8 Equivalent stress block – cracked section



Figure 6.9 Equilibrium forces on cracked section

a factor of 1.1, which relates the assumed compressive strength for the rectangular section to the actual stress distribution. This factor is included in the following determination of the moment of resistance. The stress block considered is shown in Figure 6.8.

As the applied stress is of a local concentrated nature, it is not considered relevant to apply the capacity reduction factor for slenderness. The assumed width of the stressed area, w_s, will depend on the vertical loading within the wall. The total upward reaction, i.e. stress multiplied by the area, must be equal to the applied vertical load in accordance with the laws of statics, to maintain the equilibrium of the section. This is illustrated in Figure 6.9.

From Figure 6.9, for equilibrium:

Vertical forces:

applied external vertical load = internal vertical reaction

i.e. $$n_w = R \qquad (1)$$

Moments:

applied external overturning moment about centre line of axial load = internal moment of reaction about centre line of applied axial load, i.e. lever arm.

i.e. $$M_A = R \times l_a$$

but $$l_a = \left(\frac{t}{2} - \frac{w_s}{2}\right)$$

therefore $$M_A = R \times \left(\frac{t}{2} - \frac{w_s}{2}\right) \quad (2)$$

The upward reaction,

$$R = \text{stress} \times \text{area}$$

$$= 1.1\frac{f_k}{\gamma_m} \times w_s / \text{unit length}$$

But, from equation (1)

$$R = n_w$$

therefore $$n_w = 1.1\frac{f_k}{\gamma_m} w_s$$

i.e. $$w_s = \frac{n_w \gamma_m}{1.1 f_k}$$

Substituting for R and w_s in equation (2):

$$M_A = n_w\left(\frac{t}{2} - \frac{n_w \gamma_m}{1.1 f_k \times 2}\right)$$

which may be rearranged:

$$M_A = \frac{n_w}{2}\left(t - \frac{n_w \gamma_m}{1.1 f_k}\right) \quad \text{(cracked section)}$$

This is the expression for equilibrium, and thus the design moment of resistance vertically, MR, is given by the expression:

$$\text{MR} = \frac{n_w}{2}\left(t - \frac{n_w\, \gamma_m}{1.1 f_k}\right) \quad \text{(cracked section)}$$

Note that n_w is the design load, and therefore includes the factor of safety. Note also that the 1.1 factor applied to f_k does not strictly comply with the formula given in BS 5628, clause 36.5.3. However, it is catered for elsewhere in the Code (Appendix B).

Example 4

Repeat Example 3 assuming a sheet dpc at base level which is not capable of transmitting tensile stresses.

Applied design moment at base $M_A = 1.26$ kN m/m run. With a dpc at the base, the section must be designed as a cracked section, and thus the design moment of resistance, MR, must be greater than or equal to the applied design moment.

$$\text{MR} \geq M_A$$

$$\frac{n_w}{2}\left(t - \frac{n_w \gamma_m}{1.1 f_k}\right) \geq M_A$$

where

f_k = characteristic design compressive stress
$\gamma_m = 2.5$
and, from Example 3
$t = 215$ mm
$n_w = \gamma_f G_k + \gamma_f \times \rho \times h \times t$
$= 0.9 \times 2 + 0.9 \times 18 \times 3 \times 0.215 = 12.25$ kN/m
$M_A = 1.26$ kN m

Hence

$$f_k \text{ required} \geq \frac{n_w \gamma_m}{1.1\left(t - \frac{2M_A}{n_w}\right)}$$

$$\geq \frac{12.25 \times 2.5 \times 10^3}{1.1\left(215 - \frac{2 \times 1.26 \times 10^6}{12.25 \times 10^3}\right) \times 10^3}$$

$$\geq 2.99 \text{ N/mm}^2$$

From Table 5.4, units with a compressive strength of 10 N/mm^2 or more are required, laid in mortar designation (ii). The compressive strength of the wall should also be checked where the capacity reduction factor, β, is a maximum. The characteristic flexural tensile stress required should be determined at the point of maximum bending moment in the span, and at this point will be based on an uncracked section.

6.4 Cavity Walls

When cavity walls are subject to lateral loading, usually only one leaf is loaded. For example, in the case of external wind loading (and no internal pressure), it is only the external leaf of the cavity which is loaded. The other leaf can only contribute to the resistance if (a) the two leaves are joined in such a way as to act together (as in the case of diaphragm walls), or (b) the load is transmitted to the other leaf of the wall and is shared in some ratio between the two leaves.

In order to achieve the first option, the connection between the two leaves must be able to transmit both horizontal and vertical internal shear stresses. The standard types of wall ties, i.e. vertical twist, butterfly and double-triangle, manufactured in accordance with BS EN 845, are not strong enough to transmit these stresses across a cavity. However, when provided at the spacing recommended in BS 5628, clause 29.1, this will ensure that the applied lateral loading is shared between the two leaves, as illustrated in Figure 6.10.

It should be noted that wall ties are required to resist both tensile and compressive loads and the capacity in compression is greatly affected by the cavity width. Many wall ties used today do not match the descriptions in previous British Standards, but will need to be carefully chosen since the new specification for ancillary components for masonry BS EN 845-1 requires the suppliers to provide technical information on wall ties, rather than being specified in the BS EN.

Where the load is carried by one leaf only, the loadbearing capacity of the wall should be based on the horizontal cross-sectional area of that leaf alone, although the stiffening effect of the other leaf can be taken into account when calculating the slenderness ratio. Each leaf of a cavity wall should be not less than 75 mm thick. The width of the cavity may vary between 50 mm and 150 mm but should not be wider than 75 mm where either of the leaves is less



Figure 6.10 Wall ties effect on laterally loaded cavity wall behaviour



Figure 6.11 Effect of differing leaf thickness in cavity wall behaviour

than 90 mm in thickness. In special circumstances and with appropriate supervision, the width of the cavity may be reduced below 50 mm.

6.4.1 Vertical Twist Ties

With vertical twist type ties, or ties of equivalent strength, the loading is considered to be fully transmitted by the ties from the outer leaf to the inner leaf. The two leaves will thus deflect together to support the applied loading. Note that traditional fishtail ends to vertical twist ties are not permitted on health and safety grounds.

Under the action of loading, the two leaves must deflect to a similar profile, and the amount of deflection of each leaf must be similar, otherwise they will move apart. If both leaves have the same moment of inertia, I, modulus of elasticity, E, and length, L, the load will be shared equally between the two as the deflection, which is measured in terms of EI/L, will be similar. If one leaf has a greater moment of inertia than the other, a greater load will be required to produce the same deflection as the leaf with the smaller moment of inertia.

Thus the leaf with the greater moment of inertia will resist a greater load than the leaf with the smaller moment of inertia. That is to say, the load resisted by each leaf will be in proportion to its stiffness, as measured by the quantity EI/L. But, as E and L are generally similar for each leaf of a cavity wall, the proportion may be based on the I value.

With regard to the cavity wall with differing I values for each leaf, shown in Figure 6.11, if W_1 is the load on leaf 1,

$$\text{deflection, } \delta_1 = \frac{5 \times W_1 \times L_1^3}{384 \times E_1 \times I_1}$$

and W_2 is the load on leaf 2,

$$\text{deflection, } \delta_2 = \frac{5 \times W_2 \times L_2^3}{384 \times E_2 \times I_2}$$

But, deflections must be equal, i.e. $\delta_1 = \delta_2$, and here, $E_1 = E_2$ and $L_1 = L_2$.

Thus $$\frac{W_1}{I_1} = \frac{W_2}{I_2}$$

But the total lateral load, $W = W_1 + W_2$.

i.e. $$W_2 = W - W_1$$

Substituting this in the above equation

$$\frac{W_1}{I_1} = \frac{W - W_1}{I_2}$$

Multiply by $I_1 \times I_2$, then

$$W_1 I_2 = W I_1 - W_1 I_1$$

which becomes

$$W_1 = \frac{W I_1}{I_1 + I_2}$$

That is to say, the load on leaf 1 is obtained from the total load in proportion to the moment of inertia of leaf 1. Similarly, the load on leaf 2 will be in proportion to its moment of inertia.

When dealing with cavity walls with vertical twist ties, or equivalent, the applied design load may, in accordance with BS 5628, be apportioned between each leaf of the wall in proportion to its moment of inertia, related to the sum of the moments of inertia for each leaf. Each leaf may then be designed to produce a moment of resistance to this loading on the basis of a cracked or uncracked section, as appropriate.

The design lateral strength for a cavity wall tied with vertical twist-type wall ties or ties with equivalent strength and stiffness should be taken as the sum of the design lateral

strengths of the two leaves, allowing for the additional strength of any piers bonded to one or both of the leaves.

Where butterfly or double-triangle ties are to be used, the design lateral strength of the cavity wall may be taken as the sum of the design lateral strengths of the two leaves, provided that the ties are capable of transmitting the compressive forces to which they are subjected; when the ties are not capable of transmitting the full force, the contribution of the appropriate leaf should be limited accordingly.

When it is required to check the compressive resistance of the ties, or to assess the strength required for another type of tie to be considered equivalent to a vertical twist tie, the Code states that (apart from double-triangle and wire butterfly ties) the appropriate value of the load in tension may be used for the compression load.

There are now many varieties of ties available, particularly to replace fishtail ties which have sharp edges and should not be used. The designer will need to refer to the manufacturer's information to obtain design values of any tie particularly in tension and compression.

6.4.2 Double-triangle and Wire Butterfly Ties

When double-triangle or butterfly ties are used, the loading may, in accordance with BS 5628, be apportioned as described in section 6.4.1, provided that the ties are capable of transmitting the compressive forces to which they are subjected. The Code states that for double-triangle and wire butterfly ties laid in mortar designation (i), (ii), (iii) or (iv), the characteristic compressive resistance may be taken as 1.25 kN and 0.5 kN respectively, where the width of the cavity is no more than 75 mm, and 0.65 kN and 0.35 kN for cavities up to 100 mm wide. Butterfly ties are only recommended for minor structures.

In cases where these types are not capable of transmitting the necessary compressive loading, the loaded leaf will be required to resist a greater proportion of the applied loading or specially designed ties could be used. Values for the characteristic strengths of wall ties are given in Table 6.5, later in this chapter.

6.4.3 Selection of Ties

The required spacing of ties is given in clause 29.1.5 of the Code and the criteria for selection of ties including their spacing is given in Table 6.2. The spacing may be varied, provided the number of ties per square metre on elevation is not less than the values given in the table. Additional ties may be necessary around the sides of openings.

The minimum embedment of a tie in a mortar joint should be 50 mm in each leaf. The width of the cavity may vary between 50 mm and 150 mm but, in accordance with the Code, may not be wider than 75 mm where either of the leaves is less than 90 mm in thickness. However, the Code does allow that in special circumstances, with appropriate supervision, the width of the cavity may be reduced below 50 mm.

Table 6.2 Selection of wall ties: types and lengths (extended from BS 5628: Part 1: 2002, Table 6)

Least leaf thickness (one or both) (mm)	Nominal cavity width (mm)	Permissible type of tie		Tie length[b] (mm)	Tie spacing density (number of ties/m^2)
		Shape name[a] in accordance with BS 1243 (now superceded)	Type member[a] in accordance with DD 140: Part 2		
75	75 or less	Butterfly[e], double triangle or vertical twist	1, 2, 3 or 4	175	4.9
90	75 or less	Butterfly[e], double triangle or vertical twist	1, 2, 3 or 4	200	
90	76–90	Double triangle[d] or vertical twist	1 or 2	225[c]	2.5
90	91–100	Double triangle[d] or vertical twist	1 or 2	225	
90	101–125	Vertical twist	1 or 2	250	
90	126–150	Vertical twist	1 or 2	275	

[a] The strength and stiffness of masonry/masonry ties in accordance with DD 140 range from type 1, the stiffest, to type 4 the least stiff. For ties complying with BS 1243, the vertical twist is the stiffest and the butterfly the least stiff.

[b] This column gives the ties lengths, in 25 mm increments, that best meet the performance requirement that the embedment depth will be not less than 50 mm in both leaves, after taking into account all building and material tolerances, but that also the ties should not protrude from the face. The designer may vary these in particular circumstances provided that the performance requirement is met.

[c] The minimum length requirement exceeds the maximum specified under BS 1243 but 225 mm double triangle format ties, which otherwise comply with BS 1243, should be suitable.

[d] Double triangle ties of shape similar to those in BS 1243, having a strength to satisfy type 2 of DD 140: Part 2, are manufactured. Specialist tie manufacturers should be consulted if 225 mm long double-triangle format ties are needed for 91 mm to 100 mm cavities.

[e] Butterfly ties should only be used for minor structures

Where large uninterrupted expanses of cavity walling are constructed, the differential movements due to thermal movement, elastic shortening under load, etc., between the two leaves of a wall may cause loosening of the ties. The heights and lengths of the external cavity walls should, therefore, be limited for this reason, in addition to any movement joint requirements.

The Code recommends that the outer leaf should be supported at intervals of not more than every third storey, or 9 m, whichever is less. For buildings not exceeding four storeys, or 12 m in height, whichever is less, the Code considers it satisfactory for a wall to be uninterrupted for its full height. These requirements should be carefully considered in conjunction with the requirements for movement joints, as discussed in Appendix 3. These heights are considered by the authors to be an absolute maximum. Greater frequency of support should be provided, where possible.

6.4.4 Double-leaf (Collar-jointed) Walls

When a wall is constructed of two separate leaves with a vertical joint not exceeding 25 mm wide between them, i.e. a cavity wall with a very narrow cavity, in accordance with the Code it may be designed as a cavity wall, or as a single-leaf effectively 'solid' wall – with an effective thickness equal to actual overall thickness – provided the following conditions are satisfied.

(1) Each leaf is at least 90 mm thick.
(2) For concrete blockwork, the characteristic compressive strength, f_k, (see Chapter 5) should be multiplied by 0.9.
(3) If the two leaves of the wall are of different materials, e.g. one leaf clay bricks and the other concrete blocks, it should be designed for assessment of strength requirements on the assumption that it is entirely constructed of the weaker strength units. The possibility of differential movement between the two differing materials should be considered, and additional joints, etc., provided if required.
(4) The vertical load is applied to both leaves, and the eccentricity of the vertical load does not exceed $0.2t$, where t is the overall thickness of the wall, i.e. two leaves plus the vertical joint thickness.
(5) Flat metal wall ties of cross-sectional area 20 mm × 3 mm are provided at centres not exceeding 450 mm both horizontally and vertically. Alternatively, an equivalent mesh may be provided at the same vertical centres.
(6) The minimum embedment of the ties into each leaf is 50 mm.
(7) The vertical 'collar' joint between the two leaves is solidly filled with mortar as the work proceeds. This, perhaps, is the most difficult requirement to ensure is properly carried out. Solidly filling a narrow vertical joint between two leaves of masonry is not as easy as filling the perpend joints between individual units and, because of the additional time and labour involved, there is always a possibility that it will not be done thoroughly. It is also very difficult to check that the work has been completed satisfactorily. Thus if this type of wall is to be designed and used as a 'solid' wall, particular attention must be paid to the supervision of the work, and the operatives should be made fully aware at the outset of the standard of workmanship that is required.

6.4.5 Grouted Cavity Walls

In the case of cavity walls with a cavity of between 50 mm and 100 mm filled with concrete, the wall may be designed, in accordance with the Code, as a single-leaf wall, i.e. effectively a solid wall, the effective thickness being taken as equal to the actual overall thickness, subject to the following conditions:

(1) The concrete has a 28 day strength not less than that of the mortar.
(2) Requirements (1), (3), (4), (5) and (6) for collar-jointed walls (see section 6.4.4) are complied with.

It should be noted that the grouting operation needs to be undertaken in stages to avoid the pressure of the fresh grout exceeding the capacity of the ties, bearing in mind that the mortar may not be at full strength.

6.4.6 Differing Orthogonal Ratios

For cavity walls in which the two leaves have different orthogonal ratios (see section 6.2.1), the Code recommends that the applied lateral load should be shared between the two leaves in proportion to their design moments of resistance. This requirement is subject, of course, to sections 6.4.1 and 6.4.2 regarding the transfer of loading between the two leaves. The orthogonal ratio is mainly used for panel walls – thus design is usually related to uncracked sections. The section modulus, Z, used in the analysis of such sections, is related to the moment of inertia and hence to the relative stiffness of each leaf.

6.5 Effective Eccentricity Method of Design

As explained in the introduction to this chapter, vertical loading on a member tends to increase its resistance to bending. As shown in Figure 6.2, case 1, where the vertical loading is sufficiently large, the internal stresses within the section are compressive throughout the section. In such cases, an effective eccentricity may be obtained. The applied moment on the section, due to the lateral loading, may be replaced by the actual axial loading at some eccentricity to the centre line, as illustrated in Figure 6.12.

The section may then be designed, as described in Chapter 5, for an axial load applied at an eccentricity of e_{ef}. The design compressive stress may then be assessed using Table 5.15, based on an eccentricity at the top of the member, e_{ef}, and the compressive stress would be load/area with no increase for M/Z due to the eccentricity, as this has been taken into account in the capacity reduction factor, β.

Example 5

The brick wall shown in Figure 6.13 is subject to a uniformly distributed vertical line loading of 50 kN/m run (design load) applied along the centre line. The wall is simultaneously subject to a design lateral load of 0.8 kN/m^2.



Figure 6.12 Eccentricity method of design for laterally loaded masonry walls



Figure 6.13 Wall details for Example 5

The end conditions are obviously important in determining the applied bending moment but, for this example, assume that the bending moment due to the lateral loading may be taken as $wL^2/8$ for simplicity of analysis, the wall being considered to span simply supported between top and bottom lateral restraints.

Therefore

$$\text{design bending moment} = 0.125 \times 0.8 \times 2.6^2 = 0.676 \text{ kN m/m length}$$

$$\text{design axial load} = 50 \text{ kN/m length}$$

Therefore, resultant effective eccentricity, e_{ef}

$$= \frac{0.676 \times 10^6}{50 \times 10^3}$$

$$= 13.52 \text{ mm}$$

$$\text{Eccentricity, as proportion of } t, = \frac{13.52}{215}t, \quad \text{i.e. } 0.06t.$$

$$\text{The slenderness ratio of the wall} = \frac{h_{ef}}{t_{ef}} = \frac{2600}{215} = 12.1$$

Thus from Table 5.15, the capacity reduction factor, β, for the wall with combined axial and lateral loading will be given as follows:

Slenderness ratio = 12

Therefore for eccentricity at top of wall, $e_x = 0 - 0.5t$, $\beta = 0.93$
and for $e_x = 0.1t$, $\beta = 0.87$
Thus by interpolation, for $e_x = 0.06t$, $\beta = 0.92$

Determination of the brick strength and mortar designation is then carried out as described in Chapter 5.

6.6 Arch Method of Design

6.6.1 Vertical Arching

As an alternative to the effective eccentricity method for walls and columns under axial loading, another method of design is given in the Code, based on the formation of a vertical arch.

There are various prerequisites to the use of this method relating to the supports, the design load and the dimensions of the panel, which must be fulfilled in each case. It is felt by the authors that there are certain dangers in the use of this design method, unless these requirements are most strictly complied with. In addition, careful thought should be given to the requirements in respect of practical considerations. For example, the development of arch thrusts requires rigid supports. The provision of concrete floors, etc., may afford adequate restraint. However, concrete and masonry move differentially, and cracks may develop at the junction of the two materials, which may invalidate design assumptions. Similarly, the vertical axial load available to resist the arch thrust must be carefully analysed. It will generally be the characteristic dead load, but the dispersion of vertical loading to other parts of the structure may reduce the actual load available to resist the arch thrust. Alternatively, the dead load at the time of applying the lateral load may be less than in the final condition if, for instance, a basement retaining wall is back-filled at an early stage and before additional vertical loading is available from the superstructure. All these aspects require very close scrutiny before this method of analysis is considered suitable.

The formula given in the Code is based on the following analysis, for which reference to Figure 6.14 should be made. The member is considered to behave under ultimate conditions in the 'three-pinned arch' mode of failure, under the action of a lateral loading, q_{lat}, and a vertical axial load, n. A small crack develops, and hinges form at positions A, B and C (see Figure 6.14). The member deflects slightly and an arch ABC is formed within its thickness.



Figure 6.14 Vertical arching behaviour

Taking moments about C:

$$n \times (t - \delta) + q_{\text{lat}} \times \frac{h}{2} \times \frac{h}{4} = \frac{hq_{\text{lat}}}{2} \times \frac{h}{2}$$

but, as the deflection, δ, is very small $(t - \delta)$ can be taken as t.

Substituting and rearranging in the above equation, the lateral loading, q_{lat}, may be expressed as follows:

$$q_{\text{lat}} = \frac{8nt}{h^2}$$

A general factor of safety is then applied to this expression to obtain the design lateral strength of the wall. This general factor of safety is taken in the Code to be equal to 2. The actual factor of safety, in this instance, is not a partial factor of safety for materials, as no material strengths are directly involved. It is simply a numerical value which is being used but, in view of the caution expressed earlier, perhaps a more onerous safety factor should be employed.

As discussed in section 6.3.2, the assumption of a pin, i.e. knife-edge, support is not correct, and the points of contact A, B and C will have some finite width parallel to the thickness of the wall. The width of this bearing will have the effect of marginally reducing the lateral strength, and normally this can be assumed to be well catered for within the general factor of safety adopted.

Thus in accordance with BS 5628, the design lateral strength of an axially loaded wall or column may be determined from the following formula:

$$q_{\text{lat}} = \frac{4 \times t \times n}{h_{\text{a}}^2}$$

where

q_{lat} = design lateral strength per unit area of wall or column.

n = axial load per unit length of wall available to resist the arch thrust. For normal design it should be based on the characteristic dead load. When considering the effects of misuse or accident, it should be the approximate design load (see Chapter 8).

h_{a} = clear height of wall or column between concrete surfaces or other construction capable of providing adequate resistance to rotation across the full thickness of a wall.

t = actual thickness of wall or column.



Figure 6.15 Wall details for Example 6

This formula may be used provided that the wall is contained between concrete floors affording adequate lateral support and adequate resistance to rotation across the full width of the wall. The reduction of the safety factor to a numerical value of only 2.0 in the 1992 reprint of BS 5628: Part 1 and maintained in the 2002 reprint is not encouraged by the authors, but rather that a value between 2.5 and 3.5 be used similar to material safety factors.

The stresses occurring at dpc level, and the effectiveness of the lateral restraints in resisting the horizontal forces, must also be considered. The axial stress due to n, or the appropriate design load, must not be less than 0.1 N/mm^2, and the h_{a}/t ratio must not exceed 25 in the case of narrow brick or block walls, or 20 for all other types of wall.

Example 6

Determine the design lateral strength of the wall shown in Figure 6.15. (In this example the safety factor employed has been left as 2.5 because of the concerns expressed earlier about the design method.)

From Table 5.11, $\gamma_{\text{m}} = 2.5$
and from Figure 6.15, $n = 25$ kN/m run
$t = 215$ mm
$h_{\text{a}} = 3450$ mm

Thus considering 1 m length of wall:

$$\text{design lateral strength, } q_{\text{lat}} = \frac{8 \times 0.215 \times 25}{3.45^2 \times 2.5}$$

$$= 1.45 \text{ kN/m height}$$

i.e. design lateral strength of wall = 1.45 kN/m^2 on elevation.

Thus the wall is capable of resisting a design lateral loading of 1.45 kN/m^2 on elevation, i.e.

$$\gamma_{\text{f}} W_{\text{k}} = 1.45 \text{ kN/m}^2$$

The strength of the units required and the mortar should then be determined as in Chapter 5, the stresses due to the lateral loading being ignored as far as this part of the design is concerned.



Figure 6.16 Wall details for Example 7

Table 6.3 Design lateral strength with returns = $k \times q_{lat}$ (BS 5628, Table 10)

Number of returns	Value of k			
	$\frac{L}{h_a}$ = 0.75	1.0	2.0	3.0
1	1.6	1.5	1.1	1.0
2	4.0	3.0	1.5	1.2

The lateral strength is an inherent property of the wall, relative to the particular vertical loading being considered. On the basis of the formula given in the Code, it should be noted that the lateral strength varies in direct proportion to the characteristic dead load, and in inverse proportion to the square of the height of the member.

6.6.2 Vertical Arching: Return Walls

In situations where walls or columns are considered suitable for design on the basis of vertical arching (see section 6.6.1), and are supported by return walls of suitable strength, the design lateral strength may be increased. If such return walls are provided, a proportion of the applied loading will be resisted by horizontal spanning of the member, decreasing the amount to be resisted by vertical spanning. The return walls must, of course, be capable of resisting the horizontal reactions transmitted to them. The Code provides for an increase in the value obtained from the formula for the design lateral strength. The amount of the increase depends on whether return walls are provided on one or both sides, and on the ratio of the clear height, h_a, to the length, L, of the member. Values for the appropriate modification factor, k, to be applied to the design lateral strength obtained from the formula in section 6.6.1 are given in Table 6.3.

Example 7

Determine the design lateral strength of the wall in Figure 6.15, if it is provided with returns, as shown in Figure 6.16.

Modification factor, k:

$$L = 6.4, h_a = 3.45$$



Figure 6.17 Lateral load distribution to supporting walls

Therefore, $L/h_a = 1.85$, i.e. two returns.

Thus from Table 6.3, the modification factor may be taken as $k = 1.5$, although by interpolation a higher value could be found.

Thus

$$\text{design lateral strength} = kq_{lat} = 1.5 \times 1.45 = 2.18 \text{ kN/m}^2 \text{ on elevation}$$

The return walls should, of course, be checked to ensure that they are capable of resisting the horizontal reactions. The appropriate method of design is given later in this chapter. The loading on the walls may reasonably be assumed to be that on the area of wall on elevation, enclosed by lines drawn at 45° to the corners, as illustrated in Figure 6.17.

6.6.3 Horizontal Arching

In the case of walls with minimal axial loading, but which are built 'solidly' between supports capable of resisting an arch thrust, the Code provides a method of design based on the assumption that, under lateral loading, a horizontal arch is developed within the thickness of the wall. A similar assumption could be made when a number of walls are built continuously past supports (see Figure 6.18).

The warnings given in section 6.6.1 are equally applicable when horizontal arch thrusts are being considered. A small change in the length of a wall in arching can considerably



Figure 6.18 Horizontal arching opportunities

reduce the arching resistance. Very careful consideration is required as all masonry will move, either expanding or contracting, due to the effects of temperature, moisture, etc. In practice, it is also difficult to butt masonry tightly to the flanges of steel columns, etc.

Longer lengths of masonry should always be provided with joints, and the position of the joints should be considered before this method of analysis is adopted. Designers must make certain that no joints are introduced into walls which have been designed on the basis of arching.

Unlike vertical arching, which is essentially an inherent property of an axially loaded wall, horizontal arching has to be assessed on the basis of the applied lateral loading, the compressive strength of the masonry, and the effectiveness of the junction between the wall and the supports. The effectiveness of the wall/support junction, and the ability of the support to satisfactorily resist the arch thrust, without, for example, excessive deflection, which would invalidate the design assumptions, require careful attention to detail. In particular, the wall/support junction should be solidly filled with mortar.

The design analysis given in the Code is shown in Figure 6.19 and is similar to that for vertical arching. However, the width of the bearing at the assumed 'pinned' joints, see section 6.6.1, is taken as one tenth of the wall thickness – the method adopted being similar to the design of cracked sections (see section 6.3.2).

From Figures 6.19 and 6.20, taking moments at centre line of bearing C for the external forces

$$q_{\text{lat}} \times \frac{L}{2} \times \frac{L}{2} = T\left(t - \delta - \frac{t}{10}\right) + q_{\text{lat}} \times \frac{L}{2} \times \frac{L}{4}$$

But

arch thrust, T = bearing stress × area

$$= 1.5\frac{f_k}{\gamma_m} \times \frac{t}{10} \text{ per unit height}$$

Therefore

$$q_{\text{lat}}\frac{L^2}{4} = 1.5\frac{f_k}{\gamma_m} \times \frac{t}{10}\left(t - \delta - \frac{t}{10}\right) + q_{\text{lat}}\frac{L^2}{8}$$

The Code recommends that, if the ratio of length to thickness, i.e. L/t, is 25 or less, the deflection under the design lateral load can be ignored. If L/t exceeds 25, then allowance should be made.

Thus if $L/t < 25$, δ is assumed = 0.

$$q_{\text{lat}}\frac{L^2}{8} = 1.5\frac{f_k}{\gamma_m} \times \frac{t}{10}\left(t - \frac{t}{10}\right)$$

$$q_{\text{lat}} = 1.5\frac{f_k}{\gamma_m} \times 9 \times \frac{t^2}{100} \times \frac{8}{L^2}$$

$$q_{\text{lat}} = \frac{108}{100} \times \frac{f_k}{\gamma_m} \times \left(\frac{t}{L}\right)^2$$

Considering the design assumptions, etc., the factor (108/100) is ignored, and this formula is then given in the Code as the design lateral strength:

$$q_{\text{lat}} = \frac{f_k}{\gamma_m}\left(\frac{t}{L}\right)^2$$



Figure 6.19 Horizontal arching behaviour



Figure 6.20 Enlarged detail at A (Figure 6.19) – bearing C and B are similar



Figure 6.21 Wall details for Example 8

where

q_{lat} = design lateral strength per unit area of wall
t = overall thickness
f_k = characteristic compressive strength of masonry (see Chapter 5)
L = length of wall
γ_m = partial factor of safety for materials (see Table 5.11).

The Code also states that the supporting structure has to be designed to be capable of resisting the arch thrust with negligible deformation.

Example 8

Determine the compressive strength required for bricks in the wall shown in Figure 6.21, to resist a design lateral loading, of 3.3 kN/m^2. The bricks are to be laid in mortar designation (ii), and $\gamma_m = 2.5$ (special).

Applied design lateral loading = 3.3 kN/m^2

Therefore, design lateral strength, q_{lat}, required = 3.3 kN/m^2

$L/t = 4600/215 = 21$, i.e. $L/t \leq 25$ and therefore

$$q_{lat} = \frac{f_k}{\gamma_m}\left(\frac{t}{L}\right)^2$$

Therefore, knowing q_{lat} required:

$$f_k(\text{required}) = \frac{q_{lat}(\text{required}) \times \gamma_m}{(t/L)^2}$$

$$= \frac{3.3 \times 2.5 \times 10^{-3}}{(215/4600)^2}$$

$$= 3.78\ \text{N/mm}^2$$

Thus from Table 5.4, with mortar designation (ii), units with a compressive strength of 10 N/mm^2 are required.



Figure 6.22 Free standing wall section

6.7 Free-standing Walls

6.7.1 General

Free-standing walls may be external boundary walls, parapet walls or internal walls where no restraint is provided to the top or sides of the wall. They are designed as vertical cantilevers, allowance being made for the stability moment due to the self-weight of the wall.

Consider a section of wall as in Figure 6.22. When a lateral loading is applied to the wall, the tendency to overturn will be resisted by a moment due to the product of the self-weight of the wall and the lever arm. The lever arm being the distance from the line of action of the self-weight of the wall and the point about which the wall is tending to overturn. This moment is termed the stability moment (see also section 6.3.2).

The walls are designed to cantilever, either from the top of the foundations or from the point of horizontal lateral restraint – provided that the restraint is capable of resisting the horizontal reaction or shear from the wall. When stiffer elements, such as piers, are introduced into a free-standing wall, the sections of wall between the piers may be designed as panel walls supported on three sides, or spanning horizontally (see later, section 6.9) and the piers themselves designed as cantilevers to resist the reactions from the panel. The Code recommends that the mortar used for free-standing walls should not be weaker than designation (iii). In addition, it recommends limiting the height of a free-standing wall to twelve times its effective thickness.

6.7.2 Design Bending Moments

The calculation of the design bending moments of a free-standing wall is based on simple statics, the design bending moment on a wall being assessed by taking moments about a particular point. As shown in Figure 6.23, when a wall is subjected to a uniformly distributed wind loading of W_k, and horizontal line loading of Q_k, the bending moment is obtained as follows:



Figure 6.23 Free standing wall behaviour



Figure 6.24 Wall details for Example 9

Total characteristic wind load = $W_k \times h$ per unit length

Applied design wind load = $W_k h \gamma_f$ per unit length

Applied design bending moment, M_A,
about face of wall due to wind = load × lever arm
$= W_k h \gamma_f \times h/2$

Characteristic imposed lateral load = Q_k

Applied design imposed lateral load = $\gamma_f Q_k$

Applied design bending moment, M_A,
about face of wall due to imposed load = load × lever arm
$= \gamma_f Q_k \times h_L$

Therefore, total design bending moment,
$M_A = W_k \gamma_f h^2/2 + Q_k \gamma_f h_L$

where

W_k = characteristic wind load (see section 5.2)
γ_f = partial safety factor for loads (see section 5.3; *note*: factors only applicable to free-standing walls, Table 5.1)
h = clear height of wall or pier above restraint, assuming moments taken about this point
Q_k = characteristic imposed load (see section 5.2)
h_L = vertical distance between the point of application of the horizontal load, Q_k, and the lateral restraint – assuming moments taken about this point.

Example 9

A 6 m high internal free-standing wall in a bus depot is to be designed for an internal wind loading of 0.2 kN/m^2, and an imposed loading of 0.74 kN/m run from a handrail fixed to the wall 1.0 m above floor level (see Figure 6.24).

$\gamma_f = 1.2$ (see Table 5.1).

Design wind load $= 0.2 \times 6 \times 1.2 = 1.44$ kN/m run

Design imposed load $= 0.74 \times 1.2 = 0.89$ kN/m run

Design bending moment $= (1.44 \times 6/2) + (0.89 \times 1.0)$
$= 4.32 + 0.89 = 5.21$ kN/m run

6.7.3 Design Moment of Resistance

The design moment of resistance must be assessed on the basis of either an uncracked or a cracked section, in accordance with sections 6.3.1 and 6.3.2, depending on whether a damp proof course capable of transmitting the tensile stresses is included. In external boundary walls, the damp proof course often consists of two courses of engineering bricks, which would probably be capable of transmitting the tensile stresses. In order to achieve the best use of materials, free-standing walls are often built in geometrical configurations other than the usual rectangular section. Fin walls and diaphragm walls are suitable, as also are chevron, curved and zig-zag walls. The relevant section properties should be used, therefore, when deriving the design moment of resistance for each particular section being considered.

6.8 Retaining Walls

Retaining walls are generally considered to be free-standing walls retaining earth, liquid or stored material, on one side. The design procedure is similar to that for free-standing walls, as discussed in section 6.7. According to BS 5628, the earth pressure should be treated as an imposed load, and the characteristic value taken as the active pressure in accordance with the relevant code of practice for earth-retaining structures.

6.9 Panel Walls

In section 6.7, free-standing walls were considered – a free-standing wall generally being considered as a wall with no restraint at the top and sides, and little or no imposed vertical loading. Such walls behave as vertical cantilevers. In section 6.6, the lateral strength of axially loaded walls was discussed, and from this the increased lateral resistance of a wall, due to the application of a vertical imposed loading, was demonstrated.

In buildings, walls are seldom free-standing, being usually continuous past floors, and with return walls, columns or piers providing restraint to the sides. Thus the wall is no longer a simple vertical cantilever, and may be continuous in one or two perpendicular directions. If such a wall also performs a supporting function, in addition to its enclosing or cladding function, the increased lateral resistance due to the vertical loading will mean that the panel is much stiffer in the vertical direction – providing most resistance in this direction and spanning vertically. If, on the other hand, the wall does not perform a loadbearing function by supporting the vertical loading, and acts merely as a cladding, it is often termed a 'panel wall'. The term is usually applied to a non-loadbearing cladding wall supported by a structural frame. Walls of this kind are subjected to mainly lateral loading, with little or no vertical loading other than their self-weight. However, this is structurally wasteful of the high capacity of masonry to support vertical loading.

6.9.1 Limiting Dimensions

BS 5628 recommends various limiting dimensions to ensure that panel walls are not too slender. The recommended heights and lengths vary according to the support conditions at the panel edges. Figures 6.25–6.27 show typical examples and provide relevant values for masonry set in mortar designations (i) to (iv) designed in accordance with the Code.



$h \times L \leq 1500t_{ef}^2$
where t_{ef} is the effective thickness

but neither h or L to be greater than $50 \times t_{ef}$

two or more sides continuous



$h \times L \leq 1350t_{ef}^2$
where t_{ef} is the effective thickness

but neither h or L to be greater than $50 \times t_{ef}$

all other cases

(a) Panel supported on three edges

Figure 6.25 Limiting dimensions for three sided wall panels



$h \times L \leq 2250t_{ef}^2$
where t_{ef} is the effective thickness

but neither h or L to be greater than $50 \times t_{ef}$

three or more sides continuous



$h \times L \leq 2025t_{ef}^2$
where t_{ef} is the effective thickness

but neither h or L to be greater than $50 \times t_{ef}$

all other cases

(b) Panel supported on four edges

Figure 6.26 Limiting dimensions for four sided wall panels



$h \leq 40t_{ef}$
where t_{ef} is the effective thickness

(c) Panel simply supported top and bottom

Figure 6.27 Limiting dimensions for wall panels simply supported top and bottom

The bending moments and shear forces capable of being resisted by panel walls vary with the edge support conditions. Panels may be simply supported, fully continuous or free, depending on the support condition at any particular edge. Supports are generally formed vertically by piers, intersecting or return walls, or steel or concrete columns. Lateral supports are provided by roofs, floors and foundations.

A simple support may be assumed where a panel is adequately tied to the supporting structure with metal wall ties, or similar. 'Tied', in this context, means a connection capable of resisting the tensile or compressive load, depending on the direction of loading which, in the case of wind load, may be in both directions, as wind loading is reversible. The supporting structure must obviously be able to resist the applied loading, and the wall ties or other fixings should be designed to transfer this loading (see section 6.9.2). A simple support may also be generally assumed where a dpc occurs, although the effectiveness of the support provided should be checked by calculation.

Continuity may be assumed where masonry is provided with return ends, or is continuous past and tied to a column or beam. (Again, in all cases, the supporting structure must be capable of resisting the applied loading.) In the case of cavity walls, only one leaf need be continuous, provided wall ties are used (see section 6.4.3) between the two leaves and between each section of the discontinuous leaf and the support. Where the leaves are of differing thickness, the thicker leaf should be continuous in accordance with the Code.

Typical examples of support conditions are illustrated in Figures 6.28 and 6.29.

6.9.2 Design Methods

As with many other structural elements or forms, walls subject to mainly lateral loads are not capable of precise calculation. The Code provides two approximate methods which may be used to assess the strength of such walls:

(a) as a panel supported on a number of sides,
(b) as an arch spanning between supports.

Walls of irregular shape, or those with openings, require careful consideration and neither of the above methods can be used directly. Although some guidance is given in Appendix D of the Code, each case should be studied carefully by the designer to assess reasonable assumptions to be used in the design. (For further information and examples, see Chapter 11.)

Method (a) is dealt with in the sections which follow (sections 6.9.3–6.9.5). The alternative method (b) is described in section 6.6.3.

6.9.3 Design Bending Moment

The design bending moments vary with the design load, the vertical and horizontal spans, the orthogonal ratio, μ, and the relevant design bending moment coefficient, α. The orthogonal ratio was discussed in section 6.2.1. The bending moment coefficient, α, depends on the edge support conditions, i.e. continuous, discontinuous or free, and the position of the section under consideration.



Figure 6.28 Details providing simple support conditions (indicative only, see Chapter 7 for typical details)



Figure 6.29 Details providing continuity at supports

The design bending moment per unit height of a panel in the horizontal direction may, in accordance with the Code, be expressed as follows:

$$\text{Applied design bending moment, } M_A = \alpha W_k \gamma_f L^2$$

when the plane of bending is perpendicular to the bed joints,

where

α = bending moment coefficient from Table 6.4
γ_f = partial safety factor for loads (see Table 5.1)
L = length of the panel between supports
W_k = characteristic wind load per unit area (see section 5.2).

The Code states that, at a damp proof course, the bending moment coefficient, α, may be taken as for an edge over which full continuity exists when there is sufficient vertical load on the dpc to ensure that its flexural strength is not exceeded. This means that full continuity may be assumed for the determination of α, provided the dpc can transmit the tensile stresses or, if not, that there is sufficient vertical loading to ensure that no tensile stresses are developed across the section, i.e. as in case 1, Figure 6.2.

The applied design moment in the vertical direction, M_A, is given by the following formula:

$$M_A = \mu\alpha W_k \gamma_f L^2$$

when the plane of bending is parallel to the bed joints, provided that the edge conditions justify treating the panel as partially fixed, where μ = orthogonal ratio modified for the vertical loading as appropriate (see section 6.2.1). The remaining terms being as for the horizontal moment.

Values of the bending moment coefficient, α, are given in Table 6.4 for various values of the orthogonal ratio, μ, modified for vertical loading as necessary (see section 6.2.1), various edge conditions, and various ratios of height to length. This table is based on Table 9 of BS 5628.

Table 6.4 Bending moment coefficient in laterally loaded wall panels (BS 5628, Table 9)

Key to support conditions:

—— denotes free edge

simply supported edge

an edge over which full continuity exists



	μ	Values of α						
		h/L						
		0.30	0.50	0.75	1.00	1.25	1.50	1.75
A	1.00	0.031	0.045	0.059	0.071	0.079	0.085	0.090
	0.90	0.032	0.047	0.061	0.073	0.081	0.087	0.092
	0.80	0.034	0.049	0.064	0.075	0.083	0.089	0.093
	0.70	0.035	0.051	0.066	0.077	0.085	0.091	0.095
	0.60	0.038	0.053	0.069	0.080	0.088	0.093	0.097
	0.50	0.040	0.056	0.073	0.083	0.090	0.095	0.099
	0.40	0.043	0.061	0.077	0.087	0.093	0.098	0.101
	0.35	0.045	0.064	0.080	0.089	0.095	0.100	0.103
	0.30	0.048	0.067	0.082	0.091	0.097	0.101	0.104
B	1.00	0.024	0.035	0.046	0.053	0.059	0.062	0.065
	0.90	0.025	0.036	0.047	0.055	0.060	0.063	0.066
	0.80	0.027	0.037	0.049	0.056	0.061	0.065	0.067
	0.70	0.028	0.039	0.051	0.058	0.062	0.066	0.068
	0.60	0.030	0.042	0.053	0.059	0.064	0.067	0.069
	0.50	0.031	0.044	0.055	0.061	0.066	0.069	0.071
	0.40	0.034	0.047	0.057	0.063	0.067	0.070	0.072
	0.35	0.035	0.049	0.059	0.065	0.068	0.071	0.073
	0.30	0.037	0.051	0.061	0.066	0.070	0.072	0.074
C	1.00	0.020	0.028	0.037	0.042	0.045	0.048	0.050
	0.90	0.021	0.029	0.038	0.043	0.046	0.048	0.050
	0.80	0.022	0.031	0.039	0.043	0.047	0.049	0.051
	0.70	0.023	0.032	0.040	0.044	0.048	0.050	0.051
	0.60	0.024	0.034	0.041	0.046	0.049	0.051	0.052
	0.50	0.025	0.035	0.043	0.047	0.050	0.052	0.053
	0.40	0.027	0.038	0.044	0.048	0.051	0.053	0.054
	0.35	0.029	0.039	0.045	0.049	0.052	0.053	0.054
	0.30	0.030	0.040	0.046	0.050	0.052	0.054	0.055

Table 6.4 (*cont'd*)

	μ	Values of α						
		h/*L*						
		0.30	0.50	0.75	1.00	1.25	1.50	1.75
 D	1.00	0.013	0.021	0.029	0.035	0.040	0.043	0.045
	0.90	0.014	0.022	0.031	0.036	0.040	0.043	0.046
	0.80	0.015	0.023	0.032	0.038	0.041	0.044	0.047
	0.70	0.016	0.025	0.033	0.039	0.043	0.045	0.047
	0.60	0.017	0.026	0.035	0.040	0.044	0.046	0.048
	0.50	0.018	0.028	0.037	0.042	0.045	0.048	0.050
	0.40	0.020	0.031	0.039	0.043	0.047	0.049	0.051
	0.35	0.022	0.032	0.040	0.044	0.048	0.050	0.051
	0.30	0.023	0.034	0.041	0.046	0.049	0.051	0.052
E	1.00	0.008	0.018	0.030	0.042	0.051	0.059	0.066
	0.90	0.009	0.019	0.032	0.044	0.054	0.062	0.068
	0.80	0.010	0.021	0.035	0.046	0.056	0.064	0.071
	0.70	0.011	0.023	0.037	0.049	0.059	0.067	0.073
	0.60	0.012	0.025	0.040	0.053	0.062	0.070	0.076
	0.50	0.014	0.028	0.044	0.057	0.066	0.074	0.080
	0.40	0.017	0.032	0.049	0.062	0.071	0.078	0.084
	0.35	0.018	0.035	0.052	0.064	0.074	0.081	0.086
	0.30	0.020	0.038	0.055	0.068	0.077	0.083	0.089
 F	1.00	0.008	0.016	0.026	0.034	0.041	0.046	0.051
	0.90	0.008	0.017	0.027	0.036	0.042	0.048	0.052
	0.80	0.009	0.018	0.029	0.037	0.044	0.049	0.054
	0.70	0.010	0.020	0.031	0.039	0.046	0.051	0.055
	0.60	0.011	0.022	0.033	0.042	0.048	0.053	0.057
	0.50	0.013	0.024	0.036	0.044	0.051	0.056	0.059
	0.40	0.015	0.027	0.039	0.048	0.054	0.058	0.062
	0.35	0.016	0.029	0.041	0.050	0.055	0.060	0.063
	0.30	0.018	0.031	0.044	0.052	0.057	0.062	0.065
G	1.00	0.007	0.014	0.022	0.028	0.033	0.037	0.040
	0.90	0.008	0.015	0.023	0.029	0.034	0.038	0.041
	0.80	0.008	0.016	0.024	0.031	0.035	0.039	0.042
	0.70	0.009	0.017	0.026	0.032	0.037	0.040	0.043
	0.60	0.010	0.019	0.028	0.034	0.038	0.042	0.044
	0.50	0.011	0.021	0.030	0.036	0.040	0.043	0.046
	0.40	0.013	0.023	0.032	0.038	0.042	0.045	0.047
	0.35	0.014	0.025	0.033	0.039	0.043	0.046	0.048
	0.30	0.016	0.026	0.035	0.041	0.044	0.047	0.049
 H	1.00	0.005	0.011	0.018	0.024	0.029	0.033	0.036
	0.90	0.006	0.012	0.019	0.025	0.030	0.034	0.037
	0.80	0.006	0.013	0.020	0.027	0.032	0.035	0.038
	0.70	0.007	0.014	0.022	0.028	0.033	0.037	0.040
	0.60	0.008	0.015	0.024	0.030	0.035	0.038	0.041
	0.50	0.009	0.017	0.025	0.032	0.036	0.040	0.043
	0.40	0.010	0.019	0.028	0.034	0.039	0.042	0.045
	0.35	0.011	0.021	0.029	0.036	0.040	0.043	0.046
	0.30	0.013	0.022	0.031	0.037	0.041	0.044	0.047
I	1.00	0.004	0.009	0.015	0.021	0.026	0.030	0.033
	0.90	0.004	0.010	0.016	0.022	0.027	0.031	0.034
	0.80	0.005	0.010	0.017	0.023	0.028	0.032	0.035
	0.70	0.005	0.011	0.019	0.025	0.030	0.033	0.037
	0.60	0.006	0.013	0.020	0.026	0.031	0.035	0.038
	0.50	0.007	0.014	0.022	0.028	0.033	0.037	0.040
	0.40	0.008	0.016	0.024	0.031	0.035	0.039	0.042
	0.35	0.009	0.017	0.026	0.032	0.037	0.040	0.043
	0.30	0.010	0.019	0.028	0.034	0.033	0.042	0.044

Note 1: Linear interpolation of μ and *h*/*L* is permitted

Note 2: When the dimensions of a wall are outside the range of *h*/*L* given in this table, it will usually be sufficient to calculate the moments on the basis of a simple span. For example, a panel of type A having *h*/*L* less than 0.3 will tend to act as a free-standing wall spanning vertically, while the same panel having *h*/*L* greater than 1.75 will tend to span horizontally.

Table 6.4 (*cont'd*)

Key to support conditions:

—— denotes free edge

simply supported edge

an edge over which full continuity exists



	μ	Values of α						
		h/L						
		0.30	0.50	0.75	1.00	1.25	1.50	1.75
 J	1.00	0.009	0.023	0.046	0.071	0.096	0.122	0.151
	0.90	0.010	0.026	0.050	0.076	0.103	0.131	0.162
	0.80	0.012	0.028	0.054	0.083	0.111	0.142	0.175
	0.70	0.013	0.032	0.060	0.091	0.121	0.156	0.191
	0.60	0.015	0.036	0.067	0.100	0.135	0.173	0.211
	0.50	0.018	0.042	0.077	0.113	0.153	0.195	0.237
	0.40	0.021	0.050	0.090	0.131	0.177	0.225	0.272
	0.35	0.024	0.055	0.098	0.144	0.194	0.244	0.296
	0.30	0.027	0.062	0.108	0.160	0.214	0.269	0.325
 K	1.00	0.009	0.021	0.038	0.056	0.074	0.091	0.108
	0.90	0.010	0.023	0.041	0.060	0.079	0.097	0.113
	0.80	0.011	0.025	0.045	0.065	0.084	0.103	0.120
	0.70	0.012	0.028	0.049	0.070	0.091	0.110	0.128
	0.60	0.014	0.031	0.054	0.077	0.099	0.119	0.138
	0.50	0.016	0.035	0.061	0.085	0.109	0.130	0.149
	0.40	0.019	0.041	0.069	0.097	0.121	0.144	0.164
	0.35	0.021	0.045	0.075	0.104	0.129	0.152	0.173
	0.30	0.024	0.050	0.082	0.112	0.139	0.162	0.183
 L	1.00	0.006	0.015	0.029	0.044	0.059	0.073	0.088
	0.90	0.007	0.017	0.032	0.047	0.063	0.078	0.093
	0.80	0.008	0.018	0.034	0.051	0.067	0.084	0.099
	0.70	0.009	0.021	0.038	0.056	0.073	0.090	0.106
	0.60	0.010	0.023	0.042	0.061	0.080	0.098	0.115
	0.50	0.012	0.027	0.048	0.068	0.089	0.108	0.126
	0.40	0.014	0.032	0.055	0.078	0.100	0.121	0.139
	0.35	0.016	0.035	0.060	0.084	0.108	0.129	0.148
	0.30	0.018	0.039	0.066	0.092	0.116	0.138	0.158

Note 1: Linear interpolation of μ and *h/L* is permitted

Note 2: When the dimensions of a wall are outside the range of *h/L* given in this table, it will usually be sufficient to calculate the moments on the basis of a simple span. For example, a panel of type A having *h/L* less than 0.3 will tend to act as a free-standing wall spanning vertically, while the same panel having *h/L* greater than 1.75 will tend to span horizontally.

6.9.4 Design Moments of Resistance

The design moments of resistance are those based on an uncracked section, as given in section 6.3.1.

6.9.5 Design of Ties

Where wall ties are used to provide simple support, they should be checked to ensure that they can adequately resist the applied loadings. Values for the characteristic strength of wall ties used as panel supports are given in Table 6.5. The value of the partial factor of safety, γ_m, for use with ties used as supports, should be 3.0. However, when considering the probable effects of misuse or accidental damage, this value may be halved. The reaction along an edge of a wall due to the design load may normally be assumed to be uniformly distributed for the purposes of designing the means of support. The load to be transmitted from a panel to its support may, in the case of simple supports, be taken by ties to one leaf only, provided that there is adequate connection between the two leaves. Reference should be made to the requirements for shear resistance of ties in unbonded masonry which is discussed in section 6.10.1.

Example 10

Design suitable ties for the wall load shown in Figure 6.30.

Total design load $= 2.5 \times 4 \times 6 = 60$ kN

Reaction at each edge $= \dfrac{60}{2} = 30$ kN

Table 6.5 Characteristic strengths of wall ties used as panel supports (extended from BS 5628: Part 1)

Type (*Note:* the minimum embedment of a tie in the mortar joint should be 50 mm into each leaf.)	Characteristic strengths of ties engaged in dovetail slots set in structural concrete	
	Tension and compression (kN)	Shear (kN)
Dovetail slot types of ties[a]		
(a) Galvanised or stainless steel fishtail anchors 3 mm thick, 17 mm min. width in 1.25 mm thick glavanised or stainless steel slots, 150 mm long, set in structural concrete	4.0	5.0
(b) Galvanised or stainless steel fishtail anchors 2 mm thick, 17 mm min. width, in 2 mm thick galvanised or stainless steel slots, 150 mm long, set in structural concrete	3.0	4.5
(c) Copper fishtail anchors 3 mm thick, 17 mm min. width, in 1.25 mm copper slots, 150 mm long, set in structural concrete	3.5	4.0

	Characteristic loads in ties embedded in mortar					
	Compression (kN)		Tension (kN)		Shear (kN)[b]	
	All mortar designations		Mortar designations			Mortar designations
	75 cavity	100 cavity	(i) and (ii)	(iii)	(iv)	(i), (ii) or (iii)
Cavity wall ties[c]						
(a) Wire butterfly type: zinc coated mild steel or stainless steel	0.5	0.35[d]	3.0	2.5	2.0	2.0
(b) Vertical twist type: zinc coated mild steel or bronze or stainless steel	same values as for tension for respective mortar designations		5.0	4.0	2.5	3.5
(c) Double-triangle type: zinc coated mild steel or bronze or stainless steel	1.25	0.65	5.0	4.0	2.5	3.0

[a] Fishtail anchors although specified in BS 5628 are not generally in accordance with health and safety regulations and safety or proprietary ties should be used
[b] Applicable only to cases where shear exists between closely abutting surfaces
[c] Superseded BS 1243 describes these specific forms but BS EN 845–1 describes wall ties as wire, thick plate, thin plate and helical. Galvanized ties should only be used in an internal dry environment
[d] Butterfly ties are not recommended for cavity widths over 75 mm and should only be used in minor structures



Figure 6.30 Wall details for Example 10

Try ties type (a), Table 6.5:

Characteristic load in shear = 5.0 kN

$$\text{Design load in shear} = \frac{5.0}{\gamma_m} = \frac{5.0}{3} = 1.67 \text{ kN}$$

$$\text{Number of ties required} = \frac{30}{1.67} = 17.96, \text{ i.e. } 18$$

$$\text{Therefore, provide type (a) ties at } \frac{4000}{18}$$

= 222 mm c/c, i.e. vertically at 225 mm c/c.

6.10 Propped Cantilever Wall Design

The design method for propped cantilever walls in single-storey buildings under wind loading conditions is described in BS 5628, clause 36.9.

The vertical span of such a wall is given as extending from the top (prop) of the wall down to the foundation or to a point of adequate horizontal lateral support – a ground slab, perhaps. The prop at the top of the wall may be provided by a roof bracing system, which is discussed in more detail in Chapter 12. Clause 36.9 introduces the concept of stability moment of resistance as was discussed earlier in Chapter 6 and will feature in the various design examples that follow.

The stability moment of resistance (MR_s) across any bed joint is given by the formula:

$$MR_s = Nl_a$$

where

N = design vertical axial load
l_a = lever arm.

(*Note:* The formula is presented in clause 36.9 as $n_g x$ which has been transposed as $N_g l_a$ to be consistent with the use of symbols elsewhere in this book.)

In calculating the magnitude of N, account must be taken of any uplift forces on the roof. In order to provide for rotation at the base of the wall due to deflection of the roof prop, the MR_s should be generated by gravity forces only, ignoring any flexural tensile resistance at this level which is, at best, unreliable and, at dpcs, usually non-existent. This is termed a 'cracked section' design.

The Code design method requires three conditions to be satisfied as follows:

(a) The maximum bending moment in the height of the wall should be resisted by the flexural tensile strength of the wall at that level. At the lower support the design moment of resistance due to gravity forces should be assessed using factors of safety of 0.9 on the dead load and 1.4 on the wind load.
(b) The wall should be stable when designed using the 'cracked section' approach – ignoring any flexural tensile resistance – and using safety factors of 1.0 on both the dead and wind loads respectively.
(c) Compressive stresses should be checked.

The authors are content with design condition (a) but are extremely concerned that design condition (b) will produce wholly unrealistic wall thickness requirements and are disappointed that no guidance is given for calculating the flexural compressive strength required in design condition (c). An additional calculation is provided at the end of Example 10 in Chapter 11 to demonstrate the authors' concerns with satisfying design condition (b) above. It can, in fact, be shown that a modern bungalow wall constructed with a 102.5 mm brick external leaf and a 200 mm lightweight blockwork internal leaf would fail to satisfy design condition (b) which, surely, cannot be its intention. Until this problem with clause 36.9 is resolved the authors recommend the continued use of the design method described in Chapter 11 and calculated in Example 6.

6.10.1 Geometric and other Sections in Shear

The vertical shear stress at the critical interface of a diaphragm wall section is shown in section 13.9.3 and elsewhere throughout this book. Such stress conditions must be resisted by either:

(a) the masonry itself being bonded across the interface, values for the strength of which are given in section 6.12.1; or
(b) where the masonry is unbonded, flat metal shear connectors placed in the bed joints, the size and spacing of which are derived from the formula:

$$ru = \frac{12 t_w s v}{0.87 f_y}$$

where

r = width of connector
u = thickness of connector
t_w = width of masonry section in vertical shear
s = spacing of connectors
v = design vertical shear stress on masonry section
f_y = characteristic tensile strength of connector.

This formula was introduced into the Code, as clause 36.9.4.1(b) for the first time in the December 1992 reprint. The authors are unaware of the basis of its derivation and some cautionary comments about its use are included as part of Example 4 in Chapter 11.

6.11 Eccentricity of Loading in Plane of Wall

In crosswall construction, and other similar structural forms, the walls are subject to loading in the plane of the wall. This is usually the result of wind loading on the building elevation. The walls then act as vertical cantilevers, stability and the resistance moment being provided by the vertical loading in the wall (see Figure 6.31).

The resultant eccentricity of the combined lateral and vertical loading is calculated from consideration of statics. All



Figure 6.31 In-plane lateral loading



Figure 6.32 Isometric view of building

the stresses in the walls are then calculated by an elastic analysis, and the increased compressive stress due to the wind loading in the plane of the wall should be checked against the wall's tendency to buckle. An example is given in Chapter 11.

Where, as in Figure 6.32, several walls provide resistance to wind loading, the horizontal force should be distributed between the walls in proportion to their flexural stiffness at right angles to the direction of the force. Thus in unreinforced masonry, where Young's modulus will not vary from wall to wall, the horizontal force is distributed between the walls in relation to their respective moments of inertia. The connections between the various walls must be capable of transmitting the necessary loadings.

It is important to check that the floors, roofs, etc., which are generally used to distribute the loading from the elevations to the crosswalls, are capable of distributing them in the proportion determined from the respective I values of the walls.

6.11.1 Design of Walls Loaded Eccentrically in the Plane of the Wall

In the case of crosswalls, and walls acting in a similar fashion, the intensity of loading at any particular position should, in accordance with the Code, be assessed on the basis of the load distribution shown in Figure 6.33. The strength of the wall should then be determined in accordance with sections 5.13 and 5.14.

6.12 Walls Subjected to Shear Forces

So far, consideration has been given to masonry subject to flexural bending stresses. However, when members are subjected to bending, they are also required to resist shear forces, and the resulting shear stresses must generally be investigated.

6.12.1 Characteristic and Design Shear Strength

The characteristic shear strength of masonry is influenced by several factors which include the direction of the applied shear, the axial stress or pre-load on the wall (or other



Figure 6.33 Load distribution from loading eccentric to plane of wall



Figure 6.34 Shear forces acting in the horizontal and vertical planes of bonded masonry

member) and the mortar designation. In the horizontal direction of the horizontal plane (see Figure 6.34) the Code allows for the increase in shear strength due to vertical loading by allowing the characteristic shear stress to be increased by 0.6 times the stress due to vertical loading up to certain limiting values – both dead and imposed loading being considered to give the worst conditions.

For mortar designations (i) and (ii), the characteristic shear strength for walls may be taken as follows:

$$f_v = (0.35 + 0.6g_A)\ \mathrm{N/mm^2}$$

with a limit of 1.75 N/mm^2, where g_A is the design vertical load per unit of the wall cross-section due to vertical dead loads, and imposed load when the imposed load is permanent, calculated from the appropriate loading condition.

For mortar designations (iii) and (iv), the characteristic shear strength for walls may be taken as:

$$f_v = (0.15 + 0.6g_A)\ \text{N/mm}^2$$

with a maximum of 1.4 N/mm^2.

A characteristic shear strength value, f_v, as shown in Figure 6.34 is given for bonded masonry in the vertical direction of the vertical plane and may be taken as:

(a) for bricks set in mortar designations (i) and (ii), f_v = 0.7 N/mm^2
(b) for bricks set in mortar designations (iii) and (iv), f_v = 0.5 N/mm^2
(c) for dense aggregate solid concrete blocks having a minimum strength of 7 N/mm^2 set in mortar designations (i), (ii) or (iii), f_v = 0.5 N/mm^2.

The design shear strength is then obtained by reducing the characteristic strength by an appropriate partial factor of safety and is given by the formula f_v/γ_{mv}, where γ_{mv} is the partial factor of safety. For mortar not weaker than designation (iv), γ_{mv} = 2.5. When considering the probably effect of misuse or accident, γ_{mv} may be reduced to 1.25.

6.12.2 Resistance to Shear

Provision against the ultimate limit state of shear being reduced may be assumed where the shear stress due to the horizontal design load is less than, or equal to, the design shear strength:

$$v_h < \frac{f_v}{\gamma_{mv}}$$

where v_h is the shear stress produced by the horizontal design load calculated as acting uniformly over the horizontal cross-sectional area of the wall.

Example 11

Check the shear stress at the base of the wall shown in Figure 6.35. Assume mortar designation (ii).

Consider 1 m length of wall:

Applied design lateral load at base (assume for this example, half applied load resisted at base) is

$$V = \gamma_f W_k \times \frac{h}{2}\ \text{per unit length}$$

Appropriate γ_f, from Table 5.1 = 1.4



Figure 6.35 Wall details for Example 11

Therefore, $V = 1.4 \times 1.5 \times \frac{4}{2} = 4.2$ kN/m run

Therefore, applied design shear stress (assumed to act uniformly over horizontal cross-section of wall) is

$$V_h = \frac{4.2 \times 10^3}{10^3 \times 215}$$

$$= 0.019\ \text{N/mm}^2$$

Characteristic shear stress, $f_v = (0.35 + 0.6g_A)\ \text{N/mm}^2$

$$g_A = \frac{\gamma_f G_k}{\text{cross-sectional area}}$$

Appropriate γ_f, from Table 5.1 = 0.9

$$\text{Thus, } g_A = \frac{0.9 \times 5 \times 10^3}{10^3 \times 215} = 0.021\ \text{N/mm}^2$$

(*Note:* The self-weight of the wall has been ignored since similar shear stress occurs at the top of the wall where self-weight does not enhance shear resistance.)

Therefore, $f_v = 0.35 + 0.6 \times 0.021 = 0.36$ N/mm^2

$$\text{Therefore design resistance to shear stress} = \frac{f_v}{\gamma_{mv}} = \frac{0.36}{2.5}$$

$$= 0.14\ \text{N/mm}^2$$

Thus, $v_h < \frac{f_v}{\gamma_{mv}}$, and is therefore satisfactory.

If the wall in the above design example were to be reinforced or post-tensioned, additional factors relating to the characteristic shear strength, f_v, must be taken into account and these are discussed in section 15.3.6.

7 Strapping, Propping and Tying of Loadbearing Masonry

In all structures, it is essential that the design engineer, in making assumptions regarding the behaviour of the structure, ensures that all such assumptions are soundly based, practical to achieve, and adequately catered for in the structural details. There are few aspects of the design/detail process more involved in this problem than the strapping, propping and typing requirements of loadbearing masonry.

Assumptions regarding restraint, end support conditions, resistance to uplift forces, etc., must all be carefully considered and detailed. These points are just as important in small single-storey structures as they are in tall heavy engineering projects. In fact, modern lightweight cladding and partitions have meant that more and more building types are sensitive to relatively small changes in loading conditions. For example, when lightweight decking is used, stress reversal occurs at much lower wind suction than for more heavy forms of roof cladding (see Figure 7.1).

In the past, reliance for stability, particularly on single-storey buildings, was often achieved using traditional room dividing walls without the need for calculations. However, since the introduction of lightweight non-loadbearing partitions, the stability of such structures has become critical for relatively small wind loadings (see Figure 7.2).

In the above examples, the need for adequate connections to transfer wind uplift and shear loads from the various elements to which they are applied into the elements on which they are to be resisted, is absolutely critical to the overall stability of the building. Wall restraints, uplift straps, ties and seating connections are far more critical than many engineers and architects realise and, in masonry structures in particular, these elements often become the items which determine the completed building's life. They are all too often the ill-conceived weak link of the structure, which can be such that repair or replacement is more costly than demolition and rebuilding. It is essential that more consideration is given to corrosion and the life expectancy of these elements for the conditions in which they are built than has been given in the recent past.



Figure 7.1 Wind uplift and imposed and dead load combinations

For centuries, masonry structures have proved to be very adaptable and have been handed down from one generation to the next, and successfully modified or altered to meet changing needs and patterns of use. The economic and environmental advantages of this can scarcely be overemphasized. In recent years, however, the rate of change in the approach to design has not kept pace with the rapid changes in materials and construction techniques. Numerous failures have already occurred and, if the traditional virtues of masonry construction are to be maintained, it is important that the pitfalls of recent trends be corrected in the next generation of buildings.

Extra attention to the function and expected life of the small but essential elements already referred to will go a long



Figure 7.2 Plans on typical single-storey building

way towards reducing the number of future problems. The forces in these elements, the practicability of the construction, the environment in which they must survive and the materials of which they are made, are most important considerations.

The importance of both the overall stability and the detailed connection of element to element cannot be overemphasised. Many building failures have resulted from the lack of an engineering check on overall stability and the connection of element to element, and this is particularly highlighted by hybrid structures where elements of different materials have been designed by different specialists and no overall stability check has been made.

In construction, compliance with the accidental damage requirements (see Chapter 8), plus the greater awareness of stability problems with tall buildings tend to lead engineers to a more suitable and robust structure. But modern construction methods and materials have produced 'non-traditional' buildings and thus a greater need for engineering design. Engineering design is as much to do with the joining of individual elements to form a robust structure, as it is to do with the design of the individual elements of which it is composed.

It is this aspect of design, namely the strapping of walls to floors and roofs, with which this chapter is concerned and, in the broadest terms, the two objectives could be summarised as:

(a) to identify situations where tying problems exist,
(b) to suggest specimen details which would form the basis of a solution for each situation.

Here, as in all engineering design, there are no special details which are universally applicable and the engineer must select his own solution for the individual requirements of structural adequacy. While it is right and proper for codes and building regulations to insist on the placing of straps in certain situations, and to insist on a minimum standard, the varied nature of tying problems forbids placing too firm restrictions on the engineer's freedom to deal with each case on its merits. Nevertheless, the general guidance given in this chapter should prove useful.

7.1 Structural Action

Before highlighting the problem areas, it may be useful to review quickly the way in which a typical low-rise masonry structure would be made to work. From this exercise, the reason for the inclusion of ties in the design should become evident and certain problem areas should emerge.

The design of a solid wall under eccentric loading can be undertaken using the basis of design in Chapters 5 and 6. The strength of the material and the geometric property of slenderness ratio are the basis for the design. Assumptions do need to be made concerning the support of the wall at its top and at its base, in order that the slenderness ratio can be calculated. It follows that the design of such walls implicitly places on the engineer the responsibility to ensure that such edge conditions present in the completed structure are as assumed in the design. The easiest way and, indeed, in many cases the only way, is to tie the wall to a floor or roof.



Figure 7.3 Deflection profiles of restrained / unrestrained laterally loaded walls

As an example, consider a two-storey house which is built unrestrained except for the roof which is carried by the wall. Such a wall (Figure 7.3) will have a possible failure mode similar to that shown. This is an inherently weak situation when viewed as a stability problem, and an extremely thick wall would be required on this basis.

It must be remembered, of course, that this presupposes that the wall has no returns. In the majority of domestic construction, returns are present if only because of the traditional approach to house building. Certainly, following the aftermath of Ronan Point, the multi-storey flats failure which drew attention to accidental damage and progressive collapse, the unreturned type of wall is no longer common, since good practice now suggests that a loadbearing panel should be strengthened with at least one substantial return wall. Having said this, however, the mode of failure shown in Figure 7.3 is possible towards the free edge of a three-sided panel, or in the central region of a four-sided one of large length. If the wall is restrained at floor level, the failure mode would change to the S shape shown in Figure 7.3, giving a smaller slenderness ratio which would allow a wall of less thickness to be justified. Clearly then, there is a distinct advantage to be gained in structural efficiency by restraining the deflection at all floor levels, as



Figure 7.4 (a) Timber floor abutting cavity wall, (b) timber floor 'built-in' to cavity wall



Figure 7.5 Eccentricity of workmanship

well of course at the roof level. Such restraint of horizontal movement can be of two main types.

Figure 7.4(a) shows schematically a pinned horizontal support. The connections between wall and floor do prevent horizontal movement but are not sufficiently rigid to afford any resistance to rotation on the wall at floor levels. In Figure 7.4(b), however, the floors are carried through the walls. If the floors are of sufficient stiffness they afford a degree of resistance to rotation, which results in a reduced effective length and hence slenderness ratio.

There is another stability requirement, however, regarding strapping, namely the workmanship and inbuilt 'out of balance' factor should the wall be built with an initial out of balance, i.e. as shown in Figure 7.5. Here a tie force P would be required to hold the wall stable against the overturning effect of the applied dead and live load, W, which is now eccentric with respect to the base of the wall.

The moment equation is written:

$$W \times e = P \times h$$

neglecting the self-weight of the wall, where

W = vertical load
P = required tie force
e = eccentricity
h = height

(see Figure 7.5).

P is therefore related to the maximum load, W, to which the wall is likely to be subjected, and the eccentricity, e.

If P is assumed to be n% of W then:

$$W \times e = \frac{nW}{100} h$$

This suggests that the eccentricity, e, is n% of h. At present, a figure of $2\frac{1}{2}$% of the maximum applied weight is recommended for P sufficient to restrain a wall of 2.54 m storey height when it is built out of balance by 63 mm. Generally speaking, there is a consensus of opinion that $2\frac{1}{2}$% is a figure of the right order, which, furthermore, is common to concrete and steel codes of practice and which allows a certain added factor to cover other aspects of workmanship detail and eccentricities due to deflections. It is certainly a figure by which previous practice has been shown to be both workable and adequate.

At this stage, the wall is restrained at the floor level and any out of balance will be resisted by the tie. Any wind loading, whether positive pressure or negative suction, will also need to be carried by the tie arrangements. It is necessary to consider the distribution of these forces when they have been transferred via the strapping into the masonry.

Consider a simple box type structure as shown in Figure 7.6. In section, the structure has a degree of stiffness based on the cantilever action of the walls. Nevertheless, it is basically a mechanism (unless some form of movement joint could be introduced) and, on application of the wind



Figure 7.6 Box type structure behaviour

load, the structure would sway through the position shown dotted on the figure as it collapsed. This mode of failure can be prevented by restraining the sway using walls A and B. If the floor is strong enough to act as a stiff plate, the two walls C and D can be held vertical if the wind force is transferred into walls A and D. Both these walls are extremely stable and stiff when loaded with in-plane forces and made to act as a shear wall. To obtain this action, some form of shear key must be present, or introduced, between the floor plate and walls A and B at the floor level.

Similarly the converse should apply. When a wind force is considered to act on walls A or B, they may not have sufficient returns to give total structural stability and, consequently, the wind forces when transferred into the floor plate must be taken via a shear key on to walls C and D. These two walls, acting as shear walls (together with any contributions from the four returns) provide the stability in the longitudinal direction of the building.

There are, therefore, two main actions that the floor plate has to perform. The first is to provide horizontal support to the top or bottom of the wall at floor level, while the second is to provide a means of shear transfer between the wind loaded wall and the perpendicular shear walls. Each of these is considered in more detail below.

7.2 Horizontal Movement

Floor Bearing onto Walls

Many possible arrangements exist to ensure that floors bear onto walls. These can range from the floor being insitu concrete which is carried in bearing on the full width of the wall, to the floor being of timber joists and boarding which is 'suspended' between the walls on joist hangers. A possible mid-range solution is shown in Figure 7.7, where the joists are carried part way into the inner leaf.

To be confident that the wall will have no detrimental movement, it must be strapped to the floor. This need not be at every joist, but must be at a spacing which can be justified by calculations. To stop the wall moving in direction A, an L-type strap could be used as shown. This would



Figure 7.7 Timber floor bearing onto inner leaf of cavity wall

then act as a tie. Should the wall attempt to move in direction B relative to the floor, the tie will not restrain it and some other arrangement must be introduced to prohibit such movement. This could be an angle stud affixed to the top of the beam, as indicated, or a batten, positioned where the angle is shown to be, running along the length of the wall and securely fixed to the joists.

Floors Abutting Walls

Where floors abut the wall, but are not spanning onto it, a similar type of strapping arrangement could be used (see Figure 7.8). The L-shaped strap will restrain the wall from movement in direction A by acting as a tie. Should there be movement in direction B, however, the floor must be made to act as a stop. This can be achieved by packing between the wall and the first joist. The joist, however, is not particularly stiff in the situation where it may bend about its minor axis. To give this external joist added stiffness the first two or three joists could be braced either by diagonal strutting or by blocking as shown on the plan form (Figure 7.9). Such an arrangement will effectively restrain the wall from any horizontal deflection. Without the packing piece between wall and joist, it would be possible for the tie to either



Figure 7.8 Timber floor abutting inner leaf of cavity wall



Figure 7.9 Shear keying between walls and floors

buckle or slip in the mortar joint and it is for this reason that it should be included in the joint detail.

Internal walls with the floors solidly abutting on either side will have the same effect, in general, of restraining wall movements.

The foregoing details rely, however, on the assumption that the floor remains horizontally undeflected with respect to the rest of the structure, otherwise a 'house of cards' type of total collapse may ensue.

7.3 Shear Keying between Wall and Floors

The final arrangement of ties to restrain all walls from horizontal movement is shown in Figure 7.9. It can be seen that, while one set of straps is acting in tension (or the floor acting as a compression plate), the other set of straps, orthogonally placed with respect to the first set, will act as a shear key. In many cases, this amount of shear keying, combined possibly with other shear connections which are also present, such as joists carried into walls on joist hangers, will suffice. Nevertheless, there may be situations where the forces to be transmitted from the floor into the wall are of such magnitude that special fixings will need to be incorporated which are capable of resisting the shear forces involved.



Figure 7.10 Detail for holding down of roof

7.4 Holding Down Roofs Subject to Upward Forces

Thus far, the need for connecting floors to walls has been due to horizontal forces acting on the wall.

Another major area of concern is the connection between the roof and the wall. All that has previously been said about strapping masonry to floors is still relevant to roofs. In many cases, however, there is an added problem of holding down a roof on which suction is liable to act. This is more relevant to flat roofs and pitched roofs of shallow slope. In the situation shown schematically in Figure 7.10, not only must the normal ties and shear keys be present (although they have been omitted for reasons of clarity from the figure), but also the roof must be sufficiently well connected to enough of the masonry to ensure that it is still 'held down' when the worst suction acts on the roof. Generally speaking, this is achieved by connecting the roof to several courses of brickwork or blockwork at the top of the wall. The exact number of courses picked up by the holding-down strap will depend on the amount of uplift, and will be calculated on the basis that the total weight of the masonry plus roof is greater than the total uplift forces by a suitable safety margin.

In practice, the roof is rarely tied down directly to the masonry. A timber wall plate is positioned on top of the wall and the roof is then tied down to the wall plate (see Figure 7.11). Many proprietary brands of fixing are available which are quite adequate for this job and, in general, there is little difficulty in holding the rafter or truss down to the wall plate. This cannot be said of the problem of holding down the wall plate, and its accumulated uplift on the wall, and it is this aspect of the detail which is predominant. It must be remembered that the use of a wall plate also reopens the question of shear keys, and the shear strength of the timber/mortar interface between the wall plate and the wall. In general, where shear is a problem, the holding down details should be appraised to check the adequacy of shear resistance.

7.5 Areas of Concern

From the foregoing structural considerations, three major areas of concern can be seen to exist:



Figure 7.11 Detail for holding down of roof

(a) the tension/compression connections of walls to floors and roofs,
(b) the connections of floors and roof plates to shear walls,
(c) the tying down of wall plates to the walls.

These connections require careful, calculated, and detailed design.

It should be remembered, of course, that these connection requirements are not unique to loadbearing masonry. The design of many structures would require similar careful detailing of connections, the prime example of which is a structure using precast concrete loadbearing panels. It is essential, however, to be both aware of the limitations of the materials, and be ready to exploit any advantageous properties which they may possess. Because of this, the final detail of masonry connections may differ considerably from those used in other forms of construction, although the fundamental considerations for incorporating them into the design are the same for all types of structures.

7.6 Other Factors Influencing the Details of Connections

Besides the overriding consideration of structural adequacy, other factors emerge which not only influence the final detail of the strap arrangements, but are also open to debate and could be considered controversial.

Consider the Strength of the Strap

At present, BS EN 845, Part 1, the British Standard for ties, tension straps, hangers and brackets suggests that straps are provided with a maximum thickness not exceeding half of the mortar bed joint thickness. The EN standards are performance standards and therefore do not provide a prescriptive value of 5 mm for a strap as previously given in BS 1243. The need for such a 5 mm thickness of metal is questionable on the grounds of strength but in many situations is justifiable on grounds of durability. If it is assumed that durability is not a problem and a 3 mm thickness is considered, this has certain advantages when considering 'buildability' highlighted by the possible avoidance of rebating the straps into joists.



Figure 7.12 Strap to masonry behaviour

Considering the strength of a 3 mm strap in tension, the lateral forces of two- and three-storey housing generally vary, depending on location between approximately 0.8 and 2 kN/m run. Assuming 1.8 m centres, the strap load lies between 1.44 and 3.6 kN. A tie of 3 mm × 30 mm cross-section with two 6 mm diameter holes gives a net area of 54 mm^2. The maximum working stress would be approximately 40 N/mm^2, which is acceptable for mild steel. A 3 mm thickness for ties should prove more than adequate in pure tension on strength grounds. It is possible that an L strap, bent down into the cavity, would be pulled straight by the range of forces which could act on it. BS EN 846, Part 4 details tests to determine the load capacity and load deflection characteristics of straps.

Consider Crushing of the Brick

Assume that only the top one-third of the 100 mm turn-down of the strap bears on the wall when the strap is tensioned by the 3.6 kN force. The bearing force on the masonry, assuming the triangular distribution shown in Figure 7.12, is then:

$$2 \times \frac{3.6 \times 1000}{30 \times 33} = 7.3 \text{ N/mm}^2$$

This is an acceptable value for common bricks and many blocks.

Consider the Bending Value of the Strap

Again assume the stress block is 33 mm deep.

The lever arm of the forces about the right-angled bend is:

$$\frac{33}{3} = 11 \text{ mm}$$

$$\text{Moment} = 11 \times 3.6 \times 10^3 = 39\,600 \text{ N mm}$$

$$Z = \frac{30 \times 3^2}{6} = 45 \text{ mm}^3$$

$$\text{Stress in strap} = \frac{39\,600}{45} = 880 \text{ N/mm}^2$$

This is clearly an unacceptable stress. It may not, however, be a governing factor since a small deflection will ensue at this stress level, which, in turn, will affect the bearing area, which, in turn, will reduce the moment. The system should therefore reduce to stability, assuming the masonry does not begin to crush. It is this interplay of parameters that

makes this topic more amenable to a laboratory investigation than a theoretical analysis. Nevertheless, if the right-angle bend could be strengthened against a bending failure mode, the performance of the strap would be greatly enhanced. One way of achieving this would be to use slot indentations in the steel strap in the region of the right-angled bend. The suggestion of using 100 mm turn-downs into the cavity is a compromise between the requirements of catching more than one brick or block yet limiting the maximum lever arm of the force about the right-angled bend. The 100 mm value is purely arbitrary. BS EN 846, Part 4 specifies tests on straps in wallettes.

Where more than one solution would fulfil the basic requirement of structural adequacy, the deciding factors are likely to be concerned with ease of construction (buildability), and with its related parameter, cost. One example of such considerations is the question of whether to screw, bolt or nail floor beams into joist hangers. On both grounds nailing is preferable.

Assuming the approximate figure of 2 kN/m run tie force as the maximum of the range with joist hangers spaced at 600 mm centres, the force per joist hanger is 1.2 kN. Assuming a C16 timber group, without allowing any reduction factors, five nails would suffice. In many practical situations four 11 gauge nails would be required. Clearly this is a more economical solution than bolting.

Another example on 'buildability' arises where connections have to fulfil several functions. This occurs where a roof must not only be strapped to a wall, but must also be held down to it while, at the same time, the wall plate must also transfer shear load from the wind load on the gable ends. In such situations, it is not uncommon to find this already complex detail further complicated by the positions in which the nail plates have been used on the trusses.

Where precast floor beams have been used spanning in one direction, it is possible to find the screed damaged at the centre of the span against abutting walls, caused by the difference between the deflection of the beams at the centre span and the inability of the tie to deflect at the point where it emerges through the mortar course of the wall. This type of irritating performance failure requires careful consideration to be given to likely deflection contours of two-, three- or four-sided panels. Possibly a more stringent deflection limit, with consideration given to the value to be adopted, needs to be introduced for such situations.

In certain situations, for example large walls of more than normal height, there may be concern for the way in which the outer leaf is tied to the inner leaf at the region where the inner leaf is effectively restrained against lateral movement at the top. In situations like this, there is an argument for placing an extra number of wall ties in the immediate vicinity of strapping.

BS 5628 includes in its Appendix C details and requirements for connections to floors and roofs by means of metal anchors and joist hangers capable of resisting lateral movement.

The Code requires that the effective cross-section of anchors and of their fixings should be capable of resisting the appropriate design loading, which is the sum of:

(a) the simple static reactions to the lateral applied design horizontal forces at the line of lateral support, and
(b) 2.5% of the total design vertical load that the wall or column is designed to carry at the line of lateral support; the elements of construction that provided lateral stability to the structure as a whole need not be designed to support this force.

The Code also states that the designer should satisfy himself that loads applied to lateral supports will be transmitted to the elements of construction providing stability, e.g. by the floors or roofs acting as horizontal girders or plates.

The stress assumed for design purposes is to be the characteristic yield strength (or its equivalent), as laid down in the appropriate British Standard, divided by $\gamma_m = 1.15$. Anchors should be provided at intervals of not more than 2 m in houses or not more than 1.25 m for all storeys in all other buildings. Galvanised mild steel straps having a cross-section of 30 mm × 5 mm may be assumed to have adequate strength in buildings of up to six storeys in height.

The Code also gives other types of buildings where simple resistance or enhanced resistance may be assumed, provided certain conditions of tying are incorporated (see Chapters 5 and 6).

The following illustrated examples of strapping and tying should help the engineer in selecting a suitable detail. The design examples which follow the illustrations will give guidance on the assessment of the forces involved.

The typical details which follow show methods of holding down roofs, stabilising walls at floor and roof levels, and shear transfer from roofs and floors to walls. It should be noted that the dimensions are only typical, and each detail must be designed to cater for the load and the environmental conditions.

7.7 Illustrated Examples of Strapping and Tying



Figure 7.13 Method of securing wall plate to an external loadbearing wall to resist uplift



Figure 7.14 Method of securing wall plate to internal brickwork loadbearing walls to resist uplift



Figure 7.15 Method of securing wall plate to hollow block inner leaf of cavity wall and hollow block internal walls to resist uplift (suitable for walls 140 mm thick and over)



Figure 7.16 Method of securing wall plate, to resist uplift, where walls are plastered (This is an alternative to details in Figures 7.13 and 7.15.)



Figure 7.17 Method of securing wall plate



Figure 7.18 Location of details for timber pitched roof and timber floor



detail of external loadbearing wall fixing to stablise wall at eaves level
Location 1 fixing



detail of block partition wall fixing to stablise wall at eaves level
Location 2 fixing



detail of plastered brick partition wall fixing to stablise wall at eaves level
Location 2 fixing



detail of unplastered brick partition wall fixing to stablise wall at eaves level
Location 2 fixing

Figure 7.19 Eaves details for timber pitched roof (see Figure 7.18 for location)



detail of fixing to stablise wall at eaves level
Type 4 fixing



detail of truss on block partition wall stablising wall at eaves level
Type 5 fixing



detail of fixing to stablise bracing wall at eaves level
Type 6 fixing



detail of fixing to unplastered brick partition wall, trusses off wall, to stablise wall at eaves level
Type 5 fixing



detail of fixing to block partition wall fixing to stablise wall at eaves level
Type 2 fixing



detail of plastered brick partition wall fixing, truss on wall, to stablise wall at eaves level
Type 3 fixing

Figure 7.20 Eaves details for timber pitched roof (see Figure 7.18 for location)



Figure 7.21 Fixing of timber floor joists spanning onto walls (see Figure 7.18 for location)



Figure 7.22 Fixing of timber floor joists spanning onto walls (see Figure 7.18 for location). Standard herringbone and solid strutting between joists



detail of fixing of timber roof members spanning parallel to gable wall to stablise wall Location 4 fixing

detail of fixing of timber roof members spanning parallel to compartment wall to stablise wall Location 6 fixing

Figure 7.23 Fixing of timber roof members spanning parallel to walls (see Figure 7.18 for location)



plan on gable at truss level

section through sheeted gable showing method of tying gable wall to roof bracing system (function is to stabilise the gable)

Figure 7.24 Timber pitched roof – details of sheeted gable



Figure 7.25 Timber pitched roof – details of brick gable wall



Figure 7.26 Location of details for timber flat roof and concrete floor



detail of external loadbearing wall fixing to stablise wall and hold down roof at roof level
Location 1 fixing

detail of internal loadbearing wall fixing to stablise wall and hold down the roof at roof level
Location 3 fixing

detail of plastered brick partition wall fixing to stablise wall at roof level
Location 2 fixing

Figure 7.27 Fixing of timber flat roof members spanning onto walls (see Figure 7.18 for location)



detail of fixing of timber floor spanning parallel to brick partition wall (unplastered) to stablise wall
Type 2 fixing



detail of fixing of timber floor spanning parallel to gable wall to stablise wall and hold roof down
Location 4 fixing



detail of fixing of timber floor spanning parallel to partition wall to stablise wall
Location 5 fixing



detail of fixing of timber floor spanning parallel to bracing wall to stablise wall and transfer shear
Location 6 fixing

Figure 7.28 Fixing of timber roof joists spanning parallel to walls (see Figure 7.18 for location). Standard herringbone and solid strutting between joists



external loadbearing wall

detail of fixing of concrete floor spanning onto brick external wall to stablise wall
Location 1 fixing

partition wall

detail of fixing of concrete floor spanning onto partition wall to stablise wall
Location 2 fixing

internal loadbearing wall

detail of fixing of concrete floor spanning onto loadbearing wall to stablise wall
Location 3 fixing

Figure 7.29



gable wall

detail of fixing of concrete floor spanning parallel to brick external wall to stablise wall
Location 4 fixing

partition wall

detail of fixing of concrete floor spanning parallel to partition wall to stablise wall
Location 5 fixing

bracing wall

detail of fixing of concrete floor spanning parallel to loadbearing wall to stablise wall
Location 6 fixing

Figure 7.30



either **or**

Figure 7.31 Timber floor bearing directly onto wall and stabilising wall



standard joist hanger – nailed

nailed or bolted improved joist hanger

Figure 7.32 Joist hanger connection detail



typical joist hanger
(size and fixings vary according to load and joist size – see manufacturer's literature)

Figure 7.33 Typical joist hanger



typical restraint straps
(size and fixings vary – see manufacturer's literature)

Figure 7.35 Typical straps



insitu concrete



timber joists

Figure 7.34 Stabilising wall for parallel spanning members



Figure 7.36 Typical pressed plates



Figure 7.37 Typical framing anchors



Figure 7.38 Typical floor plan

7.8 Design Examples: Straps and Ties for a Three-storey Masonry Building

A typical three-storey building is to be built using loadbearing brick and block walls, precast concrete floor units and gang nail roof trusses.

The following calculations are for a number of typical elements and illustrate the procedures adopted and demonstrate the use of different strap details. For this reason, the calculations are not necessarily complete in themselves, being designed to be illustrative by nature. The designs are also based on working load design limits.

Roof Construction

Roof: Tiles on battens and felt on gang nail trusses at 600 mm centres.
Ceiling: 12 mm plasterboard. Fibre glass between trusses.

Floor Construction

Floor: Precast concrete floor units with 65 mm finishing screed.
Ceiling: 12 mm plasterboard on battens.

Loadings (BS 6399: Part 1) Residential Buildings

Roof	*Dead loads*
Tiles	$= 0.45\ \text{kN/m}^2$
Felt and battens	$= 0.10\ \text{kN/m}^2$
Trusses	$= 0.15\ \text{kN/m}^2$
Plasterboard	$= \underline{0.20}\ \text{kN/m}^2$
	$\underline{0.90}\ \text{kN/m}^2$
	Imposed load
	$0.75\ \text{kN/m}^2$

Floors	*Dead loads*
Screed and finishes	$= 1.60\ \text{kN/m}^2$
Precast units	$= 2.20\ \text{kN/m}^2$
Plasterboard and battens	$= 0.25\ \text{kN/m}^2$
Services	$= \underline{0.10}\ \text{kN/m}^2$
	$\underline{4.15}\ \text{kN/m}^2$
	Imposed load
	$1.50\ \text{kN/m}^2$



Figure 7.39 Typical cross-section

Wind loading (BS 6399: Part 2: 1997) (referred to as the wind code in these calculations):

Table 1, building location – Wirral – Merseyside

Basic wind speed, say $V = 23\ \text{m/s}$

Site wind speed, $V_s = V_b \times S_a \times S_d \times S_s \times S_p$

Clause 2.2.2.2.2, $S_a = 1.0 + 0.001\Delta_s$

(where Δ_s is the site altitude above mean sea level – take this as 20 m)

$S_a = 1.02$

Clause 2.2.2.2.3, direction factor $S_d = 1$

(building orientation unknown)

Clause 2.2.2.2.4, seasonal factor $S_s = 1$

Clause 2.2.2.2.5, probability factor $S_p = 1$

Therefore $V_s = 23 \times 1.02 \times 1 \times 1 \times 1 = 23.46\ \text{m/s}$

Effective wind speed, $V_e = V_s \times S_b$

(where S_b is a factor based on building height and closeness to sea – Table 4 of wind code. In this example assume for speed that effective height H_e for use in Table 4 is 10.8 m and that the building is in the country and 2 km from the sea.)

From Table 4, $S_b = 1.791$

Therefore $V_e = 23.46 \times 1.791 = 42.02\ \text{m/s}$

Dynamic pressure, $q_s = 0.613 \times 42.02^2 \times 10^{-3}\ \text{kN/m}^2$

$= 1.082\ \text{kN/m}^2$

The wind forces on a building are divided into two categories:

(a) The forces from the wind pressure acting normal to the surfaces of the building.
(b) The forces parallel to the surface under consideration, i.e. drag forces which will be ignored in order to simplify the calculations. (Must be checked in practice.)

Wind pressure on walls is given by:

$$p_e = q_s \times C_{pe} \times C_a \quad \text{(external pressure) and}$$
$$p_i = q_s \times C_{pi} \times C_a \quad \text{(internal pressure)}$$

where C_{pe} is determined from Table 5 of the wind code, C_a is determined from Figure 4 of the wind code, and C_{pi} is determined from Table 16 and section 2.6.

From Table 4,

$$\frac{D}{h} = \frac{12.5}{10.8} = 1.16$$ this is close to 1, therefore say $C_{pe} = +0.8$

$C_{pe} = +0.6$ for wind blowing east to west on Figure 7.38.

C_{pe} leeward suction coefficient = −0.3 (wind direction north to south) and −0.1 (wind direction east to west).

Use worst case coefficients i.e. +0.8 and −0.3 for all walls.

There are higher coefficients at zones close to corners; these will be discussed later but not figure in the rest of the calculations.

The value of C_{pi} depends on whether there is a dominant opening likely in a storm. In a building of this nature there is a negligible probability of a dominant opening occurring during a storm. Therefore, $C_{pi} = +0.2$ and −0.3.

Need to determine C_a in order to calculate final pressures.

C_a depends on minimum diagonal dimension of any side of the building. Worst case is the gable end where the minimum diagonal dimension is approximately $\sqrt{(12.5^2 + 7.8^2)} = 15$ m, ignoring gable. Therefore C_a = 0.935 from Figure 4 using line A.

Therefore external pressure, p_e = 1.082 × 0.8 × 0.935 = 0.81 kN/m^2

C_a for internal pressure is determined from Figure 4 also but the diagonal is determined as described in section 2.6 of the wind code. For this example take

$$a = 10 \times \sqrt[3]{(\text{internal volume of storey})}$$
$$= 10 \times \sqrt[3]{(200 \times 2.6)}$$
(200 m^2 is approximate area of each floor and each storey is 2.6 m high)
$$= 80.4$$

Therefore C_a for internal pressure = 0.828 (Figure 4 line A and diagonal = 80 m)

Therefore internal pressure, p_i = 1.082 × (–0.3) × 0.828 = −0.27 kN/m^2

Pressure on walls:

Applied pressure, $p = p_e - p_i = 0.81 - (-0.27) = 1.08$ kN/m^2

Now consider the wind pressure on the roof. The roof angle is 22½°.

Looking at Table 10 of the wind code there are many local uplift effects around the edges, which will be ignored at present, but discussed later.



Figure 7.40 Wind pressure on roof

The worst general case from Table 10 will be for a wind direction of 90° where uplift is −0.6 and −0.25. There are many permutations of wind direction and uplift that can be considered, but often in the simpler structures it is quicker and easier to consider the worst case only, which is often easily sufficient as will be shown in the following calculations.

Wind on gables, maximum C_{pe} = −0.6 worst case, as mentioned above.

C_{pi} for both cases, as before, = +0.2 and −0.3.

When the wind is normal to the main elevations and C_{pe} values are such that there is a net horizontal force applied to the roof, the value of this force is the difference between the C_{pc} values multiplied by the dynamic wind pressure and this value resolved into the horizontal direction.

$$\text{Net horizontal force} = (0.25 - 0.45) \times 0.81 \times \sin 22\tfrac{1}{2}°$$
$$= 0.062 \text{ kN/m}^2$$

This value is sufficiently small for it to be assumed, without further calculations, that the normal truss fixings will dissipate the load into the lateral walls.

It will therefore be assumed that the pressure applied to the roof is uniform over the roof and has a maximum value of

$$p_e - p_i = (-1.082 \times 0.6 \times 0.935) - (1.082 \times 0.2 \times 0.828)$$
$$= -0.79 \text{ kN/m}^2$$

Resolving this pressure into the vertical direction, then

$$\text{Pressure} = -0.79 \times \cos 22\tfrac{1}{2}° = -0.73 \text{ kN/m}^2$$

Design for elements to resist wind loading:

Consider area A shown shaded on Figure 7.38, forces applied to walls and roof (worst case):

Pressure on gable	$P_1 = +1.08$ kN/m^2
Pressure on rear elevation	$P_2 = +1.08$ kN/m^2
Pressure on roof	$P_3 = -0.73$ kN/m^2

These wind forces applied to the various parts of the building must be transmitted through the walls down to ground level.

For wind pressure on the gable walls, the corridor, front and rear external walls acting as shear walls will best transfer this loading to ground level. For wind on the front and rear elevations, the gable wall will transfer the forces down to the ground level together with walls internal to Flat A which are parallel to the gable wall.

It is therefore necessary to check that these walls are capable of taking this loading to ground floor level.



Figure 7.41 Enlarged plan of area 'A'

Consider the Gable Wall

Since the gable wall has no support from internal walls, it must be designed to span vertically between floors. The floors must, therefore, be capable of transferring this load to the corridor and external walls.

The horizontal force at floor level due to wind load is:

$$F = 1.08 \times 2.6 = 2.81 \text{ kN/m}^2$$

Calculate the axial load on the inner leaf, assuming density of blockwork = 18 kN/m^3. The worst condition will be at first floor level, maximum load in the wall is then

$$3 \times 2.6 \times 18 \times 0.1 = 14.04 \text{ kN/m}^2$$

From BS 5628: Part 1: 1978: section 4, clause 28.2.1, the lateral restraint must resist the horizontal forces plus 2½° of the axial load.



Figure 7.42 Gable wall to floor connection detail

$$\text{Forces to be resisted} = 2.81 + \left(14.0 \times \frac{25}{1000}\right) = 3.16 \text{ kN/m}^2$$

From BS 5628, clause 25:

$$\text{Permissible shear} = \frac{0.35 + 0}{3.5}$$

$$= 0.10 \text{ N/mm}^2 \quad \left(\text{from} : \frac{f_v + 0.6 g_A}{\gamma_m}\right)$$

$$\text{Actual shear stress} = \frac{3.16 \times 10^3}{100 \times 10^3} = 0.032 \text{ N/mm}^2$$

Therefore detail satisfactory.

A precast concrete floor with screed will be adequate to transfer these forces to the corridor and external walls by diaphragm or plate action.

At eaves and at roof level, the forces must also be transferred. This must be done by the roof acting as a plate and in order to do this it may need to be braced.

The masonry will tend to act as a propped cantilever and thus:

$$F_1 = \frac{3}{8} h \times \text{wind pressure}$$

$$F_2 = \frac{5}{8} h \times \text{wind pressure} + \text{pressure from wall below}$$

The maximum height, H, and thus maximum values of F_1 and F_2 occur at the ridge. These are:



Figure 7.43 Timber floor support to laterally loaded masonry wall



Figure 7.44 Detail of timber strap connection to cavity wall



Figure 7.45 Plan at rafter level

$$F_1 = \frac{3}{8} \times 2.6 \times (+)\,1.08 = +1.053\ \text{kN/m}^2$$

$$F_2 = \left(\frac{5}{8} \times \frac{1}{2}\right) 2.6 \times (+)\,1.08 = 3.16\ \text{kN/m}^2$$

The positive (inward) forces may be transferred into the roof by introducing a tight pack between the wall and the truss. However the negative (outward) forces not calculated here but demonstrated earlier, require additional measures.

Therefore, in accordance with Appendix C of BS 5628, introduce metal straps of minimum cross-sectional area of 30×5 mm at 1.200 m centres at both roof and eaves level.

The strap should be designed as follows:

(a) To resist direct tensile force from the wind plus $2^1/_2\%$ of the axial load.
(b) To resist bending at the return down the cavity face.
(c) To avoid any local crushing of the masonry.
(d) With suitable fixings to connect the strap to the trusses.

Having transferred the wind loading into the roof structure, it is now necessary to design the roof and any bracing necessary to transmit this loading to the resisting walls.

Introducing bracing as shown, the bracing should be fixed to the underside of the rafters.

Both the bracing and its fixings should be designed to resist the compressive and tensile forces from pressure and suction on the gable wall. Similarly, bracing should be introduced at eaves level to transmit the forces to the lateral walls.

Consider the External Wall to the Rear Elevation

The external wall, see Figure 7.46, has a series of intersecting walls at a maximum of 2.8 m centres, built directly off the precast units. It is not advisable, for reasons of different deflections, to bond these walls into the external walls. Metal anchors or wall ties may be introduced in the bed joints to afford these non-loadbearing intersection walls some degree of lateral support. These ties also offer the external cavity wall lateral support. To accommodate differential deflection, butterfly ties or similar should be used in every bed joint of the blockwork. The external walls can then be made to span horizontally between the internal walls. The internal walls are not continuous to ground level, and this necessitates the forces being transferred at each floor into the main dividing walls, which will then transfer the forces to ground level.

Consider a 1 m strip of wall. The maximum force on the internal wall is:

$$(2.8 + 1.8)/2 \times 1.08 = 2.48\ \text{kN/m height}$$

The internal wall must be designed to resist:

(a) overturning in the plane of the wall,
(b) horizontal shear failure on the bed joints.



Figure 7.46 Elevation on internal wall



Figure 7.47 Uplift loading on roof

Having transferred the force into the floor then, as for the gables, the floor must be designed to transfer this loading into the resisting walls.

Consider Wind Forces on the Roof

Roof loading

Dead weight = 0.9 kN/m²

Imposed load = 0.75 kN/m²

Wind loading = −0.73 kN/m² (uplift)

The dead weight of the roof must be sufficiently heavy to provide a factor of safety of 1.4 over the uplift from the wind. If this factor is not achieved the roof must be strapped down to prevent the possibility of it lifting off. Thus the factor of safety = 0.9/0.73 = 1.23 which is inadequate. Therefore uplift to be designed for is

$$\frac{0.9}{1.4} - 0.73 = -0.087 \text{ kN/m}^2$$

$$\text{Net upward force, } R_A = \frac{0.087 \times 6.25}{5.5}\left(\frac{6.25}{2} - 0.75\right)$$

$$= 0.08 \text{ kN/m}$$

At the corridor wall, $R_A = 0.23$ kN/m

The roof trusses bear onto a wall plate which then sits on the wall. The fixing of the trusses to the wall plate should be designed to resist the uplift force.

The force on each truss = 0.23 × 0.6 = 0.138 kN (trusses at 600 mm c/c). Thus if the trusses are skew nailed to the wall plate and using the withdrawal value given in BS 5268, Part 2, Table 23, for 4 mm diameter smooth round wire nails in C16 timber:

Resistance to withdrawal using two nails = 2.26 N/mm penetration

$$\text{Penetration length required} = \frac{0.138 \times 10^3}{2 \times 2.26} = 30.5 \text{ mm}$$

To ensure this penetration is achieved use 75 mm long nails. Alternatively, use proprietary fixings which can be justified.



Figure 7.48 Elevation on straps



Figure 7.49 Fixing of holding down straps to wall



Figure 7.50 Area of wall resisting uplift from strap

It is necessary to tie down the wall plate to the blockwork to resist the net upward forces. The centres of the straps must be limited to the maximum distance the wall plate can span to transfer the uplift from each truss to the strap positions.

The strap should be designed to resist the full tensile force due to uplift and the fixings likewise designed to transfer the force into the blockwork. For this purpose the strap can be assumed to be connected to triangular areas of blockwork (as shown in Figure 7.49) enclosed by a 45° line (see Figure 7.50). Note that where straps are close together (or very long) the area from two adjoining straps may overlap. Obviously the same area of blockwork cannot be used to resist the uplift on both straps.

8 Stability, Accidental Damage and Progressive Collapse

During recent years, there has been an increasing number of collapses of different types of structures built in a variety of structural materials. Apart from the ever-present causes of mistakes in design, erection and construction, the situation has been aggravated by changes in:

(a) the methods of design and construction,
(b) the increased use of specialist sub-contractors,
(c) the lack of awareness, by some designers, that sound structural elements can be inadequately connected and thus form unstable structures,
(d) the increase in the hazard of accidental forces.

(a) Methods of Design and Construction

The continuing decrease in the factors of safety (with the accompanying increase in stresses), together with the continuing pressure to cut costs by reducing the amount of material and labour in construction, have led to the almost total disappearance of traditional massive structural forms. Buildings are far less robust than they used to be, and are now relatively flimsy. The introduction of new and comparatively untried materials, which are not standing up to the test of time, has not helped the situation. Structural design is becoming more and more complex and sophisticated, increasing the possibility of errors being made by young engineers whose education is becoming more theoretical and less practical.

(b) Increased Use of Specialist Sub-contractors

It is not uncommon, for example, to find that a piling contractor has designed and formed the foundations for steel columns, designed and erected by a steel fabricator, used to support a prestressed concrete deck designed and erected by another specialist, on which has been erected a glued laminated timber frame designed by yet another specialist. Each element of this hybrid structure is normally perfectly structurally adequate in itself, but, since there has been no overall engineering supervision and responsibility, the resulting complete structure may be structurally unsound.

(c) Inadequate Connection of Structural Elements

It is not uncommon for designers to consider a wall as being restrained top and bottom, and then fail to check that it is in fact so restrained. Designers sometimes fail to appreciate that returns on the ends of walls, or other restraint or stiffening, may be necessary. A number of single-storey factories, and similar structures, have the main loadbearing wall inadequately restrained by the roof trusses, so that the effective height is greater than the designer has allowed for (see Figure 8.1). Further increasing the risk, the non-axial loaded gable wall, subject to wind loading, is not only unrestrained at roof level but movement joints are positioned between it and the side, or return, walls. The gable wall has thus no returns on its ends and is unstable on its horizontal axis and, lacking restraint from the roof, it is not robust on its vertical axis (see Figure 8.2). It is hardly surprising that collapses of gable walls in factories, etc., are not uncommon. Indeed, it is surprising that more of them do not fail.

Similar faults occur in multi-storey structures, where floors and roofs are not adequately tied or strapped to the walls, and where walls lack edge restraint.

In the authors' opinion, this particular aspect of design and construction is of very great importance and, for that reason, the whole of Chapter 7 was devoted to the subject.

(d) Risk of Accidental Damage

The decrease in robustness, together with an increase in the possibility of blast and impact forces from chemical plants, gas explosions, traffic accidents, etc., and changes in the use of structures leading to the chance of overloading, have combined to make all structures – in all materials – more susceptible to accidental damage, less stable, and more prone to the risk of progressive collapse (also called disproportionate collapse).

Having outlined some of the major causes of failures, it has to be admitted that, statistically, the risks are not very great. For example, from surveys by the Construction Industry Research and Information Association (CIRIA), and others, it has been estimated that the risk of a fatality due to a structural accident is 1 : 3 000 000 – as against 1 : 8000 from a car accident. Or again, the financial losses due to fires are about 200 times more than the losses due to structural accidents. However, this does not give the designer the right to take risks – low though they may be. People want to be as 'safe as houses', and the emotional, social and political impact and implications of a structural accident far outweigh a rational acceptance of the risk.

8.1 Progressive Collapse

'Progressive collapse' is the term used to describe the behaviour of a structure when local failure of a structural member (beam, column, slab, wall, etc.) occurs due to an accident of limited magnitude, destroying or removing the member and causing adjoining structural members to collapse. A chain reaction – 'house of cards' or 'domino'



Figure 8.1(a) Error in effective height assumption



Figure 8.1(b) Effective height where roof bracing provided

effect – can then spread throughout the whole or the major part of the structure, causing it to become unstable and collapse. Thus the final major damage is out of all proportion to the initial and minor cause.

After the disaster at the Ronan Point concrete system-built high-rise block of flats in May 1968, when the removal of only one wall panel caused widespread damage to the structure and the deaths of four people, it became mandatory for engineers to check certain structures to ensure that the removal of any structural element would not cause a spread of collapse. The factor of safety required against progressive collapse is low, being only 1.05. It should be appreciated that, although the structure might not collapse, it



Figure 8.2 Stable and unstable wall examples



Figure 8.3 Wall behaviour following removal of part

may be unserviceable due to excessive cracking and deflection, and be left with an unacceptably low load-carrying capacity. It may well need extensive repair or even rebuilding. The provision in the design is, therefore, limited to the immediate safety of the occupants.

To keep this problem in proportion, experience has shown that masonry structures have an innate ability to withstand shock and are resistant to progressive collapse. Masonry structures have the capacity to arch, span and cantilever over openings caused by the removal of a structural wall or other support (see Figure 8.3).

Many masonry structures were seriously damaged by bombing and fire during the Second World War, and did not collapse. There have been numerous incidents since, when masonry structures have suffered incompetent demolition during alterations, impact from heavy lorries, blast from explosions, removal of support floors and roofs due to fire damage, etc., without collapsing.

8.2 Stability

All structural codes for all materials will pay attention to the problem of stability and structural masonry is no exception.

To limit the effects of accidental damage and to preserve structural integrity, BS 5628, clause 20.1, provides general recommendations which may be interpreted as follows:

(1) The designer responsible for the overall stability of the structure should ensure that the design, details, fixings, etc., of elements or parts of the structure are compatible, whether or not the design and details were made by him. This means, for example, not only checking that a specialist roof design can carry its own load, but also ensuring that it is properly tied to the walls and can transfer, say, wind forces from them.

(2) The designer should consider the plan layout of the structure, returns at the ends of walls, interaction



Figure 8.4 Plan layouts of structural forms of varying degrees of robustness

between intersecting walls, slabs, trusses, etc., to ensure a stable and robust design.

The Code does not define or quantify 'robustness', but most designers would probably assume it to mean a structure's ability not to suffer a major collapse due to minor accidental damage. To obtain a consensus of opinion on an acceptable degree or quantity of robustness has proved difficult. Probably because any one designer's opinion depends not only on his experience, but also on his confidence and daring, or his caution and apprehension. Figure 8.4 shows plan layouts of masonry structures with differing degrees of robustness.

(3) The designer should check that lateral forces acting on the whole structure are resisted by the walls in the plans parallel to those forces, or are transferred to them by plate action of the floors, roofs, etc., or that the forces are resisted by bracing or other means.

The interaction between the walls, floors and roof affects the robustness of the structure. The lateral forces on the walls can be transferred to shear walls (walls parallel to the line of action of the lateral forces) by the floors or roof acting as horizontal diaphragms or wind girders – this being known as 'plate action'. The plate action of a roof was shown in Figure 8.1(b). Floors, however, vary in their ability to provide plate action. A two-way spanning insitu reinforced concrete slab bedded into the external wall and continuous over the internal



Figure 8.5 More robust insitu concrete floor

walls (see Figure 8.5), is obviously stiffer than precast concrete planks simply supported on the walls and not provided with lateral ties to the edge walls or continuity over the internal walls (see Figure 8.6).



Figure 8.6 Less robust precast concrete unit floor



Figure 8.7 Degree of robustness of various floor systems

Figure 8.7 shows flooring alternatives for a multi-storey masonry structure and indicates the variation in the degree of robustness imparted to the structure.

(4) Structures should be designed to resist a uniformly distributed horizontal load of 1.5% of the total characteristic dead load ($0.015G_k$) above any level for the load conditions given in clauses 22b (dead and wind load) and 22c (dead, imposed and wind load).

(5) Adequate strapping or tying (see Chapter 7) should be provided, where appropriate at floors and roofs.

(6) Earth retaining and foundation structures. The overall dimensions and stability of earth retaining and foundation structures (e.g. the area of pad footings, etc.) should be determined by appropriate geotechnical procedures, which are not considered in this Code. However, in order to establish section sizes and strengths, which will give adequate safety and serviceability without undue calculation, it is appropriate in normal design situations to apply values of γ_f comparable to those applied to other forms of loading.

The factor γ_f should be applied to all earth and water loads unless they derive directly from loads which have already been factored in alternative ways to those described in clause 21 and clause 22 of BS 5628, Part 1, in which case the loads should be derived to achieve equilibrium with other design loads. When applying the factor γ_f, no distinction is made between adverse and beneficial loads.

8.3 Accidental Forces (BS 5628, clause 20)

No structure can be expected to resist excessive loads due to an extreme cause, such as a large plane crashing into it, but it should be able to withstand the impact of a lorry, or the possible mis-use of temporary and slight overloading, without collapsing completely. Nor should it suffer damage disproportionate to such a cause. Only the column, wall or slab, etc., subject to the excessive load should suffer primary damage, and *not* the adjoining structural elements.

When, because of the use or position of a structure, there is a potential hazard such as a fuel dump or a chemical plant (e.g. the Flixborough disaster in the 1970s where an explosion caused severe damage to buildings in the vicinity), the design should ensure that, in the event of an accident, there is an acceptable probability that despite serious damage the structure will remain standing.

A fairly typical case is that of a bus garage where the columns supporting the lintels over the large door openings are liable to vehicle impact. The danger can be reduced by protecting the columns with bollards and designing the lintels as a continuous beam. In the event of a column being removed, the beam should be able to span over the greater length with a factor of safety of 1.05 (see Figure 8.8).



Figure 8.8 Effect of column removal on the behaviour of the structure

8.4 During Construction

Although it is the contractor's normal contractual responsibility to maintain the safety of the works during construction, i.e. be responsible for the design and erection of all temporary works, to ensure adequate temporary bracing, shores, etc., the designer has a statutory duty of care in accordance with the Construction Design and Management (CDM) Regulations. The designer must consider whether special precautions or special temporary propping are needed to ensure the stability of the structure. If the designer considers that special precautions, etc., are necessary, he should inform the contractor, in writing, that such measures are advisable. Since, unfortunately, some contractors are eager to be absolved of their contractual responsibility to maintain the safety of the works, care must be taken by the designer in specifying the special precautions. If such care is not taken, the designer could find himself responsible for the design of all temporary works.

8.5 Extent of Damage

When a column or wall collapses due to accidental damage, known as 'primary' damage, the beams or slabs supported by the column or wall will suffer 'consequential' or 'secondary' damage. The structure must have adequate residual stability not to collapse completely, and the Code further advises that the designer should satisfy himself that '. . . collapse of any significant portion of the structure is unlikely to occur'. What is 'significant' is not defined, and is left to the engineer's judgement. The collapse of a carpet warehouse, which damages a few carpets, can be considered morally and emotionally as not so serious as the collapse of a school assembly hall killing a hundred children, but failure of either structure must be avoided.

Specific guidance is given in The Building Regulations, particularly Part A (2004 Edition). These rules are the minimum that must be followed, but do not restrict the engineer's judgement on an individual case basis. Where an engineer feels that there is a need for a more robust design based on professional judgement then that design should subsume the rules given in The Building Regulations. The guidance given in The Building Regulations, Part A, 2004 relates to different classes of buildings which are categorised as below. Regulation A3 requires that the building shall be constructed so that in the event of an accident, the building will not suffer collapse to an extent disproportionate to the cause.

Class 1

Houses not exceeding four storeys; agricultural buildings and buildings into which people rarely enter, provided that no part of the building is closer to any other building or area where people have access, than a distance equal to 1.5 times the height of the building being designed.

Class 2A

Five-storey single-occupancy houses; hotels of four storeys or less; flats, apartments and other residential buildings of four storeys or less; offices of four storeys or less; industrial buildings of three storeys or less; retail premises not exceeding three storeys or less than 2000 m^2 floor area in each storey; single-storey educational buildings; all buildings not exceeding two storeys to which members of the public are permitted and which contain floor areas not exceeding 2000 m^2 at each storey.

Class 2B

Hotels, flats, apartments and other residential buildings exceeding four storeys but not exceeding 15 storeys; educational buildings exceeding one storey but not exceeding 15 storeys; retailing premises exceeding three storeys but not exceeding 15 storeys; hospitals not exceeding three storeys; offices exceeding four storeys but not exceeding 15 storeys; car parking not exceeding six storeys; all buildings to which members of the public are admitted which contain floor areas exceeding 2000 m^2 but less than 5000 m^2 at each storey.

Class 3

All buildings given above as Class 2A and 2B that exceed the limits on area and/or number of storeys: grandstands accommodating more than 5000 spectators; buildings containing hazardous substances and or processes.

The Building Regulations specify that for each building class the following provision must be made.

For Class 1 buildings: If the building is designed and constructed in accordance with Part A3 of The Building Regulations or other guidance given in A1 and A2 of the same regulations for normal use, then no additional measures are likely to be necessary. However the professional engineer must decide if there is a risk of disproportionate collapse for each and every structure for which he/she is responsible, irrespective of compliance with The Building Regulations. The example of the bus garage given in section 8.3 above might come under Class 1 buildings and therefore have no specific requirements for disproportionate collapse consideration in accordance with The Building Regulations, but this does not absolve the engineer from considering if the structure should be designed considering disproportionate collapse possibility.

For Class 2A buildings: For this class of buildings, provide effective horizontal ties, or effective anchorage of suspended floors to walls, as described in the Code and described in this chapter.

For Class 2B buildings: For this class of buildings, provide effective horizontal ties as for Class 2A buildings plus either of the following:

- effective vertical ties as defined in BS 5628, Part 1 in all supporting columns and walls, or
- check that the removal of any supporting column, or any beam supporting a column, or any nominal length of supporting wall (only one element at a time to be removed in each storey) does not render the building unstable and that the extent of any collapse, resulting from the removal, does not exceed 15% of the floor area

of that storey or 70 m^2, whichever is smaller (see example in Figure 8.9(a)). The collapse must not extend further than the immediate adjacent storeys. Where the removal of the elements does exceed the collapse extents given above then that particular element must be designed as a 'key element' in accordance with The Building Regulations, Part A3.

For Class 3 buildings: For this class of buildings 'a systematic risk assessment of the building should be undertaken taking into account all the normal hazards that may reasonably be forseen, together with any abnormal hazards'.

In the seven-storey crosswall apartment structure shown in Figures 8.9(a) and 8.9(b), an accident has taken place on the third floor. The external wall and two crosswalls have been blown out, and the third and fourth floors damaged. The Building Regulations state that the designer must cater for the removal of any one element at a time. This is reasonable in that when one wall is destroyed, it is likely to reduce the pressure on the other walls. The second floor may be subject to debris loading. This is the limit of allowable damage and the remaining structure must have adequate residual stability, as stated in BS 5628.



Figure 8.9(a) Example of extent of damage to floor permissible under Part A of Building Regulations



Figure 8.9(b) Example of vertical damage to permissible under Part A of Building Regulations

8.6 Design for Accidental Damage

8.6.1 Partial Safety Factors

The partial safety factor for design load, γ_f, is reduced as follows:

Design dead load $= 0.95G_k$ or $1.05G_k$

Design imposed load $= 0.35Q_k$ (except that, in the case of buildings used predominantly for storage, or where the imposed load is of a permanent nature, $1.05Q_k$ should be used)

Design wind load $= 0.35W_k$

The partial safety factors for material strength, γ_m, may be halved when considering the effects of accidental damage. For a wall or column with a high axial load subjected to a lateral design load, and treated as a 'protected' member (see later for definition), γ_m may be further reduced to 1.05.

Example 1

For simplicity, let G_k and Q_k be unity for the two-span continuous slab shown in Figure 8.10. Determine the end reaction and the characteristic strength required for the end walls ($\gamma_m = 2.5$).

If the central support is removed by accident, determine the characteristic strength required for the end walls, $\gamma_m = 1.25$ (see Figure 8.11). Note that slenderness considerations of the walls have been omitted to simplify demonstration of the principle.

This very simplified example serves to emphasise that when checking a designed structure for accidental damage,



Figure 8.10 Beam details for Example 1



Figure 8.11 Beam details for Example 1

Table 8.1 Detailed accidental damage recommendations

Class 1 (See section 8.5, this book)	Plan form and construction to provide robustness, interaction of components and containment of spread of damage (see clause 20)				
		Additional detailed recommendations			
		Mandatory	Option (1)	or	Option (2)
Class 2A (See section 8.5, this book)	Plan form and construction to provide robustness, interaction of components and containment of spread of damage (see clause 20)	*Horizontal ties* Peripheral, internal and column or wall in accordance with clause 37.3 and Table 13	None		None
Class 2B (See section 8.5, this book)	Plan form and construction to provide robustness, interaction of components and containment of spread of damage (see clause 20)	*Horizontal ties* Peripheral, internal and column or wall in accordance with clause 37.3 and Table 13	*Vertical elements* Vertical elements, unless protected, proved removable, one at a time, without causing collapse or Option (2)		*Vertical ties* In accordance with clause 37.4 and Table 14
Class 3 (See section 8.5, this book)	Form decided by engineer following a systematic risk assessment of all hazards	Design and details to satisfy the outcome of the risk assessment	None		None

the loads are decreased and the allowable stress increased. It should be noted that although the end walls in the example may stand up, the floor slab may have such an excessive deflection as to be unserviceable.

8.6.2 Methods (Options) of Checking

An experienced designer can check by eye to establish if a designed structure is robust and capable of withstanding accidental damage. But, since robustness – like beauty – is a subjective assessment (see also section 8.2), there may be differences of opinion between the designer and the checking authority.

A multi-storey cellular structure (see Figure 14.37), having short spans, two-way continuous rc floor slabs with good tying to the outer leaf of the external cavity wall, numerous sturdy partitions bonded into the loadbearing walls, etc., would be unlikely to need checking for accidental damage. Similarly, a deep diaphragm wall of moderate height, capped by a continuous rc beam with a rigidly braced and stiff-sheeted roof firmly fixed to it, is hardly likely to collapse completely if a heavy lorry crashes into it. Where a detailed check is necessary, the engineer is referred to Table 12 of the Code (see Table 8.1) provides the designer with a number of options. (Please note that Table 12 of BS 5628, Part 1, 2002 currently conflicts with The Building Regulations, Part A and should be ignored along with any reference to category 1 and 2 type structures in section 5 of BS 5628, Part 1.)

Oddly enough, a piloti base does not count as a storey – thus the building shown in Figure 8.12 is a four-storey building. Basements on the other hand do count as a storey.



Figure 8.12 Example of piloti base which does not count as a storey

The Building Regulations Part A is specific in the requirements for a Class 2A structure, i.e. horizontal ties must be provided (see Table 8.3). However for a Class 2B structure, the engineer does have two options with respect to vertical elements. These options are to provide horizontal ties as Class 2A structures plus either:

Option 1: Check the extent of damage caused by the removal of individual vertical loadbearing elements as described in Part A of The Building Regulations and design the element as a protected member if this is excessive, or

Option 2: Provide vertical ties in the structure in accordance with the Code (see later for details).

8.6.3 Loadbearing Elements

These are defined in Table 11 and clause 37.5 of the Code (see Table 8.2).

It will be noted from the table that the length of a wall, which forms a vertical loadbearing element, depends upon

Table 8.2 Loadbearing elements (BS 5628, Table 11)

Type of loadbearing element	Extent
Beam	Clear span between supports or between a support and the extremity of a member
Column	Clear height between horizontal lateral supports
Slab or other floor and roof construction	Clear span between supports and/or temporary supports[a] or between a support and the extremity of a member
Wall incorporating one or more lateral supports[b]	Length between lateral supports or length between a lateral support and the end of the wall
Wall without lateral supports	Length not exceeding 2.25*h* anywhere along the wall (for internal walls) Full length (for external walls)

[a] Temporary supports to slabs can be provided by substantial or other adequate partitions capable of carrying the required load
[b] Lateral supports to walls can be provided by intersecting or return walls, piers, stiffened sections of wall, substantial non-loadbearing partitions in accordance with (a), (b) and (c) of clause 37.5, or purpose-designed structural elements



Figure 8.13 Example of area of wall considered to be removed for progressive collapse calculations

the position of the wall and the presence of lateral supports. For example, the complete length of an external wall, without lateral supports, must be removed for an accidental damage check. On the other hand, for an internal wall, only a length 2.25 × clear storey height need be considered to be removed. Thus in the case of an internal wall in a block of flats with a clear height between lateral supports of 2.5 m, only a length 2.25 × 2.5 m = 5.625 m need be considered removed at any one time (see Figure 8.13).

The designer must check the worst condition for structural collapse, i.e. where to remove the 5.625 m length of the internal wall to create the most critical overall design condition.

For both internal and external walls, the provision of vertical bracing by lateral supports reduces the length of the wall to be examined for the effects of removal. What constitutes a 'lateral support' is defined in clause 37.5 of the Code as:

(a) an intersecting or return wall,
(b) a pier or stiffened section of the wall,
(c) a substantial partition.

Detailed descriptions of these are as follows:

(a) An intersecting or return wall tied to the wall for which it provides lateral support, with connections (bonding, wall ties, straps) capable of resisting a force of the lesser of 60 kN or $(20 + 4N_s)$ kN, where N_s is the number of storeys including the ground floor and the basement of the building, per metre height of the wall. The value 60 kN or $(20 + 4N_s)$ kN is the basic horizontal tie force F_t. The intersecting or return wall must have a length of $h/2$ without openings, be at right angles to the supporting wall, and have an average mass of not less than 340 kg/m^2 (see Figure 8.14).

(b) A pier or stiffened section of the wall, not more than 1 m in length, and capable of resisting a force the lesser of 90 kN or $(30 + 6N_s)$ kN, per metre height of the wall (see Figure 8.15).

(c) A substantial partition at right angles to the wall, having an average mass of not less than 150 kg/m^2, and



Figure 8.14 Intersecting wall requirements for calculation of length of wall removed for progressive collapse calculations



Figure 8.15 Column and pier requirements for calculation of length of wall removed for progressive collapse calculations

tied with connections capable of resisting 30 kN or $(10 + 2N_s)$ kN per metre height of the wall. The partition need not be in a straight line but should, in effect, divide the bay into two compartments (see Figure 8.16).

Since many buildings have return walls, intersecting walls and substantial partitions, it is not often necessary to add further lateral supports to a wall. On the few occasions when it is necessary to add lateral supports, it is generally preferable to add masonry piers – rather than to introduce steel or rc columns – so as to limit the number of trades, operations, etc., on the site.

The reason for tying the lateral supports to the wall is to prevent large areas tearing off, and to assist a yield line type failure (see Figure 8.17).

For a clear storey height of, say, 2.5 m and a distance of 3.5 m between lateral supports – a typical case in a block of flats – the load on the ties can be calculated approximately (see Figure 8.18).

The accidental load on the shaded area in Figure 8.18 is

$$= \left(2.5 \times 1 + \frac{2 \times 2.5 \times 2.5}{2} \times \frac{1}{2}\right) \times 34$$

$$= \left(2.5 + \frac{2.5^2}{2}\right) \times 34 \text{ kN/m}^2$$

The tying resistance/m height is

$$= \frac{\left(2.5 + \frac{2.5^2}{2}\right)}{2.5} \times 34$$

$$= (1 + 1.25) \times 34$$

$$= 76.5 \text{ kN}$$

This compares reasonably with the required force of 30 kN in type (c) support, 90 kN in type (b) and 60 kN in type (a). The reason for the comparatively low force of 30 kN in type (c) is that a substantial partition dividing a bay into two compartments assumes that it limits the accidental damage to one compartment only.

8.6.4 Protected Member

Some structural members are so vital to the stability of a structure that removal by damage would cause extensive collapse or damage to the whole structure. An extreme case is depicted in Figure 8.19, where it is obvious that the removal of the column or cantilever would result in the collapse of the structure.

Such members, and their connections, must be designed to resist the full accidental loading of 34 kN/m^2, applied from any direction to the member directly, together with the reaction from contiguous (connected) building components (i.e. sheeting, walling, etc.) also subjected to the same accidental loading. In practice, most building components would have a much lower ultimate lateral resistance and would fail way below a loading of 34 kN/m^2, and thus transmit relatively low reactions to the protected member.



Figure 8.16 Partition wall requirements for calculation of length of wall removed for progressive collapse calculations



Figure 8.17 Yield line type damage of wall where tied to intersecting walls



Figure 8.18 Example of calculation of area of yield line type damage



Figure 8.19 Example of single support for whole structure

The protected member must, as stated above and shown in Figure 8.20, be able to withstand an accidental loading in any direction.

The ability of masonry walls or piers to withstand an accidental force of 34 kN/m^2 applied vertically seldom creates problems. However, problems do arise when the force is applied laterally to a wall that does not have a sufficiently high axial load to provide the precompression necessary



Figure 8.20 Directions in which accidental damage force are applied

to counteract the flexural tensile stress and reduce it to an acceptable level. The acceptable level is that strength multiplied by half the partial factor of safety for material strength, γ_m.

Conversely, it can be considered that a wall which by virtue of its axial load can withstand the lateral accidental loading, with an acceptable partial safety factor, is of itself a protected member. In practice, it is quite common to find that there is sufficient precompression in loadbearing masonry to counteract the flexural tensile stress at about the third, or sometimes the fourth, storey down from the roof. It follows that it is not always necessary to check most walls on the lower storeys of buildings in Class 2B, particularly internal walls. However, to reiterate a point made earlier, the authors feel that designers should check all walls, etc., on their first projects until they have gained sufficient experience to dispense with checking by calculations and, using their engineering judgement, check by eye.

Option 1

Under this option (see Table 8.1), the removal analysis applies to vertical members only, and does not apply to floor and roof slabs – for which, horizontal tying is required.

The provision of lateral supports to walls, plus the provision of a robust plan form, will obviously reduce the amount and the spread of damage to the vertical loadbearing elements. To reduce the spread of horizontal damage, and the repercussion of secondary damage to the vertical elements, the floors must be able to span or cantilever over the damaged area.

The normal secondary, or distribution, reinforcement in continuous insitu rc slabs is usually sufficient to allow the floor to span or cantilever over a damaged, failed or removed, internal vertical support. With floors constructed of simply supported precast concrete units, extra reinforcement is usually necessary. Similarly, timber floors normally need tying round their periphery, and some two-dimensional tying internally. The basic horizontal tie force, F_t, to be used in determining the amount of tying required is the same as that for the vertical elements, mentioned above, namely F_t = 60 kN or $(20 + 4N_s)$ kN, whichever is the lesser of the two values, where N_s = number of storeys including the ground floor and any basements.

The Code requirements for peripheral (external), internal, and column and wall ties are provided in Table 8.3.

Table 8.3 Requirements for full peripheral, internal and column or wall ties (BS 5628, Table 13)

Type of tie	Unit of tie force	Size of design tie force	Location of tie force (arrowed)	Fixing requirements and notes
A *Peripheral*	kN	F_t	Around whole perimeter 	Ties should be: (a) placed within 1.2 m of edge of floor or roof in perimeter wall (b) anchored at re-entrant corners or changes of construction
B *Internal* (both ways)	kN/m width	F_t or $\frac{F_t(G_k + Q_k)}{7.5} \times \frac{L_a}{5}$ whichever is the greater F_t F_t or $\frac{F_t(G_k + Q_k)}{7.5} \times \frac{L_a}{5}$ whichever is the greater	*One-way spans* (i.e. in crosswall or spine construction) (i) in direction of span (ii) in direction perpendicular to span *Two-way spans* (in both directions) 	(a) Internal ties should be anchored to perimeter ties or continue as wall or column ties (b) Internal ties should be provided: (1) uniformly throughout slab width, or (2) concentrated in beams (6 m max. horizontal tie spacing), or (3) within walls 0.5 m max. above or below the slab at 6 m max. horizontal spacing (4) in addition to peripheral ties spaced evenly in perimeter zone (c) Calculation of tie forces should assume: (1) $(G_k + Q_k)$ as the sum of average characteristic dead and imposed loads in kN/m^2 (2) L_a as the lesser of: the greatest distance in metres in the direction of the tie, between the centres of columns or other vertical loadbearing members whether this distance is spanned by a single slab or by a system of beams and slabs, or 5 × clear storey height, *h*
C *External column*	kN	$2F_t$ or $(h/2.5)F_t$ whichever is the lesser where *h* is in metres		(a) Corner columns should be tied in both directions (b) Tie connection to masonry may be based on shear strength or friction (but not both) (c) Wall ties (where required) should be (1) spaced uniformly along the length of the wall, or (2) concentrated at centres not more than 5 m apart and not more than 2.5 m from the end of the wall (d) External column and wall ties may be provided partly or wholly by the same reinforcement as perimeter and internal ties
D *External wall*	kN/m length of loadbearing wall			

Note: Basic horizontal tie force = F_t = 60 kN or (20 + 4 N_s) kN, whichever is the lesser of the two values, where N_s is the number of storeys (including ground and basement)

At first sight, the table may appear formidable. However, on better acquaintance, it proves to be reasonably straightforward.

In clause 37.3, the Code states that horizontal ties should be provided at each floor level and at roof level. When the roof is of lightweight construction, no ties need be provided at that level. Such roofs are defined as 'roofs comprising timber or steel trusses, flat timber roofs, or roofs incorporating concrete or steel purlins with asbestos or wood-wool decking'. The Code also states that 'horizontal ties may be provided in whole or in part by structural members which may already be fully stressed in serving other purposes'. It cites the example, mentioned earlier, of reinforcement in insitu slabs, and also masonry in tension. If the masonry's tensile strength is used, it must not be perpendicular to the bed joints (see Figure 8.21).

According to the Code, 'ties should be positioned to resist most effectively accidental damage'. Assistance on this topic is provided in the final column of Table 13 in the Code.

Example 2

An eight-storey hall of residence with 102.5 mm brick crosswalls at 4 m centres, supporting continuous insitu rc floor slabs, has a lightweight roof. Determine the peripheral, internal and external ties required (see Figures 8.22(a) and (b)).



Figure 8.21 Preferred direction for tensile loading



Figure 8.22(a) Plan on Example 2



Figure 8.22(b) Plan on corner column of Example 2

Basic tie force = 60 kN or $(20 + 4 \times 8) = 52$ kN. Use 52 kN.

Ties are required at each floor slab, but not at the roof since it is of lightweight construction. (The roof may need vertical straps to act as ties to resist wind suction.)

(a) Peripheral Ties

$$F_t = 52 \text{ kN/m}$$

$$A_s = \frac{52 \times 10^3}{0.87 \times 460} = 130 \text{ mm}^2$$

Use one No. 16 mm HY bar/m (see Figure 8.23).



Figure 8.23(a) Plan on peripheral ties of Example 2



Figure 8.23(b) Section on peripheral ties of Example 2

In effect, peripheral ties act like a splint running around the outer face of the building, tying it together (see Figures 8.23(a) and (b)).

(b) Internal Horizontal Ties (in Direction of Span)

$$F_t = 52 \text{ kN} \quad \text{or} \quad \frac{F_t (G_k + Q_k)}{7.5} \times \frac{L_a}{5} \text{ kN/m}$$

where

$G_k + Q_k$ = sum of average characteristic dead and imposed loads in kN/m^2
= 7.5 kN/m^2 for domestic buildings
L_a = the lesser of the span (in direction of ties) or five times the clear storey height.

Let $h = 2.5$ m, then L_a = the lesser of 4 m or 5×2.5 m = 4 m

Therefore

$$\frac{F_t (G_k + Q_k)}{7.5} \times \frac{L_a}{5} = \frac{52 \times 7.5}{7.5} \times \frac{4}{5}$$

$$= 41.6 \text{ kN/m}$$

Since this is less than F_t = 52 kN, use 52 kN/m in design of ties, i.e. same as for peripheral ties. The continuity reinforcement would normally be adequate. If it is not, all that is necessary is to add extra reinforcement (see Figures 8.24(a) and (b)).

(c) Internal Transverse Ties (Ties Parallel to Crosswalls)

$$F_t = 52 \text{ kN/m}$$

check that distribution reinforcement is adequate. If not, add extra reinforcement (see Figures 8.24(a) and (b)).



Figure 8.24(a) Section on continuity ties of Example 2



Figure 8.24(b) Section on continuity ties of Example 2

(d) External Wall Ties

Tie force $= 2F_t$ or $\frac{h}{2.5}F_t$, whichever is the lesser

Since $h = 2.5$, $\frac{h}{2.5}F_t = 52$ kN/m

The only practical method of resisting this tie force is in shear between the slab and the masonry (see Figure 8.25).

$$\text{Shear contact area} = 2 \times 103 \times 1000 \text{ mm}^2$$

$$\text{Shear resistance} = \frac{f_v}{\gamma_{mv}} \times \text{shear area}$$

Taking the worst case of no increase due to axial loading,

$f_v = 0.35$ N/mm^2 for brickwork in 1 : 1 : 6 mortar
$\gamma_{mv} = 1.25$ for accidental damage



Figure 8.25 Shear contact area for tie force

therefore

$$\text{shear resistance} = \frac{0.35}{1.25} \times 2 \times 103 \times \frac{1000}{10^3}$$

$$= 58 \text{ kN/m}$$

Note that lower down the building, the friction against the tie force between the concrete slab and the wall could be used, assuming the coefficient of friction = 0.6.

(e) External Column Tie (see Figure 8.26)

Assume for planning reasons the gable and the main side wall are stopped short of the external corner, and the support is provided by a masonry column:

(i) the column should be tied in both directions;
(ii) the tie connection may be based on shear strength or friction, but not both.

$$\text{Contact area} = \frac{\text{shear force}}{\text{shear stress}} = \frac{73.5 \times 10^3}{2 \times 0.35/1.25} = 131\,000 \text{ mm}^2$$

Provide 360 × 360 mm bearing minimum (see Figure 8.27).

Determine F_t for the spine wall structure shown in Figure 8.28.

Assume $G_k + Q_k = 20$ kN/m^2, $h = 3$ metres, $N_s = 6$.



Figure 8.26 Resultant tie force for corner columns



Figure 8.27 Section on corner column for example in Figure 8.28



Figure 8.28 Plan on tie force example

F_t = lesser of 60 kN or [20 + (4 × 6)], i.e. 44 kN.

L_a = lesser of 8 m or 5 × 3 m, i.e. 8 m.

Therefore

$$\frac{F_t(G_k + Q_k)}{7.5} \times \frac{L_a}{5} = \frac{44 \times 20}{7.5} \times \frac{8}{5}$$

$$= 187.7 \text{ kN/m}$$

Use F_t = 187.7 kN/m.

This example shows that the internal tie force is affected by the span and the loading of the floor.

Option 2

Under this option (see Table 8.1), neither vertical nor horizontal elements may be removed, and both horizontal and vertical tying are required. If the structure is tied (as prescribed in the Code) in three directions, as shown diagrammatically in Figure 8.29, there should only be limited damage due to accidental forces, and the structure should have adequate residual stability.

The vertical tie reinforcement is either placed in insitu concrete pockets in a brick wall, or threaded through cellular blocks, and then grouted up (see Figure 8.30).

Both techniques are clumsy and time-consuming. This, together with the fact that the minimum thickness of a solid wall, or the loadbearing leaf of a cavity wall, must be at least 150 mm thick – thus restricting the use of half brick, 102.5 mm, walls – is likely to make this option unattractive to designers. Its main use is likely to be in buildings subject to high blast forces from chemical works and the like. When the option is used, the vertical ties form, in effect, rc columns which could perform an alternative load path carrying capacity. This increases the ability of the structure to arch, span and cantilever over damaged areas.

Clause 37.4 of the Code states that vertical tying is effective only when horizontal tying capable of resisting a horizontal force of F_t kN/m width is also present, and that the floor is of precast or insitu concrete or other heavy flooring units.

The same clause goes on to state: 'the wall should be contained between concrete surfaces or other similar construction, excluding timber, capable of providing resistance to lateral movement and rotation across the full width of the wall'. The ties should extend from the roof down to either the foundations or to the level where the wall, by virtue of compression due to dead load, may be considered to be protected. The ties should be continuous, but should be anchored separately and fully at each floor level (see Figure 8.31).

This method reduces the risk of the walls above and below the damaged wall being torn out of position due to it being blasted out by the accidental force. Table 14 in the Code gives the requirements for vertical ties (see Table 8.4).

The tie force formula is based on the ability of a wall to arch vertically (if restrained top and bottom) when subject to a lateral load:

$$\text{tie force} = \frac{34A}{8000}\left(\frac{h_a}{t}\right)^2 \text{ N}$$

Example 3

Determine the area of tying reinforcement in pockets at 5 m centres (note maximum spacing) in the 150 mm inner loadbearing leaf of a cavity wall (note minimum width). The clear height of the wall is 3 m.



Figure 8.29 Directions of ties required in a structure

Table 8.4 Requirements for vertical ties (BS 5628, Table 14)

Minimum thickness of a solid wall or one loadbearing leaf of a cavity wall	150 mm
Minimum characteristic compressive strength of masonry	5 N/mm^2
Maximum ratio h_a/t	20
Allowable mortar designations	(i), (ii), (iii)
Tie force	$\frac{34A}{8000}\left(\frac{h_a}{t}\right)^2$ N or 100 kN/m length of wall or per column, whichever is the greater
Positioning of ties	5 m centres, max. along the wall and 2.5 m, max. from an unrestrained end of any wall

Notes: A = horizontal cross-sectional area in mm^2 of the column or wall including piers, but excluding the non-loadbearing leaf, if any, of an external wall of cavity construction
h_a = clear height of a column or wall between restraining surfaces
t = the thickness of column or wall



Figure 8.30 Methods of providing vertical ties in masonry walls



Figure 8.31 Separate anchorage for vertical ties

$A = 150 \times 5 \times 1000 = 750\,000 \text{ mm}^2$

$t = 150 \text{ mm}$

$h_a = 3000 \text{ mm}$

$$\text{Vertical tie force} = \frac{34 \times 7.5 \times 10^5}{8 \times 10^3}\left(\frac{3 \times 10^3}{1.5 \times 10^2}\right)^2$$

$$= 128 \times 10^4 \text{ N}$$
$$= 1280 \text{ kN}$$

$$\text{Minimum tie force} = 100 \text{ kN/m} \times 5 \text{ m}$$
$$= 500 \text{ kN}$$

$$A_s = \frac{1280 \times 10^3}{400}$$

$$= 3200 \text{ mm}^2$$

Use four No. 32 mm HY bars per pocket.

8.6.5 General Notes

(1) The basic tie force $F_t = 60$ kN or $(20 + 4N_s)$ kN for buildings of various heights is given in the following table.

No. of storeys, N_s	4	5	6	7	8	9	10	10+
F_t (kN)	0	40	44	48	52	56	60	60

(2) Detailed design for accidental damage is a familiar concept to structural designers.
(3) It is possible that a designer's first attempt at checking and designing for accidental damage may be slow and laborious – as indeed, any other first design usually is. But experience shows that what, at first sight, appears complex is really comparatively simple.
(4) With experience, designers will tend to build-in robustness and check for accidental damage using Option (1). If the vertical and horizontal elements are not removable, one at a time, or protected, most designers would probably adjust the structural layout, or add vertical tying from Option (2).
(5) In the design of a wide range of structures, particularly those with insitu rc floors, the designer will quickly find that all he needs to do is to provide some horizontal ties and check the unprotected external walls on the upper three or possibly four storeys.

9 Structural Elements and Forms

Perhaps the most rewarding part of designing in masonry is forming the various materials and elements into interesting, efficient and useful structural forms. In order to simplify the approach to structural forms, it is probably best to first consider the various structural elements that can be formed with masonry units, and then to consider the ways in which these elements can be put together.

9.1 Structural Elements

9.1.1 Single-leaf Walls

A single-leaf wall may be of any thickness provided the masonry units are bonded together (see Figure 9.1). Single-leaf walls are mainly used for internal loadbearing walls, boundary walls and retaining walls.

9.1.2 Double-leaf Collar-jointed Walls

This type of wall is often used internally and externally where a double-leaf thickness is required structurally, but a stretcher bonded face is required for architectural reasons (see Figure 9.2).

Due to the weakness of the collar joint in wall type 1, it is necessary to design the wall in a similar manner to that of a cavity wall. However, by the use of metal ties or mesh reinforcement through the joint, the condition can be improved to a minimum standard (see type 2 in Figure 9.2), which can then be considered as a solid wall. The main improvement is the ability of the joint to take vertical shear forces. Special care must be taken to see that the wall is constructed as specified, since this is critical to the wall's behaviour under load and hidden from view after construction.



Figure 9.1 Single-leaf walls

9.1.3 Double-leaf Cavity Walls

Double-leaf cavity walls are mainly used for external walls, the cavity being incorporated to prevent damp penetration, and the two leaves are tied together with metal ties (see Figure 9.3).

Normal ties are considered capable of transferring some horizontal forces across the cavity from one leaf to the other, but not capable of transferring any significant vertical shear forces across the cavity. The wall is, therefore, designed as two separate leaves, each leaf carrying the vertical loads applied directly to it, the only assistance provided by the opposite leaf being increased resistance to buckling and the ability to transfer horizontal loads such as wind across the cavity.

Specially designed cavity walls can be assumed to transfer vertical shear forces, but only when wall ties specifically designed to transfer them without significant distortions are incorporated at suitable centres for the loading conditions involved.

The cavities of double-leaf walls are sometimes filled with non-loadbearing material such as insulation quilt to improve the overall thermal insulation qualities of the wall.

9.1.4 Double-leaf Grouted Cavity Walls

A grouted cavity wall can be designed as a solid wall, provided that the leaves are spaced a minimum of 50 mm apart, suitably tied with metal wall ties, and grouted with concrete of a strength at least equivalent to that of the mortar (see Figure 9.4). This form of construction is often used in similar conditions to the double-leaf collar-jointed wall and designed in a similar manner (see section 9.1.2).

Grouted cavity walls may also be reinforced (see Figure 9.5). The addition of the reinforcement assists the wall in counteracting tensile forces, and is particularly useful when



Figure 9.2 Double-leaf collar-jointed walls



Figure 9.3 Double-leaf cavity wall



Figure 9.4 Double-leaf grouted cavity wall



Figure 9.5 Reinforced grouted cavity wall

lateral loads are to be resisted. It should be noted that filling the cavity with grout has a detrimental effect on the wall's ability to resist damp penetration.

9.1.5 Faced Walls

Faced walls consist of two different masonry units, bonded together in a manner which provides a particular facing to the wall. They are used where a solid wall is necessary, but where the facing material has to have properties not required for the backing. A typical example is indicated in Figure 9.6, where a 327 mm faced wall provides a special facing brick on one side but incorporates a more economical inner unit to which plaster may be applied. Attention must be given, when selecting different units which are to be bonded together, to see that the shrinkage, thermal and other movements of the units are compatible. The design procedure for a faced wall is similar to that of any other solid wall, but it is generally assumed that the full thickness of the wall is constructed in the weaker unit.



Figure 9.6 Faced wall



Figure 9.7 Veneered walls

9.1.6 Veneered Walls

Veneered walls have a facing which is attached to the backing, but not bonded to it in such a way as to induce composite action under load (see Figure 9.7).

This type of wall is often used where an expensive facing is required and/or the structural qualities of the veneer are of little assistance to the loadbearing capacity of the wall. In other cases, veneered walls are used when the facing veneer is likely to need replacement within the life of the structure.

The design of a veneered wall must take account of the dead weight of the veneer. However, the structural effect of the veneer should be neglected. As in the case of faced walls, the possibility of differential vertical movements from shrinkage, thermal and other effects must be considered to make sure that loosening of the ties and/or buckling of the veneer, etc., will not occur.

9.1.7 Walls with Improved Section Modulus

Previous chapters have already discussed the problems relating to masonry walls which have to resist large bending moments at positions of low gravitational loads. As mentioned earlier, the greatest problem relates to the tensile stresses.

Consider the calculation involved in determining these stresses:

$$\text{Maximum tension stress} = \frac{W}{A} - \frac{M}{Z} \quad \text{(see Chapter 3)}$$

where

W = vertical load
A = cross-sectional area
M = applied bending moment
Z = section modulus.

To improve these stress conditions without changing the mass of the wall, it is necessary to improve the section modulus, Z, without changing the area, A. This can be achieved by a redistribution of the material to locate the majority of it at a greater distance from the neutral axis of the section.

For example, consider the two sections 1 and 2 shown in Figure 9.8.

The areas of both sections are equal, i.e.

$$\text{section 1 area} = 2 \times 2 = 4$$
$$\text{section 2 area} = (2 \times 2.5) - (1 \times 1) = 4$$

But the Z value of section 2 is greater than that of section 1, i.e.



Figure 9.8 Using hollow section to create greater section modulus

Figure 9.9 Chevron or zig-zag wall

$$\text{section 1:}\quad Z = \frac{2 \times 2^2}{6} = 1.333$$

$$\text{section 2:}\quad Z = \frac{1}{1.25}\left(\frac{2 \times 2.5^3}{12} - \frac{1 \times 1^3}{12}\right)$$

$$= 2.013$$

This method of improving the section modulus of the wall, when large bending moments are to be resisted, is the main advantage achieved with the wall sections which follow.

Chevron or Zig-zag Walls

The chevron or zig-zag wall (Figure 9.9) is particularly useful for free-standing walls and other walls required to resist large bending moments. It achieves its extra stiffness and higher Z/A ratio from the changes in direction on plan, and the shape of the wall also results in a very pleasing appearance which has been very successfully used for the external walls of churches, boundary walls, etc.

Diaphragm Walls

The diaphragm wall (Figure 9.10) is basically a wide cavity wall with cross ribs bonded or specially tied to the leaves of masonry to provide suitable vertical shear resistance at the junctions. This type of wall is particularly suitable for tall single-storey buildings enclosing large open areas. The width between the leaves is increased to suit the particular design condition, and large Z/A ratios can be achieved making economical use of the masonry. Diaphragm walls have been successfully used on sports and drama halls,



Figure 9.10 Diaphragm wall



Figure 9.11 Typical mass filled diaphragm



Figure 9.12 Piered wall

factories, etc., and a typical dimension for such use would be in the region of 550–1100 mm overall width.

Mass Filled Diaphragms

The diaphragm wall can also be used for retaining walls and is sometimes mass filled (see Figure 9.11). This form of diaphragm is constructed in lifts, and filled with rubble or other material to provide mass for stability. In some cases the rubble is grouted to form a monolithic mass. For this type of construction, the ribs should always be properly bonded.

Piered Walls

A piered wall is a wall stiffened by piers bonded into the wall, at regular centres (see Figure 9.12).

The use of piers is mainly suited to local stiffening of load-bearing walls at high concentrated load locations, and in

the external walls of single-storey buildings in the range of 3–5 m height which are required to resist some lateral loading. The piers have the effect of increasing the effective thickness of the wall, thus reducing the slenderness ratio and enabling it to carry higher compressive loading. The most complicated form of design tends to be that of a piered cavity wall with combined lateral and vertical loading, where the piers are bonded to the inner or outer leaf and the two leaves tied in the normal manner using standard wall ties.

The design considers the pier and a portion of the leaf bonded to it as a T section and the opposite leaf as a second member tied to it. It is considered that the ties across the cavity are capable of transmitting some horizontal forces but are unable to transmit vertical shear. Due to the unsymmetrical geometry of the section, the pier has greater moment of resistance in one direction than in the other, and for bending moments which can occur in either direction the shape is not ideal.

In cases where the forces involved would demand large piers, the fin wall, diaphragm wall and/or post-tensioned wall should be considered.

Fin Walls

A fin wall is basically a piered wall in which the pier has been extended to more slender proportions and has taken on the major role in resisting lateral load. The fin is the main structural element and is designed as a T section bonded into the intersecting leaf of masonry. The boundary between piers and fins is a rather grey area, but this should not be allowed to confuse the designer since the structural behaviour and design considerations at this boundary are basically the same. Like the diaphragm, the fin wall profile results in a large Z/A ratio, achieving economical use of the masonry in resisting bending moments. Due to the unsymmetrical geometry of the section, the fin has a greater moment of resistance in one direction than in the other and, while this is sometimes a slight disadvantage, its attractive form often compensates in its selection for a project. Fin wall construction has been successfully used for retaining walls, sports and drama halls, factories and multi-storey buildings (Figure 9.13).



Figure 9.13 Fin wall

9.1.8 Reinforced Walls

Reinforced walls have developed from the need for masonry walls to resist tensile stresses in excess of the normal permissible tensile stresses for masonry acting alone.

Walls are often constructed with reinforcement contained in the cavity, although sometimes the reinforcement is located in vertical ducts or holes through the masonry (see Figure 9.14). The void around the reinforcement is either completely grouted up or completely filled with mortar, as the work proceeds, in order to provide a suitable bond between the reinforcement and surrounding masonry. The reinforcement is located in the most suitable position to resist the applied moment or tensile force, i.e. in the tension face of the wall. The design of the wall is similar to that of reinforced concrete, using the masonry in the compression zone to resist the compressive stresses, and the reinforcement in the tensile zone to resist the tensile stresses.

Reinforced walls are mainly used for retaining walls where large lateral loads are to be resisted, but they can also be used in any location where the gravitational loads are small compared with the lateral or uplift forces involved. Care should be taken when using reinforced walls to see that suitable and adequate protection against corrosion is provided by quality of the masonry and mortar and the cover to the reinforcement.

In order to improve the effectiveness of reinforced walls resisting large bending moments, consideration should be given to shapes other than single- or double-leaf walls, for example, the lever arm of the reinforcement can be improved by using fins, diaphragms or piered sections. One method is to construct a pier or fin with a central void,



Figure 9.14 Reinforced walls



Figure 9.15 Reinforced and post-tensioned pier

to reinforce this void, and then to grout up the reinforcement. Alternatively, a post-tensioned rod could be used within the void (see Figure 9.15). These solutions have the effect of reducing the required size of the pier or fin and increasing the height to which such walls can be used.

Working details should always be as simple as possible, keeping the number of trades and the sequence of operations to a minimum. Grouting can be carried out in short lifts, using a liquid grout. Air vents and weep holes must be provided to allow the air to escape during grouting (but not the grout itself, since this would stain the face of the wall) and to keep a check that the grout has reached the various levels within the void.

9.1.9 Post-tensioned Walls

Inducing precompression is yet another way of making large improvements in a masonry wall's ability to resist lateral or uplift loads.

The aim of post-tensioning is to induce compressive stresses into the brickwork prior to the application of lateral or uplift forces. The induced compressive stresses must, therefore, be cancelled out by the loading condition before any tensile stress can be developed in the masonry. Thus it is possible to calculate the precompression needed to prevent any tensile stress developing, and to induce this compression by post tensioning high tensile steel rods which apply their reaction forces onto the panel being considered. The tension is applied to a threaded steel rod by tightening a nut against a cap plate which, in turn, induces compression in the wall. The steel rod is generally anchored into the foundation.

Having established the precompression required, it is then possible to determine the tensile force which must be developed within the post-tensioning rod, the rod diameter required, the torque needing to be applied and the maximum compressive stress induced in the brickwork. A check should be made to ensure that the rod is suitably anchored and that the reaction is adequately catered for (see Figure 9.16).

Post-tensioned walls are often used for spandrel panels below long window openings, retaining walls, tall diaphragm and fin walls, and for other conditions where the gravitational forces involved are small compared with the uplift or lateral forces needed to be resisted.

It is important, when using post-tensioning rods, to see that suitable and adequate protection is given to all the steel components in order that corrosion does not occur within the required design life of the building. It is also important to ensure that the required torque is suitably noted on any working drawings and details of the wall, and that adequate instructions are given to the contractor. To prevent the possibility of the torque (and thus the prestress) reducing, a locking device should be provided by the use of a lock nut or by grouting up solid the nut's seating plate.

9.1.10 Columns

Basically a column is a very short length of wall, and is defined as an isolated vertical loadbearing member whose width is not more than four times its thickness (see Figure 9.17). Strictly, this would only apply to rectangular columns, but many other shapes can obviously be utilised provided that adequate bonding of the masonry can be achieved.

Columns are generally used where large, open, uncompartmented areas are required, and the shapes are often determined by economic, aesthetic or other physical requirements. For example, the four types of column



Figure 9.16 Post-tensioned walls



Figure 9.17 Plan on column



Figure 9.18 Typical column sections

in Figure 9.18, could be used for either aesthetic appeal, structural suitability or accommodation of ducts, flues, etc., depending on the various design considerations.

The design of columns is dealt with in Chapters 10 and 11 and involves the determination of the slenderness ratio, the reduction factors of area, and the consideration of shear and other stresses.

Columns, like walls, can be built with cavities, can be solid masonry, double-leaf collar-jointed, grouted cavity, faced, veneered, post-tensioned or reinforced. The design considerations for columns are similar to those for walls, as outlined earlier, with additional problems involving the determination of the effective thickness and consideration of the small cross-sectional area.

Since the cross-sectional area of a column is small, the probability of a given proportion of the masonry having a lower than average strength is greater than would be the case for a member of large cross-sectional area. This, of course, also applies to conventional walls of small cross-sectional area. Here, again, it is necessary to introduce a reduction factor related to the small area.

9.1.11 Arches

The arch is one of the most efficient methods of forming a support with materials which have good compressive resistance and low tensile resistance, because its configurations can produce an equilibrium condition made up of compression forces (see Figure 9.19).

It is one of the most visually attractive structural forms. However, although vast numbers were built during the industrial revolution, arches are, unfortunately, rarely used to-day. Corresponding with the decline in their use has been a decline in the number of craftsmen experienced in this form of construction. For that reason, it seems unlikely that a speedy revival in arch construction will take place – despite the fact that for certain structures the arch offers the best solution.



Figure 9.19 Arch



Figure 9.20 Brick arch floor



Figure 9.21 Inverted brick arch foundation

An interesting past use is to be found in the brick arch floors of many nineteenth century dock warehouses. The arches were topped off with a weak concrete or other levelling material, and were sometimes constructed above a cast iron framework (see Figure 9.20).

The extra weight on the frame and foundations when compared with more modern forms of construction, has rendered this type of flooring uneconomical. Contemporary design techniques could, of course, reduce both the weight and the economic disadvantages.

Another past use of interest was in foundations constructed with inverted arches, the loads from columns or walls being dispersed via the arch from a point or knife-edge load onto a more uniform loading on the sub strata (see Figure 9.21).

Although, as noted earlier, it seems unlikely that we shall see a speedy and widespread revival in arch construction,



Figure 9.22 Circular tube construction



Figure 9.24 Typical sections through reinforced masonry beams

it should certainly not be written off. Conditions have changed greatly since it went out of fashion, and the application of modern techniques of design and construction could well bring this attractive and efficient structural form back into rather more common use.

9.1.12 Circular and Elliptical Tube Construction

The arch and the inverted arch can be combined to form a completely circular or elliptical cross-section that is particularly useful for the construction of shafts, tunnels chimneys, etc. In the case of shafts and tunnels, the critical loading conditions tend to be those of external pressures acting through lines which radiate from the centre (see Figure 9.22), and which can be resolved into a compression ring of forces ideally suited to masonry construction.

In addition to this property, the tubular shape has good resistance to longitudinal bending moments, and this is exploited in chimney construction.

9.1.13 Composite Construction

As mentioned previously, other materials can be combined with masonry to give greater resistance to bending moments, etc. This has often been done unintentionally. For example, reinforced concrete beams are frequently designed to carry large panels of masonry and, in reality, the assumed compressive stresses calculated as existing in the concrete do not in fact occur, because the masonry above the beam resists the bending compression forces (see Figure 9.23).

The condition indicated by the above example has been



Figure 9.23 Composite construction

simplified for clarity. However, it should be noted that existing knowledge on composite action is insufficient for full exploitation and, for that reason, designs stresses tend to be lower than in more conventional designs. It is also essential to take into account the vertical stresses occurring in the wall, since these have an effect upon the bending resistance of the composite panel. Thus the design procedure involves calculating the vertical stress, prior to determining the permissible bending stresses. In addition, openings through the wall will reduce the composite action. Nevertheless, quite large openings can be accommodated without destroying the advantages of this action, and the reduced effect can be taken into account in the design.

It is also necessary to design the reinforced concrete beam to support a height of 'wet' uncured masonry for the temporary condition during construction. The lift of wet masonry is also determined from the anticipated height of masonry likely to require support prior to the mortar having achieved sufficient strength to act compositely with the beam.

9.1.14 Horizontally Reinforced Masonry

As mentioned in section 9.14, when combined with reinforcement, masonry can be made to resist much greater bending moments. Hence, reinforced masonry can be used for beams and slabs to span and cantilever over quite large openings. The reinforcement is located in holes in specially manufactured units, or in the perpendicular joints of the masonry (see Figure 9.24).

The design of reinforced masonry is similar in basic principles to the design of reinforced concrete, the reinforcement being located in the tensile face of the combined section. The design procedure is dealt with in detail in Chapter 15. Special attention is needed when using reinforced masonry in external or exposed conditions to ensure that adequate protection is provided to the reinforcement.

9.2 Structural Forms

9.2.1 Chimneys

During the industrial revolution, the need to remove smoke and other gases to a high level in the atmosphere, to prevent excessive local pollution, brought masonry chimneys onto the industrial scene. The engineers found that the problems



Figure 9.25 Chimneys

caused by wind loading and temperature stresses had taken on new proportions.

Like other chimneys, masonry chimneys are designed as cantilevers resisting horizontal wind loading, and require checking for increased stress conditions caused by the temperature gradient. The effect of wind around chimneys and related oscillation has become better understood – though still not fully – because of the experience gained from this period in engineering history.

The chimney is generally tapered to give increased resistance to bending, as the applied bending itself increases. Consideration must be given to the possibility of sulphate attack, particularly at and near the top of the chimney, and suitable masonry and mortar must be chosen and specified for the expected condition. At low level, allowance must be made for flue openings, etc., and local stiffening is often necessary in this location to facilitate the rapid increase in stresses due to the reduced section at the point of maximum bending (see Figure 9.25).

The use of reinforcement can greatly improve the resistance of the masonry to the applied bending moments, and/or reduce the amount of masonry needed.

Reinforced masonry can also be valuable in extending the height of existing chimneys. This can be done by adding an extra outer skin of masonry leaving a reinforced cavity between the old and the new wall and extending the height of the structure, as in Figure 9.26.

Chimneys are not necessarily restricted to a circular or square cross-section. Clover-leaf, elliptical, hexagonal, triangular and many other cross-sections can be used to accommodate varying numbers of flues and to give a pleasant appearance (see Figure 9.27).



Figure 9.26 Chimney extension



Figure 9.27 Chimney cross-sections



Figure 9.28 Crosswall construction

Particular care must be taken when using complicated shapes to see that temperature stresses do not become excessive.

9.2.2 Crosswall Construction

In most buildings, the wall layouts are mainly dictated by functional requirements. Often, however, with a little more consideration of the structural implications, a plan can be developed to suit both the functional and the structural requirements. For example, a multi-storey hostel block containing numerous bedsitters with only a few basic layouts can frequently be planned to have the same types one above the other, and all the room-dividing walls can then line through from the bottom to the top of the building (see Figure 9.28).

The dividing walls can thus be used for the structure of the buildings, supporting the floor and roof slabs, and resisting lateral wind loads from the main elevations. The corridor walls then support the corridor floors and resist the wind loads acting on the gable ends. The resulting structure forms a very stiff construction, and the stairs and lift shafts add even greater stiffness for resisting wind loads, the slabs being designed as plates to transfer the lateral loads to the main crosswalls in the rooms and staircase areas. An example of the economical cross-section of such walls is a nine-storey hostel constructed using only 102 mm thick brick walls for the full height – the stresses in the main crosswalls being within normal acceptable limits without the need for any other structural framework. In designing crosswall buildings it is necessary to ensure that the wall thickness required for sound and fire resistance are incorporated, since often, in staircase areas, etc., these requirements demand thicker walls than do the structural considerations.

The speed of construction of such buildings is very impressive, particularly if the plan form and size of the building allows it to be constructed in quarters, using the 'spiral' method whereby the trades can follow each other around the building from one quarter to the next completing their section of the work (see Figure 9.29).

From the stage indicated in the figure, the bricklayers on completion of Bay 4 would move up to the next floor and start work in Bay 1. The other trades, i.e. shutterers, steel fixers and concretors would all move on one bay – the construction continuing to 'spiral' up the building keeping all trades constantly employed.



Figure 9.29 Spiral methods of construction

In addition to the normal consideration of wind, superimposed and dead loading, many multi-storey buildings must also be designed to prevent progressive collapse due to accidental damage, and to take account of the possible differential movements of the inner and outer leaves of the external cavity walls. These conditions demand extra consideration from the designer, particularly in the detailing and design of floor slabs and the use of alternative support. For example, in order to overcome the critical effects of the vertical differential movement on the outside walls, it is necessary to support the outer leaf of brickwork at intervals of height up the building (see Figure 9.30), and to incorporate special details which allow the movement to take place without detrimental effects to the building.

The requirements to be satisfied with regard to both progressive collapse and differential vertical movement are dealt with in more detail in Chapter 8 and Appendix 3. Some buildings require larger room sizes than those needed for hostel accommodation and larger areas of natural light. An example of this is school classrooms (see Figure 9.31).

With some thought in planning, a floor plan that repeats on all floors can often be achieved, and the main crosswalls can be used as loadbearing elements. It is important in this form of construction to see that a sufficient length of walls at right angles to the main crosswalls is provided to resist wind loading normal to the gables. The floors again span



Figure 9.30 Accommodating differential construction



Figure 9.31 Crosswall classroom blocks

between the main crosswalls, transferring lateral loading to the wind walls, and vertical and lateral loads to the crosswalls. They provide the necessary restraint to the walls at each floor level. As in the previous example, the normal room-dividing walls provide the main structure and eliminate the need for a separate structural frame.

9.2.3 Cellular Construction

Another suitable form for multi-storey buildings with small rooms is cellular construction. Generally, this has been used for domestic buildings but it is also suitable for small office accommodation, etc. The rooms in this case form a number of cells, and again the aim is to use all the separating walls for the main structure and to line up the walls from the bottom to the top of the building (see Figure 9.32).

In the majority of cases all the walls are loadbearing with the exception of toilet partitions and other minor room-dividing walls. In all other aspects the wall in cellular construction is similar to the crosswall, except that it is easier to achieve similar stiffness in all wind directions because of the cellular arrangement.

9.2.4 Column and Plate Floor Construction

For buildings requiring large open areas, widely spaced columns can be used in a column and plate construction. In this case (see Figure 9.33), the columns are designed to carry the vertical loads and, if sufficient walls can be located to resist the wind forces, such as those around stair and lift enclosures, gable walls, etc., the floors can be used as plates which span horizontally, transferring the wind forces from the external cladding to the walls.

Some buildings are of such a layout that the crosswalls required to resist wind cannot be accommodated. In these cases the columns can be T, cruciform or channel shapes designed to resist the horizontal reactions from the wind – each individual column resisting its own local area wind reactions (see Figure 9.34).

Columns can also be reinforced or post-tensioned in order to accommodate large bending moments in a neater, smaller and more economical section.



Figure 9.32 Cellular construction



Figure 9.33 Column and slab braced structure



Figure 9.34 Column and slab unbraced structure

9.2.5 Combined Forms of Construction

In many buildings the required layout demands both large open areas and smaller enclosed rooms, and combinations of the forms already mentioned can be used (see Figure 9.35).

The example shown indicates a successful combination of column and plate and crosswall construction. Many variations can be made, always provided that sufficient masonry is accommodated to deal with the loading conditions. The



Figure 9.35 Horizontal combined forms



Figure 9.36 Vertical combined forms (podium construction)

structural forms shown in Figure 9.35, are combined on each floor. However, different forms can be successfully combined in a vertical condition as, for example, the podium construction shown in Figure 9.36.

For this condition to be successfully achieved, however, detailed planning is necessary to obtain the most economical solution, particularly with regard to the locations of the loadbearing walls and columns. The construction is basically a concrete or steel frame up to first floor level and loadbearing masonry above. This construction ties in nicely with the greater flexibility of use often demanded at ground floor level.

9.2.6 Diaphragm Wall and Plate Roof Construction

Diaphragm wall and plate roof construction is mainly suitable for tall single-storey buildings enclosing large open areas such as sports halls, gymnasia, swimming pools and industrial buildings. Buildings can be constructed using diaphragm external walls, as outlined in section 9.1.7, and the roof forms a horizontal plate, which is used to prop the walls against lateral loading (see Figure 9.37). In order to transfer the reactions from the wall into the roof diaphragm, a capping beam is often provided which can be used as the seating for fixing the roof beams, to resist the uplift forces and, if necessary, as a boom member of the roof girder.

In Figure 9.37, for the wind direction shown, the roof plate spans from gable to gable and transfers the forces, via the ring beam and roof plate, into the gable wall where the wall stiffness for that direction is greatest. For a wind loading condition on the gable, the plate would span between the main elevations and transfer the loads via the ring beam into the main elevation walls. In many cases, the roof decking material is suitable for use as a plate. However, in situations where this is not so, a horizontally braced girder, or similar, can be used incorporating the ring beam as a boom member to transfer the propping force to the transverse walls of the building. For more detailed information see Chapter 13.

9.2.7 Fin Wall and Plate Roof Construction

Fin wall and plate roof construction is an alternative to the diaphragm and plate roof. The form is again mainly used on tall single-storey buildings and the main difference is in the type of external wall construction (see Figure 9.38).

The basic design is similar to that of the diaphragm, and plate and is dealt with in more detail in Chapter 13. Again, the walls are designed as propped cantilevers and use is made of the roof deck as a plate for propping the tops of the walls. However, in this situation, bracing is usually needed in the roof to achieve adequate plate action.

9.2.8 Miscellaneous Wall and Plate Roof Construction

Possible variations of the outside wall configuration for the building types mentioned in sections 9.2.6 and 9.2.7 are numerous, and the main aim should be to achieve a high Z/A ratio and to take maximum advantage of the gravitational forces involved, thus giving a wide scope for imaginative shapes and configurations using the masonry suitably dispersed around the neutral axis of the section (see Figure 9.39).

9.2.9 Spine Wall Construction

Spine walls are suitable for more flexible open-plan arrangements where a number of main walls, such as



Figure 9.37 Diaphragm and plate roof construction



Figure 9.38 Fin wall and roof plate construction



Figure 9.39 Miscellaneous wall construction



Figure 9.40 Spine wall construction

corridor walls, stair walls, lift shafts, toilets and services, can be in a fixed location as, for example, in office buildings (see Figure 9.40).

Spine walls, together with the external face walls, are used as the main loadbearing walls supporting the floor loads and should line up vertically through the building. It is also most important to provide sufficient wind walls at right angles, as in stair and lift areas (see Figure 9.40), in order to be able to resist the wind loading on all elevations. The principal advantage of this form of construction is the added flexibility of room arrangements, since all dividing partitions can be of a temporary nature and supported on the main floors. Floors are again used as the horizontal plate members distributing the wind reactions from the external elevations to the nearest structural wall normal to the wind direction.

9.2.10 Arch and Buttressed Construction

In the past, the beautiful form of arch and buttress construction has been adopted for many structures, for example, bridges, industrial buildings, warehouses, churches, etc. (see Figure 9.41). The aim is to keep all forces in the masonry in compression.

The thrust from the arch ring is transferred to the foundations by the propping action of the buttress, and the shape and size of both the arch and the buttress are proportioned to produce equilibrium within the form, using compressive forces only.

Buttressed arches are still as attractive and useful as ever, and it is a pity that many designers do not consider them, especially when designing churches. The possible combination of the arch and buttress with diaphragm, fin,



Figure 9.41 Arch and buttress construction



Figure 9.42 Compression tube examples

reinforced and post-tensioned walls opens up for the designer a wonderful opportunity to make masonry church buildings a most attractive development using modern forms of construction.

The use of this form is, however, not only suited to churches. In the years to come, it is likely that a better understanding of the structural behaviour of the arch and buttress, along with further developments, will produce structures of more economical proportions, making better use of masonry, and possibly combining them with other materials to produce buildings which will compete with those of the past for their visual effect and low maintenance costs.

9.2.11 Compression Tube Construction

Many structures, particularly those to be constructed underground, have to resist external pressures which might crush them. Because of masonry's good resistance to compressive forces, such structures can be designed in a similar manner to the arch and buttress, keeping all the forces in compression, thereby avoiding or limiting undesirable tensile or bending stresses. The use of circular or elliptical tube forms can give the desired result (see Figure 9.42). This type of construction is often used for tunnels, shafts, sewers, etc.

In the case of the vertical shaft, the design pressures are in balance and the forces resolve into a circular compression ring. The shaft is constructed in sections, working from the top and progressing in short lifts as the shaft is excavated (see Figure 9.43).



Figure 9.43 Vertical shaft construction

In the case of sewers, the theoretical forces are not often equal on all sides, and some bending could occur in a circular form. Variations on the shape of the cross-section will reduce or increase these bending moments, and the aim should be to produce a shape suitable for the use and keeping the masonry thickness to a minimum – the ideal shape being that which produces only direct compressive forces.

This chapter has outlined some of the elements and forms in structural masonry that are possible, practical and economically advantageous. The design and application of the more common elements and forms are dealt with in detail in the chapters which follow. Doubtless, there are many other possibilities. Certainly, there is room for experienced and imaginative designers to develop their own solutions and to break fresh ground.

10 Design of Masonry Elements (1): Vertically Loaded

The basis of design of plain masonry has been examined in Chapters 3–6. In this and the following chapter, the recommendations of BS 5628 will be applied to specific design problems.

10.1 Principle of Design

The principle of the design is to satisfy the equation

$$\frac{\beta t f_k}{\gamma_m} \geq n_w \quad \text{(see section 5.11 and BS 5628, clause 32.2.1)}$$

in which, for walls, a unit length (linear metre) of wall is considered.

The required wall thickness or column size or, when applicable, the correct choice of geometric profile for a particular element will, initially, as with any other structural material, be unfamiliar and the guidance which follows should be of some help to the inexperienced designer. As in most structural design, the approach is based on trial and error. Experience and familiarity with the materials and components available will lead to more accurate initial assessments.

10.2 Estimation of Element Size Required

In general, the mechanism of failure of a wall or column is that of buckling under vertical loading imposed from walls and floors over. Buckling is directly proportional to the stiffness of an element, and the stiffness can be expressed as I/L, where I is the second moment of area of the element and L is the effective length of the element.

For a given effective length, the second moment of area, I, of an element would need to be increased as the loading was increased to contain the buckling tendency to the same degree of safety. For solid walls, this is done by simply increasingly the wall thickness and thus the I value. Conversely, for a given loading, the second moment of area, I, of the element would again need to be increased as the effective length was increased.

The capacities of various solid wall thicknesses to carry loads over differing effective lengths can only become familiar to the designer with time and application of the design process. The expression used to measure the tendency of the element to buckle is 'slenderness ratio' and is written as h_{ef}/t_{ef}, where h_{ef} is the effective height (or length) of the element and t_{ef} is its effective thickness. An element with a high slenderness ratio has very little capacity to carry loading due to the tendency to buckle at relatively low stress, whereas an element with a low slenderness ratio has more reserve to carry loading because of its lower tendency to buckle.

However, the designer should not limit his thoughts to simply increasing the wall thickness to provide a greater second moment of area. There are often economies to be achieved by using the material in another geometric profile, in exactly the same way as concrete or steel I, T or box beams were developed. The case for such a choice of element would generally be more applicable to a heavily loaded element of large effective length where the direct stresses and the buckling tendency are extremely high. By the same logic, rectangular rather than square column sections would be a more sensible choice where lateral restraint, capable of preventing buckling of the column, is provided at mid-height and to the minor axis of the element (see Figure 10.1).

The designer should be encouraged to think more in terms of the radius of gyration and second moment of area properties of an element, rather than 'effective thickness', as this will lead to inventiveness and ingenuity in overcoming the more difficult problems.

10.3 Sequence of Design

It should now be evident that the design sequence can be written as a four-stage operation:

Stage 1: Calculate the characteristic load and design load.
Stage 2: Estimate wall thickness (or column size or geometric profile).
Stage 3: Calculate the design strength required for the wall (or element) to support the design load as calculated in stage 1.
Stage 4: Amend wall thickness or geometric profile if necessary and determine the required brick and mortar strengths.

Stage 2 of the design sequence has been dealt with in section 10.2 and stages 1, 3 and 4 will be considered, in practical terms, by examining design examples.

10.4 Design of Solid Walls

As the second moment of area of a solid wall is directly proportional to its thickness, the effective thickness (which for solid walls is the actual thickness) will be used in the calculations which follow.

Example 1

Design the internal brick wall in the ground-floor storey of the building shown in Figure 10.2. The wall is plastered both sides and forms part of a large building project where extensive testing of materials and strict site supervision will be implemented.



Figure 10.1 Benefit of rectangular sections when restrained about weaker axis



Figure 10.2 Cross-section

The loading may be assumed as:

characteristic dead loads roof $= 4.00\ \text{kN/m}^2$
floors $= 5.00\ \text{kN/m}^2$

characteristic superimposed loads roof $= 1.50\ \text{kN/m}^2$
floors $= 3.00\ \text{kN/m}^2$

density of brickwork for own weight $= 18.00\ \text{kN/m}^3$

The secondary effects of wind stresses due to the possibility of the element concerned acting as a shear wall to provide overall stability should be ignored for the purposes of this design example, but will be investigated in Chapter 11.

Stage 1: Calculate Design Load on Wall, n_w

The design load is obtained from the characteristic loads which are increased by the appropriate partial safety factor γ_f to allow for the type of loading and load combination being considered, i.e. dead loading, superimposed loading and wind loading. The degree of partial safety factor applicable to each of these loading types takes account of the degree of accuracy of that particular load. Values of γ_f are given in BS 5628, clause 22. For the combination of loading being considered in this example, dead plus superimposed only, case (a) factors for γ_f are applicable, requiring partial safety factors of 1.4 and 1.6 to be applied to G_k (characteristic dead load) and Q_k (characteristic superimposed load) respectively (see Table 5.1).

(a) Characteristic dead loads, G_k:

$$\text{roof} = \frac{5+5}{2} \times 4 = 20.00\ \text{kN/m}$$

$$\text{3 floors} = \frac{5+5}{2} \times 5 \times 3 = 75.00\ \text{kN/m}$$

$$= 95.00\ \text{kN/m}$$

Estimation of the wall's own weight should take account of the possibility of reducing the wall thickness in the upper storeys of the building and, for this purpose, it will be assumed that for this example the wall over can be sensibly reduced to a half brick wall at first floor level.

Wall own weight:

12 mm plaster both sides $= 2 \times 0.012 \times 21 \times 12.9 = 6.00\ \text{kN/m}$
102.5 mm brick wall $= 0.1025 \times 18 \times 8.4 = 15.50\ \text{kN/m}$
215 mm brick wall $= 0.215 \times 18 \times 4.5 = 17.42\ \text{kN/m}$

$$= 38.92\ \text{kN/m}$$

$$\text{Total characteristic dead load, } G_k = 38.92 + 95.00$$
$$= 133.92\ \text{kN/m}$$

(b) Characteristic superimposed loads, Q_k (super reductions from BS 6399, Part 1, Table 2, have been ignored for simplicity):

$$\text{roof} = \frac{5+5}{2} \times 1.5 = 7.50\ \text{kN/m}$$

$$\text{3 floors} = \frac{5+5}{2} \times 3 \times 3 = 45.00\ \text{kN/m}$$

$$Q_k = 52.50\ \text{kN/m}$$

Design load on wall n_w:

As stated previously, from BS 5628, clause 22(a), for this combination of loading, dead plus superimposed:

design dead loads = $\gamma_f \times G_k$ (characteristic dead loads) where $\gamma_f = 1.4$

and

design superimposed load = $\gamma_f \times Q_k$ (characteristic superimposed loads) where $\gamma_f = 1.6$.

Therefore, design load on wall:

$$n_w = (1.4 \times 133.92) + (1.6 \times 52.50)$$
$$= 271.5\ \text{kN/m}$$

Stage 2: Estimate Wall Thickness

The wall is required to support its loading over quite a large effective height and, therefore, a reasonably low value of slenderness ratio will be required to limit the buckling tendency. BS 5628 permits a maximum slenderness ratio of 27 (clause 28.1) and for estimation purposes it can be expected that, to provide adequate reserve in the allowable stresses to carry the moderately heavy loads, a limit of around 16 on the slenderness ratio would be required.

Assessed slenderness ratio (SR) = 16.

$$\text{Slenderness ratio, SR} = \frac{h_{ef}}{t_{ef}}$$

therefore

$$t_{ef} = \frac{h_{ef}}{\text{SR}}$$

Due to enhanced restraint from floor $h_{ef} = 0.75 \times 4.5$

$$t_{ef} = \frac{4.5 \times 0.75}{16}$$

$$\text{estimated } t_{ef} = 0.211\ \text{m}$$

But, to suit standard brick dimensions, try 215 mm thick wall.

(*Note:* The factor of 0.75 applied to the actual height to determine the effective height in the equation will be dealt with in stage 3 of the design process following.)

By inspection, it is noted that the design of a 102.5 thick (half-brick) wall would produce a slenderness ratio of 32 which is in excess of the maximum permissible value of 27 and, therefore, for standard bricks, a 215 mm thick wall is the minimum thickness appropriate to this effective height.

Stage 3: Calculate Design Strength of Wall

Design strength = $\frac{\beta t f_k}{\gamma_m}$ per linear metre (BS 5628, clause 32.2.1).

(a) Determine capacity reduction factor, β:

For the purpose of this example, it is assumed that any intersecting crosswalls are at such centres as to offer little lateral support to the wall. The slenderness ratio of the wall is therefore determined by its effective height rather than its effective length. Therefore,



Figure 10.3 Lateral restraint stiffness affecting effective height

$$\text{slenderness ratio, SR} = \frac{\text{effective height}}{\text{effective thickness}} = \frac{h_{ef}}{t_{ef}}$$

Effective height: The horizontal lateral supports which dictate the effective height of this element are provided by the ground and first-floor rc slabs and, as these slabs span onto the wall, the contribution of their support can be considered to provide enhanced resistance to lateral movement. Clause 28.3.11 of BS 5628 allows an effective height of 0.75 times the clear distance between the lateral supports for this support condition. Therefore

$$\text{effective height, } h_{ef} = 0.75 \times (4500 - 150)$$
$$= 3262.5 \text{ mm}$$

It is perhaps worth considering the logic of this allowance of $0.75 \times h$ by inspecting the deflected shape of the wall at the point where it is about to buckle. The implication of enhanced resistance to lateral movement (as opposed to the alternative simple resistance to lateral movement quoted in BS 5628) is that rotation of the wall at that support position is certainly limited if not completely eliminated. The junction becomes the equivalent of a partially fixed end with the deflected shape as indicated in Figure 10.3.

Effective thickness: The effective thickness, t_{ef}, of this element, as defined in BS 5628, clause 28.4.1, is the actual thickness and has already been estimated in stage 2 of the design process as 215 mm thick. Therefore

$$\text{slenderness ratio, SR} = \frac{h_{ef}}{t_{ef}} = \frac{3262.5}{215} = 15.2$$

Eccentricity of loading: The majority of the load supported by the element under consideration is in the loadbearing wall immediately above the first floor slab, and is the accumulation of the loads from the floors, roof and walls over. The proportion of the total load on this element accruing from the first floor slab alone is relatively small. It is assumed that a half-brick wall will later be proved to be adequate for the loadbearing wall element immediately above first floor level and the detail at this junction is shown in Figure 10.4, where

W_1 = loading in loadbearing wall over
W_2 = slab loading from left-hand side
W_3 = slab loading from right-hand side.



Figure 10.4 Eccentricity of loading for Example 1

W_1 can be assumed to be applied concentrically, whereas W_2 and W_3 must be applied at a position equal to $t/6$ from the loaded face (see BS 5628, clause 31).

For this element under full dead plus superimposed loadings, $W_2 = W_3$, because the loads and spans are identical and the resultant of these two loads is concentric on the 215 mm thick wall under. Consideration should be given, however, to the possibility of one of the floor spans being completely relieved of its superimposed loading, in which case the resultant W_2 and the reduced W_3 would be eccentric on the 215 mm thick wall under. The effect of the reduced total load, but applied with an eccentricity, may be a more critical design condition than the axially applied full load. The same imbalance of load, resulting in its eccentric application, would also result from different span lengths from each side of the wall.

For the purpose of this particular example the effects of this eccentricity will be ignored but will be investigated later in the chapter.

Capacity reduction factor, β: From BS 5628, Table 7 (see Table 5.15) and for eccentricities of loading of between 0 and

0.05t, a β value of 0.854 for a slenderness ratio of 15.2 (as calculated earlier) can, by interpolation, be read off.

(b) Determine partial safety factor, γ_m:

The categories of both constructional control and manufacturing control of the structural units must be selected at the discretion of the designer after careful consideration of the relevant factors applicable to a particular project. From the information supplied for the design example, control of both items could be described as 'special' (BS 5628, Table 4 – see Table 5.11) and a materials partial safety factor γ_m of 2.5 would apply.

(c) Calculate characteristic strength required f_k:

From the basic equation

$$n_w \geq \frac{\beta t f_k}{\gamma_m}$$

Rearranged, this gives $f_k \geq \dfrac{n_w \gamma_m}{\beta t}$

in which (as previously calculated or assessed) there is:

design load, n_w $= 271.5$ kN/m
partial safety factory, γ_m $= 2.5$
capacity reduction factor, $\beta = 0.854$
wall thickness, t $= 215$ mm

therefore characteristic strength required,

$$f_k = \frac{271.5 \times 2.5}{0.854 \times 215}$$

$$= 3.7 \text{ N/mm}^2$$

The element being considered is a 215 mm thick wall in which the width of the wall is equal to the length of the brick. For narrow brick walls (referred to earlier as half-brick walls), in which the thickness of the wall is equal to the width of the brick, a shape factor of 1.15 as defined in BS 5628, clause 23.1.2 is applicable. The application of this shape factor reduces the characteristic strength required of the masonry thus:

$$f_k = \frac{n_w \gamma_m}{\beta t \times 1.15}$$

and will be applied in a later design example.

Stage 4: Determine Required Brick and Mortar Strengths

It has now been determined that, to support the calculated design loads on this particular element using a 215 mm thick brick wall, the characteristic strength required of the masonry is 3.7 N/mm^2.

From BS 5628, Table 2(a) (see Table 5.4) a brick of 10 N/mm^2 compressive strength set in a mortar designation (iv) is just not adequate (see Table 5.4), therefore use bricks of 15 N/mm^2 compressive strength set in a designation (iv) mortar.

It can be seen that this is an extremely low strength requirement, but the wall thickness of 215 mm is a minimum for the storey height and therefore no adjustment to wall thickness will be required. This design example has been specifically related to the design of a brick wall. It is evident that, for such a low strength requirement, a concrete block of say 150 mm thickness would have been acceptable and perhaps a more structurally economical alternative. This will be considered in a later design example. It should be noted that a 150 mm solid dense concrete block would exceed the manual lifting limit of 20 kg.

Example 2

Using the same criteria, design the internal brick wall between first and second floors.

Stage 1: Calculate Design Load, n_w

(a) Characteristic dead loads, G_k:

$$\text{roof} \quad = \frac{5+5}{2} \times 4 \quad = 20.00 \text{ kN/m}$$

$$\text{2 floors} = \frac{5+5}{2} \times 5 \times 2 = \underline{50.00} \text{ kN/m}$$

$$= 70.00 \text{ kN/m}$$

Wall own weight:

$$\text{plaster} = 2 \times 0.012 \times 21 \times 8.4 \quad = 4.23 \text{ kN/m}$$
$$\text{102.5 mm wall} = 0.1025 \times 18 \times 8.4 \quad = \underline{15.50} \text{ kN/m}$$
$$= 19.73 \text{ kN/m}$$

$$\text{Total characteristic dead load, } G_k = 19.73 + 70.00$$
$$= 89.73 \text{ kN/m}$$

(b) Characteristic superimposed loads, Q_k:

$$\text{roof} \quad = \frac{5+5}{2} \times 1.5 \quad = 7.50 \text{ kN/m}$$

$$\text{2 floors} = \frac{5+5}{2} \times 3 \times 2 = \underline{30.00} \text{ kN/m}$$
$$Q_k = 37.50 \text{ kN/m}$$

Design load on wall, n_w:

$$\left.\begin{array}{l} \text{Dead } n_w \quad = 1.4 \times G_k \\ \text{Superimposed } n_w = 1.6 \times Q_k \end{array}\right\} \quad \text{as Example 1}$$

$$\text{Design load } n_w \quad = (1.4 \times G_k) + (1.6 \times Q_k)$$
$$= (1.4 \times 89.73) + (1.6 \times 37.50)$$
$$= 185.62 \text{ kN/m}$$

Stage 2: Estimate Wall Thickness

Assessed slenderness ratio = 21

Therefore wall thickness required,

$$t_{ef} = \frac{2.8 \times 0.75}{21}$$

$$= 0.10 \text{ m}$$

Try brick wall 102.5 mm thick.

Stage 3: Calculate Design Strength of Wall

(a) Determine β from slenderness ratio:

Effective height, $h_{ef} = (2800 - 150) \times 0.75 = 1987.5$ mm
Effective thickness, t_{ef} = actual thickness $= 102.5$ mm

$$\text{Slenderness ratio, SR} = \frac{h_{ef}}{t_{ef}} = \frac{1987.5}{102.5} = 19.4$$

The possibility of eccentricity of loads due to imbalance of dead and superimposed loads will, for simplicity, again be ignored for this design example. Therefore, from Table 7 of BS 5628, by interpolation (see Table 5.15): β = 0.721 for SR = 19.4 and $e_x = 0$ to $0.05t$.

(b) The partial safety factor, γ_m will remain, as for Example 1, as 2.5 for special categories.

(c) Calculate characteristic strength required, f_k.

It is hoped to use a 102.5 mm thick brick wall for this element and BS 5628, clause 23.1.2 permits the application of a shape factor of 1.15. Therefore

$$f_k = \frac{n_w \gamma_m}{\beta t \times 1.15}$$

$$= \frac{185.62 \times 2.5 \times 10^3}{0.721 \times 102.5 \times 1.15 \times 1000}$$

$$= 5.46 \text{ N/mm}^2$$

Stage 4: Determine Required Brick and Mortar Strengths

By inspection of Table 2(a) of BS 5628 (see Table 5.4) it is necessary to provide a brick of compressive strength 27.5 N/mm^2 set in a mortar designation (iv) (6.2 N/mm^2 provided) or lower strength brick of 20 N/mm^2 set in a designation (iii) mortar.

The compatibility of the differing brick strengths and mortar grades required for the elements in the adjacent storey heights of Examples 1 and 2 conflicts with good design practice, as will be discussed in another chapter. The designer may conclude that the lower strength 215 mm thick wall should extend to the underside of the second-floor slab where a more reasonable reduction could be employed.

Example 3

Design the concrete block internal walls shown in Figure 10.5 to support the loading shown from the rc storage slab over.

Loadings on rc slab:

characteristic dead load $= 6.5$ kN/m^2
characteristic superimposed load $= 12.5$ kN/m^2

The concrete blocks will individually measure 400 × 200 on elevation and should be assumed to have a density of 12 kN/m^3 and are solid blocks.

Stage 1: Calculate Design Load, n_w

(a) Characteristic dead loads, G_k: (assume 190 mm thick block wall)



Figure 10.5 Section for Example 3

$$\text{storage slab} = \frac{7.0}{2} \times 6.5 = 22.75 \text{ kN/m}$$

$$\text{block wall} = 12 \times 0.19 \times 6.7 = \underline{15.28} \text{ kN/m}$$
$$= 38.03 \text{ kN/m}$$

(b) Characteristic superimposed loads, Q_k:

$$\text{storage slab} = \frac{7.0}{2} \times 12.5 = 43.75 \text{ kN/m}$$

For this combination of loading (dead plus superimposed) partial safety factory values for γ_f should be taken as 1.4 and 1.6 respectively for characteristic dead and superimposed loads.

Design load on wall:

$$n_w = (1.4 \times G_k) + (1.6 \times Q_k)$$
$$= (1.4 \times 38.03) + (1.6 \times 43.75) = 54.24 + 70.0$$
$$= 124.24 \text{ kN/m}$$

Stage 2: Estimate Wall Thickness

The fairly high walls are required to support a moderately heavy load from the storage slab. As the slab spans onto the walls from one side only, eccentricity of loading will influence the capacity reduction factor and, therefore, should be taken into account when assessing the slenderness ratio for wall thickness estimation:

Assessed slenderness ratio = 22

Therefore estimated wall thickness,

$$t_{ef} = \frac{5.5}{22} \times 0.75 = 0.1875 \text{ m}$$

Try 190 mm thick concrete block wall.

Stage 3: Calculate Design Strength of Wall

(a) Determine β from slenderness ratio:

Effective height, $h_{ef} = 5.5 \times 0.75 = 4.125$ m

Effective thickness, t_{ef} = actual thickness = 190 mm

$$\text{Slenderness ratio, SR} = \frac{h_{ef}}{t_{ef}} = \frac{4.125}{0.19} = 21.71$$



Figure 10.6 Eccentricity of loading for Example 3

Eccentricity of load: From BS 5628, clause 31, the eccentricity of the load for this example may be assumed to be applied at one-third the depth of the bearing area from the loaded face (see Figure 10.6).

From Table 7 of BS 5628 (see Table 5.15): with SR = 21.71 and $e_x = 0.167t$, by interpolation, $\beta = 0.485$.

(b) The partial safety factor, γ_m, for materials and workmanship will, for this example, be assumed to be governed by the same conditions as in Example 1, hence $\gamma_m = 2.5$.

(c) Characteristic strength required, f_k:

$$f_k = \frac{n_w \gamma_m}{\beta t} = \frac{124.24 \times 2.5 \times 10^3}{0.485 \times 190 \times 1000}$$

$$= 3.37 \text{ N/mm}^2$$

Stage 4: Determine Required Block and Mortar Strengths

The applicable section of Table 2, BS 5628, is dependent on the shape of the individual block units, and is related to the ratio of their height to least horizontal dimension. The block to be used, in this example, for the estimated thickness of 200 mm, has the dimensions shown in Figure 10.7.

$$\text{Shape ratio} = \frac{200}{190} = 1.05$$

Interpolation between Tables 2(b) and 2(d), BS 5628 is necessary to find the block and mortar strength. Try solid blocks with a compressive strength of 7.0 N/mm^2 set in mortar designation (iv).

From Table 2(b) for the block chosen, $f_k = 2.8$ N/mm^2 for a height to least horizontal dimension ratio of 0.6. From Table 2(d) for the block chosen, $f_k = 5.6$ N/mm^2 for a height to least horizontal dimension ratio of between 2.0 and 4.0. Therefore interpolation between the two values is required for the ratio of 1.05, i.e.

$$f_k = \frac{(1.05 - 0.6)}{(2.0 - 0.6)} \times (5.6 - 2.8) = 3.7 \text{ N/mm}^2$$

Therefore f_k provided > 3.37 N/mm^2 required.

Use solid concrete blocks measuring 400 long × 200 high × 190 wide with a compressive strength of 7.0 N/mm^2 and set in mortar designation (iv).



Figure 10.7 Block dimensions for Example 3

10.5 Design of Cavity Walls

Cavity walls are of two basic types (see sections 9.3 and 9.4 and Figure 10.8):

(a) ungrouted cavity walls (the more common type)
(b) cement grouted cavity walls.

10.5.1 Ungrouted Cavity Walls

The great majority of ungrouted cavity walls are used on external elevations, and the vertical loading in such situations invariably results from floors and roofs spanning onto the inner leaf only. In addition, wind pressures and suctions impose lateral loading on the wall and this must also be considered in the design. This latter aspect of loading will be considered in Chapter 11. For certain arrangements and situations, cavity walls are used internally and are often loaded with floor and roof loads on both leaves. Examples of internal cavity walls occur where a plan area extends below, say, first floor level, and the line of the external cavity wall over is extended through the ground floor storey as will be seen later in Example 6. Further examples are in the use of cavity party walls for flat developments where the cavity construction is employed for sound insulation of the party wall common to both properties, and at movement joints in a building.

The stiffness of cavity walls ignores the wall ties from the point of view of transferring flexural shears across the cavity, but utilises the wall ties in that each of the two leaves has the effect of helping to prop the other. Allowance is given for this propping effect in the calculation of the effective thickness of cavity walls which is given, in clause 28.4.1 of BS 5628, as equal to two-thirds the sum of the actual thicknesses or the actual thickness of the thicker leaf, whichever is the greater.



Figure 10.8 Typical cavity walls

Example 4

For the building and loading information given for Example 1, design the ungrouted external cavity wall in the bottom storey height.

Stage 1: Calculate the Design Load, n_w

(a) Characteristic dead loads, G_k:

$$\text{roof} = \frac{5}{2} \times 4 \quad = 10.00$$

$$3 \text{ floors} = \frac{5}{2} \times 5 \times 3 = 37.50$$

$$12 \text{ mm plaster} = 0.012 \times 21 \times 12.9 = 3.25$$

$$\text{own weight of wall} = 0.1025 \times 18 \times 12.9 = 23.80$$

Note: Inner leaf only is considered in own weight wall calculation. Outer leaf is self-supporting.

$$\text{Total characteristic dead load, } G_k = 74.55 \text{ kN/m}$$

For this design example, the effect of wind loading on the wall will be ignored as this aspect will be dealt with in Chapter 11.

(b) Characteristic superimposed load, Q_k:

$$\text{roof} = \frac{5}{2} \times 1.5 \quad = 3.75 \text{ kN/m}$$

$$3 \text{ floors} = \frac{5}{2} \times 3 \times 3 = \underline{22.50} \text{ kN/m}$$

$$Q_k = 26.25 \text{ kN/m}$$

Therefore

Design load on wall:

$$\begin{aligned} n_w &= (1.4 \times G_k) + (1.6 \times Q_k) \\ &= (1.4 \times 74.55) + (1.6 \times 26.25) \\ &= 146.37 \text{ kN/m} \end{aligned}$$

Stage 2: Estimate Wall Thickness

The two most common configurations of brick cavity walls are shown in Figure 10.9.

The internal wall designed in Example 1 was shown to require an extremely low strength brick for a 215 mm thick brick wall, but a 102.5 mm thick brick wall could not be used as it exceeded the maximum slenderness ratio of 27. The external leaf of the cavity wall will stiffen the loadbearing inner leaf and therefore, for this example, try a 305 mm cavity wall.

Check the maximum slenderness ratio:

$$\begin{aligned} \text{SR} &= \frac{h_{ef}}{t_{ef}} \\ &= \frac{(4.5 - 0.15) \times 0.75 \times 10^3}{(2/3) \times (102.5 + 102.5)} \\ &= 23.87 \end{aligned}$$

which is less than the maximum permissible SR of 27.

Therefore, try a 305 mm cavity wall.

Stage 3: Calculate Design Strength of Wall

(a) Determine β from slenderness ratio:

$$\text{Effective height, } h_{ef} = (4.5 - 0.15) \times 0.75 = 3.26 \text{ m}$$

$$\text{Effective thickness, } t_{ef} = (2/3) \times (102.5 + 102.5) = 136.67 \text{ mm}$$

$$\text{Slenderness ratio, SR} = \frac{h_{ef}}{t_{ef}} = \frac{3.26 \times 10^3}{136.67} = 23.87$$

Eccentricity of load (see Figure 10.10) (from BS 5628, clause 31):

As in Figure 10.6, the eccentricity of the load on the loadbearing inner leaf of the cavity wall, $e_x = 0.167t$ (i.e. $t/6$) (see Figure 10.10).

From Table 7 of BS 5628 (see Table 5.15), with SR = 23.87 and $e_x = 0.167t$, by interpolation $\beta = 0.389$.

(b) Partial safety factor for materials and workmanship, $\gamma_m = 2.5$.

(c) Characteristic strength required, f_k:

$$f_k = \frac{n_w \gamma_m}{\beta t \times 1.15} = \frac{146.37 \times 2.5 \times 10^3}{0.389 \times 102.5 \times 1.15 \times 1000}$$

$$= 7.98 \text{ N/mm}^2$$

(The value of 1.15 is the shape factor allowed for narrow walls. See BS 5628 clause 23.1.2.)



Figure 10.9 Typical cavity walls for use in Example 4



Figure 10.10 Eccentricity of loading for Example 4

Stage 4: Determine Brick and Mortar Strengths Required

From Table 2(a) of BS 5628 (see Table 5.4) with f_k = 7.98 N/mm^2, use bricks with a compressive strength of 32 N/mm^2 set in a designation (iii) mortar.

Clearly this brick and mortar strength is not compatible with the internal 215 mm thick brick wall designed in Example 1, and the designer may wish to use the same higher strength brick type for all ground floor walls or consider blockwork instead of bricks.

Example 5

Repeat Example 4 using 215 mm thick brick inner leaf.

Stage 1: Calculate n_w

(a) Characteristic dead loads, G_k:

roof (as Example 4) = 10.00 kN/m
3 floors (as Example 4) = 37.50 kN/m
12 mm plaster (as Example 4) = 3.25 kN/m
own weight of wall = $0.215 \times 18 \times 12.9$ = 49.92 kN/m
Therefore $G_k = 100.67$ kN/m

(b) Characteristic superimposed loads, Q_k:

As Example 4, $Q_k = 26.25$ kN/m

Design load on wall: $n_w = (1.4 \times 100.67) + (1.6 \times 26.25)$
$= 182.94$ kN/m

Stage 2: Calculate Design Strength of Wall

(a) Determine β:

$$h_{ef} = 0.75 \times (4.5 - 0.15) = 3.2625 \text{ m}$$

$$\left.\begin{array}{l} t_{ef} = (2/3) \times (215 + 102.5) = 211.67 \text{ mm} \\ \text{or} = 215 \text{ mm} \end{array}\right\} \text{ use 215 mm for } t_{ef}$$

$$\text{SR} = \frac{h_{ef}}{t_{ef}} = \frac{3.2625 \times 10^3}{215} = 15.2$$

Eccentricity, $e_x = 0.167t$ (as Example 4).

From Table 7 of BS 5628 (see Table 5.15), with SR = 15.2 and $e_x = 0.167t$, $\beta = 0.696$.

(b) $\gamma_m = 2.5$ (see Example 4).

(c) Characteristic strength required, f_k:

$$f_k = \frac{n_w \gamma_m}{\beta t} = \frac{182.94 \times 2.5 \times 10^3}{0.696 \times 215 \times 1000} = 3.06 \text{ N/mm}^2$$

Stage 3: Determine Brick and Mortar Strength Required

From Table 2(a) of BS 5628 (see Table 5.4), use bricks with a compressive strength of 10 N/mm^2 set in a designation (iv) mortar.

10.5.2 Grouted Cavity Walls

Internal cavity walls, can be designed, sometimes more economically, by grouting the cavity as has been previously explained. The most common situation for this condition to exist is, perhaps, where a building plan area increases below say first-floor level as described in section 10.5.1. To maintain standard room sizes in hostel-type buildings, the cavity wall thickness is often extended through the ground floor storey, and consideration could be given in such a situation to the use of a grouted cavity wall.

Example 6

Design the internal fair-faced brick wall in the ground floor storey of the building shown in Figure 10.11 as a grouted cavity wall. The partial safety factor, γ_m, can be taken as 2.5 for the purpose of this example, the brickwork density is 18 kN/m^3 and the loadings are given in Table 10.1.

Stage 1: Calculate n_w

(a) Characteristic dead loads, G_k:

For this example, the exact position of each of the component dead loads will be considered in order to establish the eccentricity of the loading system on the wall under. The characteristic dead loads will therefore be subdivided thus:





Figure 10.11 Dimensions for Example 6

Table 10.1

	Main roof	Low roof	Floors
Characteristic dead loads (kN/m²)	4.8	6.0	6.0
Characteristic superimposed loads (kN/m²)	1.5	3.0	4.0

$$G_{k1} = \text{ground floor wall} \quad 18 \times 0.255 \times 3.3 = 15.15$$

$$\text{and 1st to 3rd floor walls} \quad 18 \times 0.1025 \times 8.25 = \underline{30.44}$$

$$G_{k1}\ \text{total} = 45.59\ \text{kN/m}$$

$$G_{k2} = \text{low roof} = 6 \times \frac{4}{2} = 12.00\ \text{kN/m}$$

$$G_{k3} = \text{main roof} = 4.8 \times \frac{6}{2} = 14.40\ \text{kN/m}$$

$$3\ \text{floors} = 3 \times 6 \times \frac{6}{2} = \underline{54.00\ \text{kN/m}}$$

$$G_{k3}\ \text{total} = 68.40\ \text{kN/m}$$

$$\text{Total characteristic dead load} = G_{k1} + G_{k2} + G_{k3}$$
$$= 45.59 + 12.00 + 68.40$$
$$= 125.99\ \text{kN/m}$$

(b) Characteristic superimposed loads, Q_k:

As for the characteristic dead loads, the characteristic superimposed loads will be subdivided thus:

$$Q_{k1} = \text{low roof} = 3 \times \frac{4}{2} = 6.0\ \text{kN/m}$$

$$Q_{k2} = \text{main roof} = 1.5 \times \frac{6}{2} = 4.5\ \text{kN/m}$$

$$3\ \text{floors} = 4.0 \times \frac{6}{2} \times 3 = \underline{36.0\ \text{kN/m}}$$

$$Q_{k2}\ \text{total} = 40.5\ \text{kN/m}$$

$$\text{Total characteristic superimposed load} = Q_{k1} + Q_{k2}$$
$$= 6.0 + 40.5$$
$$= 46.5\ \text{kN/m}$$

Design load on wall:

$$n_w = (1.4 \times G_k) + (1.6 \times Q_k)$$
$$= (1.4 \times 125.99) + (1.6 \times 46.5)$$
$$= 250.79\ \text{kN/m}$$

Now consider the resultant position of the design load from the eccentricities of the various components:

Position of resultant design load, n_w, must take account of partial safety factors, γ_f, for loadings as shown below.

Position of resultant: Taking moments about left-hand face of wall as shown in Figure 10.12:

$$n_w e = (G_{k2} \times 1.4 \times 34.2) + (Q_{k1} \times 1.6 \times 34.2)$$
$$+ (G_{k1} \times 1.4 \times 127.5) + (G_{k3} \times 1.4 \times 220.8)$$
$$+ (Q_{k2} \times 1.6 \times 220.8)$$
$$= (574.56) + (328.32) + (8137.82)$$
$$+ (21\ 143.81) + (14\ 307.84)$$
$$= 44\ 492.35$$



Figure 10.12 Loading for eccentricity for Example 6



Figure 10.13 Eccentricity for Example 6

Therefore

$$e = \frac{44\ 492.35}{250.79} = 177.41\ \text{mm} \quad \text{(see Figure 10.13)}$$

$$e_x = 177.41 - 127.50 = 49.94\ \text{mm} = 0.196t$$

In practice, an experienced designer would tend to 'guesstimate' this eccentricity, rather than rely on such a theoretical analysis which is difficult to justify.

Stage 2: Estimate Wall Thickness

The wall thickness is assumed to be dictated by the external cavity wall over as 305 mm for planning requirements.

Stage 3: Calculate Design Strength of Wall

(a) Determine β:

The effective thickness of a grouted cavity wall, as defined in clause 29.6 of BS 5628, can be taken as the actual overall

thickness. Careful supervision of the grouting is essential to ensure compliance with this definition.

$$\text{SR} = \frac{h_{\text{ef}}}{t_{\text{ef}}} = \frac{0.75 \times 3.3 \times 10^3}{305} = 8.11$$

e_x, as calculated previously, = 0.196t.

From Table 7 of BS 5628 (see Table 5.15), by interpolation: $\beta = 0.67$.

(b) γ_m as quoted for this example = 2.5.

(c) Characteristic strength required for wall, f_k:

$$f_k = \frac{n_w \gamma_m}{\beta t} = \frac{250.79 \times 2.5 \times 10^3}{0.67 \times 305 \times 1000} = 3.07 \text{ N/mm}^2$$

Stage 4: Determine Brick and Mortar Strengths Required

From Table 2(a) of BS 5628 (see Table 5.4), use bricks with a compressive strength of 10 N/mm^2 set in a designation (iv) mortar together with concrete grout to give a 28 day cube strength of 10 N/mm^2 and wall ties in accordance with BS 5628.

10.5.3 Double-leaf (or Collar-jointed) Walls

The most common use of double-leaf walls is likely to be found where a wall thicker than a half-brick wall is required for either functional or design purposes, but where the architect requires stretcher bond and fair-faced work on both wall faces. The design given in Example 1 would be exactly the same for the same total thickness of double-leaf wall, provided that the detail conditions as specified in clause 29.5 of BS 5628 are satisfied.

10.6 Design of Walls with Stiffening Piers

The possibility of a half-brick wall buckling under axial loads can be significantly reduced by the introduction of piers placed at regular, specified centres and fully bonded into the wall itself. The use of stiffening piers to increase the second moment of area of a wall section is, of course, not limited to half-brick walls and can be applied to any solid wall thickness as well as to cavity walls. It is considered, however, that if a 215 mm thick brick wall does not have an adequate slenderness ratio to withstand a particular loading condition, the design calls for the selection of a geometric shape best suited to provide the necessary second moment of area. The most common occurrence of this situation would occur in an extremely high wall which is required to support heavy axial loading. The design philosophy for such an element would be based upon second moment of area and radius of gyration, rather than slenderness ratio as traditionally calculated from effective thickness, and a diaphragm or fin wall profile is generally the most suitable geometric form. The design philosophy will be dealt with in more detail later in section 10.8.

Example 7

Design the internal wall given for Example 1 as a half-brick wall adequately stiffened by the introduction of brick piers.

The design for Example 1 resulted in a 215 mm thick brick wall of extremely low strength merely to provide for the maximum permissible slenderness ratio. The best use is not being made of brickwork's natural compressive strength in this design and the pier-stiffened half-brick wall is an obvious alternative choice, as will be shown in this example.

Stage 1: Calculate n_w

The design load will be taken as the same as for Example 1:

$$n_w = 271.5 \text{ kN/m}$$

Stage 2: Estimate Wall/Pier Configuration

There are no simple and realistic guidelines that can be applied to the selection of the size and spacing of stiffening piers. The trial and error approach related to the objective of achieving a reasonable slenderness ratio will eventually lead to the designer becoming more familiar with the benefits gained from the introduction of stiffening piers. For this example, we will select a wall/pier profile as shown in Figure 10.14 and check its suitability.

Stage 3: Calculate Design Strength of Wall

(a) Determine β:

Effective thickness is improved by the introduction of the stiffening piers and is the product of the actual thickness of the wall (102.5 mm) and the stiffening coefficient K obtained from BS 5628, Table 5 (see Table 5.12):

Stiffened wall properties:

$$\frac{\text{pier spacing}}{\text{pier width}} = \frac{2.500}{0.327} = 7.64$$

$$\frac{\text{pier thickness, } t_p}{\text{wall thickness, } t} = \frac{215}{102.5} = 2.1$$



Figure 10.14 Dimensions for Example 7



Figure 10.15 Dimensions for Example 8

By interpolation from BS 5628, Table 5, $K = 1.36$.

$$\text{Effective thickness, } t_{ef} = K \times t = 1.36 \times 102.5 = 139.4 \text{ mm}$$

$$\text{Slenderness ratio, SR} = \frac{h_{ef}}{t_{ef}} = \frac{0.75 \times (4.5 - 0.15) \times 10^3}{139.4} = 23.4$$

As for Example 1, $e_x = 0$. Thus from BS 5628, Table 7 (see Table 5.15) $\beta = 0.557$.

(b) Partial safety factor, $\gamma_m = 2.5$, as Example 1.

(c) Calculate characteristic strength, f_k required:

As well as stiffening the wall, the piers are quite capable of supporting some of the axial load and the loadbearing area of the piers should be added to that of the wall in determining the required characteristic strength. The equivalent thickness of solid wall per metre length with allowance for the pier area for this example is calculated as follows:

$$\frac{\text{wall area + pier area}}{\text{length}} = \frac{(102.5 \times 2500) + (112.5 \times 327)}{2500}$$

i.e. equivalent solid thickness = 117.22 mm

$$f_k = \frac{n_w \gamma_m}{\beta \times t \times 1.15} = \frac{271.5 \times 2.5 \times 10^3}{0.557 \times 117.22 \times 1000 \times 1.15} = 9.04 \text{ N/mm}^2$$

Stage 4: Select Brick and Mortar Strength Required

From Table 2(a) of BS 5628 (see Table 5.4), by interpolation, use a brick of compressive strength 33 N/mm^2 set in a designation (ii) mortar. The strength requirements for this wall should be compared for compatibility with the external cavity wall designed in Example 4.

Example 8

Now reconsider the external ungrouted cavity wall designed in Example 4 to investigate the effect of stiffening the inner leaf with piers.

Stage 1

The design load on the wall will be taken as 146.37 kN/m, as for Example 4.

Stage 2

The same configuration of stiffening piers as was used for Example 7 will be considered. The wall profile to be designed is therefore shown in Figure 10.15.

Stage 3: Design Strength of Wall

(a) Determine β:

From BS 5628, clause 28.4.2, Figure 2, the effective thickness of a pier-stiffened cavity wall is given as the greatest of:

(a) $(2/3) \times (102.5 + 102.5K)$, where K is the stiffening coefficient for the internal leaf,
(b) 102.5
(c) $K \times 102.5$.

The stiffening coefficient K for the internal leaf of the cavity wall is calculated in exactly the same manner as in Example 7 and, as the selected pier spacing and configuration are identical, $K = 1.36$.

$$\text{Effective thickness, } t_{ef} = (2/3) \times (102.5 + 1.36 \times 102.5) = 161.27 \text{ mm}$$

$$\text{Slenderness ratio, SR} = \frac{h_{ef}}{t_{ef}} = \frac{0.75 \times (4.5 - 0.15) \times 10^3}{161.27} = 20.2$$

As for Example 4, $e_x = 0.167t$.

By interpolation from BS 5628, Table 7 (see Table 5.15) $\beta = 0.553$.

(b) Partial safety factor for materials, γ_m, will be taken as 2.5, as was used for Example 4.

(c) Characteristic strength required:

$$f_k = \frac{n_w \gamma_m}{\beta \times t \times 1.15}$$

The equivalent thickness of the inner leaf, which is supporting the load, is increased to allow for the piers, in the same way as in Example 7:

Equivalent thickness = 117.22 mm (as Example 7).

Therefore

$$f_k = \frac{146.37 \times 2.5 \times 10^3}{0.553 \times 117.22 \times 1000 \times 1.15} = 4.91 \text{ N/mm}^2$$

Stage 4: From BS 5628, Table 2(a) (see Table 5.4)

Use a brick of compressive strength 15.0 N/mm^2 set in a designation (iii) mortar.

10.7 Masonry Columns

The two most common forms of columns generally encountered in design are: (a) the simple rectangular column for the full storey height of a building, and (b) the columns formed by adjacent window or door openings in walls. Other more complex forms are often encountered where an architectural feature is required and these are discussed later in this chapter.

Example 9: Simple Solid Brick Columns

It is proposed that the ground floor storey to the building designed in Example 1 should be made 'open plan' by replacing the central spine wall with a series of brick columns placed at 3.0 m c/c supporting reinforced concrete beams which carry the floors and walls over. Although not considered here, the designer will need to consider the robustness of the brick column which can be vulnerable to accidental damage. This should be considered even if the requirement falls outside of Part A of The Building Regulation rules on disproportionate collapse (see Chapter 8).

Stage 1: Calculate Design Load on Columns

The design load per metre length of the wall calculated in Example 1 was 271.5 kN/m, therefore, the design load per column spaced at 3.0 m centres = $3 \times 271.5 = 814.5$ kN. (Note that this is a conservative appraisal of the load. A more accurate assessment can be made by omitting the weight of the ground floor wall and including the weight of the reinforced concrete beam and pier.)

Stage 2: Estimate Column Size

The lateral restraint is afforded by the rc first floor slab and beams and, therefore, a square column section is the most suitable profile to provide an equal slenderness ratio to both axes.

The considerable loading will require such a large column section, simply in consideration of the load, that this is likely to provide adequate stability against the tendency to buckle. This aspect will, therefore, have little effect on the column size selection. A simple load/area calculation shows that a 327 mm square brick column will require an extremely high strength brick and mortar combination. It is therefore decided to use a larger column size of lower unit strength, and a 440 mm square solid brick column is selected for trial purposes.

Stage 3: Design Strength Required

(a) Determine β:

$$\text{Slenderness ratio, SR} = \frac{h_{ef}}{t_{ef}}$$



Figure 10.16 Effective height for masonry columns

The effective height for columns should be taken as the clear distance between lateral supports and is shown in Figure 10.16 as:

clear distance between lateral supports = 4.5 – 0.5 = 4.0
i.e. effective height, h_{ef} = 4.0 m
effective thickness, t_{ef} = actual thickness = 440 mm

$$\text{SR} = \frac{h_{ef}}{t_{ef}} = \frac{4.0 \times 10^3}{440} = 9.1$$

The eccentricity of loading on the column can again be taken as 0 to 0.05t. Therefore, from BS 5628, Table 7 (see Table 5.15) for SR = 9.1 and $e_x = 0$, β = 0.983.

(b) The partial safety factor for materials, γ_m, will again be taken as 2.5, as for Example 1.

(c) Calculate characteristic strength required, f_k:

Columns are often subject to clause 23.1.1 of BS 5628 in which the loaded area of the element is considered. The area reduction factor which takes account of the possibility of a below-strength unit (brick or block) being included in a small plan area, the single unit therefore representing a significant proportion of the loadbearing element, is applicable where the horizontal loaded cross-sectional area is less than 0.2 m^2. For example, the column has a cross-sectional area of 0.44 × 0.44 = 0.194 m^2, the area reduction factor is therefore applicable and is calculated as:

$$0.7 + (1.5 \times A) = 0.7 + (1.5 \times 0.194) = 0.991$$

Therefore

$$f_k = \frac{814 \times 2.5 \times 10^3}{0.985 \times 0.991 \times 440 \times 440}$$

$$= 10.77 \text{ N/mm}^2$$

Stage 4: By Interpolation from BS 5628, Table 2(a) (see Table 5.4)

Use bricks with a compressive strength of 42 N/mm^2 set in a designation (ii) mortar for 440 mm square solid brick columns at 3.0 m c/c.

Example 10: Columns Formed by Adjacent Openings

Adjacent door and window openings invariably leave a column of brickwork which is required to support increased load intensity resulting from the lintel loads, in addition to the basic load in that length of wall.



Figure 10.17 Dimensions for Example 10

The external cavity wall considered in Example 4 is to be punctured with windows measuring 1200 wide and 1800 high placed at 1640 centres. A typical elevation of the wall is shown in Figure 10.17. Wind loading will be ignored for this example but will be considered in Chapter 11.

Stage 1: Calculate Design Load, n_w

(a) Characteristic dead loads, G_k:

From Example 4, $G_k = 74.55$ kN/m

Characteristic dead load on column, $G_k = 74.55 \times 1.64$
$= 122.26$ kN

(b) Characteristic superimposed load, Q_k:

From Example 4, $Q_k = 26.25$ kN/m

Characteristic super load on column, $Q_k = 26.25 \times 1.64$
$= 43.05$ kN

Design load on column, $n_w = (1.4 \times G_k) + (1.6 \times Q_k)$
$= (1.4 \times 122.26) + (1.6 \times 43.05)$
$= 240.0$ kN

Stage 2: Estimate Column Thickness

Based upon a maximum slenderness ratio of 27 and an effective height of 4.350 (being the clear height between supports):

$$\text{minimum } t_{ef} = \frac{4.350}{27} = 161 \text{ mm}$$

It is clear that thickenings are required between the windows and a 215 mm thick inner leaf will be adopted.

Stage 3: Calculate Design Strength of Column

By inspection of the elevation in Figure 10.17, it is clear that the column's weakest axis is that tending to buckle perpendicular to the elevation. The column axis parallel to the elevation will therefore not require calculation.

(a) Determine β from slenderness ratio:

h_{ef} = clear height between supports = 4.350 m

$t_{ef} = 215$ or $(2/3) \times (215 + 102.5)$
$\therefore t_{ef} = 215$ mm

$$\text{Slenderness ratio, SR} = \frac{4350}{215} = 20$$



Figure 10.18 Bearing details for window lintel in Example 10

Eccentricity of loading:

Figure 10.18 shows the bearing detail of the window lintel.

Therefore, from Table 7, BS 5628 (see Table 5.15), with SR = 20 and $e_x = 0.186t$, by interpolation $\beta = 0.5282$.

(b) Partial safety factor, $\gamma_m = 2.5$ (as Example 4).

(c) Area reduction factor:

$$\text{Area reduction factor} = 0.7 + (1.5 \times A)$$
$$= 0.7 + (1.5 \times 0.215 \times 0.44) = 0.842$$

(d) Characteristic strength required, f_k:

$$f_k = \frac{240 \times 2.5 \times 10^3}{0.528 \times 0.842 \times 0.215 \times 0.440 \times 10^6}$$

$$= 14.3 \text{ N/mm}^2$$

Stage 4: From BS 5628, Table 2(a) (see Table 5.4)

Use bricks with a compressive strength of 47 N/mm^2 set in a designation (i) mortar. Clearly, this extremely high strength brick and mortar is the result of the heavy loading on the wall and the large window to wall proportions, and the client could be advised to accept smaller windows or thicker columns between the windows.

Example 11: Feature Columns

Example 9 will be reconsidered, to add interest, by making the columns cruciform-shaped as shown in Figure 10.19.



Figure 10.19 Dimensions for Example 11

Column properties:

Area, $A = 0.2311\ \text{m}^2$

$I_{xx} = I_{yy} = 0.005\,17\ \text{m}^4$

Radii of gyration
$r_{xx} = r_{yy} = 0.1496\ \text{m}$
$I_{vv} = I_{uu} = 0.006\,13\ \text{m}^4$

Radii of gyration
$r_{vv} = r_{uu} = 0.1629\ \text{m}$

therefore r_{xx} is critical.

Stage 3: Design Strength Required

(a) Determine β from slenderness ratio:

$$\text{Slenderness ratio, SR} = \frac{h_{ef}}{t_{ef}}$$

$h_{ef} = 4.0\ \text{m}$

t_{ef} = calculate equivalent solid column to give equal radius of gyration.

$$\text{Radius of gyration} = \sqrt{(I/A)} = 0.1496\ \text{m}$$

$$0.1496 = \sqrt{\left(\frac{bt^3/12}{bt}\right)} = \sqrt{\left(\frac{t^2}{12}\right)}$$

$$t = \sqrt{(12 \times 0.1496^2)} = 0.518\ \text{m}$$

$$\text{Slenderness ratio, SR} = \frac{4.0}{0.518}$$

$$= 7.72$$

Local stability of the cruciform column must also be checked by considering the possibility of buckling in the outstanding legs of the profile (see Figure 10.20), thus:

$$\text{Slenderness ratio, SR} = \frac{\text{effective length}}{\text{effective thickness}} = \frac{2 \times 215}{215} = 2$$

The outstanding leg is considered to be a cantilever and hence the effective length is determined using a factor of 2.

Therefore, the previously calculated slenderness ratio value of 7.72 will be used in the determination of β. Eccentricity of loading will be taken as for the previous example i.e. 0 to 0.05*t*. This can be assumed, for this example, as the rigid floor slab applies the load concentrically into the column. For other loading arrangements the eccentricity should be carefully analysed.

Therefore, from BS 5628, Table 7 (see Table 5.15), for SR = 7.72 and $e_x = 0$ to $0.05t$, $\beta = 1.0$.

(b) Partial safety factor, γ_m, will again be taken as 2.5.

(c) Area reduction factor is not applicable as area of column exceeds $0.2\ \text{m}^2$.

(d) Characteristic strength required, f_k:

$$f_k = \frac{814.50 \times 2.5 \times 10^3}{0.2311 \times 1.0 \times 10^6}$$

$$= 8.81\ \text{N/mm}^2$$

Stage 4: By Interpolation from BS 5628, Table 2(a) (see Table 5.4)

Use bricks with a compressive strength of $32\ \text{N/mm}^2$ set in a designation (ii) mortar.



Figure 10.20 Local stability for cruciform section for Example 11

10.8 Diaphragm Walls

The diaphragm wall is mostly used in tall single-storey buildings where its function is primarily to provide stability against wind loading. It can replace the steel or concrete structural frame which may otherwise be required for this purpose. This aspect of the diaphragm wall, and other geometric profiles, are covered in Chapter 13. However, diaphragm walls can be successfully and economically used to support heavy axial loading, particularly where the load has to be supported at a considerable height. The geometry of the diaphragm profile provides increased resistance to buckling owing to its *I* value and, therefore, the capacity reduction factor β does not reduce the characteristic compressive strength by as much as would be applicable to an equivalent solid wall.

Example 12: Design of Diaphragm Wall under Axial Loading

An overhead loading platform is shown in Figure 10.21. The superimposed loading on the rc slab is $100\ \text{kN/m}^2$.



Figure 10.21 Dimensions for Example 12



Figure 10.22 Diaphragm wall profile



Figure 10.23 Bearing detail – diaphragm wall

Stage 1: Calculate Design Load

(a) Characteristic dead load, G_k, per metre length:

rc slab $= 24 \times 0.4 \times 2.44 = 23.33$ kN
spreader beams $= 24 \times 0.225 \times 0.44 = 2.38$ kN
own weight of wall $= 0.2366 \times 20 \times 7.275 = 34.425$ kN
$= 60.135$ kN

(b) Characteristic superimposed load, Q_k:

$$\text{on rc slab } Q_k = 100 \times 2.44 = 244$$

$$\text{Design load on wall } n_w = (1.4 \times G_k) + (1.6 \times Q_k)$$
$$= (1.4 \times 60.135) + (1.6 \times 244)$$
$$= 474.59 \text{ kN/m}$$

Stage 2: Estimate Wall Thickness

Unlike solid walls, the cost of diaphragm walls does not increase significantly as the thickness increases. The two half-brick leaves are merely spaced further apart to increase the overall thickness of the wall and are connected together with cross-ribs. The materials required to achieve this increased thickness are an extremely small proportion of the total. Clearly, the further apart the two leaves are, the better the resistance to overall buckling and with only a minor increase in cost. Space restrictions are likely to play a more significant part in assessing the wall thickness but for this example a 440 mm thick wall will be considered (see Figure 10.22).

Stage 3: Calculate Design Strength of Wall

Wall properties per metre in length:

Area, $A = 236.586 \times 10^3$ mm^2

Moment of inertia, $I = 4862.35 \times 10^6$ mm^4

Radius of gyration, $r = 143.36$ mm

Equivalent solid wall:

from $r = \sqrt{(I/A)}$, as Example 11, $t = 496.61$ mm = equivalent solid thickness.

It is considered that, until a SR based on radius of gyration is introduced into BS 5628, the equivalent solid thickness of the diaphragm wall should not exceed the actual overall thickness. Hence $t = 440$ mm.

(a) Determine β:

To eliminate eccentricity of load in the wall from the slab, the bearing detail shown in Figure 10.23 will be used. Local stability of the leaves and ribs should be checked. However, with this relatively stocky section, this will not be critical.

The capacity reduction factor, β, will therefore be based on the overall section.

The continuity reinforcement tied into the rc spreader beam can be considered to provide an enhanced support condition and the effective height, h_{ef}, will be taken as $0.75 \times 7.5 = 5.625$ m.

Effective thickness of equivalent solid wall = actual thickness

i.e. $t_{ef} = 440$

Therefore $\text{SR} = \dfrac{5625}{440} = 12.8$

Eccentricity of load = 0, therefore, from BS 5628, Table 7, $\beta = 0.914$ (see Table 5.15).

(b) Partial safety factor $\gamma_m = 2.5$, as before.

(c) Characteristic strength required, f_k:

$$f_k = \frac{n_w \gamma_m}{\beta \times \text{area}}$$
$$= \frac{474.59 \times 2.5 \times 10^3}{0.914 \times 236.586 \times 10^3}$$
$$= 5.49 \text{ N/mm}^2$$

Stage 4: By Interpolation from BS 5628, Table 2(a) (see Table 5.4)

Use bricks with a compressive strength of 22.4 N/mm^2 set in a designation (iv) mortar.

Example 13: Comparison with Solid Walls

The diaphragm wall design in Example 12 will, for purposes of comparison, now be designed as a solid wall.

Stage 1

Design load on wall as Example 12, $n_w = 474.59$ kN/m.

Stage 2

For comparison purposes a 215 mm thick solid wall will be designed, as this has virtually the same quantity of materials as the diaphragm wall. A 327 mm thick wall would obviously be better suited to minimise the buckling tendency, but requires considerably more material.



Figure 10.24 Bearing detail – solid wall



Figure 10.25 Dimensions for Example 14

Stage 3: Calculate Design Strength of Wall

(a) Determine β:

$$\text{Slenderness ratio} = \frac{0.75 \times 7.5 \times 10^3}{215} = 26$$

Eccentricity of load = 0.167*t*, therefore, by interpolation from BS 5628, Table 7, β = 0.333 (see Table 5.14 and Figure 10.24).

(b) Partial safety factor, $\gamma_m = 2.5$.

(c) Characteristic strength required, f_k:

$$f_k = \frac{n_w \gamma_m}{\beta t}$$

$$= \frac{474.59 \times 2.5 \times 10^3}{0.333 \times 215 \times 10^3}$$

$$= 16.57 \text{ N/mm}^2$$

Stage 4: From BS 5628, Table 2(a) (see Table 5.4)

Use bricks with a compressive strength of 57.14 N/mm^2 set in a designation (i) mortar.

The difference in the strength requirements for virtually the same quantity of materials shows the value of the diaphragm wall for such an application. The additional workmanship must, of course, be set against the material saving for the diaphragm wall in order to relate the comparative economics of the two solutions. In both solutions it has been assumed that the stability of the platform is provided by other elements not considered in this design.

10.9 Concentrated Loads

Concentrated loads, such as occur at beam bearings and the like, are analysed using increased characteristic compressive strengths, f_k, from those shown in Table 2(a) of BS 5628 (see Table 5.4). The amount by which f_k is allowed to increase is governed by the type of bearing, and three bearing types are illustrated in BS 5628, Figure 4, for guidance. Two main considerations dictate the bearing type stress increase, being:

(a) The location of the concentrated load relative to the end of the wall in which the load's capacity to disperse in both directions is considered.

(b) The length of bearing of the beam onto the wall in which the possibility of spalling due to insufficient bearing length is considered. The eccentricity of load produced in this bearing type should be considered separately in the assessment of the capacity reduction factor β for the wall as a whole.

Example 14: Design of a Wall with Beam Bearing

Consider Example 9 and investigate the effect of the rc beam bearing onto the external gable wall. The beam bearing detail is shown in Figure 10.25 and the loadings, etc., are to be taken as for Example 1.

Stage 1: Calculate Design Loads on Wall

UDL_1 (characteristic dead load G_k from inner leaf only not influenced by load from beam reaction).

Half-brick wall = $0.1025 \times 18 \times 8.4$ = 15.50 kN/m
Design load = $1.4 \times G_k = 1.4 \times 15.5$ = 21.70 kN/m

Point load *W*:

From Example 1, the design load per metre length of the spine wall = 271.5 kN/m. The first brick column is spaced 3.0 m away from the gable wall and, therefore, the beam reaction at the bearing onto the gable wall

$$= 271.50 \times \frac{3.0}{2}$$

$$= 407.25 \text{ kN}$$

Stage 2

The wall thickness will be assumed to be already established as a 300 mm thick cavity comprising two half-brick leaves with a 100 mm cavity.

Stage 3: Design Strength Required

Consideration of beam bearings requires two design checks:

(a) The local effect immediately beneath the bearing area.
(b) The overall effect on the wall taking account of whatever other loads are already in the wall.

The recommended procedure is to design the latter condition initially to establish the minimum brick and mortar strengths required, and then to proceed to check the local



Figure 10.26 Spreading effect of bearing for Example 14

condition, including a concrete spreader or padstone beneath the beam bearing if found necessary. The introduction of such a spreader is likely to be more economical than increasing the brick and mortar strength of the whole wall. Figure 10.26 shows the spread effect of the bearing load.

UDL_1 from wall over:

UDL_2 is spread of load at 45° through brickwork and is additive to UDL_1 at $0.4h$ for slenderness considerations.

Design load at $0.4h$ level: UDL_1 (as calculated) = 21.70

However it is necessary to add the depth of wall below the bearing, i.e. $(0.5 + 1.6) \times 1.4 \times 0.102.5 \times 18 = 5.42$ kN/m

UDL_1 revised to $21.70 + 5.42 = 27.12$ kN/m

$$UDL_2 = \frac{407.25}{3.64} = 111.88 \text{ kN/m}$$

Total design load $= 143.48$ kN/m

(a) Determine β:

$$\text{Slenderness ratio, SR} = \frac{h_{ef}}{t_{ef}}$$

$$= \frac{0.75 \times 4.35 \times 10^3}{(2/3) \times (102.5 + 102.5)}$$

$$= 23.87$$

Eccentricity of load: The load from the wall over (UDL_1) can be taken as applied on the centre line of the inner leaf in the lower storey. The beam will be assumed to be sensibly rigid with minimum rotation at the bearing. The application of this load will therefore also be on the centre line of the inner leaf, $e_x = 0$.

Therefore, from BS 5628, Table 7, β = 0.536 (see Table 5.15).

(b) Partial safety factor $\gamma_m = 2.5$, as before.

(c) Calculate characteristic strength required, f_k:

$$f_k = \frac{n_w \gamma_m}{\beta \times t \times 1.15}$$

$$= \frac{139 \times 2.5 \times 10^3}{0.536 \times 102.5 \times 1.15 \times 10^3}$$

$$= 5.5 \text{ N/mm}^2$$

Stage 4: By Interpolation Select Brick/Mortar Strengths for Wall from BS 5628, Table 2(a) (see Table 5.4)

Use bricks with a compressive strength of 20 N/mm^2 set in a designation (iii) mortar.

Now design the beam bearing using the strength of brick and mortar, introducing a spreader, if required, beneath the beam. The calculation will therefore assess the minimum width of bearing area required. The beam or spreader will take full bearing onto the wall width and is a considerable distance from the ends of the wall. By inspection, the detail can be classed as a bearing type 2 from BS 5628, Figure 4 (see Figure 5.48). The local design strength can be taken as:

$$\frac{1.5 f_k}{\gamma_m} \quad \text{and is equal to} \quad \frac{W}{bx}$$

where

W = bearing load + (UDL_1 × width of beam at bearing)
b = width of bearing area
x = thickness of bearing area.

Therefore

$$b = \frac{W \gamma_m}{1.5 f_k x}$$

$$= \frac{(407.25 + (21.7 \times 0.3)) \times 2.5}{1.5 \times 5.8 \times 102.5}$$

$$= 1.16 \text{ m}$$

This is greater than $4t = 0.410$ m given in BS 5628, Figure 4, for bearing type 2 and is therefore not acceptable (see Figure 5.48).

The simplest solution is to introduce a brick pier for the bearing width required. Hence, try a 215 mm thick × 750 mm long pier. The introduction of the pier will obviously strengthen the wall, so far as the initial part of the design is concerned, however, the same brick and mortar strength will be checked (see Figure 10.27):

$$\text{Width of bearing, } b = \frac{(407.25 + (21.7 \times 0.3)) \times 2.5 \times 10^3}{1.5 \times 5.8 \times 215}$$

Area required, $A = 553$ mm $\quad (4 \times 0.215 = 0.86 > 0.553$ m)

Use 215 × 750 long brick pier with 215 × 750 × 225 deep concrete padstone beneath the beam bearing.



Figure 10.27 Pier dimensions for Example 14

11 Design of Masonry Elements (2): Combined Bending and Axial Loading

Chapter 10 related the basis of design, set out in Chapter 5, to specific problems of axially loaded masonry elements. This chapter will progress to the more common design conditions of combined bending and axial loading. The bending moments (BM) applied to these elements could be the result of lateral loading or eccentric loads, or a combination of both, and Chapter 10 has already introduced bending in the form of eccentric vertical loads. The recommendations of BS 5628, Part 1 are applied in the following examples to specific design problems of element design, and the guidance given in Chapter 6 will be followed.

11.1 Method of Design

The design method is based upon trial and error. Again, experience and familiarity will help the accuracy of initial estimates.

Some important questions which must be considered at the early stages are:

(a) In which direction, related to the bed joints, is the bending occurring (see Figure 11.1)?
(b) Is it reasonable for the particular design being considered to allow flexural tensile stresses to develop (see Figure 11.2)?
(c) Is the ratio of bending moment to axial load, i.e. M/W, high or low (where M = bending moment and W = axial load) (see Figure 11.3)?
(d) Is a cracked section likely (see Figure 11.8), and is a cracked section permissible for the element being designed (see Figure 11.4)?
(e) Is the total wall section likely to act as a homogeneous mass, or is shear slip likely to occur within the section (see Figure 11.5)?
(f) What restraint is already provided to the element, and what additional restraint could economically be achieved (see Figure 11.6)?

For example, referring back to Chapter 6, it will be noted that the flexural tensile resistance when bending is applied normal to the perpendicular joints is greater than when bending is applied normal to the bed joints. In addition, it will be noted that most dpc membranes cannot be relied upon to resist tensile stresses, and that care is needed when



Figure 11.1 Failure planes of laterally loaded masonry wall panels



Figure 11.2 Examples of flexural tensile stress resistance



Figure 11.3 Examples of ratio of moment against vertical load



Figure 11.4 Brick silt pit



Figure 11.5 Shear slip in cavity walls



Figure 11.6 Restraints to wall panels



Figure 11.7 Increasing lateral bending moment capacity resistance of wall panels

deciding on whether or not to rely upon tensile resistance for a particular loading condition.

The ratio of bending moment to axial load, M/W, is also particularly important since, where the ratio is low, normal slender elements of solid or cavity construction would usually be suitable. However, when the bending moment to load ratio, M/W, is high, then the material can be used more economically by improving its lever arm using a diaphragm, T or other suitable section with a high Z/A ratio, i.e. section modulus over cross-sectional area (see Chapter 9). Alternatively, post-tensioned or reinforced masonry can be used where large bending moment to load ratios are to be resisted (see Figure 11.7).

Post-tensioning or reinforcement give additional resistance moment due to the greater resistance to tensile stresses afforded by these methods.

Where no flexural tensile stresses can be relied upon, the section can often be designed on the basis of a cracked section using the effective areas and section modulus of the uncracked portion of the masonry. This design could be carried out by checking the serviceability limit state under working load and ultimate limit state under ultimate load, or the design could be checked on working load only, using a suitable safety factor against overturning and flexural compressive failure (see Figure 11.8).

Care must be taken, however, when designing such walls since, in some elements, a cracked section could be undesirable from the point of view of serviceability limit state (see Figure 11.4). Before calculating the section properties of a section, it must be decided whether or not the section will behave as one mass when bending is applied. For example, consider a cavity wall with butterfly ties subjected



Figure 11.8 Consider section and stress block at working load assuming stress within elastic range



Figure 11.9 Inadequacy of wall ties in cavity walls

to bending. The wall when subjected to bending would tend to distort the ties (see Figure 11.9).

The two leaves deflect approximately equally being linked together by the wall ties but not fixed rigidly enough to prevent vertical shear slip from distorting the ties. The two leaves (1) and (2) shown in Figure 11.9, would tend to rotate about points O_1 and O_2 respectively. The section modulus of such a section would, therefore, be approximately equal to the sum of the separate section moduli of each leaf, and not the section modulus of the total section about its own neutral axis. This assumes that the transfer of load between the two leaves is achieved via compression of the ties. In fact, BS 5628 reduces the effective cross-section to even less (see Chapter 6).

Alternatively, a wall constructed with a similar quantity of bricks, but built in a bonded form such as a totally solid wall or a diaphragm wall, would have a much increased section modulus due to the shear resistance across the bonded joints connecting the two leaves (see Chapter 13). Consideration of the possible restraints which can be provided to the element can have a large effect on the capacity of the element to resist bending. For example, a long gable wall of a single-storey building, with no restraint at roof level and no connecting walls, would require to be designed as a cantilever; whereas, a similar gable with a suitable restraint at roof level could be designed as a propped and tied cantilever (see Figure 11.10).

The result of such a difference in restraint is to reduce the maximum bending moment in the wall, and to increase



Figure 11.11 Initial wall thickness for Example 1

the permissible flexural compressive stresses due to the improved effective height of the wall. In the following examples these points will be highlighted in the elements designed.

Example 1: Effects of Varying the Wall Section

This is an illustration of the effects of varying the wall sections to resist bending and axial load where the ratio M/W is large.

As previously stated, the choice of wall elements will depend very much on the ratio of bending moment to axial load M/W. For example, consider a condition where the axial load is from the own weight of the wall only and a large bending moment has to be resisted. Assume the own weight of the wall to be equal to W per 102 mm of thickness per metre length at a level being considered and calculate the resistance moments of various sections.

First consider a normal 305 mm cavity wall with 102 mm thick leaves (see Figure 11.11). The section being considered is at dpc level, and the dpc can be assumed to have zero resistance to tensile forces at right angles to the bed joint. Normal cavity ties also can be assumed to provide very little shear resistance between the leaves and, therefore, it can be assumed that no vertical shear is transferred across the cavity.

The wall's resistance to bending at this location is therefore provided by the weight of the wall acting at its lever arm



Figure 11.10 Behaviour of walls in single storey buildings restrained at the roof



Figure 11.12 Additional wall thickness for Example 1

about the point of rotation. The point of rotation would occur at the compression side of the section and, for the purposes of this example, it can be assumed to be approximately at the edge of each leaf, i.e. leaf (1) rotates about point O_1 and leaf (2) rotates about point O_2.

The wall's resistance to overturning based upon zero tensile resistance at the dpc level and zero shear resistance of the cavity ties would be:

$$(W \times 51) + (W \times 51) = \text{resistance moment}$$

i.e. $$\text{resistance moment} = 102W \text{ mm}$$

i.e. $$\text{allowable applied BM} = \frac{102W \text{ mm}}{\text{safety factor}}$$

Now consider a condition where this resistance moment is insufficient for the design bending moment, and assume that a 102 mm bonded thickness is added to the inner leaf (see Figure 11.12). Based upon the assumptions previously mentioned, the resistance to overturning of this section would be:

$$\text{resistance moment} = (2W \times 107.5) + (W \times 51)$$
$$= 266W \text{ mm}$$

giving

$$\text{allowable applied BM} = \frac{226W \text{ mm}}{\text{safety factor}}$$

This means that, by adding 50% more masonry to the wall, the resistance moment has increased 160%.

Consider now the various methods of increasing the wall's resistance moment. It can be achieved by:

(a) increasing the lever arm of the load,
(b) increasing the vertical load,
(c) increasing both the lever arm and the load,
(d) using a dpc capable of resisting tensile stresses.

The most economical solution, in terms of the amount of masonry, would be to increase the lever arm with little or no increase in the cross-sectional area of the wall. One method of achieving this is to open up the cavity of the wall, and to introduce cross-ribs which make the two leaves interact, i.e. using a diaphragm wall (see Figure 11.13).

Assume that a diaphragm, as shown in Figure 11.13, is to be used, that ribs are suitably spaced and bonded to transfer the shear forces across the cavity, and that the spacing is



Figure 11.13 Dimensions for Example 1



Figure 11.14 Diaphragm wall option for Example 1

Table 11.1

Section	A (m²)	Z ($\times 10^{-3}$ m³)	$\frac{Z}{A}$ ratio
Normal cavity	0.204	3.468	0.017
Thickened leaf cavity	0.317	9.438	0.030
Diaphragm	0.225	27.730	0.123

adequate to prevent buckling of the leaves, etc. The conditions shown in cross-section in Figure 11.14 are therefore, applicable, that is, assuming the own weight of each leaf of 102 mm thick is W per metre run and that 10% extra brickwork is added to the original cavity wall in the form of cross-ribs. The resistance moment to overturning of this section can be assumed to rotate about the point O_1 indicated in Figure 11.14, since the cross-ribs provide shear resistance. Assuming, as before, zero tensile resistance and the point of rotation at the edge of the wall (note these two assumptions would have to be verified in an actual element design):

$$\text{resistance moment} = 2.2W \times 219.5$$
$$= 482.9W \text{ mm}$$

$$\text{allowable applied BM} = \frac{482.9W \text{ mm}}{\text{safety factor}}$$

This means that, by adding 10% more masonry, the diaphragm solution achieves $100 \times 482.9/102 = 473\%$ of the resistance moment of the original wall. Other properties of these three walls are shown in Table 11.1 for comparison purposes.

Now consider the effect of post-tensioning, assuming that the compressive stresses in the diaphragms are less than the allowable, as is often the case since tensile stresses usually govern the resistance moment (see Figure 11.15).

Therefore, additional compressive force can be applied at the centre line of the wall (assuming bending critical in both directions) to give maximum lever arm for the design conditions.



Figure 11.15 Prestressed wall option for Example 1

Post-tensioned masonry elements are dealt with in Chapter 15. However, the advantage of adding a further load by precompressing the masonry using this method can be seen, since any increase in the load W increases the stability moment by the same proportion (for further details refer to Chapter 15).

In the preceding examples, gravitational weight and post-tensioning have been used in resisting bending and the advantages of varying the section have been indicated. In many cases, however, the wall section being considered in resisting bending moments will be located where the masonry will have some resistance to tensile stresses and therefore, instead of merely a gravitational condition existing, there will also be tensile stresses which can be developed. Here, the stress condition should be checked against the allowable, and since, in general, the development of critical tensile stresses will occur when the compressive stresses are well within the allowable, it is likely that elastic conditions will be applicable in the compressive zone.

The stress condition can, therefore, be checked on the basis of:

$$f = \frac{P}{A} \pm \frac{M}{Z}$$

where

M = applied bending moment
P = applied axial load
A = cross-sectional area
Z = section modulus.

From Table 3.1, Chapter 3, the advantage of increased section modulus for the diaphragm shape can be clearly seen along with the need for a high Z/A ratio for economic use of material in resisting large bending moments.

BS 5628 provides three alternative methods of calculating the design moment of resistance of walls subject to axial and lateral loading:

(a) treating the masonry section as an arch (clause 36.4.4),
(b) the 'effective eccentricity' method (clause 36.8),
(c) employing the formula $(f_{kx}/\gamma_m + g_d)Z$ (clause 36.5.3).

The authors consider the arch method as the most unreliable as it is often too dependent upon variable factors of workmanship, which are usually outside the control of the designer.

The eccentricity method is more applicable to instances of high axial load to bending moment ratio and is limited in its application of eccentricities of up to $0.3t$, which is the extent of Table 7 in BS 5628 for the calculation of β (see Table 5.15).

The use of the formula $(f_{kx}/\gamma_m + g_d)Z$ was previously limited to the design of free-standing walls. The 1992 version to BS 5628, Part 1 (amended August 2002) has, in clause 36.9, broadened its application to include the design of propped cantilever walls in single-storey buildings, and some comment on its application is made in section 6.10. The authors continue to believe that its application is equally appropriate in other circumstances as the design examples given on the following pages will demonstrate. In its presented form, the formula considers only flexural tensile stresses whereas loading conditions can arise in which flexural compressive stresses also require consideration, but for which no guidance is given in the Code. Hence, in some of the examples that follow, suggested methods of dealing with the attendant flexural compressive stresses are included.

The first problem which faces the designer is which formula/design method to apply to a particular problem. The answer to this can only come from the designer's own familiarity with the use and limitations of each method. Once again, there is no substitute for experience.

Example 2: Solid Brick Wall, 215 mm Thick

Design the solid brick retaining wall of the coal fuel store shown in Figure 11.16. It can be assumed that the cover slab is capable of acting as a tie to resist the reaction at this point from the wall. The fuel store is of such a length that horizontal spanning of the wall can be ignored.

The characteristic loadings to be used in the design will be taken as:

(i) cover slab
dead = 3.60 kN/m^2
superimposed = 2.50 kN/m^2

(ii) superstructure above cover slab
dead = 80.0 kN/m run of wall
superimposed = 25.0 kN/m run of wall.

For simplicity of analysis, it can be assumed that the fuel can be filled to the full height of the wall, and that the pressure at the base of the wall from the fuel, derived from Rankine's formula,

$$\text{density} \times h\left(\frac{1-\sin\theta}{1+\sin\theta}\right) = 10.5\ \text{kN/m}^2$$

The loading from the structure above can be assumed to be applied on the centre line of the thickness of the retaining wall.

The axial loading from the structure above the fuel store cover slab will enable the retaining wall to be designed as



Figure 11.16 Detail of fuel store



Figure 11.17 Loading diagram and bending moment diagram for Example 2

fixed both top and bottom and the loading and bending moment diagrams are shown in Figure 11.17.

Design pressure at base of wall = $\gamma_f \times 10.5 = 1.6 \times 10.5 = 16.8\ \text{kN/m}^2$

Design BM at top of wall $= \dfrac{wh^2}{15} = \dfrac{16.8 \times 2^2}{15 \times 2} = 2.24\ \text{kN m}$

Design BM at 0.55h from top $= \dfrac{wh^2}{23.3} = \dfrac{16.8 \times 2^2}{23.3 \times 2} = 1.44\ \text{kN m}$

Design BM at base of wall $= \dfrac{wh^2}{10} = \dfrac{16.8 \times 2^2}{10 \times 2} = 3.36\ \text{kN m}$

Characteristic vertical loads in retaining wall:

dead loads, G_k:

superstructure over (as given) $= 80.00\ \text{kN/m}$

cover slab $= 3.6 \times \dfrac{4}{2} = 7.20\ \text{kN/m}$

ow (own weight) brickwork $= 20 \times 0.215 \times 2 = 8.60\ \text{kN/m}$

$= 95.80\ \text{kN/m}$

superimposed loads Q_k:

superstructure over (as given) $= 25.0\text{kN/m}$

cover slab $= 2.5 \times \dfrac{4}{2} = 5.0\ \text{kN/m}$

$= 30.0\ \text{kN/m}$

Minimum design vertical load $= G_k \times \gamma_f = 95.8 \times 0.9$

$= 86.22\ \text{kN/m}$

Maximum design load $= (G_k \times \gamma_f) + (Q_k \times \gamma_f)$

$= (95.8 \times 1.4) + (30 \times 1.6)$

$= 182.12\ \text{kN/m}$

Due to high axial load to bending moment ratio, the wall will be designed using the effective eccentricity method which takes account of the flexural compressive stresses. The amount of axial load to bending moment will ensure that the full width of retaining wall is subject to compressive stresses and no tensile stresses will develop.

Calculate eccentricity due to slenderness of wall:

$$e = t\left[\frac{1}{2400} \times \left(\frac{h_{ef}}{t_{ef}}\right)^2 - 0.015\right]$$

$$= 215\left[\frac{1}{2400} \times \left(\frac{0.75 \times 2}{0.215}\right)^2 - 0.015\right] = 1.135\ \text{mm}$$

The slenderness eccentricity diagram is shown in Figure 11.18. This eccentricity diagram should be superimposed onto the eccentricity diagram resulting from the design bending moment diagram.

Calculate eccentricities from design BM diagram:

e at top of wall, max. $= \dfrac{M_A}{n_w} = \dfrac{2.24}{86.22} = 26\ \text{mm}$

e at 0.55h level, max. $= \dfrac{M_A}{n_w} = \dfrac{1.44}{86.22} = 16.7\ \text{mm}$



Figure 11.18 Slenderness eccentricity diagram

e at base of wall, max. $= \dfrac{M_A}{n_w} = \dfrac{3.36}{86.22} = 39$ mm

e at top of wall, min. $= \dfrac{M_A}{n_w} = \dfrac{2.24}{182.12} = 12.3$ mm

e at 0.55h level, min. $= \dfrac{M_A}{n_w} = \dfrac{1.44}{182.12} = 7.9$ mm

e at base of wall, min. $= \dfrac{M_A}{n_w} = \dfrac{3.36}{182.12} = 18.4$ mm

Eccentricity diagrams derived from BM diagram are shown in Figure 11.19.

Superimpose eccentricity diagrams as in Figure 11.20.

Now design the wall as an axially loaded wall combining the minimum axial load of 86.22 kN with the maximum eccentricity, for β calculation, of 0.181t and the maximum axial load of 182.12 kN with the minimum eccentricity, for β calculation, of 0.086t.

$$\text{Slenderness ratio for both loading conditions} = \frac{0.75 \times 2000}{215}$$

$$= 7$$

Consider minimum load/maximum eccentricity:

From BS 5628, Table 7, with SR = 7 and $e_x = 0.181t$, β = 0.7 (see Table 5.15).

Then, from $n_w = \dfrac{\beta t f_k}{\gamma_m}$,

required characteristic compressive strength of masonry, f_k:

$$f_k = \frac{\text{min. design load} \times \gamma_m}{\beta \times t \times 1 \text{ metre length}}$$

$$= \frac{86.22 \times 10^3 \times 2.5}{0.7 \times 215 \times 1000}$$

$$= 1.43 \text{ N/mm}^2$$



(a) maximum eccentricity from minimum design load



(b) minimum eccentricity from maximum design load

Figure 11.19 Eccentricity diagrams for Example 2



(a) maximum combined eccentricity diagram
maximum combined eccentricity
e = 39 mm = 0.181t



(b) minimum combined eccentricity diagram
minimum combined eccentricity
e = 18.4 mm = 0.086t

Figure 11.20 Combined eccentricity diagrams for Example 2



Figure 11.21 Typical section through boundary wall

Now consider maximum load/minimum eccentricity:

From BS 5628, Table 7, with SR = 7 and $e_x = 0.086t$, $\beta = 0.897$ (see Table 5.15).

Hence, required characteristic compressive strength of masonry, f_k:

$$f_k = \frac{\text{max. design load} \times \gamma_m}{\beta \times t \times 1 \text{ metre length}}$$

$$= \frac{182.12 \times 10^3 \times 2.5}{0.897 \times 215 \times 1000}$$

$$= 2.36 \text{ N/mm}^2$$

Select, from BS 5628, Table 2(a), for a required minimum characteristic strength, masonry constructed of bricks with a minimum crushing strength of 35 N/mm^2 set in a designation (i) mortar (see Table 5.4). Note that this specification provides a characteristic compressive strength far in excess of that designed. However, for the practical considerations of abrasion from the fuel and durability in use, the specification quoted is considered to be the minimum acceptable.

Example 3: Free-standing Walls

The free-standing boundary garden wall shown in Figure 11.21 is to be constructed in solid clay brickwork. The wall is of considerable length with straight movement joints placed at 10 m centres. Close quality control of materials and workmanship can be expected, and the client is particularly interested to know the effect of introducing a felt dpc at ground level. The characteristic wind loading on the wall, W_k, may be taken as 0.6 kN/m^2 for the purpose of this example and density of the masonry will be assumed to be 20 kN/m^3.

The critical loading condition for which the wall must be designed is not that of axial loading but rather that of lateral loading due to wind pressures. The wall will act as a vertical cantilever and the loading and bending moment diagrams are shown in Figure 11.22.

Design bending moment at base of wall:

$$\text{BM} = W_k \times \gamma_f \times \frac{h^2}{2}$$

where

W_k = characteristic wind load
γ_f = partial safety factor for loads
h = clear height of wall above horizontal support.

Therefore,

$$\text{BM} = \frac{0.6 \times 1.4 \times 2.5^2}{2}$$

$$= 2.625 \text{ kN m}$$

The resistance to this moment is provided by either:

(a) the tensile resistance of the wall at its base, or
(b) the gravitational stability of the wall where a felt dpc at ground level has eliminated its tensile resistance.

Case (a) will be considered first and the client's interest in the effect of introducing the felt dpc at ground level will be investigated afterwards.

Case (a): Wall capable of resisting tensile stresses at ground level (note, this can be achieved with certain engineering bricks coursed in at ground level as discussed in previous chapters). The loading condition for this example is that of low axial load to comparatively high bending moment. In this case, there is little doubt that the formula for the design moment of resistance should be:

$$\text{Design MR} = \left(\frac{f_{kx}}{\gamma_m} + g_d \right) Z$$



Figure 11.22 Loading diagram and bending moment diagram for Example 3

where

f_{kx} = characteristic flexural tensile strength at the critical section
γ_m = partial safety factor for materials
g_d = design vertical load per unit area (axial compressive stress)
Z = elastic section modulus of wall.

In this particular example, the flexural compressive stress is not critical and will not be checked. However, the inexperienced designer should check the compressive stresses in all such examples in order to establish when such checks need to be carried out (this will be dealt with in greater detail in a later example). Once again, the design process is one of trial and error and a section must be selected and checked for adequacy.

Try 330 mm thick solid wall (fully cross-bonded) constructed of bricks with a characteristic compressive strength of 35 N/mm^2 and a water absorption of greater than 12% set in a designation (iii) mortar.

Then, for these materials:

$f_{kx} = 0.30$ N/mm^2, from BS 5628, Table 3.

$\gamma_m = 2.5$ special BS 5628 Table 4b.

$$g_d = \frac{\gamma_f \times \text{density} \times \text{thickness} \times \text{height}}{\text{thickness}}$$

$$= \frac{0.9 \times 20 \times 0.33 \times 2.5}{0.33 \times 10^3} = 0.045 \text{ N/mm}^2$$

$$Z = \frac{bt^2}{6} = \frac{1000 \times 330^2}{6} = 18.15 \times 10^6 \text{ mm}^3$$

Therefore

$$\text{Design MR} = \left(\frac{f_{kx}}{\gamma_m} + g_d\right) Z$$

$$= \left(\frac{0.3}{2.5} + 0.045\right) \times 18.15 \times 10^6$$

$$= 2.995 \text{ kN m} > 2.625 \text{ kN m}$$

Hence, the wall section is adequate provided the flexural tensile resistance required at ground level can be relied upon.

Case (b): Check the effect of introducing a felt dpc at ground level – thus the wall should be designed as a gravity structure. The design bending moment remains unaltered.

Try 440 mm thick solid wall constructed of the same materials as for case (a). From design experience, it is known that a 330 mm thick solid wall is theoretically inadequate although, in practice, many such walls are constructed but can blow over in exceptionally high gales. The design moment of resistance of the wall is derived from the gravitational stability of its base and will be termed 'base stability moment'. The calculation of the 'base stability moment', MR_s, will be based upon the rectangular stress block shown in Figure 11.23, which is derived from BS 5628, Appendix B, where:



Figure 11.23 Stress block for base stability moment

BM = design bending moment
G_k = characteristic dead loading
γ_f = partial safety factor for loads
f_k = characteristic compressive strength of masonry
γ_m = partial safety factor for materials
l_a = lever arm
w_s = width of stressed area.

The essence of this design approach is that the minimum width of wall is fully stressed to create the maximum lever arm about which the dead weight of the wall rotates to achieve the maximum gravitational stability moment, MR_s, for the materials considered, hence:

$$MR_s = \gamma_f \times G_k \times l_a \text{ per m length of wall}$$
$$\gamma_f \times G_k = 0.9 \times 20 \times 0.44 \times 2.5$$
$$= 19.80 \text{ kN}$$

In order to calculate the lever arm, the minimum width of stressed area, w_s, must first be calculated. This is calculated from a simple stress equals load/area consideration, hence (see Figure 11.23):

$$\frac{1.1 f_k}{\gamma_m} = \frac{\gamma_f G_k}{w_s \times 1 \text{ m length of wall}}$$

Therefore

$$w_s = \frac{19.8 \times 10^3 \times 2.5}{1.1 \times 8.5 \times 1000}$$

$$= 5.3 \text{ mm}$$

Then

$$l_a = 220 - \frac{5.3}{2}$$

$$= 217.35 \text{ mm}$$

$$MR_s = \frac{19.8 \times 217.35}{10^3}$$

$$= 4.304 \text{ kN m} > 2.625 \text{ kN m}$$

Thus the specified 440 mm thick wall is adequate and it is likely that a lower strength of brick and/or mortar would be adequate if checked.



Figure 11.24 Behaviour of collar jointed walls

Example 4: Collar-jointed Walls

Another free-standing garden wall is to be designed, similar to that of the previous example, but reduced in height to 1.5 m. The client requires that both faces of the wall should be constructed in stretcher bond. The wall will be designed both with and without ties connecting the two stretcher bond leaves together to investigate the effect of their inclusion.

As for the previous example, the wall will act as a vertical cantilever and the design bending moment is

$$\text{BM} = W_k \times \gamma_f \times \frac{h^2}{2} = 0.6 \times 1.4 \times \frac{1.5^2}{2} = 0.945 \text{ kN m}$$

The Code definition of a collar-jointed wall is: 'two parallel single-leaf walls, with a space between not exceeding 25 mm, filled solidly with mortar and so tied together as to result in common action under load'. To ensure common action under load for a collar-jointed wall with lateral loading, the ties need to be designed to resist the shear force between the two leaves which is tending to cause 'slip' between these faces, as shown in Figure 11.24.

It will be assumed that the wall is capable of resisting flexural tensile stresses for its full height (i.e. no felt dpc) hence:

$f_{kx} = 0.3 \text{ N/mm}^2$ (BS 5628, Table 3).

$\gamma_m = 2.5$ special (BS 5628 Table 4b).

$$g_d = \frac{\gamma_f \times \text{density} \times \text{thickness} \times \text{height}}{\text{thickness}}$$

$$= \frac{0.9 \times 20 \times 0.215 \times 1.5}{0.215 \times 1 \times 10^3} = 0.027 \text{ N/mm}^2$$

$$Z = \text{section modulus} \left(\frac{bt^2}{6}\right) = \frac{215^2 \times 10^3}{6}$$

$$= 7.704 \times 10^6 \text{ mm}^3$$

Therefore

$$\text{Design MR} = \left(\frac{0.3}{2.5} + 0.027\right) \times 7.704 \times 10^6$$

$$= 1.132 \text{ kN m} > 0.945 \text{ kN m}$$

Thus the 215 mm thick wall specified is adequate provided adequate ties are included to ensure full interaction between the two leaves – which is what the design will now proceed to check.



Figure 11.25 Plan on metre length of wall

Figure 11.25 shows a plan on a metre length of the wall showing the neutral axis (N/A) coinciding with the slip face of the wall section.

Shear stress, for which the ties must be designed, occurs on the slip face between the two leaves which is the neutral axis of the full 215 mm thick section, and the means by which shear stress resistance is provided is discussed in section 6.10.1. Shear stress, v_h, is given by the equation:

$$v_h = \frac{VA\bar{y}}{Ib}$$

where

V = horizontal shear force at point of maximum rate of change in BM
A = area of shaded portion
$\bar{y}$ = distance from N/A to centroid of shaded area
I = moment of inertia of section
b = 1 metre length of wall
NA = neutral axis of full 215 mm thick wall section.

For this example:

$$V = W_k \times \gamma_f \times h = 0.6 \times 1.4 \times 1.5 = 1.26 \text{ kN}$$

$$A = 1000 \times 215 \times 0.5 = 107.5 \times 10^3 \text{ mm}^2$$

$$\bar{y} = \frac{215}{4} = 53.75 \text{ mm}$$

$$I = \frac{bt^3}{12} = \frac{1000 \times 215^3}{12} = 0.828 \times 10^9 \text{ mm}^4$$

Therefore, design shear stress:

$$v_h = \frac{VA\bar{y}}{Ib}$$

$$= \frac{1.26 \times 10^3 \times 107.5 \times 10^3 \times 53.75}{0.828 \times 10^9 \times 1000}$$

$$= 0.0088 \text{ N/mm}^2 = 8.8 \text{ kN/m}^2$$

This shear stress is to be resisted by flat metal shear ties of 3 mm × 20 mm cross-section built into the bed joints, and their vertical spacing is derived from the formula given in the Code and in section 6.10.1 as:

$$ru = \frac{12 t_w s v}{0.87 f_y}$$

where

r = width of connector
u = thickness of connector
t_w = width of masonry section in vertical shear
s = spacing of connectors
v = design vertical shear stress on masonry section
f_y = characteristic tensile strength of connector.

which can be rearranged as:

$$s = \frac{ruf_y}{13.8 t_w v}$$

hence

$$s = \frac{20 \times 3 \times 250}{13.8 \times 1000 \times 8.8 \times 10^{-3}}$$

$$= 124 \text{ mm vertical spacing of ties per m length}$$

Use 8 ties per square metre of wall area.

The authors are unaware of the derivation of this formula from the Code and are concerned that, at first sight, the properties of the metal tie appear to be the limiting factor in the design, whereas local crushing of the mortar into which the ties are bedded is likely to occur long before failure of the steel. It appears that this may be the purpose of the factor of 12 in the above equation, but the magnitude of this factor would depend upon whether the tie was laid flat (with the 20 mm width in bearing) or vertically (with the 3 mm width in bearing). In the absence of other information, the authors consider that the formula should be applied only in situations where the ties are bedded flat.

Now consider the same wall constructed in two stretcher bond leaves, but without any ties connecting them together. The design will, therefore, be based upon each leaf acting independently. The design BM remains as before as 0.945 kN m.

$$\text{Design MR} = 2 \text{ leaves} \times \left(\frac{f_{kx}}{\gamma_m} + g_d \right) Z$$

where

$$Z \text{ per leaf} = \left(\frac{bt^2}{6} \right) = \frac{1000 \times 102.5^2}{6} = 1.751 \times 10^6 \text{ mm}^3$$

Therefore

$$\text{Design MR} = 2 \left(\frac{0.3}{\gamma_m} + 0.027 \right) \times 1.751 \times 10^6$$

$$= 0.515 \text{ kN m} < 0.945 \text{ kN m}$$

This is less than the design bending moment of 0.945 kN m and the section will crack. The wall should now be checked as a cracked section using a rectangular stress block to calculate the stability moment of resistance, as demonstrated in an earlier example (see Figure 11.23).



Figure 11.26 Stress block per leaf for base stability moment

The stability moment stress block for this example is shown in Figure 11.26, in which the total design bending moment is shared equally between the two leaves, where:

$$\frac{M_A}{2} = \frac{0.945}{2} = 0.4725 \text{ kN m}$$

$$G_k \times \gamma_f = \text{density} \times \text{thickness} \times \text{height} \times \gamma_f$$
$$= 20 \times 0.1025 \times 1.5 \times 0.9$$
$$= 2.767 \text{ kN/m per leaf}$$

Thus, as demonstrated in an earlier example:

$$\frac{1.1 f_k}{\gamma_m} = \frac{G_k \times \gamma_f}{w_s \times 1 \text{ m length of wall}} \quad \left(\text{stress} = \frac{\text{load}}{\text{area}} \right)$$

Therefore

$$w_s = \frac{G_k \times \gamma_f \times \gamma_m}{1.1 f_k \times 1 \text{ m length of wall}}$$

$$= \frac{2.767 \times 10^3 \times 2.5}{1.1 \times 8.5 \times 1000} = 0.74 \text{ mm}$$

Then, lever arm:

$$l_a = \frac{\text{wall thickness}}{2} - \frac{w_s}{2}$$

$$= \frac{102.5}{2} - \frac{0.74}{2}$$

$$= 50.88 \text{ mm}$$

and stability moment:

$$\text{MR}_s = G_k \times \gamma_f \times l_a$$

$$= \frac{2.767 \times 50.88}{10^3}$$

$$= 0.141 \text{ kN m} < 0.4725 \text{ kN m}$$

The two leaves act simultaneously and the total stability moment is therefore twice that calculated above = 0.141 × 2 = 0.282 kN m. The method of construction is therefore unsuitable for the design condition, which demonstrates that it is good practice to include wall ties to make the masonry more structurally efficient.



Figure 11.27 Section through balustrade wall

Example 5: Solid Concrete Block Walls

A viewing gallery to a sports centre is to have a 200 mm thick balustrade wall constructed in solid concrete blockwork. The designer is required to check whether the wall is stable or whether any additional supports are required. A section through the wall is shown in Figure 11.27. It consists of 200 mm thick concrete blockwork constructed with blocks of 7.0 N/mm^2 crushing strength (no void solid blocks) set in designation (iii) mortar. The blocks in this case are assumed to be category 1 units to BS EN 771, Part 3 but with sufficient voids to keep the units to a weight less than 20 kg, for manhandling requirements. The voids are to be filled with concrete with a compressive strength exceeding that of the block.

Characteristic superimposed line load at top of wall, $Q_k = 0.74$ kN/m (BS 6399, Part 1)

$$\text{Design superimposed loading} = Q_k \times \gamma_f = 0.74 \times 1.6 = 1.184 \text{ kN/m}$$

Design bending moment = $1.184 \times 1 = 1.184$ kN m (based on cantilever action of wall)

$$\text{Characteristic dead loading, } G_k = \text{density} \times \text{height} \times \text{area} = 15 \times 1 \times 0.2 = 3.0 \text{ kN/m}$$

$$\text{Minimum design dead loading} = G_k \times \gamma_f = 3.0 \times 0.9 = 2.7 \text{ kN/m}$$

$$\text{Design moment of resistance} = \left(\frac{f_{kx}}{\gamma_m} + g_d\right) Z$$

where

$f_{kx} = 0.25$ N/mm^2 (BS 5628, Table 3)

$\gamma_m = 2.5$ special

$$g_d = \frac{G_k \times \gamma_f}{\text{area}} = \frac{2.7}{0.2 \times 10^3}$$

$$= 0.0135 \text{ N/mm}^2$$

$$Z = \frac{200^2 \times 1000}{6} = 6.67 \times 10^6 \text{ mm}^3$$

Therefore

$$\text{Design MR} = \left(\frac{0.25}{2.5} + 0.0135\right) \times 6.67 \times 10^6 = 0.76 \text{ kN m}$$

This is inadequate because the design bending moment has been calculated as 1.184 kN/m. Therefore, stiffening piers, post-tensioning or some other form of additional support is required. The two possibilities mentioned, stiffening piers and post-tensioning, are dealt with later. The use of hollow blocks supported on a reinforced concrete beam makes reinforced masonry an option (see Chapter 15).

Example 6: External Cavity Wall

A three-storey single occupancy house is shown in Figure 11.28. The gable wall is to be designed for the loadings given, assuming that the wall is constructed with both leaves in brickwork.



Figure 11.28 Dimensions for Example 6

Characteristic wind loading $= 0.8\ \text{kN/m}^2$
Roof, characteristic dead load $= 6.5\ \text{kN/m}^2$
Roof, characteristic super load $= 0.75\ \text{kN/m}^2$
Floors, characteristic dead load $= 5.0\ \text{kN/m}^2$
Floors, characteristic super load $= 1.5\ \text{kN/m}^2$
Density of masonry $= 20\ \text{kN/m}^3$

Since this is single occupancy with less than five storeys, the structure is class 1 in accordance with Part A3 of The Building Regulations and will not need horizontal ties, etc. The ground floor slab is tied to, but not supported on, the inner leaf of the gable wall to be designed.

Design wall in lowest storey:

Characteristic dead loads, G_k, (inner leaf only):

$$\text{roof} \quad = 6.5 \times \frac{4}{2} \quad = 13.00\ \text{kN/m}$$

$$2\ \text{floors} \quad = 2 \times 5.0 \times \frac{4}{2} \quad = 20.00\ \text{kN/m}$$

$$\text{ow wall} = 0.1025 \times 20 \times 8.2 = 16.80\ \text{kN/m}$$

$$= 49.80\ \text{kN/m}$$

Characteristic superimposed loads, Q_k, (inner leaf only):

$$\text{roof} \quad = 0.75 \times \frac{4}{2} \quad = 1.50\ \text{kN/m}$$

$$2\ \text{floors} = 2 \times 1.5 \times \frac{4}{2} = 6.00\ \text{kN/m}$$

$$= 7.50\ \text{kN/m}$$

Characteristic dead load, G_k, (outer leaf only):

$$\text{ow wall} = 0.1025 \times 20 \times 8.2 = 16.80\ \text{kN/m}$$

Minimum design load (inner leaf):

$$\gamma_f \times G_k = 0.9 \times 49.80 = 44.80\ \text{kN/m}$$

Minimum design load (outer leaf):

$$\gamma_f \times G_k = 0.9 \times 16.8 = 15.12\ \text{kN/m}$$

Maximum design load (inner leaf):

$$(\gamma_f \times G_k) + (\gamma_f \times Q_k) = (1.4 \times 49.8) + (1.6 \times 7.5)$$
$$= 81.72\ \text{kN/m}$$

Design wind loading:

$$\gamma_f \times W_k = 1.4 \times 0.8 = 1.12\ \text{kN/m}^2$$

Note: The effect of wind uplift on the roof must be taken into account when calculating the minimum design load on the wall. In order to assess the moments due to wind loading in the lowest storey of wall, the end support conditions must be considered.

The rc floor slab built in at first floor level in conjunction with the wall panel extending into the second storey above can be considered to constitute a fully fixed or continuous support condition. The lower storey height of wall extends down below the ground floor slab to the foundation. The ground floor slab, as well as the ground beneath it, will prevent inward movement of the wall. However, the earth fill against the wall externally (filling the foundation excavation) will not necessarily be adequately compacted and is considered unreliable as a support to prevent outward movement of the wall. If the span of the lower storey height of the wall is taken as between ground and first floor slabs, it will be necessary to introduce ties built into the bed courses and concreted into the ground floor slab. The ties should be capable of resisting the reaction at this point due to wind suction forces on the wall panel. Having provided ties at ground slab level and built in the slab at first floor level, it is considered reasonable to treat both supports as continuous, and the bending moment diagram is as shown in Figure 11.29.

Three critical sections require investigation:

(a) at the bottom of the wall panel where the inclusion of the dpc requires the section to be checked as a 'cracked section' where the moment of resistance is provided by the stability moment,
(b) at mid-height of the wall panel where the flexural tensile and compressive stresses as well as the axial compressive stresses should be checked,
(c) at the top of the wall panel where the dpc above the level considered again requires the section to be checked as a 'cracked section'. However, the moment of resistance at the upper support will be less than at the



Figure 11.29 Loading diagram and bending moment diagram for Example 6

lower support, due to the reduced dead load available and, therefore, as the applied bending moment at these two levels is the same, only the upper support position needs to be checked for flexural tensile stresses.

The design resistance moment at mid-height of the wall panel will be calculated from the formula:

$$\text{Design MR} = \left(\frac{f_{kx}}{\gamma_m} + g_d\right)Z$$

rather than from the effective eccentricity. This is because the effective eccentricity method is considered more appropriate for solid, bonded walls where the effective thickness of the wall, for calculating the slenderness ratio, is the actual thickness. In cavity wall construction, the effective thickness of the wall is two-thirds the sum of the thickness of the two leaves. For this reason, the authors consider the formula $(f_{kx}/\gamma_m + g_d)Z$ a more realistic analysis of resistance moment, provided consideration is given to the flexural compressive stresses as well as the flexural tensile stresses, under design loading. The formula $(f_{kx}/\gamma_m + g_d)Z$ is based purely on flexural tensile resistance and a suggested method is given later in this example for considering the flexural compressive stresses.

The specification for the bricks and mortar for the two leaves is given as:

Outer leaf: Facing bricks with a water absorption between 7% and 12% and a crushing strength of 35 N/mm^2 set in a designation (iii) mortar.

Inner leaf: Commons with a water absorption in excess of 12% and a crushing strength of 20 N/mm^2 set in a designation (iii) mortar.

Check resistance moment at mid-height of wall panel:

$$\text{Resistance moment (per leaf)} = \left(\frac{f_{kx}}{\gamma_m} + g_d\right)Z$$

$$\text{total MR} = \text{MR outer leaf} + \text{MR inner leaf}$$

Outer leaf:

$$f_{kx} = 0.4\ \text{N/mm}^2 \quad \text{(BS 5628, Table 3)}$$

$$\gamma_m = 2.5 \text{ special}$$

$$g_d = \frac{15.12 \times 10^3}{0.1025 \times 10^6} = 0.147\ \text{N/mm}^2$$

$$Z = \frac{1 \times 0.1025^2}{6} = 1.751 \times 10^6\ \text{mm}^3$$

Inner leaf:

$$f_{kx} = 0.3\ \text{N/mm}^2 \quad \text{(BS 5628, Table 3)}$$

$$\gamma_m = 2.5 \text{ special}$$

$$g_d = \frac{44.8 \times 10^3}{10^6 \times 0.1025} = 0.437\ \text{N/mm}^2$$

$$Z = \frac{1 \times 0.1025^2}{6} = 1.751 \times 10^6\ \text{mm}^3$$

Total MR:

$$= \left[\left(\frac{0.4}{2.5} + 0.147\right) \times 1.751 \times 10^6 + \left(\frac{0.3}{2.5} + 0.437\right) \times 1.751 \times 10^6\right] \times 10^{-6}$$

$$= (0.537 + 0.975) \times 10^{-6}$$

$$= 1.512\ \text{kN m}$$

This section is adequate as the resistance is greater than the applied bending moment of 0.42 kNm.

It should be noted that the total resistance moment has been calculated by adding the resistance moments of the individual leaves of the cavity wall. BS 55628 permits this if wall ties which are capable of transferring the wind forces across the cavity are provided. Now check the 'cracked section' resistance moment at the upper support position.

The minimum dead loads in each leaf at this level must first be calculated as follows:

Characteristic dead loads, G_k, (inner leaf):

$$\text{roof} \quad = 6.5 \times \frac{4}{2} \qquad = 13.00\ \text{kN/m}$$

$$\text{floor} \quad = 5.0 \times \frac{4}{2} \qquad = 10.00\ \text{kN/m}$$

$$\text{ow wall} = 0.1025 \times 20 \times 5.2 = \underline{10.66}\ \text{kN/m}$$

$$= 33.66\ \text{kN/m}$$

Characteristic dead load, G_k, (outer leaf):

$$\text{ow wall} = 0.1025 \times 20 \times 5.2 = 10.66\ \text{kN/m}$$

Minimum design load (inner leaf):

$$\gamma_f \times G_k = 0.9 \times 33.66 = 30.29\ \text{kN/m}$$

Minimum design load (outer leaf):

$$\gamma_f \times G_k = 0.9 \times 10.66 = 9.59\ \text{kN/m}$$

The design moment of resistance is now calculated from the stability moments produced by these calculated minimum dead loads. The stress block producing the resistance moment for each leaf is identical to that shown in Figure 11.26, hence:

$$\frac{1.1 f_k}{\gamma_m} = \frac{\text{min. design load}}{w_s \times 1\ \text{m length}}$$

therefore

$$w_s = \frac{\gamma_m \times \text{min. design load}}{1.1 f_k \times 1\ \text{m length}}$$

Outer leaf:

$$w_s = \frac{2.5 \times 9.59 \times 10^3}{1.1 \times 8.5 \times 1000}$$

and

$$l_a = \frac{\text{wall thickness}}{2} - \frac{w_s}{2}$$

$$= \frac{102.5}{2} - \frac{2.56}{2} = 49.97\ \text{mm}$$

Then design resistance moment for outer leaf

$$= \frac{49.97}{10^3} \times 9.59 = 0.479 \text{ kN m}$$

Inner leaf:

$$w_s = \frac{2.5 \times 30.29 \times 10^3}{1.1 \times 5.8 \times 1000} = 11.87 \text{ mm}$$

and $$l_a = \frac{102.5}{2} - \frac{11.87}{2} = 45.32 \text{ mm}$$

Then design moment of resistance for inner leaf

$$= \frac{45.32}{10^3} \times 30.29$$

$$= 1.373 \text{ kN m}$$

$$\text{Total MR} = \text{MR outer leaf} + \text{MR inner leaf}$$
$$= 0.479 + 1.373$$
$$= 1.852 \text{ kN m}$$

The section is adequate as the resistance moment is greater than the applied bending moment of 0.84 kN m.

As described earlier, there is no need to calculate the resistance moment at the lower support as this will be larger than the 1.852 kN m calculated above, due to the additional dead loading. However, the flexural compressive stresses at this lower level may require investigation.

The maximum axial design loading for this storey height of wall should now be calculated in accordance with the methods described in Chapter 10. The flexural compressive stresses should be calculated under dead plus superimposed plus wind loading conditions. The following design method is considered a reasonable approach – although this aspect is not covered in detail in BS 5628.

Figure 11.30 shows the stress block across a wall subject to pure axial loading and with no eccentricity of that load. The maximum compressive stress allowable in the wall section is limited by the walls tendency to buckle, hence the inclusion of the capacity reduction factor, β.

Figure 11.31 shows the stress block across a wall subject to purely flexural loading conditions.



Figure 11.30 Stress block under axial loading



Figure 11.31 Stress block under flexural loading

Two limiting conditions can be said to apply to the maximum allowable stresses which are given as f_{kx}/γ_m for flexural tensile stresses and $1.1f_k/\gamma_m$ for flexural compressive stresses, the latter having been adopted in Appendix B to BS 5628 for the derivation of β. The flexural tensile stresses will invariably be the limiting factor under such a loading condition. However, if the axial compressive stresses already in the wall are added to the flexural compressive stresses, this may produce a more critical design condition. Consideration must be given to the need for limiting the flexural compressive stresses due to the possibility of buckling of the section under the application of such stress. Buckling of a section, due to flexural compressive stresses, will occur perpendicular to the direction of application of the bending. Two common sections are shown in Figure 11.32.

Clearly, the shear wall section shown in Figure 11.32(b) is the more critical with respect to buckling due to flexural compressive stresses, although there is no guidance given in BS 5628 on a design method to take account of such a buckling tendency. The authors consider that the following design method provides a safe and practical solution:

(a) In the first instance, the wall should be checked for maximum axial loading only, using the design principles explained in Chapters 5 and 10. The capacity reduction factor, β, applicable to this stage of the design, should be derived from the maximum slenderness ratio. The maximum allowable stress under this loading condition is $\beta f_k/\gamma_m$.

(b) The additional compressive stress resulting from the bending due to lateral loading is then considered, and the maximum allowable combined compressive stress is $1.1f_k \times \beta/\delta_m$, in which a 10% increase has been applied to the flexural aspect of the stress in a similar manner to Appendix B of BS 5628. The capacity reduction factor, β, should be derived from the slenderness ratio which incorporates the effective thickness appropriate to the direction of buckling tendency (i.e. perpendicular to the direction of application of the bending), as shown in Figure 11.32.

The stress blocks relevant to the two stages of the design are shown in Figure 11.33.



Figure 11.32 Bending about major and minor axes



Figure 11.33 Combined axial load and bending moment diagrams

Now check the upper storey wall panel for the same gable wall. First, consider the likely action of this wall panel and the moments for which it must be designed.

At second floor level, continuity will exist to some extent as was demonstrated for the lower wall panel. At roof level, however, the amount of continuity is contentious. While the inner leaf will derive some continuity from the dead loading from the roof slab, the outer leaf has no continuity and, for simplicity, this support will be treated as pin-jointed. The upper wall panel will therefore act as a propped cantilever, and the two critical sections will occur at second floor level and 3/8*h* down from roof level where the maximum wall moment occurs for a propped cantilever.

The minimum design loads must be calculated at the two critical levels.

At second floor level:

Characteristic dead loads, G_k, (inner leaf only):

$$\text{roof} \quad = 6.5 \times \frac{4}{2} \qquad = 13.00 \text{ kN/m}$$

$$\text{ow wall} = 0.1025 \times 20 \times 2.6 = \underline{5.33} \text{ kN/m}$$
$$= 18.33 \text{ kN/m}$$

Characteristic dead loads, G_k, (outer leaf only):

$$\text{ow wall} = 0.1025 \times 20 \times 2.6 = 5.33 \text{ kN/m}$$

At $\frac{3}{8}h$ down from roof:

Characteristic dead loads, G_k, (inner leaf only):

$$\text{roof} \quad = 6.5 \times \frac{4}{2} \qquad = 13.00 \text{ kN/m}$$

$$\text{ow wall} = 0.1025 \times 20 \times \frac{2.6 \times 3}{8} = \underline{20.00} \text{ kN/m}$$
$$= 15.00 \text{ kN/m}$$

Characteristic dead load, G_k, (outer leaf only):

$$\text{ow wall} = 0.1025 \times 20 \times \frac{2.6 \times 3}{8} = 2.00 \text{ kN/m}$$

Minimum design loads:

$$\text{inner leaf: 2nd floor} = 0.9 \times 18.33 = 16.50 \text{ kN/m}$$

$$\frac{3}{8}h \text{ level} \qquad = 0.9 \times 15.00 = 13.50 \text{ kN/m}$$



Figure 11.34 Loading diagram and bending moment diagram for example 2

$$\text{outer leaf: 2nd floor} = 0.9 \times 5.33 \quad = 4.8 \text{ kN/m}$$

$$\frac{3}{8}h \text{ level} \qquad = 0.9 \times 2.0 \quad = 1.8 \text{ kN/m}$$

The loading conditions and design bending moment diagram are shown in Figure 11.34. The design wind load remains the same as for the lower wall panel.

The moment of resistance at second floor level should be designed as a 'cracked section' due to the inclusion of the dpc and, once again, the stress block producing the resistance moment for each leaf is identical to that shown in Figure 11.26, hence:

$$\frac{\beta \times 1.1 f_k}{\gamma_m} = \frac{\text{min. design load}}{w_s \times 1 \text{ m length}} \quad (\text{but } \beta = 1.0)$$

therefore

$$w_s = \frac{\gamma_m \times \text{min. design load}}{1.1 f_k \times 1 \text{ m length}}$$

Outer leaf:

$$w_s = \frac{2.5 \times 4.8 \times 10^3}{1.1 \times 8.5 \times 1000} = 1.28 \text{ mm}$$

and

$$l_a = \frac{\text{wall thickness}}{2} - \frac{w_s}{2}$$

$$= \frac{102.5}{2} - \frac{1.28}{2} = 50.60 \text{ mm}$$

Then design moment (for outer leaf only) = 4.8 × 0.0506 = 0.243 kN m.

Inner leaf:

$$w_s = \frac{2.5 \times 16.5 \times 10^3}{1.1 \times 5.8 \times 1000} = 6.5 \text{ mm}$$

and

$$l_a = \frac{102.5}{2} - \frac{6.5}{2} = 48.0 \text{ mm}$$

Then design moment of resistance (for inner leaf only) = $16.5 \times 0.048 = 0.792$ kN m.

Total MR = MR outer leaf + MR inner leaf = 0.243 + 0.792 = 1.035 kN m.

This section is adequate as the resistance moment is greater than the applied bending moment of 0.946 kN m.

Now check the resistance moment at the position of maximum design moment in the wall height (i.e. (3/8)*h* from the top of the wall) again using the formula:

$$\text{MR} = \left(\frac{f_{kx}}{\gamma_m} + g_d \right) Z$$

$$\text{Total MR} = \text{MR outer leaf} + \text{MR inner leaf}$$

Outer leaf:

$$f_{kx} = 0.4 \text{ N/mm}^2 \quad \text{(BS 5628, Table 3)}$$

$$\gamma_m = 2.5 \text{ special}$$

$$g_d = \frac{1.8}{0.1025} = 0.017 \text{ N/mm}^2$$

$$Z = \frac{10^3 \times 102.5^2}{6} = 1.751 \times 10^6 \text{ mm}^3$$

Inner leaf:

$$f_{kx} = 0.3 \text{ N/mm}^2 \quad \text{(BS 5628, Table 3)}$$

$$\gamma_m = 2.5 \text{ special}$$

$$g_d = \frac{13.50}{0.1025} = 0.132 \text{ N/mm}^2$$

$$Z = \frac{10^3 \times 102.5^2}{6} = 1.751 \times 10^6 \text{ mm}^3$$

Then, total MR:

$$= \left(\frac{0.4}{2.5} + 0.017 \right) \times 1.751 \times 10^6$$

$$+ \left(\frac{0.3}{2.5} + 0.132 \right) \times 1.751 \times 10^6$$

$$= 0.31 + 0.44 = 0.75 \text{ kN m}$$

This section is adequate as the resistance moment is greater than the applied bending moment of 0.532 kN m. The compressive stresses should be checked using the method



Figure 11.35 Forces for checking section as cracked

suggested earlier but, by inspection, these will also be acceptable.

Now check that the wall complies with clause 36.9.1(b) of the Code in which the base moment is permitted to exceed $wh^2/8$ but, at the level of M_w, must be checked as a 'cracked section' (see Figure 11.35).

$$\text{Prop force} = (1.12 \times 2.6 \times 0.5) - \left(\frac{1.035}{2.6}\right) = 1.058 \text{ kN}$$

$$\text{Zero shear} = \frac{1.058}{1.12} = 0.95 \text{ m from top of wall}$$

$$\text{Therefore, } M_w = 1.058 \times 0.95 - 1.12 \times \frac{0.95^2}{2} = 0.50 \text{ kN m}$$

Now calculate the minimum design load at level of M_w characteristic dead loads:

Inner leaf only $= 13.0 + (0.1025 \times 20 \times 0.95) = 14.95$ kN/m
Outer leaf only $= 0.1025 \times 20 \times 0.95 = 1.95$ kN/m

and check this level acting as a 'cracked section'.

Inner leaf only:

$$w_s = \frac{2.5 \times 14.95 \times 10^3}{1.1 \times 5.8 \times 1000} = 5.86 \text{ mm}$$

$$l_a = \frac{102.5}{2} - \frac{5.86}{2} = 48.32 \text{ mm}$$

Therefore design moment for resistance (for inner leaf only)

$= 14.95 \times 0.048\,32 = 0.722$ kN m

Outer leaf only:

$$w_s = \frac{2.5 \times 1.95 \times 10^3}{1.1 \times 8.5 \times 1000} = 0.52 \text{ mm}$$

$$l_a = \frac{102.5}{2} - \frac{0.52}{2} = 50.99 \text{ mm}$$

Therefore design moment for resistance (for outer leaf only)

$= 1.95 \times 0.050\,99 = 0.099$ kN m

total design moment of resistance (both leaves)

$= 0.722 + 0.099 = 0.82$ kN m

which exceeds the applied M_w of 0.5 kN m and hence the wall section is adequate. It was possible to demonstrate compliance with clause 36.9.1(b) of the Code only because of the significant contribution to the design moment of resistance which is provided by the dead load from the flat concrete roof. Where lighter-weight roofs are encountered, the design would fail to comply with clause 36.9.1(b) as will be shown in Example 10 later in this chapter.

Example 7: Double-leaf Cavity Panel Wall

It is proposed to construct a steel framed industrial building with brick cladding panels up to a height of 4.0 m above ground level. The steel stanchions are to be spaced at 5.0 m centres and the steel frame has been designed to resist all the wind loading from the cladding and wall panels. Check the wall panels, under the characteristic wind load of 1.05 kN/m^2, for the masonry specification given below. A felt dpc is to be included at the base of the wall and the construction details of a typical wall panel are shown in Figure 11.36, γ_m can be taken as 2.5 for special control.

Masonry specification:

Inner leaf: Solid concrete blocks with a crushing strength of 7 N/mm^2 set in a designation (iii) mortar, overall density = 15 kN/m^3.

Outer leaf: Facing bricks with a crushing strength of 27.5 N/mm^2 and a water absorption of 9% set in a designation (iii) mortar, overall density = 20 kN/m^3.

The design bending moment coefficients given in BS 5628, Table 9, will be used for this example to demonstrate their use (see Table 6.4). These coefficients are applicable only within certain dimensional proportions of the panel and this is the first check to be carried out.

Limiting dimensions in accordance with BS 5628, clause 36.3(b) (2):

$$\text{height} \times \text{length} = 4000 \times 5000 = 20 \times 10^6$$

$$2025 \times t_{ef}^2 = 2025 \times \left[\frac{2}{3}(100 + 102.5)\right]^2 = 36.9 \times 10^6$$

Therefore, height × length is less than 2025 t_{ef}^2, which complies with the requirements of Table 9.

Also check,

$$50 \times t_{ef} = 50 \times \left[\frac{2}{3}(100 + 102.5)\right] = 6750$$

Maximum dimension of panel is 5000 which is less than $50 \times t_{ef}$ as also required for Table 9. The design can therefore be based on the bending moment coefficients from Table 9.

Table 9 incorporates twelve different combinations of support conditions and, in order to decide which case is applicable, an assessment of the support condition at each edge of the panel to be designed must be made. The coefficients given in BS 5628, Table 9 were derived from experimental research using test panels, and this must be given due consideration when assessing the applicable support conditions.



Figure 11.36 Dimensions and details for example 7

Certainly, the connection of the wall panel to the stanchions, as detailed in Figure 11.35(b), can be taken to provide continuity at these vertical edges. However, the connection to the cladding rail at the top of the panel cannot be regarded as anything more than a simple support, unless the member offering support is capable of withstanding the torsional stresses which would result from a 'fixed-end' condition.

The condition at the base of the wall panel is somewhat more contentious. While even with the inclusion of the dpc, the 'cracked section' at this point can certainly develop some degree of resistance moment (as has been previously demonstrated) it is considered inadvisable to treat this support as continuous. This is because the coefficients were derived from loading test panels and such tests would naturally include the benefit of the inherent resistance moment at the base of the wall panel. It would be virtually impossible to simulate a true simple support at this position for test loading purposes and the expression 'simply supported edge' given in Table 9 should be taken to include the effect of the resistance moment when applied to the base of this wall panel. The edge support conditions are therefore indicated in Figure 11.37 as well as the bending moment locations.

The wall panel is constructed of a concrete block inner leaf and a clay brick outer leaf which have differing orthogonal ratios (see Chapter 6). As such, the design wind load will be shared between the two leaves in the proportions of their design moments of resistance.

Inner leaf:

$$\text{design MR} = \frac{f_{kx}}{\gamma_m} Z$$

where

$f_{kx} = 0.60\ \text{N/mm}^2$ (BS 5628, Table 3)
$\gamma_m = 2.5$ special
$Z = \dfrac{1 \times 0.1^2}{6} = 1.67 \times 10^6\ \text{mm}^3$

Therefore

$$\text{design MR} = \frac{0.6}{2.5} \times 1.67 \times 10^6 = 0.4008\ \text{kN m}$$



Figure 11.37 Edge support conditions (case G from Table 9, BS 5628)

Outer leaf:

$$\text{Design MR} = \frac{f_{kx}}{\gamma_m} Z$$

where

$f_{kx} = 1.10\ \text{N/mm}^2$ (BS 5628, Table 3)
$\gamma_m = 2.5$ special
$Z = \dfrac{1 \times 0.1025^2}{6} = 1.751 \times 10^6\ \text{mm}^3$

Therefore

$$\text{Design MR} = \frac{1.1}{2.5} \times 1.751 \times 10^6$$

$$= 0.7704\ \text{kN m}$$

Therefore, the design wind load will be shared in the ratio:

$$\frac{0.4008}{0.4008 + 0.7704} = 34\% \text{ to inner leaf}$$

$$\frac{0.7704}{0.4008 + 0.7704} = 66\% \text{ to outer leaf}$$

Hence:

inner leaf design wind load $= 0.34 \times 1.26 = 0.428\ \text{kN/m}^2$
outer leaf design wind load $= 0.66 \times 1.26 = 0.832\ \text{kN/m}^2$

From BS 5628, clause 36.4.2:

Applied design horizontal bending moment $= \alpha \times W_k \times \gamma_f \times L^2$

where

L = length of panel between stanchion supports
$W_k\gamma_f$ = proportion of design wind load
α = bending moment coefficient from BS 5628, Table 9, case G (see Table 6.4) (dependent upon the ratio height : length (h/l) = 4000/5000 = 0.8 for this example).

$$\text{Orthogonal ratio, } \mu = \frac{f_{kx/par} + \left(\dfrac{\text{design dead load} \times \gamma_m}{\text{area}}\right)}{f_{kx/perp}}$$

in which the flexural strength in the parallel direction has been increased to allow for the stress due to the minimum design vertical load, as provided for in BS 5628, clause 36.4.2.

Now consider the outer leaf only:

$$\mu = \frac{0.4 + \left(\dfrac{20 \times 0.1025 \times 0.9 \times 2.0 \times 10^3}{0.1025 \times 1.0 \times 10^6} \times 2.5\right)}{1.1} = 0.445$$

Therefore, from BS 5628, Table 9 (G) (see Table 6.4) by interpolation for $\mu = 0.445$ and $h/l = 0.8$, BM coefficient $\alpha = 0.032$.

Now consider the inner leaf only:

$$\mu = \frac{0.25 + \left(\dfrac{15 \times 0.1 \times 0.9 \times 2.0 \times 10^3}{0.1 \times 1.0 \times 10^6} \times 2.5\right)}{0.6} = 0.53$$

Therefore, from BS 5628, Table 9 (G) (see Table 6.4) by interpolation for $\mu = 0.53$ and $h/l = 0.8$, BM coefficient $\alpha = 0.0306$.

Design bending moments, as located in Figure 11.36:

Continuity moment at stanchion support

$$M_1 = \alpha \times W_k \times \gamma_f \times L^2$$
$$M_1 \text{ outer leaf} = 0.032 \times 0.832 \times 5^2$$
$$= 0.665\ \text{kNm}$$
$$M_1 \text{ inner leaf} = 0.0306 \times 0.428 \times 5^2$$
$$= 0.327\ \text{kN m}$$

Moment at mid-span in horizontal plane

$$M_2 = M_1$$

Moment at approximate mid-height in vertical plane

$$M_3 = \mu \times \alpha \times W_k \times \gamma_f \times L^2$$
$$M_3 \text{ outer leaf} = 0.445 \times 0.032 \times 0.832 \times 5^2$$
$$= 0.296\ \text{kN m}$$
$$M_3 \text{ inner leaf} = 0.53 \times 0.0306 \times 0.428 \times 5^2$$
$$= 0.173\ \text{kN m}$$

Compare applied design moments with design moments of resistance at positions of M_1 and M_2 (negative and positive moments in horizontal span):

$$\text{Inner leaf design MR} = \frac{f_{kx/perp}}{\gamma_m} Z$$

$$= \frac{0.6 \times 1.67 \times 10^6}{2.5}$$

$$= 0.4\ \text{kN m}$$

The section is adequate as the design MR is greater than the applied BM of 0.327 kN m.

$$\text{Outer leaf design MR} = \frac{1.1 \times 1.751 \times 10^6}{2.5}$$

$$= 0.77\ \text{kN m}$$

The section is adequate as the design MR is greater than the applied BM of 0.665 kN m. At position of M_3 (positive moment in vertical span)

$$\text{Inner leaf design MR} = \left(\frac{f_{kx/par}}{\gamma_m} + g_d\right) Z$$

$$= \left(\frac{0.25}{2.5} + \frac{15 \times 0.1 \times 0.9 \times 2.0 \times 10^3}{0.1 \times 1.0 \times 10^6}\right)$$

$$\times 1.67 \times 10^6$$

$$= 0.212\ \text{kN m}$$

The section is adequate as the design MR is greater than the applied BM of 0.173 kN m.

$$\text{Outer leaf design MR} = \left(\frac{0.4}{2.5} + \frac{20 \times 0.1025 \times 0.9 \times 2.0 \times 10^3}{0.1025 \times 1.0 \times 10^6}\right)$$

$$\times 1.751 \times 10^6$$

$$= 0.343\ \text{kN m}$$

The section is adequate as the design MR is greater than the applied BM of 0.296 kN m.



Figure 11.38 Loading diagram and bending moment diagram for Example 8

The wall section has been checked at all critical locations of applied BM and found to be adequate for the specification and connection details given.

Example 8: Solid Concrete Block Crosswall Acting as Shear Wall

Design the crosswall for the four-storey flats complex shown in Figure 11.38. The crosswalls are to be constructed in solid concrete blockwork and, acting as shear walls, they provide the sole resistance to wind forces on the glazed elevation. The floor-to-floor height is 2.70 m and the crosswalls are at 6.0 m centres. The following characteristic loads are to be assumed:

own weight of masonry $= 3.0\ \text{kN/m}^2$
roof – dead load $= 6.5\ \text{kN/m}^2$
– superimposed load $= 1.5\ \text{kN/m}^2$
floors – dead load $= 5.0\ \text{kN/m}^2$
– superimposed load $= 1.5\ \text{kN/m}^2$
wind load on glazed elevation $= 0.8\ \text{kN/m}^2$

Shear walls are described in more detail in Chapter 14 which deals with multi-storey structures. Briefly, shear walls, such as those shown in Figure 11.38, act about their major axes and span as vertical cantilevers to provide stability to the structure by resisting the wind forces on the building elevation.

On the glazed elevation

$$\text{Design wind loading} = W_k \times \gamma_f = 0.8 \times 1.4 = 1.12\ \text{kN/m}^2$$

Each shear wall resists wind loading from 6.0 m of glazed elevation, thus:

$$\text{Design wind load per shear wall} = 1.12 \times 6 = 6.72\ \text{kN/m}$$

The shear wall acts as a vertical cantilever and the design bending moment at the base of the wall is

$$= \frac{W_k \times \gamma_f \times h^2}{2}$$

$$= \frac{6.72 \times 11.4^2}{2} = 436.67\ \text{kN m}$$

The loading and bending moment diagrams per shear wall are shown in Figure 11.39.

Calculate design axial loadings on shear walls:

Characteristic dead loads, G_k:

roof $= 6.5 \times 6 = 39.00\ \text{kN/m}$
3 floors $= 3 \times 5.0 \times 6 = 90.00\ \text{kN/m}$
ow wall $= 11.4 \times 3 = \underline{34.00}\ \text{kN/m}$
$= 163.20\ \text{kN/m}$



Figure 11.39

Characteristic superimposed load, Q_k:

$$\begin{aligned} \text{roof} &= 1.5 \times 6 \quad = 9.00 \text{ kN/m} \\ 3 \text{ floors} &= 3 \times 1.5 \times 6 = 27.00 \text{ kN/m} \\ &= 36.00 \text{ kN/m} \end{aligned}$$

Minimum design load for dead plus wind loading combination

$$\begin{aligned} &= G_k \times \gamma_f \\ &= 163.2 \times 0.9 = 146.88 \text{ kN/m} \end{aligned}$$

Maximum design load for dead plus superimposed plus wind loading combination

$$\begin{aligned} &= (G_k \times \gamma_f) + (Q_k \times \gamma_f) \\ &= (163.2 \times 1.4) + (36 \times 1.6) = 286.08 \text{ kN/m} \end{aligned}$$

The design moment of resistance will be checked first against the formula

$$\left(\frac{f_{kx}}{\gamma_m} + g_d\right) Z$$

in which the limiting condition is the flexural tensile strength, f_{kx}. This check utilises the minimum design load for the calculation of g_d. However, it is essential that the flexural compressive stresses are also checked and a suggested design method is given later in this example for the second stage of the check.

Total minimum axial load on shear wall = 5 × 146.88 = 734.4 kN

Shear wall properties:

area $= 0.2 \times 5 = 1000 \times 10^3 \text{ mm}^2$

section modulus, $Z = \dfrac{0.2 \times 5^2}{6} = 833.33 \times 10^6 \text{ mm}^3$

MR of shear wall $= \left(\dfrac{f_{kx}}{\gamma_m} + g_d\right) Z$

The specification for the masonry is given as solid concrete blocks with a compressive strength of 10.0 N/mm^2 set in designation (iii) mortar.

γ_m can be taken as 2.5 special

therefore,

$f_{kx} = 0.25 \text{ N/mm}^2$ (BS 5628, Table 3)

$\gamma_m = 2.5$ special

$g_d = \dfrac{734.4 \times 10^3}{1000 \times 10^3} = 0.7344 \text{ N/mm}^2$

$Z = 833.33 \times 10^6 \text{ mm}^3$

Hence:

$$\text{Design MR} = \left(\frac{0.25}{2.5} + 0.7344\right) \times 833.33 \times 10^6$$

$$= 695.33 \text{ kN m}$$

The section is adequate for the first stage of the design as the design MR is greater than the applied BM of 436.67 kN m.

Now check compressive stresses under dead plus superimposed plus wind loading. The wall section needs checking at two critical levels:

(a) at foundation level, where the effect of axial loading and design bending moment are greatest, and,
(b) at a point 0.4h above the ground floor slab, where the design bending moment will be considerably less but where the capacity reduction factor, β, reduces the vertical load resistance of the wall under combined axial and lateral loading (see Figure 11.32).

Case (a): Check Stresses at Foundation Level

This check must be carried out in two stages as explained earlier (see Figure 11.32) considering (1) axial loading only and (2) combined axial and lateral loading.

Stage 1: Axial loading only

The design stress required under axial loading is given by the equation $\beta f_k/\gamma_m$. Hence

$$\frac{\text{design load}}{\text{area}} = \frac{\beta f_k}{\gamma_m}$$

$$\frac{186.08 \times 10^3}{200 \times 1000} = \frac{\beta f_k}{\gamma_m}$$

$$1.4304 = \frac{\beta f_k}{\gamma_m}$$

At foundation level the wall is fully restrained against buckling and therefore:

$\beta = 1.0$
$\gamma_m = 2.5$ special
$f_k =$ 4.5 N/mm^2 for the block and mortar specification given (by interpolation from BS 5628, Tables 2(b) and 2(c), for a ratio of $h/t = 1.0$) (see Tables 5.8 and 5.9).

Hence

$$\frac{\beta f_k}{\gamma_m} = \frac{1.0 \times 4.5}{2.5}$$

$$= 1.80 \text{ N/mm}^2$$

(which is greater than the applied design stress 1.4304 N/mm^2).

Stage 2: Combined axial and lateral loading

The design stress required under combined axial and lateral loading is given by the equation $\beta \times 1.1 f_k/\gamma_m$.

The maximum applied design compressive stress under the loading combination dead plus super wind is, from a simple elastic analysis:

$$\frac{n_w}{A} + \frac{M_A}{Z}$$

where

n_w = total design vertical load under ($D + S + W$) loading combination
A = area of shear wall
M_A = applied design bending moment at foundation
Z = section modulus of shear wall.

Design vertical load, n_w:

$$n_w = 1.2G_k + 1.2Q_k$$
$$= (1.2 \times 163.2) + (1.2 \times 36)$$
$$= 195.84 + 43.2 = 239.04 \text{ kN/m}$$

$$A = 200 \times 5000 \times 10^{-9} = 1.0 \text{ m}^2$$

$$M_A = 436.67 \text{ kN m}$$

$$Z = \frac{200 \times 5000^2 \times 10^{-9}}{6} = 0.833 \text{ m}^3$$

Maximum applied design compressive stress:

$$= \frac{n_w}{A} + \frac{M_A}{Z}$$

$$= \frac{239.04 \times 5}{1} + \frac{436.67}{0.833}$$

$$= 1195.2 + 524.21$$

$$= 1719.41 \text{ kN/m}^2 = 1.719 \text{ N/mm}^2$$

Hence, $1.719 = \dfrac{\beta \times 1.1 f_k}{\gamma_m}$

Once again $\beta = 1.0$, $\gamma_m = 2.5$ and $f_k = 4.50 \text{ N/mm}^2$.

Therefore

$$\frac{\beta \times 1.1 f_k}{\gamma_m} = \frac{1.0 \times 1.1 \times 4.5}{2.5} = 1.98 \text{ N/mm}^2$$

(which is greater than the maximum applied design compressive stress of 1.719 N/mm^2)

Case (b): Check Wall at 0.4h above Ground Floor Slab Restraint (see Figure 11.40)

Stage 1: Axial loading only

Design stress required is similar to that for case (a) in which $1.4304 = \beta f_k/\gamma_m$, where $\beta = 0.97$ (from BS 5628, Table 7) (see Table 5.15), since SR = 0.75 × 2.7/0.2 = 10.125 and $e_x = 0$ to $0.05t$, $f_k = 4.5 \text{ N/mm}^2$ and $\gamma_m = 2.5$ as before. Hence

$$\frac{\beta f_k}{\gamma_m} = \frac{0.97 \times 4.5}{2.5}$$
$$= 1.746 \text{ N/mm}^2$$

(which is greater than the applied design stress of 1.4304 N/mm^2).



Figure 11.40 Section showing case (b) critical design moment

Stage 2: Combined axial and lateral loading

The design stress required is $\beta \times 1.1 f_k/\gamma_m$, in which β is calculated from the slenderness ratio based upon the effective wall thickness perpendicular to the direction of application of the bending. For this example, the direction of application of the bending is parallel to the major axis of the shear wall and the effective thickness to be taken for the calculation of β is the actual thickness of 200 mm.

Hence, $\beta = 0.97$, as for stage 1.

$$\text{Design stress required} = \frac{0.97 \times 1.1 \times 4.5}{2.5}$$
$$= 1.921 \text{ N/mm}^2$$

$$\text{Maximum applied design compressive stress} = \frac{n_w}{A} + \frac{M_A}{Z}$$

where

$n_w = 239.04 \text{ kN/m}$ (as case (a))
$A = 1.0 \text{ m}^2$

$$M_A = \gamma_f W_k \times \frac{9.72^2}{2} \times L$$ (where L is the spacing of the shear walls)

$$= 1.2 \times 0.8 \times \frac{9.72^2}{2} \times 6 = 272.1 \text{ kN m}$$

$Z = 0.833 \text{ m}^3$

Therefore

$$\frac{n_w}{A} + \frac{M_A}{Z} = \frac{239.04 \times 5}{1} + \frac{272.1}{0.833}$$
$$= 1195.2 + 326.65$$
$$= 1521.85 \text{ kN/m}^2 = 1.522 \text{ N/mm}^2$$

(which is less that the design stress required of 1.921 N/mm^2).

The section is shown to be adequate for all stages of the design as the design moment of resistance is greater than the applied design bending moment of 436.67 kN m, and the combined flexural stresses at the two critical levels are within acceptable designed limits.

Example 9: Column Design

Four rows of masonry columns supporting the main structure of an office block are to be designed and a section of the building is shown in Figure 11.41. The characteristic wind loading for the area is to be taken as 0.65 kN/m^2 and the wall, floor and roof construction is such that the columns are loaded as in Table 11.2.

It can be assumed that the critical loading condition occurs when the wind is in the direction of the arrow shown in

Table 11.2

Column reference	A	B	C	D
Characteristic dead load (kN)	175	76	76	175
Characteristic super load (kN)	147	100	100	147



Figure 11.41 Typical cross-section



Figure 11.42 Alternative column profiles

Figure 11.41. The framework shown is repeated at 4.0 m centres and a felt dpc is to be incorporated at the base of each column. Three alternative cross-sections of columns are required for consideration by the client, the basic profiles of which are shown in Figure 11.42.

Minimum design loads (dead plus wind loading condition):

$$= \gamma_f \times G_k$$

Columns A and D $= 0.9 \times 175 = 157.5$ kN
Columns B and C $= 0.9 \times 76 = 68.4$ kN

Maximum design loads (dead plus super loading condition):

$$= (\gamma_f \times G_k) + (\gamma_f \times Q_k)$$

Columns A and D $= (1.4 \times 175) + (1.6 \times 147) = 480.2$ kN
Columns B and C $= (1.4 \times 76) + (1.6 \times 100) = 266.4$ kN

Design wind loading $= \gamma_f \times W_k$
$= 1.4 \times 0.65 \times 3.5 \times 4.0$
$= 12.74$ kN per frame of four columns

It has been assumed that the structure above the column heads will be sufficiently stiffened with crosswalls for the design wind load to be considered as acting at column head



Figure 11.43 Wind loading

height, as shown in Figure 11.43. The design wind load of 12.74 kN, acting at the mid-depth of the 3.5 m deep structure above first floor level, induces positive and negative forces into the columns and consideration is given to this later in the design. Due to the presence of the dpc at the base of the columns, the frames will be designed as fixed at the column heads and pin-jointed at their base.

It has already been demonstrated that a moment can develop at a felt dpc due to the inherent stability moment. However, to simplify the analysis for this design example, and at the same time provide an additional factor of safety on the structure, the base will be treated as pin-jointed and the rigidity will be provided by the moment connection of the column heads to the structure above (see Figure 11.44). It will be assumed that the structure above can accommodate the moments at each column head. As each column is to be of identical cross-section the total design wind load will be shared equally between the four columns as shown in Figure 11.44.



Figure 11.44 Columns bending moment diagrams

It is critical to the design assumptions to ensure that the interfaces between the structure over and the tops of the four columns can transmit the calculated flexural tensile stresses. In this example, the structure over is assumed to comprise a rigid reinforced concrete slab poured directly onto the brick columns. Precast concrete beams laid 'dry' onto the brick columns could not develop the flexural tensile stresses calculated, but may generate the required moment of resistance on the basis of a 'cracked section' design.

$$\text{Design bending moment} = \frac{12.74}{4} \times 2.5$$
$$= 7.96 \text{ kN m} \quad \text{per column}$$

Induced compression and tension in columns A and D respectively from applied wind moment:

$$C = T = \frac{12.74 \times \left(2.5 + \frac{3.5}{2}\right) \times \frac{15}{2}}{7.5^2 + 2.5^2}$$
$$= 6.5 \text{ kN}$$

Therefore, adjusted minimum load in column D under dead plus wind load = 157.5 – 6.5 = 151 kN.

Worst case minimum loading is in columns B and D, where the minimum design load of 68.4 kN is combined with the applied design BM of 7.96 kN m.

Case (a): Cruciform Columns

The proposed column profile, for trial purposes, is shown in Figure 11.45. The assessment of column trial section sizes can only be gained with experience.

Column properties:

$$\text{Area} = 451.125 \times 10^3 \text{ mm}^2$$
$$Z = 54.13 \times 10^6 \text{ mm}^3$$
$$I = 26\,836 \times 10^6 \text{ mm}^4$$
$$r = 243.9 \text{ mm}$$

The design resistance moment of the cruciform section based solely on the flexural tensile stresses:

$$= \left(\frac{f_{kx}}{\gamma_m} + g_d\right) Z$$



Figure 11.45 Cruciform column profile

(for geometric profiles the effective eccentricity method is considered not to be a realistic analysis).

Using bricks with a crushing strength of 27.5 N/mm^2 and a water absorption of 9% set in a designation (iii) mortar:

$$f_{kx} = 0.4 \text{ N/mm}^2 \quad \text{(BS 5628, Table 3)}$$
$$\gamma_m = 2.5 \text{ special}$$
$$g_d = \frac{68.4 \times 10^3}{451.125 \times 10^3} = 0.152 \text{ N/mm}^2$$
$$Z = 54.13 \times 10^6 \text{ mm}^3$$

Therefore:

$$\text{Design MR} = \left(\frac{0.4}{2.5} + 0.152\right) \times 54.13 \times 10^6$$
$$= 16.89 \text{ kN m}$$

The flexural tensile resistance moment is adequate as the design MR is greater than the applied BM of 7.96 kN m.

Check compressive stresses under applied BM and maximum design load after column has been checked for axial loading.

Check columns A and D for axial loading.

$$\text{Maximum design load} = 480.2 + \text{induced compression from wind moment}$$
$$= 480.2 + 6.5$$
$$= 486.7 \text{ kN} \quad \text{(columns A and D)}$$

This load will be assumed to be applied axially with an eccentricity of 0 to 0.05t.

From the formula radius of gyration = $\sqrt{(I/A)}$, an equivalent solid square column will be calculated in order to assess the value of β (capacity reduction factor) from BS 5628 Table 7 (see Table 5.15).

Hence

$$\text{Radius of gyration} = \sqrt{\left(\frac{I}{A}\right)} = 243.9$$

Therefore

$$\sqrt{\left(\frac{bt^3/12}{bt}\right)} = 243.9$$

but for a square section, $b = t$. Therefore

$$\sqrt{\left(\frac{t^2}{12}\right)} = 243.9$$
$$t = \sqrt{(12 \times 243.9^2)} = 845 \text{ mm}$$

Hence, column section = 845 mm × 845 mm.

Now calculate β from BS 5628, Table 7 (see Table 5.15), for an equivalent 845 mm square column section:

$$\text{Slenderness ratio} = \frac{h_{ef}}{t_{ef}}$$
$$= \frac{2.5 \times 10^3}{845} = 2.96$$



Figure 11.46 Reduced cruciform column profile

Slenderness ratio based on length of outstanding leg of cruciform profile:

$$= \frac{h_{ef}}{t_{ef}}$$

$$= \frac{2 \times 330}{225} = 2.93$$

$e_x = 0$, therefore, $\beta = 1.0$ (from BS 5628, Table 7).

$$\text{Design vertical load resistance} = \frac{\beta \times \text{area} \times f_k}{\gamma_m}$$

$$= \frac{1.0 \times 451.125 \times 10^3 \times 7.1}{2.5}$$

$$= 1281 \text{ kN}$$

The section is adequate for the design axial loading as the design vertical load resistance is greater than the applied maximum design load of 486.7 kN, although the flexural compressive stresses should be checked under combined axial and lateral loading.

Check if a smaller column profile will be adequate – profile shown in Figure 11.46.

Column properties:

$$\text{Area} = 347.60 \times 10^3 \text{ mm}^2$$
$$Z = 34.94 \times 10^6 \text{ mm}^3$$
$$I = 13\,623 \times 10^6 \text{ mm}^4$$
$$r = 198 \text{ mm}$$

Equivalent solid column = 686 mm square.

$$\text{Design MR} = \left(\frac{f_{kx}}{\gamma_m} + g_d\right) Z$$

$$= \left(\frac{0.4}{2.5} + \frac{68.4}{347.6}\right) \times 34.94 \times 10^6$$

$$= 12.4 \text{ kN m}$$

(The flexural tensile resistance moment is adequate as design MR is greater than applied BM.)

Now check columns A and D for axial load:

$$\text{Slenderness ratio} = \frac{2.5 \times 10^3}{686} = 3.6$$

$e_x = 0$, therefore, $\beta = 1.0$ (from BS 5628, Table 7) (see Table 5.15).

$$\text{Design vertical load resistance} = \frac{\beta \times \text{area} \times f_k}{\gamma_m}$$

$$= \frac{1.0 \times 347.6 \times 10^3 \times 7.1}{2.5}$$

$$= 987.20 \text{ kN}$$

Hence, the section is adequate for the design axial loading.

While the Code does not directly cater for calculating compressive stresses under combined axial and lateral loading, it is considered that more complex geometric profiles should always be checked, as it is by no means certain that flexural tensile stress will always be the limiting factor in calculating design resistance moments. Under maximum design load and applied design bending moment, the compressive stresses at the heads of columns A and D may be calculated using the following suggested design method:

Axial compressive stress under maximum design load

$$= \frac{\text{load}}{\text{area}} \times \gamma_m = \frac{486.7 \times 10^3}{347.6 \times 10^3} \times 2.5$$

$$= 3.5 \text{ N/mm}^2$$

Flexural compressive stress under applied BM

$$= \frac{\text{moment} \times \gamma_m}{Z}$$

$$= \frac{7.96 \times 10^6}{34.94 \times 10^6} \times 2.5$$

$$= 0.570 \text{ N/mm}^2$$

Maximum combined stress (axial plus flexural)

$$= 3.5 + 0.570$$
$$= 4.07 \text{ N/mm}^2$$

By inspection this is comfortably within the characteristic compressive stresses given in BS 5628, to which no reductions need apply as the capacity reduction factor, β, has already been calculated as 1.0.

Case (b): Solid Rectangular Columns

The proposed column profile, for trial purposes, is shown in Figure 11.47.

Column properties:

$$\text{Area} = 292 \times 10^3 \text{ mm}^2$$
$$Z_{xx} = 43.1 \times 10^6 \text{ mm}^3$$
$$Z_{yy} = 16.1 \times 10^6 \text{ mm}^3$$

Following the same sequence of design and the same brick/mortar specification as for case (a):

$$\text{Design moment of resistance} = \left(\frac{f_{kx}}{\gamma_m} + g_d\right) Z$$

$$= \left(\frac{0.4}{2.5} + \frac{68.4}{292}\right) \times 43.1 \times 10^6$$

$$= 16.99 \text{ kN m}$$



Figure 11.47 Solid rectangular column for Example 9



Figure 11.48 Hollow rectangular column profile

The flexural tensile resistance moment is adequate as the design MR is greater than the applied BM of 7.96 kN m.

Now check columns A and D for the maximum design axial load of 486.7 kN. Once again the axial load will be assumed to be applied concentrically and, therefore, $e_x = 0$.

$$\text{Slenderness ratio} = \frac{h_{ef}}{t_{ef}} = \frac{2.5 \times 10^3}{330} = 7.6$$

$e_x = 0$, therefore, $\beta = 1.0$ from BS 5628, Table 7 (see Table 5.15).

$$\text{Design vertical load resistance} = \frac{\beta \times \text{area} \times f_k}{\gamma_m} = \frac{1.0 \times 292 \times 10^3 \times 7.1}{2.5} = 829 \text{ kN}$$

The axial compressive stresses are adequate as the maximum design load is only 486.7 kN and it is possible that a slightly smaller section could also be shown to be adequate.

Now check maximum flexural compressive stresses under combined axial and lateral loading:

$$\text{Axial compressive stress} = \frac{\text{load}}{\text{area}} \times \gamma_m = \frac{486.7 \times 10^3}{292 \times 10^3} \times 2.5 = 4.167 \text{ N/mm}^2$$

$$\text{Flexural compressive stress} = \frac{\text{moment} \times \gamma_m}{Z} = \frac{7.96 \times 10^6}{43.1 \times 10^6} \times 2.5 = 0.462 \text{ N/mm}^2$$

Maximum combined stress (under axial and lateral loading)

$$= 4.167 + 0.462 = 4.629 \text{ N/mm}^2$$

By inspection this is comfortably within the characteristic stresses given in BS 5628 to which no reductions need apply as the capacity reduction factor, β, has already been calculated as 1.0. The section is therefore adequate in all respects.

The columns should also be checked for bending about the weaker axis when the wind loading is applied to the other building elevation at right angles using the same design principles.

Case (c): Hollow Rectangular Columns

The proposed column profile, for trial purposes, is shown in Figure 11.48 (columns orientated as column case (b)).

Column properties

$$\text{Area} = 229.6 \times 10^3 \text{ mm}^2$$
$$Z_{xx} = 43.52 \times 10^6 \text{ mm}^3$$
$$Z_{yy} = 25.21 \times 10^6 \text{ mm}^3$$
$$I_{xx} = 19\,258 \times 10^6 \text{ mm}^4$$
$$I_{yy} = 5547 \times 10^6 \text{ mm}^4$$
$$r_{xx} = 289.60 \text{ mm}$$
$$r_{yy} = 155.43 \text{ mm}$$

From $r = \sqrt{(I/A)}$, equivalent solid column = 1003×538 mm.

Following the same sequence of design and the same brick/mortar specification as for case (a):

$$\text{Design MR} = \left(\frac{f_{kx}}{\gamma_m} + g_d\right) Z = \left(\frac{0.4}{2.5} + \frac{68.4}{229.6}\right) \times 43.52 \times 10^6 = 19.93 \text{ kN m}$$

The flexural tensile resistance moment is adequate as the design MR is greater than the applied BM of 7.96 kN m.

Now check columns A and D for the maximum design axial load of 486.7 kN:

$$\text{Slenderness ratio} = \frac{h_{ef}}{t_{ef}} = \frac{2.5 \times 10^3}{538} = 4.6$$

As before, $e_x = 0$, therefore, $\beta = 1.0$ (from BS 5628, Table 7) (see Table 5.15).

$$\text{Design vertical load resistance} = \frac{\beta \times \text{area} \times f_k}{\gamma_m}$$
$$= \frac{1.0 \times 229.6 \times 10^3 \times 7.1}{2.5}$$
$$= 652 \text{ kN}$$

The axial compressive stresses are adequate as the maximum design load is only 486.7 kN.

Now check maximum flexural compressive stresses under combined axial and lateral loading:

$$\text{Axial compressive stress} = \frac{\text{load} \times \gamma_m}{\text{area}}$$
$$= \frac{486.7 \times 10^3}{229.6 \times 10^3} \times 2.5$$
$$= 5.299 \text{ N/mm}^2$$

$$\text{Flexural compressive stress} = \frac{\text{moment} \times \gamma_m}{Z}$$
$$= \frac{7.96 \times 10^6}{43.52 \times 10^6} \times 2.5$$
$$= 0.457 \text{ N/mm}^2$$

Maximum combined stress (under axial and lateral loading)

$$= 5.299 + 0.457$$
$$= 5.756 \text{ N/mm}^2$$

By inspection this is comfortably within the characteristic compressive stresses given in BS 5628 to which no reductions need apply as the capacity reduction factor, β, has already been calculated as 1.0. The section is therefore adequate in all respects.

The shear at the foot of each column of 3.185 kN should be checked using the manufacturer's recommended values for shear forces on felt dpcs. However, it is unlikely that this will be critical. It is advisable to incorporate butterfly wall ties at the corners of such hollow column sections to reduce the risk of splitting.

Example 10: Perforated External Wall

Details are shown in Figure 11.49 of the external wall in the topmost storey of a multi-storey hotel building for which the wind loading will be assumed to be 0.9 kN/m^2.

For simplicity of analysis, it will be assumed that the roof dead loading is such that under wind loading the uplift effect on the roof is exactly cancelled out by the dead load of the roof. The inner and outer leaves of the cavity wall are to be constructed in brick with a compressive strength of 20 N/mm^2 and a water absorption of 11% set in a designation (ii) mortar. The roof structure is assumed to be capable of providing adequate support to the head of the wall panel.

The design of more complicated elements, such as the perforated wall being considered in this design example, must include a rational judgement of the mode of action of the element, and will not necessarily conform exactly to the simple design procedures already used in the previous examples. The following suggested design method is one of a number of possible solutions.

By inspection, the area of wall between the windows is clearly the most critical for design purposes as the perforations eliminate this area of wall to span in two directions. In addition, this area of wall is also likely to be loaded with its own wind loading, plus wind loading from the windows and wall area above (and possibly below) the windows. As the central area of wall deflects under wind loading, the load supported would tend to shed towards the wall areas either side of the windows which, owing to the buttressing effect of the bonded crosswalls, are considerably stiffer. Consequently, where it might, under different circumstances, be expected that half of the wind on the window areas would be supported on the brickwork each side, it is considered reasonable, in this instance, to take a proportion of this load, less than half, onto the central area of wall under consideration. The area of wind to be supported by the wall area between the windows is shown in Figure 11.50.



Figure 11.49 Loading area for Example 10



Figure 11.50 Area of wind loading

The loading width is calculated as:

central wall = 900 mm

$$\text{windows} = 2 \times 900 \times \frac{3}{8} = 675 \text{ mm}$$

total width= 1575 mm

in which (3/8) of the wind on the adjacent unsupported areas has been taken to the central wall area.

The section of wall below window cill level which will be assumed to be resisting the applied wind bending moment is indicated by the dotted lines on Figure 11.50. The wind on the wall areas immediately beneath the windows could equally be considered to be supported by the cill height brickwork acting as a cantilever.

$$\text{Wind load on central wall area} = W_k \times 1.575 = 0.9 \times 1.575 = 1.42 \text{ kN/m}$$

$$\text{Design wind load} = 1.42 \times \gamma_f = 1.42 \times 1.4 = 1.988 \text{ kN/m}$$

The critical wall area will now be designed as a vertically spanning propped cantilever, and the loading and bending moment diagrams are shown in Figure 11.51.

$$\text{Wall moment} = \frac{9 \times 1.988 \times 2.5^2}{128} = 0.874 \text{ kN m}$$

$$\text{Base moment} = \frac{1.988 \times 2.5^2}{8} = 1.553 \text{ kN m}$$

The design resistance moment at the (3/8)*h* level will be based on the 900 mm wall width, whereas the resistance moment at base level will be based on the loaded width of 1575 mm, as shown to be the effective section in Figure 11.50. A felt dpc has been included at the base of the wall span and the design resistance moment at this level will therefore be based on a 'cracked section' analysis.

Minimum characteristic loads at base of wall:

Outer leaf (density of masonry = 20 kN/m^3):

wall above windows $= 20 \times 0.3 \times 0.1025 \times 1.575 = 0.970$
wall between windows $= 20 \times 1.2 \times 0.1025 \times 0.9 = 2.214$
wall below windows $= 20 \times 1.0 \times 0.1025 \times 1.575 = 3.229$
Total characteristic load, G_k $= 6.413$ kN
per 1575 mm width

$$\text{Inner leaf: (215 mm thick)} = 6.413 \times \frac{215}{102.5} = G_k$$

$$= 13.452 \text{ kN per 1575 mm width}$$

Minimum design loads = $G_k \times \gamma_f$
Outer leaf minimum design load = $G_k \times \gamma_f = 6.413 \times 0.9 = 5.772$ kN
Inner leaf minimum design load = $G_k \times \gamma_f = 13.452 \times 0.9 = 12.106$ kN

Calculate stability resistance moments using stress block shown in Figure 11.26 ($\gamma_m = 2.5$ special).

$$\frac{1.1 f_k}{\gamma_m} = \frac{\text{min. design load}}{w_s \times \text{length of section}}$$

Outer leaf:

$$w_s = \frac{5.772 \times 10^3 \times 2.5}{1.1 \times 6.4 \times 1.575 \times 10^3} = 1.3 \text{ mm}$$

Then

$$l_a = \frac{\text{wall thickness}}{2} - \frac{w_s}{2}$$

$$= \frac{102.5}{2} - \frac{1.3}{2} = 50.6 \text{ mm}$$



Figure 11.51 Loading diagram and bending moment diagram for Example 10

and

$$\text{Design MR} = \text{design load} \times l_a$$

$$= \frac{5.772 \times 50.6}{10^3} = 0.292 \text{ kN m}$$

Inner leaf:

$$w_s = \frac{12.106 \times 10^3 \times 2.5}{1.1 \times 6.4 \times 1.575 \times 10^3} = 2.73 \text{ mm}$$

Then

$$l_a = \frac{215}{2} - \frac{2.73}{2} = 104.77 \text{ mm}$$

and

$$\text{Design MR} = \frac{12.106 \times 104.77}{10^3} = 1.268 \text{ kN m}$$

Total design MR = design MR outer leaf + design MR inner leaf
$= 0.292 + 1.268 = 1.56$ kN m

The section is adequate as the design resistance moment is greater than the applied BM of 1.553 kN m.

Now check the 900 mm wide wall section at (3/8)*h* level.

Outer leaf:

wall above windows $= 20 \times 0.3 \times 0.1025 \times 1.575$
$= 0.970$ kN

wall between windows $= 20 \times (0.94 - 0.3) \times 0.1025 \times 0.9$
$= 1.181$ kN

Total characteristic load, $G_k = 2.151$ kN per 900 width

Inner leaf (215 mm thick) $= 2.151 \times \frac{215}{102.5}$
$= 4.512$ kN per 900 width

Minimum design loads $= G_k \times \gamma_f$

Outer leaf minimum design load $= 2.151 \times 0.9 = 1.936$ kN

Inner leaf minimum design load $= 4.512 \times 0.9 = 4.061$ kN

$$\text{Design resistance moment} = \left(\frac{f_{kx}}{\gamma_m} + g_d\right) Z \text{ per leaf}$$

Total design MR = design MR outer leaf + design MR inner leaf

Outer leaf:

$f_{kx} = 0.4 \text{ N/mm}^2$ (BS 5628, Table 3)
$\gamma_m = 2.5$ special

$$g_d = \frac{1.936 \times 10^3}{900 \times 102.5} = 0.021 \text{ N/mm}^2$$

$$Z = \frac{900 \times 102.5^2}{6} = 1.576 \times 10^6 \text{ mm}^3$$

Inner leaf:

$f_{kx} = 0.4 \text{ N/mm}^2$ (BS 5628, Table 3)
$\gamma_m = 2.5$ special

$$g_d = \frac{4.061 \times 10^3}{900 \times 215} = 0.021 \text{ N/mm}^2$$

$$Z = \frac{900 \times 215^2}{6} = 6.934 \times 10^6 \text{ mm}^3$$

Thus design resistance moment:

$$= \left(\frac{0.4}{2.5} + 0.021\right) \times 1.576 \times 10^6 + \left(\frac{0.4}{2.5} + 0.021\right) \times 6.934 \times 10^6$$

$= 0.285 + 1.255$

$= 1.54$ kN m

This section is adequate as the design MR is greater than the applied BM of 0.874 kN m.

(The combination of this design example is included to demonstrate the difficulties of compliance with clause 36.9.1(b) of the Code which as was discussed in section 6.10 is not considered by the authors to be a practical design approach.)

Now check compliance with clause 36.9.1(b) by designing wall at level M_w as a cracked section. As, at base level, the resistance moment was virtually the same as the applied moment, redistribution of forces and moments will be ignored.

Hence $M_w = 0.874$ kN m and minimum design loads for outer leaf = 1.936 kN and for inner leaf = 4.061 kN.

Now check as 'cracked section'.

Outer leaf:

$$w_s = \frac{2.5 \times 1.936 \times 10^3}{1.1 \times 6.4 \times 1.575 \times 1000}$$

$= 0.44$ mm

$$l_a = \frac{102.5}{2} - \frac{0.44}{2}$$

$= 51.03$ mm

Design MR $= 1.936 \times 0.051\,03$
$= 0.099$ kN m

Inner leaf:

$$w_s = \frac{2.5 \times 4.061 \times 10^3}{1.1 \times 6.4 \times 1.575 \times 1000}$$

$= 0.92$ mm

$$l_a = \frac{102.5}{2} - \frac{0.92}{2}$$

$= 50.79$ mm

Design MR $= 4.061 \times 0.050\,79$
$= 0.206$ kN m

Total design MR = 0.099 + 0.206 = 0.305 kN m which is considerably less than the applied moment of 0.874 kN m and the wall apparently fails. However, the authors expressed concern in Section 6.10 about the implications of this clause of the Code and, until the problem is resolved, recommend that the design moment of resistance in the wall height (at M_w level) is based upon its flexural tensile resistance and not its cracked section resistance.

12 Design of Single-storey Buildings

Society requires a large number and a wide range of single-story structures – not just for factories, garages and warehouses, but also for primary schools, theatres, churches, sports halls, libraries, etc.

12.1 Design Considerations

The design requirements can best be appreciated by considering the structural problems common to all types of walls in single-storey structures. Open-plan buildings (i.e. with no internal walls) will be discussed in particular since, structurally, these represent the worst case.

(a) Vertical Loads

The vertical compressive load is rarely the critical factor in the design of masonry walls since the dead load of the roof, and its imposed load are relatively light compared with multi-storey structures. Often, the wind suction on the roof is equal to, or greater than, its dead weight, and design cases frequently arise where that wall is subject to no vertical loading (other than its own weight) and the loading is mainly lateral.

(b) Bending Stresses

The bending stresses due to wind are critical, particularly the tensile stress due to bending, which is referred to in BS 5628 as 'flexural tension'. If the wall is treated as a free cantilever, with a uniformly distributed wind load, the maximum bending moment will be $ph^2/2$. On the other hand, if the roof is used to prop the wall, and a pinned joint is assumed at the base, the wall acts as a simply supported beam with a maximum free bending moment due to wind of $ph^2/8$ (see Figure 12.1).

(c) Roof Action

To enable the roof to prop the wall, so that the wall can span as a simply supported beam, as described in (b) above, it is not sufficient to merely fix the roof beams to the top of the wall because the wall could still act as a free cantilever (see Figure 12.2).

The roof must act as a plate or a wind girder so as to transfer the wind force to the gable or other transverse walls. A simple method of meeting this requirement is to fix diagonal bracing between the roof beams and purlins, this forming in effect a horizontal lattice (or wind girder), as shown in Figure 12.3. It is essential, of course, that the roof is properly strapped and tied to the walls as described in Chapter 7.

(d) Stability Moment

In the free cantilever shown in Figure 12.4, the resistance of the wall to overturning, due to the force P, is its stability moment. To over-simplify for the sake of clarity, consider the stability moment of a wall = own weight of wall × its lever arm, i.e. $W \times d/2$. If the moment due to the wind is greater than the stability moment, the wall will crack at the dpc level on the windward face, and rotate at the hinge on the leeward face.



Figure 12.1 Single storey wall behaviour with and without roof prop



Figure 12.2 Roof prop behaviour



Figure 12.3 Roof bracing



Figure 12.4 Stability moment of cracked section

The stability moment provides some fixity at the base of the wall, and is not dependent on the structural action of the wall as a free or propped cantilever, or partially restrained simply supported beam, etc. The stability moment is a resistance moment and, like any resistance moment in any structural element, is passive until activated by applied bending moments due to loading. The magnitude of the active stability moment is dependent on both the magnitude of the bending moment due to loading and any movement of the roof prop, if it is provided (see (e) Knife-edge condition, p. 175). The magnitude of the potential stability moment depends on the wall's own weight and its lever arm. The thicker a wall, the greater its own weight and lever arm, and, therefore, its stability moment.

In a diaphragm wall (see Chapter 13) the stability moment can be increased by increasing the depth of the void – thus increasing the lever arm.

Example

Determine the stability moment of a 210 mm thick solid wall, a 315 mm thick solid wall and a diaphragm wall with two leaves 102.5 mm thick and a void of 210 mm. The walls are 3 m high and built of brickwork with a density of 20 kN/m^3 (see Figure 12.5).



Figure 12.5 Various wall profiles

Wall (a):

Weight $= 3 \times 0.210 \times 20 = 12.6$ kN/m run of wall

Lever arm $= \frac{210}{2} = 105$ mm $= 0.105$ m

Stability moment $= 12.60 \times 0.105$ m $= 1.32$ kN m/m run

Wall (b):

Weight $= 3 \times 0.315 \times 20 = 18.90$ kN/m run

Lever arm $= \frac{315}{2} = 157.5$ mm $= 0.1575$ m

Stability moment $= 18.90 \times 0.1575$ m $= 2.977$ kN m/m run

Wall (c):

Weight (ignoring cross-ribs) $= 3 \times (2 \times 0.1025) \times 20 = 12.30$ kN/m run

Lever arm $= \frac{210 + (2 \times 102.5)}{2} = 207.5$ mm $= 0.2075$ m

Stability moment $= 12.30 \times 0.2075$ m $= 2.55$ kN m/m run

The stability moment is zero at the top of the wall (since there is no own weight there) and increases uniformly, if the wall is of a constant thickness, to a maximum at the base where the full weight of the wall acts. Thus the stability moment diagram is as shown in Figure 12.6.

It should be appreciated that there is a fundamental difference between the resistance moment of steelwork or reinforced concrete and the stability moment of masonry. When the bending moment exceeds the resistance moment in steel or reinforced concrete, the resistance moment is destroyed once and for all. On the other hand, in unreinforced masonry, the stability moment is not destroyed – although it may be temporarily reduced – and on relief of the bending moment is fully restored. The example which follows may help to clarify this point (Figure 12.7).



Figure 12.6 Single leaf wall and stability moment

If the bending moment due to the force P exceeds the resistance moment of the reinforced concrete, the reinforcement will fail and the cantilever will have a greatly and permanently reduced moment of resistance. A similar result will occur in the steel cantilever if the tensile weld fails. In the masonry cantilever, the lever arm will decrease slightly, as the wall tilts and thus decrease the stability moment. However, when the force P is removed, the wall will settle back into its original position and recover its full stability (resistance) moment. Since, in practice, the design force P is the maximum wind force likely to occur in the life of the building (e.g. a three second gust, once in fifty years) it is of very short and temporary duration.

Combined bending moment diagram

If the wall is propped at the top, the free bending moment due to the wind force is, as mentioned earlier, that of a simply supported beam subject to a uniformly distributed load and the maximum is $ph^2/8$. Superimposed on this is the active part of the stability moment (see Figure 12.8).

It can be shown that the maximum moment at the base due to the roof propping force, R, which is activated by wind force P/unit area, is $ph^2/8$, i.e. the propped cantilever bending moment. If this does not exceed the stability moment, the wall will act as a propped cantilever and the maximum bending moment, in the span of the wall, will be $9ph^2/128$ acting at $(3/8)h$ down the wall from the prop.

(e) Knife-edge Condition

In practice, it is not possible to form a perfectly propped cantilever – just as it is difficult to form a perfectly pinned or fixed joint. Since the roof plate will be stressed, it will strain and deflect. It can be shown that deflecting the free end of the cantilever by an amount Δ will induce a moment at its support of $3EI\Delta/L^2$ (see Figure 12.9).

For a 210 mm wall,

$$I = \frac{bd^3}{12} = \frac{1000 \times 210^3}{12} = 7.718 \times 10^8 \text{ mm}^4$$

For brickwork, E_b can be taken $= 8.68 \times 10^6$ kN/m^2 (medium strength brick in 1 : 3 mortar). For a 25 mm deflection at the top of a 3 m high wall:



Figure 12.7 Comparison of steel, concrete and masonry cantilevers



Figure 12.8 Combined bending moment diagram for stability moment



Figure 12.9 Theoretical knife-edge condition

$$M = \frac{3EI\Delta}{L^2}$$

$$= \frac{3 \times 8.68 \times 10^6 \times 7.718 \times 10^{-4} \times 25 \times 10^{-3}}{3 \times 3}$$

$$= 55.8 \text{ kNm/m}$$

The stability moment for a 210 mm wall, 3 m high is 1.32 kN m/m (see earlier).

The moment at the base of the wall, due to deflection at the top, is far in excess of the stability moment. Thus, the wall will crack at the base or dpc, and will rotate, but not collapse (see Figure 12.10).

Theoretically, the whole weight of the wall will be concentrated on a knife-edge of zero contact area and there will be an infinitely high compressive stress at point A (see Figure 12.11).

In practice, of course, the dpc or mortar will deform and the contact area will increase from the knife-edge condition, and thus the compressive stress will decrease.



Figure 12.10 Base of wall cracking and subsequent rotation



Figure 12.11 Subsequent knife-edge support



Figure 12.12 Actual contact area

The contact area, see Figure 12.12, will now be 12 mm × 1 m per metre run and

$$\text{Compressive stress} = \frac{12.6 \times 10^3}{12 \times 10^3} = 1.05 \text{ N/mm}^2$$

From the above, it will be seen that the moment at the base cannot exceed the stability moment – if it does, the wall cracks at the base and only the stability moment is operative.

(f) Tying Down of Roof

It is not uncommon with lightweight roofs for their dead (downward) load to be less than the suction (upward) force due to wind action (see Figure 12.13).

If the roof is not strapped down to the walls, or fixed to a concrete capping beam that weights it down to the walls, it



Figure 12.13 Wind suction on lightweight roofs

will lift off. A factor of safety against uplift of 1.4 is usually adopted (see Chapter 7).

(g) Slenderness Ratio

If the roof acts as a horizontal stiff plate or wind girder, and is properly fixed to the top of the wall, the wall can be considered as being adequately restrained laterally, and its effective height can be considered as being equal to its actual height. If the roof does not properly restrain the wall, the effective height should be taken as 1.5 times the actual height.

The effective thickness of walls has been dealt with in previous chapters.

The slenderness ratio must not exceed 27. So, for a 215 mm thick wall, properly restrained by the roof, the maximum height = 210 × 27 = 5.67 m. A 305 mm cavity wall (effective thickness two thirds the sum of thickness of the two leaves = 137 mm) must not exceed a height of 27 × 137 = 3.7 m. However walls of this height and thickness could not withstand normal wind pressures. As stated at the beginning of this chapter, the vertical compressive load is rarely a critical design factor in practice – since the roof loading is comparatively light. It follows, therefore that the slenderness ratio is equally rarely a critical design factor,

(h) Robustness/Disproportionate Collapse

Consideration must be given to the robustness of the structure (see Chapters 7and 8). Since the main contribution to robustness in a single-storey open-plan structure comes from the interaction and connections of the walls and the roof, it is essential to ensure that the roof is properly and adequately braced, and firmly fixed to the walls. The Building Regulations, Part A, 2004 include some single-storey structures as either Class 2A or 2B, which means that the structure must have horizontal ties or both horizontal and vertical ties. This is likely to dictate the form of wall and roof construction, particularly for large open-plan, single-storey buildings. Vertical ties in external and internal masonry walls will need to be tied to say steel roof trusses. The ceiling form will need special consideration as it will need to be tied to the walls. This requirement is likely to necessitate the need for a reinforced concrete roof. Plywood is unlikely to achieve the tying requirements.

The design of large area single-storey structures are likely to become more onerous under The Building Regulations, Part A, 2004, but this is possibly only a reflection of how engineers have or should have designed these structures previously, to be robust.

12.2 Design Procedure

Usually it is the height (vertical span) of the wall and the bending tensile stresses (flexural tension) that will develop which govern the wall's type and thickness. The stresses at the base and the position of the maximum bending moment in the wall's height must be checked.

For low walls, up to about 4 m depending on the wind pressure at the side, the normal solid or piered cavity wall may suffice.

For medium-height walls, up to about 5 m, solid or cavity walls will need stiffening with piers or thickening.

For tall walls, possibly more that 5 m in height – and almost certainly when the height exceeds 6 m – fin or diaphragm configurations should be considered.

For tall walls, check the application of post-tensioning to produce a more economical design (see Chapter 15).

The design procedure is as follows:

(1) Calculate the position and negative wind pressures.
(2) Calculate the dead, imposed and wind loading on the wall from the roof.
(3) Decide on the best distribution of structural *elements* and the overall behaviour of the structure and element interaction (see Chapter 7).
(4) Select a trial section (solid, cavity, piered, diaphragm, fin) and thickness. Check whether the use of post-tensioning is appropriate. Check the slenderness ratio.
(5) Determine the strapping down or weighting down of the roof.
(6) Check the roof plate action, i.e. provide adequate bracing and its connection to the shear walls. If there are crosswalls, or other internal transverse walls used for permanent partitions, fire breaks, etc., use should be made of them to reduce the span of the roof plate or wind girder.
(7) Determine the free bending moment, $ph^2/8$, the propped cantilever span moment, i.e. $9ph^2/128$ and the stability moment at the base of the wall.
(8) Calculate the position and magnitude of the maximum wind moment in the height of the wall, and the resistance moment of the wall, and compare.
(9) Check stresses at the base of the wall, and at the position of the maximum span moment.
(10) Revise trial section, if necessary.
(11) Choose masonry unit and mortar strengths.
(12) Calculate shear stresses.
(13) Check the stability of the transverse walls (shear walls) for roof plate wind reaction.

13 Fin and Diaphragm Walls in Tall Single-storey Buildings

The authors' experience on sports halls, gymnasia, stadia, assembly halls and structures of similar form has shown that fin and diaphragm walls are well suited to tall single-storey buildings enclosing large open areas. Such buildings account for a large number of the projects constructed in Britain, and throughout the rest of the world, and their importance is particularly relevant with the present trend in this country towards providing facilities for public recreation and leisure. The vast majority of these structures have a steel or reinforced concrete framework supporting the roof loads. The framework columns are then enveloped by a cladding material, backed up by an insulating barrier and protected on the inner face by a hard lining. Frequently, the cladding, insulation and lining require a subsidiary steel framework to provide support, and both the main frame columns, and sometimes the subsidiary frame also, require fire protection. The specification for painting the structural framework depends upon its degree of exposure and accessibility, and in unfavourable conditions the costs against this item can be unexpectedly high. The resulting 'wall' thus requires up to six different materials and several sub-contractors, suppliers and trades. The framework and cladding require frequent maintenance and do not provide the durability afforded by the use of masonry for the same purpose, neither do they possess the same aesthetic qualities which are natural in masonry construction and which can be greatly enhanced by imaginative detailing.

The fin or diaphragm wall forms the structure, cladding, insulation, lining, and fire barrier in one material, using one trade carried out by the main contractor. Maintenance is minimal, applied protective coatings are eliminated and durability is virtually ensured. They also have obvious applications to industrial structures where robustness to resist the hard wear of the associated operations is of prime importance. Vandal resistance is an added bonus to all projects employing fin and diaphragm wall construction.

Masonry, like all other structural materials, requires a full understanding of its strengths and weaknesses in order to employ it economically. Masonry's previously stated main weakness, low tensile strength, can be compensated for in design by providing a high Z/A ratio when bending stresses are involved. It is equally important to take full advantage of the gravitational forces involved, and the combination of these two aspects of masonry design led to the development of the diaphragm wall. An alternative solution to overcome masonry's poor tensile resistance is to provide precompression in the wall through post-tensioning rods spaced at designed centres and torqued to provide the axial loading which is usually missing from tall single-storey structures. This alternative is discussed later in this chapter and in Chapter 15.

In order to exploit both the highest Z/A ratio and gravitational resistance, the geometric distribution of the materials should be similar – that is, to place the material at its largest practical lever arm position. In arriving at the most suitable geometric profile, due consideration must be given to the shear forces involved and to the buckling tendency of the material in the compression zone of the profile.

For practical considerations, the geometric arrangement of the wall must also relate to multiples of standard brick or block dimensions.

A diaphragm wall comprises two parallel leaves of brickwork or blockwork spaced apart and joined by perpendicular cross-ribs placed at regular intervals to form box or I sections (see Figure 13.1 and 13.2).

The two parallel leaves of the wall act as flanges in resisting the bending stresses and are stiffened by the ribs acting as webs mainly resisting shear forces. The length of the parallel leaves, which may be considered to act with the cross-ribs, is often limited by their tendency to buckle and, therefore, the section is best appraised as an I section. The length of the flange of the I section is established in a similar way to that of the T beam in reinforced concrete design, which should be familiar to many designers. The depth between the flanges is designed to meet the individual structural and other requirements of each project. Costs and space are usually minimised by designing the shallowest depths practicable.

The fin wall was developed from the diaphragm wall and its general form is shown in Figure 13.3. The masonry T section formed by the projecting fin and the bonded leaf of the cavity wall provides the main supporting member of the structure, while the other leaf of the cavity wall provides either the lining or the cladding depending on whether the fins are externally or internally exposed. The whole fin plus the cavity wall is used in determining the slenderness ratio of the section, and a calculated length of the wall is considered to act with the fin as the flange of the T profile in resisting the lateral loading. It is more common to expose the projecting fins externally, as this is usually the preference of the architectural designer and greater structural economy can be achieved. However, they can be exposed internally, and the design principles involved are similar, although careful consideration must always be given to the direction of the loading, and the section available at a particular level to resist it. Disproportionate collapse regulations



Figure 13.1 General arrangement of diaphragm wall profiles



Figure 13.2 Diaphragm wall box and I section



Figure 13.3 Fin wall arrangement

need to be considered in choosing the particular form to use (see Chapter 8).

13.1 Comparison of Fin and Diaphragm Walls

Having concluded that, for a particular tall single-storey project, masonry is the most suitable structural material, the next decision to be made is what form: fin, diaphragm or any other, to use for the structure. Regarding fin and diaphragm walls, each has some advantages over the other and a summary of the basic considerations is given below, from which the form most suited to the function or aesthetics of the particular project can be assessed.

Diaphragm Wall

(1) Smooth, finished face both internally and externally.
(2) Better structural use of materials.
(3) Large voids are available for distribution of services, etc.
(4) No cavity ties in bonded walls.
(5) Symmetrical section for simplicity of analysis.
(6) Fewer vertical plumbing lines reduces labour costs.
(7) Smaller site area is required – beneficial on restricted sites.
(8) Slight cost saving.

Fin Wall

(1) Less roof area is required (see Figure 13.4).
(2) Less foundation area is required (see Figure 13.5).



Figure 13.4 Comparison of roofing areas



Figure 13.5 Comparison of foundation areas

(3) Has greater visual impact – more scope for architectural effect.
(4) Marginally easier to post-tension when required.
(5) Less cutting of bricks for bonding can usually be achieved.

Both the fin and the diaphragm walls become more economical, in comparison with other structural forms such as steel or reinforced concrete frameworks, as the height of the wall increases, and they are of little advantage on lower heights where normal cavity brickwork can often satisfy all the structural requirements. For further discussion on the application of fin and diaphragm walls, see section 13.11 and Chapters 10, 11, 12 and 14.

13.2 Design and Construction Details

Thorough consideration of the structural behaviour of the roof of the building is imperative for the maximum economy to be achieved in the overall building costs. The wall may be designed as a cantilever and the structure covered with the simplest possible roof construction. However, it has generally been found that, to obtain the greatest economy, the roof should be detailed and constructed in such a way that it can act as a horizontal plate to prop and tie the tops of the walls and to transfer the resulting horizontal reactions to the transverse walls of the building, where these reactions can then be transferred to the building foundations through the racking resistance of these shear walls (see Figure 13.26). To satisfy this design analysis, the details must provide adequately for fixing the tops of the walls to the roof plate, the roof plate must be capable of spanning between the shear walls, and the forces must be transferred from the roof plate into the shear walls.

A capping beam can be used on top of the wall to transfer the prop and tie forces into the roof plate. This has the potential advantage of being able to resist uplift forces from a lightweight roof and also of transferring the roof plate



Figure 13.6 Roof girder to transmit wind forces to shear walls

forces into the shear walls if the capping beam is continued all round the building. If, due to large roof openings or unsuitable decking, the plate action of the roof cannot be relied upon, a wind girder may be provided (see Figure 13.6), in which case the capping beams can often be used as booms for this girder.

The roof decking can be constructed from a variety of materials and supported in many ways. Generally, steel universal beams, castellated beams or lattice girders have been found to be the most economical means of support, spaced at centres to suit the selected decking. They do not necessarily need to relate to the centres of ribs or fins. However, in fin wall construction, the geometry of the building invariably leads to the roof supporting members lining up with the projecting fins. For long roof spans, a space deck can prove to be more economical, and the aesthetic value of this system combined with its economy, when applicable, makes it a popular proposition. Alternatively, timber laminated beams with solid timber decking may be used with considerable visual effect, although their economy would need to be balanced against the attractiveness of the finished product. The simplest solution in timber is, perhaps, provided by trusses with a suitably designed bracing system.

A capping beam is generally required at the top of diaphragm walls. However, for both fin and diaphragm walls where no capping beam is to be used, the main roof beam often requires strapping down to resist wind uplift forces. This can be quite easily done using rods cast into the padstone and taken down into the brickwork to a suitable level to ensure sufficient dead load, with an adequate factor of safety, to resist the uplift forces (see Figure 13.7).

When assessing the overall costs of the roof decking, it is necessary to take account of the value of its ability to act as a roof plate to resist the prop and tie forces discussed earlier. If an apparently less expensive roof decking is selected, any additional costs for strapping, bracing, etc., which would not necessarily have been required for apparently more expensive decking, must be included to arrive at the overall cost.



Figure 13.7 Anchoring detail for main roof beams



Figure 13.8 Typical simple building plan in fin wall construction

13.3 Architectural Design and Detailing

It is generally considered that the fin wall provides greater scope for architectural expression than the diaphragm wall. A typical simple plan layout for a fin wall building is shown in Figure 13.8 and an almost unlimited number of variations can be applied to this basic profile.

The sizes and spacing of the fins can vary, and the corner fins can be eliminated altogether as shown in Figure 13.9.

The fins themselves can be profiled on elevation, some examples of which are indicated in Figure 13.10.

The treatment at eaves level (see Figure 13.11) and the variety and mixture of the facing bricks and fin types can present unlimited and interesting visual effects.

A word of caution, however. When a mixture of bricks is to be introduced it is essential to ensure that the various bricks and/or blocks are compatible, particularly with regard to thermal and moisture movements. The structural design calculations must also take account of the differing design strengths of the masonry under these circumstances. The diaphragm wall also has possibilities for architectural expression and some examples of its treatment at roof level are shown in Figure 13.12.

It is not essential that diaphragm walls should be designed with flat faces on elevation and, particularly on tall buildings, a fluted arrangement as shown in Figure 13.13 can break up a large expanse of brickwork.



Figure 13.9 Fin variations



Figure 13.10 Typical fin elevations



Figure 13.11 Example of treatment at eaves for fin walls



Figure 13.12 Detail at head of diaphragm wall



Figure 13.13 Fluted diaphragm

The cross-ribs should, from a structural preference point of view, be bonded into the inner and outer leaves, in which case they show as headers on the elevations. A different coloured brick used for the cross-ribs can create an interesting feature. It is, however, also possible to allow the cross-ribs to butt up to the inner faces of the elevational leaves, in which case the stretcher bonding would remain uninterrupted. In such a situation, designed shear ties are necessary to tie the ribs to both the inner and outer leaves to resist the shear forces involved, and it is essential to provide in the specification adequate protection for the ties to ensure that they are sufficiently durable to resist corrosion. The amendment to Part A of The Building Regulations, 2004 specifies stainless steel cavity wall ties for all house construction, which implies stainless steel ties should be used in all construction involving masonry. The cost implications of bonded or unbonded cross-ribs vary from job to job, but it is unlikely to have a significant effect on the overall cost appraisal. Once again, the introduction of a different brick for the cross-ribs, or the inner-leaf, would require the same check for compatibility and design strengths as was discussed earlier.

13.3.1 Services

The accommodation of building services within diaphragm wall structures presents few problems owing to the large vertical voids in the wall section. The services can be placed in service ducts incorporated into the wall profile, as shown in Figure 13.14, or can be run inside the void with access points built into the relevant leaf as required.

Openings for such access points must be checked for the possibility of local overstressing in the brickwork. Service ducts housing gas pipes placed within diaphragm wall



Figure 13.14 Accommodation of service duct in diaphragm wall



Figure 13.15 Service duct detail in fin wall

voids should, of course, be ventilated. Careful consideration must always be given to the possibility of corrosion of services within these locations.

The accommodation of building services within fin wall structures is no different from that for normal cavity walls. If necessary, however, the fin profile can be made, as shown in Figures 13.9 and 13.15, to include a void for the distribution of services and the same basic considerations apply as have been discussed for the services within diaphragm walls. Both the diaphragm wall and voided fin wall are particularly suited to the inclusion of rainwater downpipes.

13.3.2 Sound and Thermal Insulation

Fin walls have almost the same sound and thermal insulating properties as normal cavity walls, and the same criteria for the improvement of both of these properties apply.

Diaphragm walls, however, because of the large internal void, possess better prospects for both sound and thermal insulation. Insulating boards and quilts of varying thicknesses can be quite easily fixed inside the void, as shown in Figure 13.16, however, the *U* value of a basic diaphragm wall is estimated to be approximately 10% higher than an equivalent traditional cavity wall owing to the greater air circulation within the larger void.

13.3.3 Damp Proof Courses and Membranes

Horizontal damp proof courses should be selected to give the necessary shear resistance to prevent sliding and should not squeeze out under vertical loading. Where flexural tensile resistance has been assumed in the structural design, particular care should be exercised in the choice and construction supervision of the damp proof course. In fin wall construction, vertical damp proof membranes separating the inner and outer leaves at door and window openings create fewer structural problems than with diaphragm walls, and can generally be quite easily accommodated. Vertical damp proof membranes are not normally necessary within diaphragm walls, except at door and window openings, provided that bricks and mortar of suitable and compatible quality are used to suit the environmental conditions. Most vertical damp proofing membranes prevent the tying of the cross-ribs to the elevational leaves and should be avoided wherever possible as this would impair the box action of the compound wall profile. If required, a bitumen based painted dpc, used in conjunction with metal shear ties, can be used in these locations. At door and window openings however, vertical damp proof membranes can be incorporated by the introduction of additional cross-ribs, as shown in Figure 13.17.

13.3.4 Cavity Cleaning

There is little difference between fin walls and ordinary cavity walls with regard to the problems of cavity cleaning. With diaphragm walls, however, this problem is significantly reduced owing to the large void and, provided that normal care is exercised during construction, no elaborate methods are necessary for cleaning out the voids.

13.4 Structural Detailing

It is essential for any structural scheme to ensure that the assumptions made in the design process are adequately provided for in the detailing and construction on site. This is equally true of masonry structures, and there is perhaps a good argument to suggest that masonry structures require slightly more attention to detailing than other forms



Figure 13.16 Insulation fixing detail in diaphragm wall



Figure 13.17 Vertical damp proof course at openings in diaphragm wall

of construction. Masonry structures have become accepted as the traditional type of building in which well-tested details of construction have evolved and become commonplace. This has had the effect of implanting the notion that, if it is a masonry structure, the traditional construction details will solve the structural aspects and hence an engineer's services are unwarranted. This was not an unreasonable attitude when the term 'masonry structure' automatically implied 'massive structure'. However, with the modern trend towards minimising the mass of the structure, to reduce both material and labour costs, such an attitude is likely to result in unstable construction. The services of engineers are warranted more today than at any other time in relation to masonry structures, and the wide scope for architectural design provided by fin and diaphragm walls is the most recent example of the value of their contribution. This contribution should not be limited to the provision of wall thicknesses and strengths, but should include an assessment of the economies to be achieved from the most suitable combination of all the structural elements of the building. Having advised on the most suitable combination of these elements, the most important task is to ensure that they are correctly detailed and constructed in relation to each other.

13.4.1 Foundations

Generally speaking, the foundations to both fin and diaphragm walls comprise simple strip footings, as shown in Figures 13.18 and 13.19, slightly wider than normal for the diaphragm wall and with local projections to support the fins in fin wall construction. The bearing pressures involved for both wall types are invariably so low that nothing more is necessary for a site which does not have a particular soil problem. Whatever problems are presented by the subsoil conditions, the foundation solution for fin and diaphragm walls is no more complex than for a traditional masonry structure and, in fact, the considerable stiffness provided by these geometric forms, combined with



Figure 13.19 Typical fin wall strip footing

their relatively lightweight construction, has created new scope for masonry structures on difficult sites. An example of this is the sports hall of a community centre for which the authors were responsible for the structural design, and which was constructed using post-tensioned diaphragm wall construction. The foundation adopted was a cellular raft, which was necessary to cater for ground subsidence resulting from the future coal extraction beneath the site. The first of these subsidence waves from the mine workings has since traversed the site resulting in a maximum subsidence of approximately 1080 mm with a maximum out-of-level across the sports hall itself of approximately 130 mm. The relatively lightweight superstructure construction permitted an economical foundation design and the success of the walls is self-evident in that there is no evidence whatever of cracking or distress in the masonry due to the subsidence movements which have occurred. A structure has therefore been provided which can withstand these massive subsidence movements with virtually no attendant maintenance implications to the client.

13.4.2 Joints

Movement control joints are required in both fin and diaphragm wall construction, their requirements being no different from that for simple loadbearing masonry, the recommendations for which are given in BS 5628, Part 3. In fin wall construction, the joints are best accommodated by introducing a double fin with the joint sandwiched between (see Figure 13.20). Similarly, with diaphragm walls, a double rib can be provided as shown in Figure 13.21.



Figure 13.18 Typical diaphragm wall strip footing



Figure 13.20 Provision of control joint in fin wall



Figure 13.21 Movement joint detail in diaphragm wall

Invariably, the materials adopted for the inner leaf of fin walls or the inner face of diaphragm walls differ from those of the external faces. It is often necessary in these circumstances to provide control joints at closer centres on the inner faces, and these intermediate joints may not necessarily demand double fins or double ribs. Any joints which are introduced into the wall leaf, however, must be located with careful consideration to the design assumptions which may have been made with respect to that wall panel, i.e. the possibility of the wall panel having been designed to span horizontally between fins, etc.

13.4.3 Wall Openings

Large door and window openings can create high local loading conditions from the horizontal wind loading and concentrated axial loads at the lintel supports. In both fin and diaphragm walls, these openings can easily be accommodated with an adjustment to the fin or rib sizes and/or spacing at the lintel bearings (see Figures 13.22 and 13.23). The designer must allow, in his calculations, not only for the increased vertical and horizontal loading involved at these locations, but also for the change to the geometric wall profile available to resist the increased loading.



Figure 13.22 Typical opening details in fin wall

13.4.4 Construction of Capping Beam

Where appropriate, it is preferable from a structural point of view to cast the rc capping beam insitu. However, the beam can be precast, ideally in bay lengths, with a suitably detailed connection between to transfer the relevant forces at the joints. Precasting appears to be the more popular solution with contractors, as it eliminates the problems of protecting facing brickwork from wet concrete runs and also saves the expense of the temporary/permanent shuttering that is required for the insitu construction. A better quality finish can also be achieved with precasting if the capping beam is to be exposed. The capping beam is used as the seating for the roof structure, as shown in Figures 13.24 and 13.25, and can be used, either alone or as part of a horizontal wind girder, to transfer the propping force at the head of the wall to the gable shear walls.

13.4.5 Temporary Propping and Scaffolding

Like most other walls, fin walls and diaphragm walls are in a critical state during erection prior to the roof being fixed, particularly when they have been designed as propped cantilevers. During this period, the contractor must take the normal precautions, such as temporarily propping the walls from the bricklayers' scaffolding or other means, to ensure stability. All propping must be suitably designed by a competent person for the loading involved. Owing to the



Figure 13.23 Treatment at openings in diaphragm wall



Figure 13.24 Capping beam detail in diaphragm wall



Figure 13.25 Capping beam detail in fin wall

inherent stiffness of both the fin and the diaphragm wall, the problem of temporary stability is considerably reduced from that of a simple wall, however, the height to which these walls are likely to extend must be taken into account in assessing the propping requirements.

It is recommended that, for both fin and diaphragm wall construction, scaffolding is erected both internally and externally to ensure not only good line and plumb but also complete filling of all bed and perpendicular mortar joints. This is particularly important at the fin and rib locations, and it is considered that working over-hand from a single scaffold platform is more likely to result in poor workmanship. The double-face scaffolding arrangement should consequently provide an adequate means of temporary propping.

In fin wall construction the scaffolding on the fin face of the wall must be erected in such a way as to allow the fins to be constructed at the same time as the main wall. Contractors may prefer to place the scaffold against the wall face, leaving pockets in the wall with the intention of block-bonding the fins into the main wall at a later date. This should not be permitted, as it not only presents a hazard in its temporary state but, more importantly, the bonding and filling of the pockets are likely to result in an inferior quality of construction, possibly far removed from the section analysed in the calculations. It is usually essential that the fins are constructed as each course rises and the scaffolding should be arranged to cater for this requirement.

Whenever temporary propping is required, i.e. when the roof structure is necessary to prop the head of the wall in the final condition, it is the designer's responsibility to bring this to the attention of the contractor and to ensure that the contractor provides a construction method that recognises this fact.

13.5 Structural Design: General

For single-storey buildings the critical design condition is rarely governed by axial compressive loading rather by lateral loading from wind forces or the requirements to satisfy the disproportionate collapse regulation if applicable to the structure. The limiting stresses are generally on the tensile face of the wall and it is therefore necessary to provide structural elements which are best equipped to limit these tensile stresses. Thus the development of the fin and diaphragm wall profiles, in which the material of the wall is placed at a greater lever arm than conventional walls, significantly reduces the tensile stresses and in turn increases the moment of resistance of the section.

Having provided the most efficient element to reduce the flexural tensile stresses, two further considerations should be made to improve even more on this efficiency, these being:

(a) To use the roof plate as a prop to the head of the wall, transferring this propping force to the gable shear walls through the stiffness of the roof plate, or through a suitable bracing system provided for the purpose, as shown in Figure 13.26. This enables the wall element to be designed as a propped cantilever, reducing the applied bending moment in the height of the wall and thus reducing the critical flexural tensile stresses.
(b) The use of post-tensioning, as shown in Figure 13.27, to increase the axial compressive stresses in the wall element and reduce the flexural tensile stresses.

Consequently, both fin and diaphragm walls, when used in tall single-storey buildings, are usually designed as propped cantilevers and the critical loading condition to consider is that of combined dead and wind loading (or accidental load where applicable, see Chapter 8). This takes into account the maximum wind uplift on the roof, and thus the maximum flexural tensile stresses within the masonry. The maximum compressive stresses (resulting from combined dead plus superimposed plus wind loading) in a diaphragm wall are, generally, so low that the selection of a suitable brick and mortar is based almost entirely on the minimum requirements for durability and absorption. For fin walls, however, these maximum compressive stresses can become more critical, particularly when the compressive stresses at the extreme end of the fin are considered, as will be demonstrated in the worked example to follow. Hence, for fin walls, the selection of a suitable brick and mortar combination is more likely to be governed by the required compressive strengths as well as the durability and absorption criteria.

Calculations are carried out on a trial-and-error basis, by adopting a trial section and then checking the critical stresses. Guidance for the assessment of trial sections for both fin and diaphragm walls is given in the worked examples which follow.

13.5.1 Design Principles: Propped Cantilever

Within the height of the wall, there are two locations of critical bending moments:



Figure 13.26 General arrangement of fin wall structure



Figure 13.27 Post-tensioned fin wall details

level A: at the base of the wall, which is usually at dpc level; *level B*: at a level approximately (3/8)*h* down from the top of the wall (see Figure 13.28).

Owing to the unsymmetrical shape of the fin wall, it is essential to check the stresses at both levels and for both directions of wind loadings. However for the diaphragm wall, only the more onerous direction of wind loading need be considered, which is usually that of wind pressure.

The lateral loading will partly dictate the spacing of the fins in fin wall construction, and the spacing of the leaves and centres of the ribs in diaphragm wall construction. These aspects will be considered in greater detail in due course.

13.5.2 Calculate Design Loadings

It is essential to consider, at each stage of the design process for both fin and diaphragm walls, the worst combination



Figure 13.28 Wall actions showing bending moment diagrams.



Figure 13.29 Adjusted design bending moment diagrams

of loading relevant to the particular check being carried out. For example, if roof uplift is likely to occur, this will affect not only the flexural tensile resistance in the height of the wall but also the fixing moment of resistance for the 'cracked section' to be designed at the base of the wall. Concentrated axial loading at lintel bearings, combined with the concentration of roof uplift forces at the same location, must also be given due consideration.

13.5.3 Consider Levels of Critical Stresses

For a uniformly distributed load on a propped cantilever of constant stiffness with no differential movement of the prop, the bending moment diagram would be as shown in Figure 13.29, case (a).

However, in reality, for both fin and diaphragm walls, some deflection will occur at the head of the wall (prop location for the propped cantilever design), and the walls are not of constant stiffness throughout their height as the stability resistance moment at any particular level is related to the vertical load in the wall at that level and this is not constant. It is, therefore, a coincidence if the resistance moment at the base is exactly equal to $ph^2/8$, which is applicable to a true propped cantilever, as will be explained. The upper level of critical stress does not necessarily occur at $(3/8)h$ from the top of the wall, but should be calculated to coincide with the point of zero shear on the adjusted bending moment diagram. The second level of critical stress to be considered will still occur at the base of the wall. This aspect of the design process is analysed in greater detail in the calculation of design bending moment below.

13.5.4 Design Bending Moments

It has been assumed that the wall acts in a similar manner to a propped cantilever, 'propped' by the action of the roof plate and 'fixed' at the base by virtue of its self-weight, the net weight of the roof structure and zero flexural tensile strength at the base. The fixed-end moment at the base due to the vertical loads is termed the 'stability moment'. Any wall has a stability moment of resistance (MR_s) throughout its height which reduces in value nearer to the top of the wall owing to the reduced self-weight. The stability moment of resistance (MR_s) effectively augments the design flexural strength of the wall at the higher level. However, the reason for taking zero flexural tensile strength at the base, even if a dpc capable of transferring tensile stresses is adopted, requires further explanation and involves the application of 'plastic' analysis.

The 'plastic' analysis of the wall action considers the development of 'plastic' hinges (or 'crack' hinges) and the implications of the mechanisms of failure. Referring to Figure 13.30, three plastic hinges are necessary to produce failure of the propped cantilever shown, and these will occur at locations A, B and C. Location C, the prop, is taken to be a permanent hinge, hence, under lateral loading, the two hinges at A and B require full analysis.

As the lateral loading is applied the wall will flex, moments will develop to a maximum at A and B and the roof plate action will provide the propping force at C.

As the roof plate is unlikely to be sensibly rigid, some deflection must be considered to occur which will allow



Figure 13.30 Plastic cantilever in propped cantilever

the prop at the head of the wall to move and the wall as a whole to rotate. This deflection of the roof plate will be a maximum at mid-span and zero at the gable shear wall positions (see Figure 13.43). Thus each individual fin will be subjected to slightly differing loading/rotation conditions. If, in addition to the stability moment of resistance at base level, flexural tensile resistance is also exploited to increase the resistance moment, there is a considerable danger that the rotation, due to the deflection of the roof plate prop, may eliminate this flexural tensile resistance by causing the wall to crack at base level. The effect of this additional rotation would be an instantaneous reduction in resistance moment at this level. This, in turn, would require the wall section at level B to resist the excess loading transferred to that level, and this could well exceed the resistance moment available at that level. Hence, the two plastic hinges at levels A and B would occur simultaneously, and possibly in advance of the design load having been reached. If, however, the flexural tensile resistance which may be available at base level is ignored, the design bending moment diagram will utilise only the stability moment of resistance at base level, and this will remain unaffected by whatever rotation may occur.

In order to determine the required brick and mortar strengths, it is first necessary to decide the maximum forces, moments and stresses within the wall. If the applied wind moment at the base of the wall should, by coincidence, be exactly equal to the stability moment of resistance (MR_s), the three maxima specified above (maximum forces, moments and stresses) will be found at the base and at a level $(3/8)h$ down from the top of the wall.

If the MR_s is less than the applied base wind moment of $\gamma_f W_k h^2/8$, or if significant lateral deflection of the roof prop occurs, the wall will tend to rotate and crack at the base. Provided that no tensile resistance exists at this level, the MR_s will not decrease because the small rotation will cause an insignificant reduction in the lever arm of the vertical load. However, on the adjusted bending moment diagram, the lever of the maximum wall moment will not now be at $(3/8)h$ down from the top and its value will exceed

$$\frac{9}{128}\gamma_f W_k h^2$$

For example, suppose the numerical value of a particular MR_s is equivalent to, say $\gamma_f W_k h^2/10$, then the reactions at base and prop levels would be:



Figure 13.31 Calculation of base and prop reactions.

$$= \frac{\gamma_f W_k h}{2} \pm \frac{\gamma_f W_k h^2}{10h}$$
$$= 0.5\gamma_f W_k h \pm 0.1\gamma_f W_k h$$
$$= 0.6\gamma_f W_k h \quad \text{at base level}$$
$$= 0.4\gamma_f W_k h \quad \text{at prop level} \quad \text{(see Figure 13.31)}$$

The MR_s is inadequate to resist a true propped cantilever base moment of $\gamma_f W_k h^2/8$, and the section will crack and any additional load resistance available at the higher level will come into play. The true propped cantilever BM diagram is adjusted to allow greater share of the total load resistance to be provided by the stiffness of the wall within its height and the adjusted BM diagram for the example under consideration is shown in Figure 13.32.

The applied wind moment at the level $0.4h$ down is calculated as:

$$(0.4\gamma_f W_k h \times 0.4h) - (0.4\gamma_f W_k h \times 0.2h) = 0.08\gamma_f W_k h^2$$

which exceeds the true propped cantilever wall moment of

$$\frac{9}{128}\gamma_f W_k h^2\ (0.07\gamma_f W_k h^2)$$

The moment of resistance provided by the wall at this level must then be checked against the calculated maximum design bending moment.



Figure 13.32 Design bending moment diagram

The action of the wall is, perhaps, better described as that of a member simply supported at prop level and partially fixed at base level, where the partial fixity can be as high as $\gamma_f W_k h^2/8$, that of a true propped cantilever.

A rigid prop is not possible in practice (nor is a perfectly 'pinned' joint or 'fully fixed-ended' strut, etc.) but the initial assumption of a perfectly rigid prop generally provides the most onerous design condition. This is illustrated in the fin wall worked example to follow.

Considering the two locations of maximum design bending moments and development of the respective moments of resistance, it is apparent that the critical design condition invariably occurs at the higher location where the resistance is dependent on the development of both flexural compressive and flexural tensile stresses in addition to the MR_s at this level. This is particularly true of the diaphragm wall. However, for fin walls, the flexural compressive stresses which occur at base level at the end of the projecting fin can become critical and, for these walls, this generalisation is less often applicable.

13.5.5 Stability Moment of Resistance, MR_S

Since single-storey buildings tend to have lightweight roof construction and low superimposed roof loading, the forces and moments due to lateral wind pressure have greater effect on the stresses in the supporting masonry than they do in multi-storey buildings. Since there is little precompression, the wall's stability relies more on its own gravitational mass and resulting resistance moment. Under lateral wind pressure loading, the wall will tend to rotate at dpc level on its leeward face and crack at the same level on the windward face, as indicated in Figure 13.33.

In limit state design, the previous knife-edge concept of the point of rotation is replaced with a rectangular stressed area, in which the minimum width of masonry is stressed to the ultimate to produce the maximum lever arm for the axial load to generate the maximum stability moment of resistance, MR_s. As such, the MR_s resulting solely from the mass of the wall and ignoring any net roof loads, for each particular wall section of constant masonry density, will vary in direct proportion to its height. Unlike the fin wall, the diaphragm wall is symmetrical in its profile, and an approximation in the calculation of MR_s is warranted for the selection of a trial section. Hence, for diaphragms of normal proportions, the lever arm can be approximated to $0.475D$, as shown in Figure 13.34.



Figure 13.33 Initial rotation in diaphragm wall



Figure 13.34 Approximate lever arm for diaphragm wall

The use of this approximated lever arm for trial section purposes is illustrated in the diaphragm wall worked example to follow and in section 13.9.4.

13.5.6 Shear Lag

Shear lag, the non-uniform stress distribution in the flanges of such structural members at T beams and box sections, is important in the design of thin-walled steel members subject to high bending stresses. It does not seem to be so critical in the design of normal timber boxbeams, rc T beams, etc., and most designers tend to ignore the phenomenon which tends to be allowed for in design rules.

There appears to be little or no experimental research into this phenomenon in brickwork (probably because the bulk of the research has been on solid wall sections and not box or T sections), and there seems to be no guidance in any code or building regulation on this topic. Experiments by the first author suggest that the flange stresses at the ribs of brick diaphragm walls with extra wide rib spacings can increase by 20%. Designers may consider this an insignificant increase when it is appreciated that the true global factor of safety is probably about 8, creating a massive reserve of stress resistance. Even after tensile failure of the test diaphragm walls the shear lag stress increase had no effect on the stability of the walls – which were heavily prestressed and subject to relatively massive lateral loading.

In the authors' opinion, from experience and recent research, the phenomenon may be ignored for normal and lightly prestressed diaphragms, fins and I brick or block sections, provided the rules given for rib spacing, etc. are adhered to.

13.5.7 Principal Tensile Stress

This topic, like shear lag, appears to have been practically ignored by designers, researchers and the codes of practice – probably because it is of little significance in solid walls. In highly stressed diaphragms, fins, etc., it can be significant, and designers should check the principal stresses in highly prestressed and highly laterally loaded sections, since recent research by the first author has shown that this is a failure condition. However, in normally loaded structures, dealt with in this manual (with the normal factors of safety), the principal stresses are most unlikely to be critical. On the very rare occasion that it is necessary to reduce

the principal tensile stress, this can be achieved easily by thickening the ribs of diaphragms or the fins, placing them at closer centres, or increasing the overall depth.

13.6 Design Symbols: Fin and Diaphragm Walls

Certain aspects of the design processes in the two worked examples which follow will vary from the procedures given in BS 5628. As a result it has been necessary to introduce additional symbols and, in order to avoid confusion, a full list of the symbols used is now included for cross-reference.

The new symbols have been marked with an asterisk (*).

$*A$	cross-sectional area
$*B_r$	centre to centre of cross-ribs
b	width of section
$*b_r$	clear dimension between diaphragm cross-ribs
C_{pe}	wind, external pressure coefficient
C_{pi}	wind, internal pressure coefficient
$*D$	overall depth of diaphragm wall
$*d$	depth of cavity (void) in diaphragm wall
f_k	characteristic compressive strength of masonry
f_{kx}	characteristic flexural strength of masonry (tensile)
$*f_{ubc}$	flexural compressive stress at design load
$*f_{ubt}$	flexural tensile stress at design load
G_k	characteristic dead load
h	height of wall
h_{ef}	effective height of wall
$*I$	second moment of area
$*I_{na}$	second moment of area about neutral axis
$*K_1$	shear stress coefficient
$*K_2$	trial section stability moment coefficient
L	length
$*L_f$	spacing of fins, centre to centre
l_a	lever arm
$*M_A$	applied design bending moment
$*M_b$	bending moment at base (base moment)
*MR	moment of resistance
$*MR_s$	stability moment of resistance
$*M_w$	maximum bending moment in wall (wall moment)
$*p_{ubc}$	allowable flexural compressive stress = $1.1\beta f_k/\gamma_m$
$*p_{ubt}$	allowable flexural tensile stress = f_{kx}/γ_m
Q_k	characteristic superimposed load
$*q$	dynamic wind pressure
$*r$	radius of gyration
SR	slenderness ratio
$*T$	thickness of leaf of diaphragm wall
t	thickness of wall
t_{ef}	effective thickness of wall
$*t_r$	thickness of cross-rib of diaphragm wall
V	shear force
v_h	design shear stress
$*W$	own weight effective fin T profile per m height
W_k	characteristic wind load
$*W_{k1}$	design wind pressure, windward wall
$*W_{k2}$	design wind pressure, leeward wall
$*W_{k3}$	design wind pressure, uplift (on roof)
$*w_s$	width of stress block
$*Y_1$	fin dimension, neutral axis to end of fin
$*Y_2$	fin dimension, neutral axis to flange face
Z	section modulus
$*Z_1$	minimum section modulus = I_{na}/Y_1
$*Z_2$	maximum section modulus = I_{na}/Y_2
β	capacity reduction factor
γ_f	partial safety factor for loads
γ_m	partial safety factor for materials
Ω	trial section coefficient ($W \times Y_2$) per m height

13.7 Fin Walls: Structural Design Considerations

13.7.1 Interaction Between Leaves

As shown in Figure 13.35, the fins are bonded to one of the leaves of a cavity wall and are considered as a T section combining the bonded leaf with the fin. The other leaf of the cavity wall is considered as a secondary member and the loading apportioned accordingly, the cavity ties being unable to transmit significant vertical shear forces but able to transmit horizontal forces across the cavity width.

It is assumed that the vertical loads applied to each leaf are taken directly on the leaf to which the load is applied, but that any resulting bending moments from eccentric loading and/or wind loading can be apportioned between the two members in accordance with their relative stiffness.

For example, in Figure 13.36, which shows in exaggerated form the assumed behaviour, the fin A and bonded leaf is considered as a T section bending about point 01. The remaining leaf, B, is considered to deflect equally, bending about point 02 and the ties deform slightly at an assumed shear resistance of zero.

13.7.2 Spacing of Fins

The choice of a suitable section must take into account the cavity wall's ability to act suitably with the fin both to



Figure 13.35 Fin wall arrangement



Figure 13.36 Assumed behaviour of fin wall



Figure 13.37 Cavity wall spanning between fins



Figure 13.38 Slenderness ratio of wall panel



Figure 13.39 Effective length of fin flange

transfer wind forces to the overall section and to prevent buckling of the flange of the T section. This involves choosing a suitable spacing for the fin to control both these conditions, and to take into account economic spacing of the roof beams where the beams are to span onto the fins. The spacing of the fins, is, therefore, governed by the following conditions:

(a) The cavity wall acting as a continuous horizontal member subject to wind load, spanning between the fins (see Figure 13.37).
(b) The cavity wall's ability to support vertical load without buckling. This is governed by the lesser of the effective vertical height or the effective length between fins (see Figure 13.38).
(c) The ability of the cross-section to resist the applied loading with the leaf and fin acting together to form a T beam (see Figure 13.39).
The effective flange of the T beam is limited to the least of:
    (i) the distance between the centres of the fins,
    (ii) the breadth of the fin plus 12 times the effective thickness of the bonded leaf,



Figure 13.40 Shear failure between fin and bonded leaf

    (iii) one-third of the effective span of the fin.
    It should be noted that clause 36.4.3 in BS 5628 embraces two of the conditions with reference to piered walls but, since it is felt that the distribution of stress into the flange is also related to the span of the fin, in a similar manner to reinforced concrete T beams, a span related limit is also necessary in accordance with item (iii).
(d) The vertical shear forces between the fin and the bonded leaf resulting from the applied bending moment on the T section (see Figure 13.40).
(e) The economic spacing of the main roof supports (where applicable).

It should be noted that while item (c) restricts the flange width for design purposes, the actual distance between fins can be greater provided that the design of the effective flange is within the permissible design stresses and that all the other design considerations are met.

13.7.3 Size of Fins

Typical fin sizes used are 0.5 m to 2 m deep at spacings of 3 m to 5 m and 330 mm to 440 mm wide. Some typical sections and their properties are shown in the design Table 13.1.

The length and thickness of the fin is governed by the tendency of the outer edge to buckle under compressive bending stress. The roof plate action and the stresses in the transverse walls which provide the reaction to the plate must be checked.

13.7.4 Effective Section and Trial Section

Owing to the unsymmetrical shape of the fin wall, the geometrical properties of the effective section, when combined bending and axial forces are considered, can vary greatly under changes in loading, particularly if a 'cracked' section is being analysed. It is therefore most important, when analysing the stability moment of resistance, MR_s, to consider carefully the effective section being stressed and the effects of the 'cracked' portion on the general performance of the wall. The tensile stresses must be kept within the limit recommended in the Code but, at dpc level, the majority of membranes must be considered to have zero resistance to tensile forces.

Table 13.1 Fin wall section properties

Fin reference letter	A	B	C	D	E	F	G	H
Fin size (mm)	665 × 327	665 × 440	778 × 327	778 × 440	890 × 327	1003 × 327	1003 × 440	1003 × 440
Effective width of flange (m)	1.971	2.084	1.971	2.084	1.971	2.084	1.971	2.084
Neutral axis Y_1 (m)	0.455	0.435	0.524	0.500	0.589	0.563	0.654	0.626
Neutral axis Y_2 (m)	0.210	0.230	0.254	0.278	0.301	0.327	0.349	0.377
Effective area (m^2)	0.386 0	0.461 1	0.426 2	0.515 2	0.459 5	0.560 1	0.496 5	0.609 8
ow of effective area per m height, W (kN)	7.720	9.222	8.458	10.216	9.190	11.202	9.930	12.196
I_{na} (m^4)	0.015 67	0.019 39	0.024 54	0.030 30	0.035 90	0.044 26	0.050 21	0.061 87
Z_1 (m^3)	0.034 41	0.044 50	0.046 84	0.060 59	0.060 96	0.078 62	0.076 77	0.098 83
Z_2 (m^3)	0.074 62	0.084 30	0.096 63	0.108 98	0.119 28	0.135 36	0.143 87	0.164 10
Trial section coefficient, Ω (kN m/m)	1.621 2	2.121 0	2.148 3	2.840 0	2.766 2	3.663 1	3.465 6	4.597 8

Fin reference letter	J	K	L	M	N	P	Q	R
Fin size (mm)	1115 × 327	1115 × 440	1227 × 327	1227 × 440	1339 × 327	1339 × 440	1451 × 327	1451 × 440
Effective width of flange (m)	1.971	2.084	1.971	2.084	1.971	2.084	1.971	2.084
Neutral axis Y_1 (m)	0.718	0.687	0.780	0.747	0.841	0.807	0.902	0.866
Neutral axis Y_2 (m)	0.397	0.428	0.447	0.480	0.498	0.532	0.549	0.585
Effective area (m^2)	0.533 1	0.659 1	0.569 7	0.708 4	0.606 4	0.757 7	0.643 0	0.807 0
ow of effective area per m height, W (kN)	10.662	13.182	11.394	14.168	12.128	15.154	12.860	16.140
I_{na} (m^4)	0.067 46	0.083 12	0.008 80	0.108 48	0.112 08	0.138 26	0.139 92	0.172 77
Z_1 (m^3)	0.093 95	0.120 99	0.112 82	0.145 22	0.133 27	0.171 32	0.155 13	0.199 50
Z_2 (m^3)	0.169 22	0.194 21	0.196 87	0.226 00	0.225 06	0.260 39	0.254 87	0.295 30
Trial section coefficient, Ω (kN m/m)	4.232 8	5.641 9	5.093 1	6.800 6	6.039 7	8.061 9	7.060 1	9.441 9

Again, owing to the unsymmetrical section, it is not as straightforward a matter, as it is for the diaphragm wall, to provide a reasonably accurate means of assessing the trial section. A 'trial section coefficient', Ω, has been included in the design Table 13.1 and relates to the own weight stability moment per metre height of wall when the rotation at base level occurs about the flange face. An illustration of the use of the trial section coefficient is given in the worked example which follows.

$$Z_1 = \frac{I_{na}}{Y_1} \qquad Z_2 = \frac{I_{na}}{Y_2}$$

Trial section coefficient, $\Omega = WY_2$

13.8 Example 1: Fin Wall

13.8.1 Design Problem

A warehouse measuring 29 m × 54 m on plan, and 8 m high, is shown in Figure 13.41. The building is to be designed in loadbearing brickwork, using fin wall construction for its main vertical structure. The fins are to project on the external face, and the wall panels between the fins are to be of 260 mm brick cavity construction. There are no internal walls within the building. The building is part of a major development where extensive testing of materials and strict supervision of workmanship will be employed.



Figure 13.41 Fin wall design example

The architect has selected particular facing bricks which are shown to have a compressive strength of 41.5 N/mm^2 and a water absorption of 8%. The bricks will be used both inside and outside the building.

13.8.2 Design Approach

BS 5628 offers three options for the design of laterally loaded walls:

(a) clause 36.4.3 in which the design moment of resistance of wall panels is given as $f_{kx}Z/\gamma_m$, and
(b) clause 36.8, which offers two further options:
  (i) design lateral strength equated to effective eccentricity due to lateral loads, or
  (ii) treating the panel as an arch.

The last option can seldom be applied to single-storey buildings due to inadequate arch thrust resistance. The remaining two options take no account of flexural compressive stresses which, in the fin wall design concept, certainly require careful consideration.

For this reason, it has been considered necessary, in order to explain properly the mechanisms involved, to diverge from the BS 5628 concept of equating design loads to design strengths. The analysis considers stresses due to design loads and relates these to allowable flexural stresses in both compression and tension.

The structure will need to be assessed to ascertain the building class in accordance with disproportionate collapse rules in Part A of The Building Regulations. This building does not admit members of the public and the floor area is less than 2000 m^2. Therefore it is classed as type 2A and requires horizontal ties in accordance with BS 5628, Part 1.

13.8.3 Characteristic Loads

(a) Wind Forces

The basic wind pressure on a building is calculated from a number of variables which include:

(a) location of building, nationally,
(b) topography of immediate surrounding area,
(c) height above ground to top of building,
(d) building geometry.

For the appropriate conditions, the basic pressure and local pressure intensities are given in BS 6399, Part 2.

In this example, these values are assumed to have been computed as:

Dynamic wind pressure, q_s, $= 0.71$ kN/m^2
C_{pe} on windward face of wall $= 0.6$
C_{pe} on leeward face of wall $= -0.5$
C_{pi} on walls, either $= +0.2$ or -0.3
C_{pe} for wind uplift on roof $= 0.7$
C_a for $C_{pe} = 0.87$ and C_a for $C_{pi} = 0.72$

Therefore, characteristic wind loads are:

Pressure on windward wall $= W_{k1} = (C_{pe} \times C_A - C_{pi} \times C_A)q_s$
$= (0.85 \times 0.87 + 0.3 \times 0.72) \times 0.71$
$= 0.678$ kN/m^2

Suction on leeward wall $= W_{k2} = (C_{pe} \times C_A - C_{pi} \times C_A)q_s$
$= (0.5 \times 0.87 + 0.2 \times 0.72) \times 0.71$
$= 0.411$ kN/m^2

Gross roof uplift $= W_{k3} = (C_{pe} \times C_A - C_{pi} \times C_A)q_s$
$= (0.7 \times 0.87 + 0.2 \times 0.72) \times 0.71$
$= 0.535$ kN/m^2

(b) Dead and Superimposed Loads

(i) Characteristic superimposed load, $Q_k = 0.6$ kN/m^2 (assumes snow load not critical). (Assuming no access to roof, other than for cleaning or repair, in accordance with BS 6399, Part 3.)

(ii) Characteristic dead load, G_k:

Assume: metal decking	$= 0.18$ kN/m^2
felt and chippings	$= 0.30$ kN/m^2
ow roof beams	$= 0.19$ kN/m^2
Total G_k	$= 0.67$ kN/m^2

13.8.4 Design Loads

The critical loading condition to be considered for such a wall is usually (wind + dead) only, although the loading condition of (dead + superimposed + wind) should be checked.

Design dead load $= 0.9G_k$ or $1.4G_k$
Design wind load $= 1.4W_k$

Therefore, by inspection, the most critical combination of loading will be given by:

Design dead load $= 0.9 \times 0.67 = 0.603$ kN/m^2

Design wind loads:

Pressure, from W_{k1}	$= 1.4 \times 0.678$	$= 0.949$ kN/m^2
Suction, from W_{k2}	$= 1.4 \times 0.411$	$= 0.575$ kN/m^2
Uplift, from W_{k3}	$= 1.4 \times 0.535$	$= 0.749$ kN/m^2

Resulting design dead-uplift $= 0.603 - 0.749 = -0.146$ kN/m^2 (suction uplift)

13.8.5 Design Cases (as shown in Figure 13.42)

Inner leaf offers minimal resistance and is ignored in calculations apart from assisting stiffness of flange in bending.

Note: Vertical loading is from own weight of effective section less the suction uplift.

13.8.6 Deflection of Roof Wind Girder

The wall is designed as a propped cantilever and utilises the fins bonded to the outer leaf to act as vertical T beams resisting the flexure.

The prop to the cantilever is provided by a wind girder within the roof decking system (the design of the wind girder is not covered by this book). The reactions from the roof wind girder are transferred into the transverse gable shear walls at each end of the building. Horizontal deflection of the roof wind girder, reaching a maximum at mid-span, has the effect of producing additional rotation at base level (see Figure 13.43) and this results in a less critical



Figure 13.42 Design load cases



Figure 13.43 Deflection of roof wind girder



Figure 13.44 Bending moment diagram for wall panel

stress condition. However, the critical stress conditions are generally experienced in the end fins where the roof wind girder deflection is a minimum.

13.8.7 Effective Flange Width for T Profile

The dimensional limits for the effective length of the wall permitted to act as the flange of the T profile are given in BS 5628, clause 36.4.3 (b), as 6 × thickness of wall forming the flange, measured as a projection from each face of the fin, when the flange is continuous. In this design example, as will be the general case in practice, the wall forming the flange is the outer leaf of a cavity wall, as defined in BS 5628, clause 29.1.1. It is, therefore, reasonable to take advantage of the stiffening effect of the inner leaf in resisting buckling of the outer leaf, when acting as the flange of the T profile. The effective flange length, measured from each face of the fin, is therefore calculated as 6 × effective wall thickness.

Thus, for an assumed fin width of 327 mm:

$$\text{Effective wall thickness} = \frac{2}{3}(102.5 + 102.5)$$
$$= 137 \text{ mm}$$

$$\text{Effective flange width} = (6 \times 137) + 327 + (6 \times 137)$$
$$= 1971 \text{ mm}$$

13.8.8 Spacing of Fins

The spacing of fins has been discussed earlier – but one aspect only, the capacity of the wall panel to span between the fins, is considered here.

There is no doubt that the support provided for the wall panel at foundation level will assist in resisting the flexure due to wind forces. However, this assistance will diminish at the higher levels of the wall panel, and for this example the wall should be designed to span purely horizontally between the fins.

The wall panels are taken as continuous spans and the maximum bending moments are shown in Figure 13.44.

The maximum moment is $W_{k1}L_f^2/14$ at the edge of the fins, for an assumed fin width of $L_f/10$.

$$\text{Design bending moment} = \frac{W_{k1}L_f^2}{14} = \frac{0.949 \times L_f^2}{14}$$
$$= 0.068\, L_f^2$$

From BS 5628, clause 36.4.3:

$$\text{Design moment of resistance} = \frac{f_{kx}Z}{\gamma_m}$$

where

f_{kx} for water absorption 7% to 12% set in designation (iii) mortar = 1.10 N/mm^2

Z for two leaves $= \dfrac{2 \times 0.1025^2 \times 1.0}{6} = 0.0035 \text{ m}^3$

γ_m from BS 5628, Table 4b (see Table 5.11), special category of construction control is applicable = 2.5

Therefore

$$\text{Design moment of resistance} = \frac{1.10 \times 0.0035 \times 10^9}{2.5 \times 10^6}$$
$$= 1.54 \text{ kN m}$$

From this check maximum span of wall panel.

Design moment = design moment of resistance

i.e. $0.068\, L_f^2 = 1.54$

therefore $L_f = \sqrt{\left(\dfrac{1.54}{0.068}\right)} = 4.75 \text{ m} = \text{maximum fin spacing}$

A fin spacing of 4.05 m is acceptable (see Figure 13.45).

13.8.9 Trial Section

It has been found in practice that a trial section can be reasonably obtained by providing a section which has a stability moment of resistance MR_s, at the level of M_b equal to $W_{k1}L_f h^2/8$ under wind pressure loading W_{k1}, i.e. when rotation at the base of the wall is about the face of the flange. For the purpose of the trial section assessment, the stability moment of resistance can be simplified to Ωh in which:

Ω = trial section coefficient from Table 13.1
h = height of fin wall.



Figure 13.45 Profile of trial section – fin section 'J' (Table 13.1)

Therefore

$$\frac{W_{k1}L_f h^2}{8} = \Omega h$$

$$\frac{0.949 \times 4.05 \times 8^2}{8} = 8\Omega$$

Therefore $\Omega = 3.843$ kN m/m height of wall

From Table 13.1, select fin wall profile 'J'.

Note: It is important that this trial section coefficient is used only for the selection of the trial section. A thorough structural analysis must always be carried out.

13.8.10 Consider Propped Cantilever Action

With 4.050 m fin centres, design wind loads on fins are (see Figure 13.46):

(a) Case (1), Pressure

$$W_{k1}L_f = 0.949 \times 4.05 = 3.843 \text{ kN/m of height}$$

(b) Case (2), Suction

$$W_{k2}L_f = 0.575 \times 4.05 = 2.329 \text{ kN/m of height}$$

Assuming MR is greater than $W_{k1}L_f h^2/8$ and zero deflection of the roof prop, the following BM diagrams can be drawn:

(a) Case (1) (Figure 13.47)

$$\text{Wall moment, } M_w = \frac{9W_{k1}L_f h^2}{128} = \frac{9 \times 3.843 \times 8^2}{128}$$

$$= 17.29 \text{ kN m}$$

$$\text{Base moment, } M_b = \frac{W_{k1}L_f h^2}{8} = \frac{3.843 \times 8^2}{8}$$

$$= 30.74 \text{ kN m}$$



Figure 13.46 Wind loadings



Figure 13.47 Case (1) pressure



Figure 13.48 Case (2) section

(b) Case (2) (Figure 13.48)

$$\text{Wall moment, } M_w = \frac{9W_{k2}L_f h^2}{128}$$

$$= \frac{9 \times 2.329 \times 8^2}{128}$$

$$= 10.48 \text{ kN m}$$

$$\text{Base moment, } M_b = \frac{W_{k2}L_f h^2}{8}$$

$$= \frac{2.329 \times 8^2}{8}$$

$$= 18.63 \text{ kN m}$$

The bending moment diagrams shown in Figures 13.47 and 13.48 are applicable only if it can be shown that the stability moment of resistance of the 'cracked section' MR_s at dpc level exceeds $W_{k1}L_f h^2/8$. This should be the first check to be carried out, and if MR_s is less than $W_{k1}L_f h^2/8$ the base moment is limited to MR_s and the BM diagram must be redrawn plotting the free moment diagram onto the fixed end moment diagram which is produced by MR_s (see Figure 13.55).

13.8.11 Stability Moment of Resistance

Clause 36.9 of BS 5628, Part 1 gives rules for determining the moment of resistance for propped cantilever walls for single-storey buildings under wind loading. Invariably, as is the case with this design example, there will be a damp proof course at or near the base of the wall. Few dpcs are capable of transmitting much flexural tensile stress across the bed joint, and in accordance with the requirements of the Code the analysis considers the 'cracked section'.

Appendix B of BS 5628 discusses the application of a rectangular stress block under ultimate conditions, and the stability moment of resistance MR_s at the level of M_b can be assumed to be provided by the axial load in the fin section acting at a lever arm about the centroid of the rectangular stress block, as shown in Figure 13.49.

13.8.12 Allowable Flexural Compressive Stresses, p_{ubc}, Taking into Account Slenderness, β, and Material, γ_m

Before the stability moment of resistance MR_s can be compared with the assumed base moment, M_b, of $W_{k1}L_f h^2/8$



Figure 13.49 Generation of MR_s – fin wall

consideration must be given to the criteria affecting the allowable flexural compressive stresses, p_{ubc}, as this value dictates the stability moment of resistance. This is demonstrated in Figure 13.49, in which the mechanism producing the stability moment of resistance MR_s is shown.

This flexural compressive stress can become significant and must be checked, taking into account the tendency of the flange or fin to buckle at the point of application of the stress.

There is limited guidance given in BS 5628 on the effect of slenderness on the flexural compressive strength of masonry. This is because the flexural strength of masonry is assumed to be limited by the flexural tensile stresses – which is, perhaps, true of panel walls and the like, but not of the analysis of more complex geometric forms such as the fin wall.

The approach to the consideration of slenderness and flexural compressive stresses which follows is believed to provide a safe and practical design. It is expected that current research will allow more sophisticated analysis to be developed.

Identification of problem:

Case (1) pressure, showing zones of maximum values of flexural compression (Figure 13.50).
Case (2) suction, showing zones of maximum values of flexural compression (Figure 13.51).



Figure 13.50 Case (1) pressure, showing zones of maximum values of flexural compression



Figure 13.51 Case (2) suction, showing zones of maximum values of flexural compression



Figure 13.52 Foundation detail

Considering the wind suction loading, case (2), flexural compression is applied to the flange of the T profile at the level of M_w. The buckling stability of the flange is provided by the projecting fin and, therefore, the effective length of the flange, for slenderness considerations, can be taken as twice the outstanding length of the flange from the face of the fin. Furthermore, if the flange is properly tied to the inner leaf of the cavity wall, the effective thickness of the flange, for slenderness considerations, can be taken as two-thirds the sum of the thicknesses of the two leaves of the cavity wall.

Flexural compression is also applied to the end of the projecting fin at the level of M_b. For this design example, the foundation is assumed to comprise a reinforced concrete raft slab, as shown in Figure 13.52. The flexural compression applicable at this level is not influenced by slenderness considerations as the raft foundations can be assumed to provide full lateral stability.

Slenderness at this level would require careful consideration if the fin foundation was at a greater depth below ground level.

Considering the wind pressure loading, case (1), flexural compression is applied to the end of the projecting fin at the level of M_w.

The buckling stability of the fin cannot be considered to be fully provided by the flange of the T profile, as the flange is not of comparable lateral stiffness to the fin and would tend to rotate in attempting to prevent the fin buckling. Rather, it is considered that the slenderness of the fin should relate partly to its height and, as the full height of the fin would be over-cautious, it is proposed that the height between points of contraflexure would provide adequate safety. The effective thickness of the fin for slenderness considerations is taken as the actual thickness.

The design flexural compressive stress p_{ubc} can therefore be expressed as:

$$p_{ubc} = \frac{1.1\beta f_k}{\gamma_m}$$

where

p_{ubc} = design flexural compressive stress
β = capacity reduction factor derived from slenderness ratio
f_k = characteristic compressive strength of masonry
γ_m = partial safety factor for materials.

With the lateral restraint provided by the raft foundation at M_b level, β can be taken as 1.0. Therefore, $p_{ubc} = 1.1f_k/\gamma_m$ at M_b level (see Figure 13.52).

For this example:

$f_k = 9.41$ N/mm^2, based on 41.5 N/mm^2 bricks set in a designation (iii) mortar from BS 5628, Table 2(a) (see Table 5.4)
$\gamma_m = 2.5$, as previously shown.

Therefore:

$$p_{ubc} = \frac{1.1 \times 9.41}{2.5} = 4.14 \text{ N/mm}^2$$

13.8.13 Calculate MR_s and Compare with M_b

(a) Consider Case (1) Pressure

From Table 13.1, ow = 10.662 kN/m height. Therefore:

$$\text{Design axial load in fin at } M_b = 0.9 \times 10.662 \times 8 = 76.77 \text{ kN}$$

$$\text{Min. width of stress block} = \frac{\text{axial load on fin}}{\text{flange width} \times p_{ubc}} = \frac{76.77 \times 10^3}{1971 \times 4.14}$$

$$= 9.4 \text{ mm} \quad \text{(see Figure 13.53)}$$

$$= 10 \text{ mm, say}$$

$$\text{Lever arm} = 397 - \frac{10}{2} = 392 \text{ mm}$$

$$MR_s = 76.77 \times 0.392 = 30.09 \text{ kN m}$$

The stability moment of resistance is shown to be less than $M_b = W_k L_f h^2/8 = 35.42$ kN m.

The base moment should therefore be limited to the value of stability moment, MR_s = 30.09 kN m, and the bending moment diagram adjusted accordingly.

(b) Consider Case (2) Suction

From Figure 13.54, it is evident that the stability moment of resistance is provided by the flexural compressive stress at the end of the projecting fin, thus:



Figure 13.53 Stress diagram for case (1) pressure



Figure 13.54 Stress diagram for case (2) suction

$$\text{Min. width of stress block} = \frac{\text{axial load on fin}}{\text{fin width} \times p_{ubc}}$$

$$= \frac{76.77 \times 10^3}{327 \times 4.14}$$

$$= 56 \text{ mm} \quad \text{(see Figure 13.54)}$$

$$\text{Lever arm} = 718 - \frac{56}{2} = 690 \text{ mm}$$

$$MR_s = 76.77 \times 0.69 = 52.74 \text{ kN m}$$

As this is greater than M_b = 22.56 kN m (see Figure 13.48), use M_b in the design of the fin section.

13.8.14 Bending Moment Diagrams

(a) Case (1) Pressure (see Figure 13.55)

MR_s (calculated) = 30.09 kN m.

Find M_w from zero shear

$$\text{Prop} = \left(3.843 \times \frac{8}{2}\right) - \left(\frac{30.09}{8}\right)$$

$$= 11.61 \text{ kN}$$

$$\text{Zero shear} = \frac{11.61}{3.843} = 3.02 \text{ m} \quad \text{from top}$$

$$M_w = (11.61 \times 3.02) - \left(3.843 \times \frac{3.02^2}{2}\right)$$

$$= 35.06 - 17.52$$

$$= 17.54 \text{ kN m}$$



Figure 13.55 Design BM for case (1) pressure



Figure 13.56 Design BM for case (2) suction

Adjustment is made to BM diagram to take account of MR_s being less than $W_k L_f h^2/8$, i.e. M_b, and therefore base moment limited to MR_s with M_w calculated by superimposing the free BM diagram onto the stability moment diagram produced by MR_s at base.

(b) Case (2) Suction (see Figure 13.56)

$$M_w = \frac{9 W_{k2} L_f h^2}{128} = \frac{9 \times 2.329 \times 8^2}{128}$$

$$= 10.48 \text{ kN m}$$

$$M_b = \frac{W_{k2} L_f h^2}{8} = \frac{2.329 \times 8^2}{8}$$

$$= 18.63 \text{ kN m}$$

No adjustment is necessary to BM diagram as MR_s is greater than $W_{k2} L_f h^2/8$, i.e. M_b, and therefore maximum M_w occurs at (3/8)h from top of wall.

13.8.15 Consider Stresses at Level of M_w

The stress considerations at the level of the maximum wall moment assume triangular stress distribution, using elastic analysis, but relate to ultimate stress requirements at the extreme edges of the fin or wall face, depending on the wind direction considered. For compressive stress conditions, this gives a conservative solution. Compliance with clause 36.9.1(b) of the Code is considered inappropriate and impractical – see section 6.10 for discussion.

(a) Case (1) Pressure (see Figure 13.57)

Properties of effective wall section from Table 13.1, are as listed below, except that own weight (ow) of effective



Figure 13.57 Stress diagram at M_w for case (1) pressure



Figure 13.58 Stress diagram at M_w for case (2) suction

section at level of $M_w = 0.9 \times 10.662 \times 3.02 = 28.98$ kN (no uplift on this elevation).

Flexural stresses at design load:

$$\text{Flexural compressive, } f_{ubc} = +\frac{28.98 \times 10^3}{0.5331 \times 10^6} + \frac{16.82 \times 10^6}{0.094 \times 10^9}$$

$$= +0.054 + 0.18$$

$$= +0.234 \text{ N/mm}^2$$

$$\text{Flexural tensile, } f_{ubt} = +\frac{28.98 \times 10^3}{0.5331 \times 10^6} - \frac{16.82 \times 10^6}{0.17 \times 10^9}$$

$$= +0.054 - 0.099$$

$$= -0.045 \text{ N/mm}^2$$

(b) Case (2) Suction (see Figure 13.58)

Properties of effective wall section from Table 13.1:

ow of effective section $= 10.662 \times 3.0$
$= 31.99$ kN at level of M_w

effective area $= 0.5331$ m^2

Z minimum $= 0.094$ m^3

Z maximum $= 0.17$ m^3

Design axial load = ow effective section
+ roof dead – roof uplift

$$= (\gamma_f \times 31.99) - (0.146 \times \frac{29}{2})$$

$$= (0.9 \times 31.99) - 2.12$$

$$= 26.67 \text{ kN}$$

Flexural stresses at design load:

$$\text{Flexural compressive, } f_{ubc} = +\frac{26.67 \times 10^3}{0.5331 \times 10^6} + \frac{10.48 \times 10^6}{0.17 \times 10^9}$$

$$= +0.050 + 0.062$$

$$= 0.112 \text{ N/mm}^2$$

$$\text{Flexural tensile, } f_{ubt} = +\frac{26.67 \times 10^3}{0.5331 \times 10^6} - \frac{10.48 \times 10^6}{0.094 \times 10^9}$$

$$= +0.050 - 0.111$$

$$= -0.061 \text{ N/mm}^2$$

13.8.16 Design Flexural Stress at M_w Levels

Design flexural tensile stress, p_{ubt} (taking account of materials partial safety factor, γ_m):

$$p_{ubt} = \frac{f_{kx}}{\gamma_m} \quad \text{(from BS 5628, clause 36.4.3)}$$

where

$f_{kx} = 0.4$ N/mm^2 for bricks with a water absorption of 7% to 12%
$\gamma_m = 2.5$ as previously shown.

Therefore

$$p_{ubt} = 0.4/2.5 = 0.16 \text{ N/mm}^2$$

By comparison with the f_{ubt} values calculated and shown in Figures 13.57 and 13.58, the wall is acceptable.

Design flexural compressive stress, p_{ubc}

$$p_{ubc} = \frac{1.1\beta f_k}{\gamma_m}$$

Calculate respective β values for case (1) and case (2) loadings at level of M_w.

(a) Case (2) Suction (Flange in Compression at M_w Level)

$$\text{Slenderness ratio} = \frac{2 \times \text{flange outstanding length}}{\text{effective thickness}}$$

$$= \frac{2 \times \left(\frac{1971 - 327}{2}\right)}{(2/3)(102.5 + 102.5)}$$

$$= 12$$

The stressed areas can be considered as axially loaded, therefore $e_x = 0$. Thus since SR = 12 from BS 5628, Table 7, $\beta = 0.93$ (see Table 5.15).

Therefore

$$p_{ubc} = \frac{1.1 \times 0.93 \times 9.41}{2.5}$$

$$= +3.85 \text{ N/mm}^2$$

(b) Case (1) Pressure (End of Fin in Compression at M_w Level)

$$\text{Slenderness ratio} = \frac{\text{effective height between points of contraflexure}}{\text{actual thickness}}$$

(The effective height used is the height between points of contraflexure which does not exactly accord with BS 5628, Part 1 which only appears to recognise enhanced restraints at each end or simple supports at each end, i.e. $h_{ef} = 0.75h$ or $1.0h$.)

$$= \frac{6042}{327} \text{ (see Figure 13.55)}$$

$$= 18.48$$

Therefore $\beta = 0.75$ from BS 5628, Table 7 (see Table 5.15)

Therefore

$$p_{ubc} = \frac{1.1 \times 0.75 \times 9.41}{2.5} = +3.10\ \text{N/mm}^2$$

By comparison with the f_{ubc} values calculated and shown in Figures 13.57 and 13.58, the wall is acceptable.

13.8.17 Consider Fins and Deflected Roof Prop

It is evident that the deflection of the roof wind girder induces additional rotation at the level of M_b.

In this design example, the MR_s limited the moment at the base under wind pressure loading, and the additional rotation will not alter the design bending moment diagram shown in Figure 13.55. The base moment for wind suction loading, when the roof support does not deflect, is $W_{k2}L_f h^2/8$. But, as the deflecting roof support induces further rotation at base level, the section cracks and takes full advantage of the stability moment of resistance, MR_s. The revised design bending moment diagram for this condition, when compared with Figure 13.56, is shown in Figure 13.59. The reduced wall moment value is obviously acceptable, while the increase in the moment at base level is also shown (Figure 13.54) to be acceptable. However, this should be fully checked if slenderness reductions are applicable at this level.

Suggested Design Procedure

After some experience, a competent designer will be able to shorten the design process considerably. A suggested design procedure for the wall is as follows:

(1) Calculate wind loadings.
(2) Calculate dead and imposed loadings.
(3) Assess critical loading conditions.
(4) Select trial section.
(5) Calculate stability moments, MR_s, at base.
(6) Calculate position of maximum wall moments.
(7) Calculate magnitude of maximum wall moment, M_w.
(8) Check compressive stress at base level.
(9) Check loadings and stresses at levels of M_w.
(10) Select brick and mortar strength required.



Figure 13.59 Bending moment diagram for deflected roof wind girder condition

13.9 Diaphragm Wall: Structural Design Considerations

13.9.1 Determination of Rib Centres, B_r

The centres of the ribs are governed by the following conditions:

(a) the outer leaf acting as a continuous horizontal slab, subject to wind load, supported by and spanning between the ribs (see Figure 13.60).
(b) as a wall liable to buckling under vertical load, the effective length of the wall being determined from either the vertical height or the length measured between adjacent intersecting walls, BS 5628, clause 28.3.2, i.e. the ribs (see Figure 13.61).
(c) leaf and rib acting together to form an I section. The length of the flange of the I beam being restricted in a similar way to that of a concrete T beam, the requirement being that it should not exceed:
  (i) one-third of the effective span of the I beam,
  (ii) the distance between the centres of the ribs of the I beam,
  (iii) the breadth of the rib plus 12 times the thickness of the flange (see Figure 13.62).
(d) if the ribs are spaced too widely, there will be shear failure between the ribs and the leaves, particularly where using ties (see Figure 13.63).



Figure 13.60 Wall spanning between ribs



Figure 13.61 Wall restrained by ribs



Figure 13.62 Rib and leaf acting as I beam



Figure 13.63 Shear failure between rib and leaf

Calculating the rib centres from these conditions gives:

Case (a)

γ_f = partial safety factor on loads

$$M_A \text{ due to wind} = \gamma_f \frac{W_k B_r^2}{10}$$

$$Z \text{ per m height} = \frac{1 \times T^2}{6} \quad \text{(where } T \text{ is thickness of leaf)}$$

Assume that the category of construction control is special (BS 5628, clause 27.2.2.2) then, from BS 5628, Table 4b, γ_m for the brickwork = 2.5 (see Table 5.11).

Assuming bricks with a water absorption greater than 12%, set in a designation (iii) mortar, from Table 3 of BS 5628 for plane of failure perpendicular to bed joints (i.e. leaf of a wall spanning horizontally between ribs):

f_{kx} = characteristic flexural strength, say 0.9 N/mm^2
= 900 kN/m^2

$$\text{Design flexural tensile stress, } \frac{f_{kx}}{\gamma_m} = \frac{900}{2.5} \text{ kN/m}^2$$

$$= 360 \text{ kN/m}^2$$

Example:

Characteristic wind pressure, $W_k = 0.573$ kN/m^2
Thickness of leaf, $T = 102.5$ mm
B_r = spacing of ribs

Consider 1 metre height of wall

$$M_A = \gamma_f \frac{W_k B_r^2}{10} = \frac{1.4 \times 0.573 \times B_r^2}{10} = 0.08 \times B_r^2 \text{ kN m}$$

$$Z = \frac{1 \times T^2}{6} = \frac{1 \times 0.1025^2}{6} = 1.75 \times 10^{-3} \text{ m}^3$$

$$\text{Design MR} = \frac{f_{kx} Z}{\gamma_m}$$

Therefore

$$0.08 \times B_r^2 = \frac{900}{2.5} \times 1.75 \times 10^{-3}$$

$$B_r = 2.8 \text{ m}$$

Case (b)

Maximum slenderness ratio = 27, Table 7, BS 5628 (see Table 5.15), i.e.

$$\frac{B_r}{T} = 27$$

therefore

$$B_r = 27 \times 0.1025 = 2.76$$

Case (c)

The requirement is that the breadth of the flange assumed as taking compression should not exceed the least of the following:

(i) one-third of the effective span, i.e. h,
(ii) the distance between the centres of the ribs, i.e. B_r,
(iii) the breadth of the rib plus 12 times the thickness of the flange.

Then the maximum flange width is the least of $h/3$, B_r or $[(12 \times T) + t_r]$ (Figure 13.64), where h = height of the wall.

Example:

Let h (height) = 6 m and $T = t_r = 102.5$ mm, then

$$B_r = \frac{6}{3} \quad \text{or} \quad [(12 \times 102.5) + 102.5]$$

$$= 2 \text{ m} \quad \text{or} \quad 1.33 \text{ m}$$

Case (d)

The shear resistance can be obtained either by bonding every alternate course of the rib into the leaf, or by using metal ties (see Figure 13.65).

From the four cases considered, (a), (b), (c) and (d), the limiting dimension for the spacing of the ribs is given by case (c) as 1.33 m. Clearly, for the majority of diaphragm walls,



Figure 13.64 Effective length of diaphragm



Figure 13.65 Shear ties between ribs and leaves



Figure 13.66 Wall profiles for typical diaphragm wall structures

constructed of half-brick ribs and leaves throughout, this will generally be the limiting dimension for the rib spacing. From experience, with wind forces around 0.6 kN/m^2 and heights of 8 m, it has been found that the rib spacings should be at about 1.0 m to 1.25 m centres.

13.9.2 Depth of Diaphragm Wall and Properties of Sections

Within reason, the greater the depth of the wall, the greater is its resistance to wind forces. If the wall width becomes too large, the buckling of the cross-ribs may become critical and this would need careful consideration. Increase in depth also improves the wall's slenderness ratio, and thus its axial loadbearing capacity. From experience, with the wind forces and wall heights mentioned above, the section needs to be 0.4 m to 0.7 m deep (Figure 13.66).

Breadths and depths of diaphragm walls are governed mainly by brick sizes and joint thicknesses. The engineer is free to design the diaphragm best suited to his project, and Figure 13.67 shows some typical breadths and depths, found useful in practice, based on the standard brick. Calculations for a typical section are below:

[(bricks) + (joints) + (rib)]



Figure 13.67 Typical diaphragm wall profiles

$B_r = [(4 \times 215) + (5 \times 10) + (2 \times {}^1/_2 \times 102.5)] \times 10^{-3} = 1.0125$ m

$b_r = 1.0125 - 0.1025 = 0.910$ m

$D = [(2 \times 215) + 10] \times 10^{-3} = 0.440$ m

$d = 0.440 - (2 \times 0.1025) = 0.235$ m

$$I = \frac{B_r D^3}{12} - \frac{b_r d^3}{12} = 6.21 \times 10^{-3} \text{ m}^4$$

$$Z = \frac{I}{y} = \frac{6.21 \times 10^{-3}}{0.44 \times 0.5} = 28.23 \times 10^{-3} \text{ m}^3$$

$A = B_r D - b_r d = (1.0125 \times 0.44) - (0.91 \times 0.235) = 0.232$ m^2

The values per metre length of the wall are:

$I = 6.21/1.0125 = 6.13 \times 10^{-3}$ m^4
$Z = 28.23/1.0125 = 27.88 \times 10^{-3}$ m^3
$A = 0.232/1.0125 = 0.229$ m^2

The section properties shown above, and others for a range of walls likely to be required, are given in Table 13.2.

13.9.3 Shear Stress Coefficient, K_1

It is necessary to check the shear stress at the junction of the rib and leaves (Figure 13.68).

$$\text{Design vertical shear stress, } v_h = \frac{VA\bar{y}}{It_r}$$

Table 13.2 Diaphragm wall section properties

Section	Dimensions				Section properties per diaphragm		
	D (m)	d (m)	B_r (m)	b_r (m)	I ($10^{-3} \times$ m^4)	Z ($10^{-3} \times$ m^3)	A (m^2)
1	0.44	0.235	1.4625	1.36	8.91	40.49	0.324
2	0.44	0.235	1.2375	1.135	7.55	34.32	0.278
3	0.44	0.235	1.0125	0.91	6.21	28.23	0.232
4	0.5575	0.352	1.4625	1.36	16.18	58.04	0.337
5	0.5575	0.352	1.2375	1.135	13.74	49.29	0.290
6	0.5575	0.352	1.0125	0.91	11.31	40.57	0.244
7	0.665	0.46	1.4625	1.36	24.81	74.62	0.347
8	0.665	0.46	1.2375	1.135	21.12	63.52	0.301
9	0.665	0.46	1.0125	0.91	17.43	52.43	0.254
10	0.7825	0.5775	1.4625	1.36	36.56	93.45	0.359
11	0.7825	0.5775	1.2375	1.135	31.18	79.69	0.313
12	0.7825	0.5775	1.0125	0.91	25.82	66.01	0.267
13	0.89	0.685	1.4625	1.36	49.46	111.14	0.37
14	0.89	0.685	1.2375	1.135	42.4	95.3	0.324
15	0.89	0.685	1.0125	0.91	34.86	78.34	0.278

Section	Section properties per metre length			Shear stress coefficient, K_1 per m^2	Trial section stability moment coefficient, K_2 (kN/m), density = 20 kN/m^3
	I ($10^{-3} \times$ m^4)	Z ($10^{-3} \times$ m^3)	A (m^2)		
1	6.09	27.69	0.222	27.74	0.835
2	6.10	27.73	0.225	27.66	0.846
3	6.13	27.88	0.229	27.51	0.862
4	11.06	39.69	0.230	20.50	1.097
5	11.10	39.83	0.234	20.44	1.116
6	11.17	40.07	0.241	20.34	1.149
7	16.96	51.02	0.237	16.56	1.347
8	17.07	51.33	0.243	16.46	1.381
9	17.21	51.77	0.251	16.37	1.426
10	24.99	63.90	0.245	13.60	1.640
11	25.19	64.40	0.253	13.49	1.692
12	25.50	65.20	0.264	13.33	1.766
13	33.82	76.00	0.253	11.64	1.926
14	34.26	77.01	0.262	11.49	1.994
15	34.43	77.37	0.274	11.44	2.085

Note: For sections 1, 4, 7, 10, 13 the flange length slightly exceeds the limitations given in BS 5628, clause 36.4.3(b). These sections have been included since they are the closest brick sizes to the flanges recommended in the Code. If the designer is concerned at this marginal variation, he may calculate the section properties on the basis of an effective flange width of 1.33 m.



Figure 13.68 Shear stress distribution diagram

where

V = design shear force
$A = B_r \times T$
$\bar{y} = \dfrac{d}{2} + \dfrac{T}{2}$

Then design vertical shear stress at XX,

$$v_h = \frac{V \times B_r \times T(d/2 + T/2)}{I \times t_r}$$

Generally, $T = t_r = 0.1025$ m.

Therefore

$$v_h = V \times \frac{B_r}{I}\left(\frac{d}{2} + \frac{0.1025}{2}\right)$$

Let

$$K_1 = \frac{B_r}{I}\left(\frac{d}{2} + \frac{0.1025}{2}\right)$$

Then $v_h = K_1 V$.

For section 3, Table 13.2

$$K_1 = \frac{1.0125}{6.21 \times 10^{-3}}\left(\frac{0.235}{2} + \frac{0.1025}{2}\right) \text{per m}^2$$

Values of K_1 for other sections are given in Table 13.2.

It should be noted that the constant K_1 has been calculated on the assumption that both ribs and leaves are constructed in half-brick walls – the derivation of K_1 would require adjustment for varying thicknesses of composition.

13.9.4 Trial Section Coefficients, K_2 and Z

Owing to the symmetrical profile of the diaphragm wall, a more direct route to a trial section has been devised and considers the two critical conditions which exist in the 'propped cantilever' action of the analysis.

Condition (1) exists at the base of the wall where the applied bending moment at this level must not exceed the stability moment of resistance of the wall.

Condition (2) exists at approximately (3/8)h down from the top of the wall where the flexural tensile stresses are a maximum and must not exceed those allowable through calculation.

Consider the two conditions.

Condition (1)

The trial section analysis is simplified by assuming that the dpc at the base level cannot transfer tensile forces and that the mass contributing to the MR_s comprises only the own weight of the masonry,

$$\text{BM at base level} = \frac{\gamma_f W_k h^2}{8} \tag{13.1}$$

(see section 13.5.5 for lever arm).

MR_s at base level

$$= \text{area} \times \text{height} \times \text{density} \times \gamma_f \times 0.475D$$
$$= 0.475(A \times h \times \gamma_f \times D \times \text{density}) \tag{13.2}$$

Equating (13.1) and (13.2) gives:

$$\frac{\gamma_f W_k h^2}{8} \le 0.475\,(A \times h \times \gamma_f \times D \times \text{density})$$

γ_f for wind and dead loads will be taken as 1.4 and 0.9 respectively.

Hence, $0.175\ W_k h^2 \le 0.4275\,(A \times h \times D \times \text{density})$

now let $K_2 = 0.4275 \times A \times D \times \text{density}$

then

$$W_k h \le 5.714 K_2$$

and

$$h \le \frac{5.714 K_2}{W_k} \tag{13.3}$$

Condition (2)

The trial section analysis is simplified by assuming that flexural tensile stresses control, γ_m, is taken as 2.5 and f_{kx} as 0.4 N/mm^2

$$\text{BM at } (3/8)h \text{ level} = \frac{9\gamma_f W_k h^2}{128} \tag{13.4}$$

$$\text{MR} = \left(\frac{f_{kx}}{\gamma_m} + g_d\right) Z \tag{13.5}$$

Equating (13.4) and (13.5) gives:

$$\frac{9\gamma_f W_k h^2}{128} \le \left(\frac{f_{kx}}{\gamma_m} + g_d\right) Z$$

$$\frac{9 \times 1.4 \times W_k \times h^2}{128} \le \left(\frac{0.4 \times 10^3}{2.5} + \frac{\gamma_f \times 20 \times 3 \times h}{8}\right) Z$$

$$0.098 W_k h_2 \le (160 + 6.75h) Z$$



Figure 13.69 Trial section coefficient K_2



Figure 13.70 Trial section Z modulus

$$Z = \frac{0.098 W_k h^2}{160 + 6.75h} = \frac{W_k h^2}{1600 + 67.5h} \qquad (13.6)$$

Two graphs have been plotted for equations (13.3) and (13.6) and for various values of W_k, which are shown in Figures 13.69 and 13.70.

For a known wall height and wind pressure, values of K_2 and Z may be read off the graphs and, using Table 13.2, the most suitable section can be obtained for full analysis. It should be remembered that the two trial section graphs have been drawn assuming fixed conditions for a number of variable quantities which are summarised thus:

(a) the wall acts as a true propped cantilever,
(b) the dpc at the base of the wall cannot transfer tension,
(c) the vertical roof loads (downwards or uplift) are ignored,
(d) γ_m is taken to be 2.5,
(e) f_{kx} is taken to be 0.4 N/mm^2,
(f) the density of masonry is taken to be 20 kN/m^3,
(g) K_2 values are calculated using an approximated lever arm method.

The trial section of graphs must be used only for the purpose of obtaining a trial section and a full analysis of the selected section must always be carried out.

13.10 Example 2: Diaphragm Wall

13.10.1 Design Problem

A warehouse measuring 30 m × 60 m and 8 m high is shown in Figure 13.71 and is to be designed in brickwork, using



Figure 13.71 Diaphragm wall design example 2

diaphragm wall construction for its main vertical structure. There are no substantial internal walls within the building to provide any intermediate support. During construction, extensive testing of materials and strict supervision of workmanship will be employed.

This building is likely to be considered as Class 2A in accordance with Part A3 of The Building Regulations and as such will require horizontal ties as given in BS 5628.

Facing bricks with a compressive strength of 41.5 N/mm^2 and a water absorption of 8% will be used throughout the building.

13.10.2 Characteristic and Design Loads

The characteristic and design loads will be taken as the same as those used for the earlier fin wall design example.



Figure 13.72 Diaphragm wall section 5

Characteristic Loads

(a) Wind forces:

all as fin wall design, hence

Pressure on winward wall, $W_{k_1} = 0.678\ \text{kN/m}^2$
Suction on leeward wall, $W_{k_3} = 0.411\ \text{kN/m}^2$
Gross roof uplift, $W_{k_2} = 0.535\ \text{kN/m}^2$
Uplift, from $W_{k_3} = 0.749\ \text{kN/m}^2$

(b) Dead and superimposed loads:

all as fin wall design, hence

Superimposed load, $Q_k = 0.75\ \text{kN/m}^2$
Dead load, $G_k = 0.67\ \text{kN/m}^2$

Design Loads

All as fin wall design, hence:

$$\text{Design dead loads} = 0.9 \times 0.67 = 0.603\ \text{kN/m}^2$$

Design wind loads:

Pressure, from $W_{k_1} = 0.949\ \text{kN/m}^2$
Suction, from $W_{k_2} = 0.575\ \text{kN/m}^2$

Design dead – uplift = $-0.146\ \text{kN/m}^2$

13.10.3 Select Trial Section

For the wall height of 8.0 m and the characteristic wind load of 0.678 kN/m^2, $K_2 = 0.95$ kN/m and $Z = 20.3 \times 10^{-3}$ m^3 can be read from Figure 13.69 and Figure 13.70 respectively. Select wall section 5 (wall section 4 could have been used also at this stage) and a full analysis using this section should then be carried out.

Wall Properties

$I/\text{m} = 11.10 \times 10^{-3}\ \text{m}^4$
$Z/\text{m} = 39.83 \times 10^{-3}\ \text{m}^3$
$A/\text{m} = 0.234\ \text{m}^2$
$K_1 = 20.44/\text{m}^2$

The wall section is shown in Figure 13.72.

13.10.4 Determine Wind and Moment MR_s at Base

Considering 1 metre width of wall:

$$\text{Design wind moment at base} = 1.4\ W_k \frac{8^2}{8}$$

$$= \frac{0.949 \times 8^2}{8} = 7.592\ \text{kN m}$$

The calculated stability moment of resistance at the base is found as follows.

Appendix B of BS 5628 discusses the application of a rectangular stress block under ultimate conditions, and the stability moment of resistance MR_s can be assumed to be provided by the axial load in the diaphragm section acting at a lever arm about the centroid of the rectangular stress block, as shown in Figure 13.73.

Hence:

$$\text{Design dead load at base} = 0.9 \times 0.234 \times 20 \times 8 = 33.70\ \text{kN}$$

$$\text{Minimum width of stress block} = \frac{\text{axial load in diaphragm}}{1000 \times p_{ubc}} \quad (13.7)$$



Figure 13.73 Generation of MR_s for diaphragm wall

Now, p_{ubc} = allowable flexural compressive stress = $1.1\beta f_k/\gamma_m$, with lateral restraint provided by the foundations assuming a raft foundation and, as for the fin wall design previously, β can be taken as 1.0. Therefore, $p_{ubc} = 1.1 f_k/\gamma_m$ at base level.

Assuming 41.5 N/mm^2 bricks in 1 : 1 : 6 mortar then f_k from Table 2(a) in BS 5628 is 9.41 N/mm^2, and assuming γ_m = 2.5 then $p_{ubc} = 1.1 \times 9.41/2.5 = 4.14$ N/mm^2.

Substituting this value in equation (13.7):

$$\text{Minimum width of stress block} = \frac{33.70 \times 10^3}{1000 \times 4.14} = 8.14 \text{ mm}$$

Therefore

$$\text{Stability MR} = 33.70 \times \left(\frac{0.5575}{2} - \frac{0.00814}{2} \right)$$

$$= 9.26 \text{ kN m} = \text{wind moment}$$
$$> 7.592 \text{ kN m}$$

It is interesting to compare the calculated value of stability moment of resistance MR_s with the approximate lever arm method suggested earlier (see section 13.5.5).

$$\text{Approximate MR}_s = \gamma_f \times 20 \times 0.234 \times 8 \times l_a$$
$$= 33.70\, l_a$$

$$\text{Approximate } l_a = 0.475D$$
$$= 0.475 \times 0.5575$$
$$= 0.265 \text{ m}$$

Therefore:

$$\text{Approximate MR}_s = 33.70 \times 0.265 = 8.93 \text{ kN m/m}$$

which is still greater than 7.592 kN m applied BM.

Since the stability moment at the base is greater than the wind moment, the maximum span moment occurs (3/8)*h* down from roof level.

$$M_w = \text{wind moment at } (3/8)h = \frac{9 \times 0.949 \times 8^2}{128}$$

$$= 4.27 \text{ kN m/m}$$

13.10.5 Consider Stress at Level M_w

The stress considerations at the level of the maximum wall moment assume triangular stress distribution, using elastic analysis, but relate to ultimate strength requirements at the extreme edges of the wall face. Compliance with clause 36.9.1(b) of the Code is considered inappropriate and impractical – see section 6.10 for discussion.

$$\text{Design axial load at } M_w \text{ level} = 0.9 \times 0.234 \times 20 \times (3/8) \times 8$$
$$= 12.636 \text{ kN}$$

Flexural Stresses at Design Load

$$\text{Stress} = \frac{\text{load}}{\text{area}} \pm \frac{\text{moment}}{\text{section modulus}}$$

Flexural compressive

$$f_{ubc} = \frac{12.636 \times 10^3}{0.234 \times 10^6} + \frac{4.27 \times 10^6}{39.83 \times 10^6} = 0.054 + 0.107$$

$$= 0.161 \text{ N/mm}^2$$

Flexural tensile

$$f_{ubt} = 0.054 - 0.107$$
$$= -0.053 \text{ N/mm}^2$$

These stresses must now be compared with the allowable flexural stresses at M_w level.

(a) Allowable flexural tensile stress, p_{ubt}

$$p_{ubt} = \frac{f_{kx}}{\gamma_m}$$

where

f_{kx} = 0.4 N/mm^2 for clay bricks with a water absorption of between 7% and 13% set in 1 : 1 : 6 mortar, taken from Table 3 of BS 5628, for the plane of failure parallel to bed joints

γ_m = 2.5, from Table 4(b) of BS 5628 for special construction control of structural units (see Table 5.11).

Therefore

$$p_{ubt} = \frac{0.4}{2.5} = 0.16 \text{ N/mm}^2$$

By comparison with calculated f_{ubt} = 0.053 N/mm^2, the flexural tensile stresses are acceptable.

(b) Allowable flexural compressive stresses, p_{ubc}

$$p_{ubc} = \frac{1.1\beta f_k}{\gamma_m}$$

Calculate the value of β.

It is assumed that the flange of the diaphragm is liable to buckle under compressive bending loading. The effective length of the flange may be taken as 0.75 times the length of the internal hollow box and the effective thickness as the actual thickness of the flange, as shown in Figure 13.74.

In this case,

$$\text{Slenderness ratio} = \frac{0.75 \times 1.135}{0.1025} = 8.30$$



Figure 13.74 Stability of diaphragm flanges



Figure 13.75 Buckling of projecting fin

Further assuming that the stressed areas are concentrically loaded, i.e. $e_x = 0$, and referring to BS 5628, Table 7 (see Table 5.15), $\beta = 0.995$ by interpolation. Therefore:

$$p_{ubc} = \frac{1.1 \times 0.995 \times 9.41}{2.5} = 4.12\ \text{N/mm}^2$$

By comparison with calculated f_{ubc} = 0.161 N/mm^2, the flexural compressive stresses are acceptable.

The local buckling has been shown to be adequately analysed. The possibility of buckling of the overall section, in its height, must now be considered. This was shown to be a critical design consideration in the design of the fin wall because of the unrestrained edge of the outstanding leg of the fin from the flange. Figure 13.75 shows that the whole of the area in compression due to the bending could buckle in the fin wall situation.

The diaphragm wall, being a symmetrical section, is not prone to this mode of failure. The flanges provide adequate restraint to buckling. The possibility of the full section buckling under axial loading is outside the scope of this design example (see Chapter 10).

13.10.6 Consider Diaphragm with Deflected Roof Prop

From Figure 13.76 it is evident that the deflection of the roof wind girder induces additional rotation at the level of M_b.

In this design example the stability moment of resistance, $MR_s = 9.26$ kN m/m, which is greater than the design wind moment at the base = 7.592 kN m/m.

Thus if the roof prop should deflect, additional rotation would occur at base level causing a cracked section and thus taking advantage of the full stability moment. The revised BM for this condition is calculated below, where it is seen that the wall moment is reduced and the wall tends towards the free vertical cantilever situation. The position of the maximum wall moment occurs at the level of zero shear.

$$\text{Prop force at top} = \frac{0.949 \times 8}{2} - \frac{9.26}{8} = 2.639\ \text{kN/m}$$

$$\text{Point of zero shear} = \frac{2.639}{0.949} = 2.78\ \text{m from top of wall}$$

Therefore

$$M_w = (2.78 \times 2.639) - \frac{0.949 \times 2.78^2}{2}$$

$$= 3.67\ \text{kN m/m}$$

This is obviously acceptable since it is less than previously calculated M_w = 4.27 kN m/m, which assumed the propped cantilever condition and the base moment being limited to $\gamma_f W_k h^2/8$.

The increase in the moment at the base level up to the value of MR_s has also been shown to be acceptable from the earlier calculations of MR_s, although this should be checked fully if slenderness reductions are applicable at this level. The adjusted bending moment diagram for the deflected prop condition is shown in Figure 13.77.



Figure 13.76 Rotation of wall for deflected prop condition



Figure 13.77 Bending moment for deflected prop condition

13.10.7 Calculate Shear Stress

Reaction at base = shear force, V

$$V = (5/8) \times 0.949 \times 8$$
$$= 4.75 \text{ kN}$$

$$v_h = K_1 V$$

Therefore

$$v_h = \frac{20.44 \times 4.75}{10^3}$$

$$= 0.097 \text{ N/mm}^2$$

Shear resistance of wall ties:

This shear stress is to be resisted by flat metal shear ties of 3 mm × 20 mm cross-section built into the bed joints, and their vertical spacing is derived from the formula given in section 6.10.1 as:

$$ru = \frac{12 t_w s v}{0.87 f_y}$$

which, rearranged becomes

$$s = \frac{ruf_y}{13.8 t_w v}$$

hence

$$s = \frac{20 \times 3 \times 250}{13.8 \times 103 \times 0.097}$$

$$= 108.8 \text{ mm} \quad \text{vertically}$$

Shear ties are required in every course in each rib at the bottom of the wall but can be varied in spacing throughout the height of the ribs as the bending moment and shear forces reduce, or the cross-ribs could be fully bonded to the flanges.

13.10.8 Stability of Transverse Shear Walls

The designer should now check the stability of, and stress in, the gable shear walls using the principles given in Chapter 11.

13.10.9 Summary

Section 5 (Table 13.2) is acceptable using standard format 41.5 N/mm^2 crushing strength bricks with water absorption of 8% set in designation (iii) 1 : 1 : 6 mortar. It is important for the designer to appreciate that the example sections tabulated are not the only ones which can be considered. The depth of the diaphragm and the rib spacing may be varied to suit particular requirements. If, for example, the architect wished to express the ribs externally at 2.5 m centres, this would be achieved easily as shown in Figure 13.78, or a normal intermediate rib could be added internally.

The designer would, however, need to check the capacity of the flange to span between the ribs and give greater consideration to the design β value. In addition, for larger rib spacings, the designer should limit the length of the wall considered to be acting as the flanges of the box section to 6 × thickness of the wall forming the flange in assessing the section modulus to be used in the design (see BS 5628, clause 36.4.3 (b)).

13.11 Other Applications

Although diaphragm and fin walls were originally developed for use in tall, single-storey, wide-span structures, they do have applications in other fields, particularly where lateral loading is more significant than axial loading.



Figure 13.78 Alternative external treatment for diaphragm wall



Figure 13.79 Plan on diaphragm landscape walling

For example, diaphragms have been used by the authors as retaining walls. On one site in particular, which was covered with a large quantity of demolition rubble, the rubble was used to fill the voids in the diaphragm, and a strong and inexpensive mass retaining wall was achieved. This wall formed part of a landscaping development scheme and is shown in Figures 13.79 amd 13.80.

Diaphragms and fins are ideal forms for retaining walls and other walls which are required to resist comparatively high bending moments. They have been used in both plain and post-tensioned forms for retaining walls and in tall buildings. Diaphragm walls can also be used as sound deflectors on motorways in urban areas. Sound deflectors are presently constructed in steel frame, precast concrete or timber and it is considered that a diaphragm wall for this purpose would be less expensive, certainly more durable, and would probably posses greater aesthetic appeal.

Masonry has been a traditional choice for use in farm buildings and there is certainly scope to extend its use, by the way of diaphragms amd fins for storage bins for grain, potatoes, etc.

Apart from new structures, fin walls have been successfully used, by the authors, for strengthening existing buildings. The rear wall of a grandstand, which was showing signs of instability, was stiffened by bonding into it at predetermined centres, a series of brick fins. The fins were designed to resist the excess of loading which the original wall was unable to support. A further application was in the use of post-tensioned fins to strengthen a retaining wall within an existing basement where a change in use of the building had resulted in an increased lateral loading on the wall, causing it to bulge and crack. The post-tensioned brick fin proved easy to construct in an extremely confined working space with difficult access and, compared with alternative schemes, was shown to be the most economic solution.

The use of fin walls in conjunction with widely spaced spine walls provides a potential solution to multi-storey structures for use in open-plan office buildings, hospital ward blocks and other similar situations where the restrictions of cross-wall or cellular construction cannot be tolerated. Progressive collapse requirements need to be carefully considered in this form of construction (see Chapter 8).

While the discussion and calculations for the diaphragms and fins have dealt only with their effectiveness to resist lateral loading, they also both possess the correct properties to resist axial loading from tall platforms. The capacity of a simple wall to support heavy axial loading is significantly reduced by its tendency to buckle. If the load is applied at a great height, the natural compressive qualities of brickwork



Figure 13.80 Diaphragm landscape walling



Figure 13.81 Diaphragm wall section 10

are not being correctly exploited if, to provide an adequate slenderness ratio, the thickness of the wall is simply increased. This approach results in a wall with low applied stresses and high material content. Both the diaphragm and fin walls will provide greatly improved slenderness ratios and, at the same time, an adequate proportion of masonry area to support the axial loading at a more efficient stress level. The slenderness ratio of a wall is often expressed as the ratio of its effective height to its effective thickness. The effective thickness of the plain solid wall is its actual thickness. The effective thickness of the diaphragm or fin walls, assuming that the full section is loaded in each case, may be calculated approximately from the radius of gyration giving an equivalent solid wall thickness.

Consider the diaphragm section 10 as given in Table 13.2 earlier and shown in Figure 13.81. Consider a metre length of wall:

$$\text{Radius of gyration, } r = \sqrt{\left(\frac{I}{A}\right)}$$

$$= \sqrt{\left(\frac{24.99 \times 10^{-3}}{0.245}\right)}$$

$$= 0.32 \text{ m} \qquad (13.8)$$

For a 1 m length of solid wall:

$$I = \frac{1 \times t^3}{12}$$

$$A = 1 \times \text{t}$$

$$r = \sqrt{\left(\frac{I}{A}\right)} = \sqrt{\left(\frac{t^3}{12t}\right)} \qquad (13.9)$$

Equating (13.8) and (13.9):

$$0.32 = \sqrt{\left(\frac{t^3}{12t}\right)}$$

$$t^2 = 12 \times 0.32^2$$

$$t = 1.110 \text{ m}$$

Hence, the 782.5 mm diaphragm wall, calculated on this basis, would be equivalent, for the calculation of slenderness ration, to a solid wall of 1110 mm thickness. This is, however, an approximate assessment and for design purposes it is usually assumed that an effective thickness equal to the actual overall thickness should be used until a slenderness ratio based on radius of gyration is introduced into BS 5628.

A worked example of a diaphragm used to support high axial loading is given in Chapter 10.

14 Design of Multi-storey Structures

The method commonly used in building multi-storey structures is to erect a steel or concrete frame and clad it with external walls to provide a weather-resistant and durable envelope. Internal walls are built to form partitions, acoustic or fire barriers, party walls, etc., and to enclose stair and lift wells. Thus the frame has to carry the loads from the roof and floors, and has to be strengthened to carry the weight of the walls. When, as is often the case, the walls are of brick or block, their compressive strength and structural potential are completely wasted.

In many cases, however, if forethought is given to the plan form and the structural layout, the internal and external walls can easily be designed to carry not only their own weight but also the floor and roof loads, and the cost of a structural frame of beams and columns can be saved.

14.1 Structural Forms

Crosswalls

These are mainly used for hotel bedroom blocks, school classrooms, student hostels, town houses and other rectangular buildings with repetitive floor plans.

Cellular Construction

This type of construction is principally used for tall tower blocks of flats, square on plan.

Spine Construction

Spine construction is used where open-plan interiors are necessary in office blocks, hospital wards, warehouses and similar structures.

Column Construction

This is an alternative to spine construction.

Before discussing the choice and design of structural forms (using plane walls, i.e. solid, cavity and piered walls, or columns, diaphragm and fin walls), it is convenient to establish briefly here, and then to consider in detail, the common factors and problems:

(1) Stability under vertical loading, and from horizontal loading (mainly due to wind) on the longitudinal and lateral axes of the structure, which must be provided for.
(2) External walls. Restraint of outer leaf of cavity walls. This is necessary even when the wall is non-loadbearing.
(3) Provision for services. Early planning of service runs is necessary, so that openings in masonry frames can be built-in.
(4) Movement joints. As with other structural materials, movement joints must be incorporated in the structure. While masonry structures tend to be more resistant to damage due to movement, it is still necessary to install movement joints.
(5) Vertical alignment of loadbearing walls. For simplicity, speed of construction and cost, walls should remain in the same vertical plane from foundations to roof. Where, for special reasons, the occasional wall cannot be lined up, it is not difficult to accommodate such plan changes – though it does tend to increase costs.
(6) Foundations. The foundations for loadbearing masonry structures are generally simpler than those for structural frames. The loads are spread along walls founded on strip footings, so that contact pressures are low. In framed structures, loads are often concentrated at the column points, so that contact pressures are high.
(7) Flexibility. Sometimes, over a period of time, there is a need to alter structures due to changing functional requirements. In many situations, masonry structures are more readily adaptable to change than steel or concrete frames.
(8) Concrete roof slab/loadbearing wall connections. Insitu concrete roof slabs should not be cast directly on to masonry walls. As the roof expands and contracts, due to thermal and other movements, the wall will tend to crack, particularly at the connection. A sliding joint, such as two layers of dpc, should be laid on top of the walls before casting the concrete.
(9) Accidental damage. This topic is discussed in detail in Chapter 8.
(10) Choice of brick, block and mortar. While it is quite simple to design every wall in every storey height with a different structural masonry unit and mortar, this increases the costs, planning and supervision of the contract. On the other hand, although the use of only one brick or block laid in one class of mortar simplifies planning and supervision enormously, it may not be the most economical solution overall. For example, engineering bricks may be necessary on the lower levels of a multi-storey block, but, as these tend to be more expensive than the low strength bricks which may be adequate on the upper floors, it would be uneconomical to use them throughout the structure. Thus before making a choice, the cost implications should be carefully considered.



Figure 14.1 Main forces acting on a structure

(11) Large openings/windows. These are not always easy to accommodate without additional framing/restraint of wall elements.

14.1.1 Stability

Figure 14.1 shows the main forces acting on a structure.

Vertical Stability

It is rare for vertical instability, i.e. collapse or cracking of walls under vertical loads, to be a major problem – provided, of course, the compressive stresses in the masonry are kept within the allowable limits and the necessary restraints to prevent buckling are provided (see Chapter 7).

Horizontal Stability

The wind acts on the external walls or cladding panels which transfer the wind force to floors and roof (which can act as a horizontal plate) which, in turn, transfer the force to the transverse walls (see Figure 14.2). The wind force creates racking in the transverse walls, as shown in Figure 14.3, but walls are highly resistant to racking action. The diagonal tension or racking stresses, which could cause cracking, are either eliminated by the vertical compressive load on the wall and/or resisted by the allowable tensile stresses in the masonry. If the tensile stress should exceed the allowable limits, consideration should be given to reinforcing or post-tensioning the walls.

The stresses at the base of the wall are due to the combined effect of the vertical loading and the moment induced by the wind force and are determined using the normal elastic stress distribution formula (see Figure 14.4):



Figure 14.2 Behaviour of structure under lateral loading



Figure 14.3 Racking action under lateral loading



Figure 14.4 Stresses occurring under lateral loading

$$f = \frac{W}{A} \pm \frac{M}{Z}$$

There is usually little danger in multi-storey structures of a wall overturning or failing in horizontal shear.

Multi-storey masonry structures tend to rely for their stability on their own weight in resisting horizontal forces due to wind. They are not capable, as can be steel or concrete frames, of being considered for design purposes as fully rigid frames. In steel or concrete structures, rigid frames tend to be necessary to resist lateral wind loading. It is not usually possible to develop as much rigidity at the junction of masonry walls and concrete floor slabs as there can be, for example, between concrete columns and beams. However, this is very rarely a difficult problem to overcome if sufficient forethought is given to the plan form and the structural layout. The use of the walls as shear walls, which replace the columns of a framed structure, can result in a very rigid design.

14.1.2 External Walls

External walls can be solid (sometimes known as single-leaf masonry), cavity, piered, diaphragms or fins. It is quite common for the outer leaf of a cavity wall, or the face of a solid wall, to be in a different quality unit from the inner leaf or face. In cavity wall construction, a very frequent example is the use of a clay facing brick externally and an insulating block internally. Note that in the case of a solid wall with different bricks on the outer and inner faces, the bricks should have compatible movement characteristics.

Cavity walls are more popular than solid walls because they are more resistant to rain penetration, and have better



Figure 14.5 Restraint of outer leaf of cavity wall at every 12 m height

thermal insulation properties. However, they are more expensive to build, and care and attention must be given to the choice and fixing of the wall ties. The outer leaf helps to restrain and stiffen the inner loadbearing leaf – but this action is only possible with sufficient, good, and durable ties. The external leaf should be properly and fully supported at every third storey height to prevent it bowing out, and to reduce the risk of loosening the wall ties due to differential movement of the inner and outer leaves. The only exception to this rule is in four-storey buildings, not exceeding 12 m in total height, where the restraint may be omitted at the designer's discretion.

While, to some extent, both leaves carry the wind load, in addition to carrying its own weight the inner leaf supports most of the floor load. Since the outer leaf tends to carry its own weight only, the choice of facing brick or block is not so restricted by strength requirements. It has been found that, if the inner leaf is overstressed, the creep action in properly tied brickwork or blockwork tends to partly redistribute the stress to the outer leaf.

A previously used method of restraining the outer leaf at every third storey, as required in BS 5628, was to project the concrete slab on to it, as shown in Figure 14.5.

If the projection of the concrete slab is considered to be aesthetically undesirable, brick slips can be used to face the edge of the slab. Details of types, fixings, etc., can be found in modern text-books on building construction. A typical detail is shown in Figure 14.6.

These details however are not suitable under current building regulations where 'cold bridging' can occur. A current method used to restrain the outer leaf is to anchor it to the slab by anchor ties or steel angles, as shown in Figure 14.7. There are proprietary fixing sytems available to achieve this fixing.



Figure 14.6 Restraint of outer leaf of cavity wall at every 12 m height



Figure 14.7 Restraint of outer leaf of cavity wall at every 12 m height

14.1.3 Provision for Services

Inevitably, pipes for hot and cold water supply, conduits for electricity cables, ducts for air-conditioning, etc., have to pass through loadbearing masonry walls. The openings or holes for these services must always be pre-planned. Services engineers are accustomed to indiscriminate breaking out of large holes and cutting chases in relatively thick walls of traditional masonry construction when upgrading or changing the services in existing buildings. They do not always appreciate that *ad hoc* alterations cannot be permitted in modern, slender, highly stressed walls. Holes and chases should not be cut without the prior approval of the structural engineer. (See also Appendix 4.)

Pre-formed openings can be arranged easily by leaving out bricks or blocks when building the wall. If the openings are large, or could cause overstressing or undesirable stress concentration in the surrounding masonry, reinforcement can be laid in the bed joints above the openings – and around, if necessary – to distribute the stress.

Detailed drawings of service holes and chases should be given to the contractor before the commencement of building operations. A typical builders-work drawing is shown in Figure 14.8.

Chases should be sawn out to the depth agreed by the structural designer, and must not be hacked out by hammer and chisel. Horizontal or diagonal chases are rarely permissible, nor are vertical chases in half-brick thick walls (102.5 mm thick).

Holes for vertical service runs through floor slabs form a very useful site aid in setting out and checking the vertical alignment of walls. Vertical ducts can easily be formed by making minor adjustments to the wall layouts (see Figure 14.9).

14.1.4 Movement Joints

On long crosswall and spine structures, it is essential to insert movement joints to counter the effects of thermal and moisture movements. They are also advisable on structures liable to undergo excessive differential settlement. Movement joints should also be used to break up L- and T-plan shapes, and other similar building configurations when they are sensitive to movement. A typical method of achieving this in crosswall structures is shown in Figure 14.10.

Services, finishes, etc., which have to cross the movement gap should be provided with flexible connection, as in concrete or steel-framed structures. The spacing of movement



Figure 14.8 Typical builders-work drawing



Figure 14.9 Services provided vertically through structure



Figure 14.10 Typical movement joint in multi-storey structure

joints depends upon the masonry units used. For example, 12 m spacing is usually adequate for clay bricks, and 6 m for concrete blocks. Detailed information on movement joints is provided in Appendix 3.

14.1.5 Vertical Alignment of Loadbearing Walls

While engineers and architects have long accepted the need for column grid layouts, and are well aware of the need to line up columns (i.e. column positions should remain constant from foundations to roof) they do not, at first, readily accept the same discipline in masonry structures – no doubt, because they have been used to placing non-loadbearing walls or partitions anywhere.

Non-loadbearing partitions can still be placed practically anywhere in a loadbearing masonry frame. But, as with steel or concrete columns, it is desirable that the loadbearing walls are lined up. They can, of course, be moved out of line – but this may mean expensive and complex beam and beam-support layouts. This factor, more than any other, has tended to militate against the use of loadbearing masonry, especially in situations where the ground floor layout differs from the upper floors. For example, in a hotel bedroom block, the ground floor may require large open spaces for restaurant, reception areas, etc. The conflicting needs of the ground floor and the upper floors can easily be reconciled by the use of podium construction (see section 14.2.7).

The authors' experience has shown that designers quickly adjust to the need for planning discipline, and welcome the benefits of repetition of floor layouts, windows, doors and other furniture, service runs, finishes, etc., which can produce savings in cost and time of erection and provide simplicity of construction.

Loadbearing masonry structures can accommodate a wide range of functional requirements. It is simply a question of choosing the form best suited to the function.



Figure 14.11 Composite wall using footing beam and masonry wall

14.1.6 Foundations

The narrowest strip footing that can be conveniently dug by an excavator usually results in a foundation area such that the soil contact pressures are low. For example, a nine-storey hostel block with 102.5 mm crosswalls, founded on a 600 mm wide concrete strip footing, would have a contact pressure of only about 325 kN/m^2.

When the ground-bearing capacity is so low that piling is necessary, the wall itself could be treated as the compression flange of a composite reinforced concrete/masonry ground beam, with attendant savings in foundation costs (see Figure 14.11). It is likely that this would be undertaken only in exceptional circumstances or in a temporary situation, since it would be difficult to ensure that future alterations to the structure might compromise its integrity and above all the overall robustness/disproportionate collapse requirement could be difficult to justify.

Because masonry walls (particularly clay brickwork) are pliant, compared with structural steel or rc frames, they are particularly economical on sites subject to mining or other subsidence. Reinforcing the lower bed joints at each storey height and providing movement joints at the correct locations, results in a wall that is highly resistant to differential settlement.

14.1.7 Flexibility

Many designers think that masonry structures are inflexible – that it is difficult to alter them, once they are built. This is not so. For example, one of the authors' most interesting change-of-use projects was the successful conversion of a Victorian ice-cream factory into an old people's home.

The spate of conversion, alterations and rehabilitation of masonry structures in the 1970s gave masonry designers the opportunity to prove that it is often easier to alter a masonry structure than a steel or concrete structure. Admittedly, the bulk of the work was on brick structures, but the same is true – albeit, perhaps, to a somewhat lesser extent – of concrete block structures. It is often easier to demolish a masonry wall than a steel or concrete column. And it is far simpler to form an opening in a masonry wall than in a reinforced concrete wall.



Figure 14.12 Slab/loadbearing wall connection

Although alterations to modern, highly stressed, loadbearing masonry structures require careful attention, it is only on rare occasions when wholesale alterations are required for a radical change of use that masonry structures become inflexible.

14.1.8 Concrete Roof Slab/Loadbearing Wall Connections

While it is good practice, and structurally beneficial, to cast floor slabs onto the walls, it is inadvisable to cast the roof slab directly on the top of the upper storey wall. The roof slab will tend to expand and contract with temperature variations and, if it is restrained by the slab/wall connection, either it or the wall will crack.

In order to reduce this effect, the roof slab should be separated from the supporting wall. This can be done simply by laying two layers of building paper on top of the wall – although this is not considered to be acceptable good practice. A more effective separation joint can be achieved by inserting a proprietary jointing material (see Figure 14.12).

14.1.9 Accidental Damage

Although, as noted earlier, provisions against accidental damage were discussed in detail in Chapter 8, it is worth repeating here the general recommendations for stability of BS 5628, which may be interpreted as follows:

(1) The designer responsible for the overall stability of the structure should ensure that the design, details, fixings, etc., of elements or parts of the structure are compatible, whether or not the design and details were made by him or her.
(2) The designer should consider the plan layout of the structure, returns at the ends of walls, interaction between intersecting walls, slabs, trusses, etc., to ensure a stable and robust design.
(3) The designer should check that lateral forces acting on the whole structure are resisted by the walls in the planes parallel to those forces, or are transferred to them by plate action of the floors, roofs, etc., or that the forces are resisted by bracing or other means.

The structure must have adequate residual stability not to collapse completely, and the Code further advises that the designer should satisfy himself or herself that '. . . collapse of any significant portion of the structure is unlikely to occur'.

14.1.10 Choice of Brick, Block and Mortar Strengths

Generally, the bottom storey masonry will be the most highly stressed. The stress diminishes with each storey height, and the most lightly stressed storey will usually be the top one. Inevitably, within any one storey height, some walls will be more heavily stressed than others. For example in, say, a six-storey hostel block, the crosswalls will be 215 mm thick minimum for sound reduction purposes, and the walls surrounding the staircase may, for fire protection purposes, also be 215 mm thick while carrying a lesser load than the crosswalls. Thus it follows that every storey height could be of a different strength masonry and that, within any one storey higher, variations in masonry strength could be employed. However, any savings in material costs due to the widespread variation would be swallowed up by the extra costs of organising, sorting, stacking, supervising, etc.

It is generally advisable to use a maximum of only three mortar strengths: 1 : $^1/_4$: 3 below dpc level or, in extremely highly stressed work, 1 : 1 : 6 (or 1 : $^1/_2$: 4) for external and highly stressed work, and 1 : 2 : 9 for internal work (i.e. mortar designations (i), (iii) and (iv) in BS 5628, respectively).

It is difficult for administrative or supervisory staff to check, by sight, the strength of the bricks, blocks, and the mix of the mortar. Reducing the cement content of the mortar produces only a minimal saving in the cost per m^2 of wall.

Every effort should be made to keep the wall of a constant thickness throughout its height. It should be kept in mind that a slender, highly stressed, wall is usually cheaper than a thick wall carrying a low stress. Brick and block strengths should generally be uniform throughout any one storey, and changes in strength should be limited to approximately every three storeys. In an eleven-storey contract, undertaken by the authors in the 1970s engineering bricks were used on the bottom three storeys, high strength bricks on the fourth to sixth floors, medium strength on the seventh to ninth, and low strengths on the top two storeys.

Note that a top storey wall, due to its small pre-load, may have excessive flexural tensile stress due to wind forces, and may require specific brick and mortar strengths to cope with this.

14.2 Crosswall Construction

Crosswall structures are one of the simplest structural forms for multi-storey buildings, and probably have the widest application. The basic form is shown in Figure 14.13 – detailed layouts are provided later in this chapter.

They are particularly suitable for long rectangular buildings which have repetitive compartmented floor plans. Typical examples are hotel bedroom blocks, study bedrooms in student hostels, school classroom blocks, town house developments and small four-bedded wards in hospital blocks. Crosswalls are necessary in such buildings – even if the designer uses a steel or concrete frame – for the following purposes:

(a) Acoustic barriers. The Building Regulations require 215 mm brick, or similar, partitions between study bedrooms (see Part E, 2003 for details). Similar thicknesses are required with concrete blocks.
(b) Party walls (separating walls). The Building Regulations require a minimum thickness of 215 mm brick, or similar for party walls between domestic units, excluding additional finishes to meet sound transmission levels. Please note however that these walls may need to be constructed as cavity walls if the floor thickness is insufficient to generate the mass required to permit a single leaf wall (see Part E as above).
(c) Fire barriers. The Building Regulations in many instances require 215 mm walls around staircases, lift shafts, vertical service ducts, etc., in addition to fire breaks along the building. Clay brickwork 100 mm thick provides 2 hours fire resistance.

14.2.1 Stability

While it is a simple process to design the crosswalls to support the vertical loading, a check must be made both on



Figure 14.13 Typical crosswall construction



Figure 14.14 Stability of structures

them, as structural elements, and the resulting structure, to ensure that there will be no collapse (instability) or overstressing due to horizontal loading from wind forces (see Figure 14.14).

Lateral Stability

Crosswalls are usually very stable under lateral loading. The stress, due solely to uniformly distributed wind loads at the base is:

$$\text{Stress} = \pm \frac{\gamma_f W_k h^2/2}{bd^2/6}$$

where

γ_f = partial safety factor
W_k = characteristic wind load
h = height of structure
b = thickness of wall
d = depth or length of wall.

Since d is usually relatively deep, the wind stresses are minimal (see Figure 14.15).

Longitudinal Stability

Unstiffened crosswall structures, i.e. crosswalls without stiffness at right angles to the plane of the wall, may not be stable under longitudinal loading from wind, and could collapse like a house of cards (see Figure 14.16).

To prevent such action, longitudinal bracing is necessary. This is usually provided (see Figure 14.17) by either:

(a) corridor walls,
(b) longitudinal external walls,
(c) stiff vertical box sections formed by the walls to staircases, lifts and services ducts, or
(d) cruciform, T-, Y-, L-shaped block plans, or other plan forms which provide longitudinal stiffness or robustness.

14.2.2 External Cladding Panel Walls

The external walls in Figure 14.17(b) may be subject to high lateral loads combined with only minimal vertical loads. Such masonry walls do not have a high resistance to bending perpendicular to their plane (see Figure 14.18).

The wall panels on the top storey are the most at risk because they are likely to be subject to the greatest wind pressure while the only compensating precompression is the vertical loading from the roof and their own weight. If a lightweight timber roof is used, there could be wind uplift forces to counteract by strapping it down to the walls. There would then be no vertical precompression in the top storey walls.

Generally, this is not a significant problem with loadbearing masonry – but it can be if the masonry is non-loadbearing and is used merely as a cladding to a steel or concrete-



Figure 14.16 Unstiffened crosswalls



Figure 14.15 Stresses in walls arising from lateral stability



Figure 14.17 Typical plan forms providing stiffness in two directions



Figure 14.18 Failure due to bending parallel to bed joints

framed structure. It is advisable to check the stresses in such panels, following the procedure set out in Chapter 11.

14.2.3 Design for Wind

The crosswalls act as shear walls under wind loading. Shear walls act as vertical, deep, stiff cantilevers in many framed structures, and resist the wind forces and moments on the structure – thus reducing the effects of wind on the frame. There is a large number of research papers on the subject, and it is discussed in detail in many good modern textbooks on the theory of structures, and an example of the design of such a shear wall is given in Chapter 11.

In most loadbearing masonry crosswall structures, the stresses due to wind are insignificant compared with those due to dead and imposed loading, as the worked examples will show. Nevertheless, it may be helpful to briefly discuss the topic here.

In a steel or concrete frame, the beams and columns are of relatively similar stiffness, rigidly connected, and are of the same material. However, in a loadbearing masonry structure, the walls are relatively sturdy, the floor slabs comparatively flimsy, and the structure will never really act as a rigid frame. The walls, having high stiffness, act as vertical cantilevers, and the floors can be considered as acting as pin-jointed props (see Figure 14.19).

The crosswall, when broken by a corridor, acts approximately as two separate cantilevers. If both walls are of the same depth, d, and thickness, they share the wind force equally. When they are not of equal depth, they share the wind force in proportion to their relative stiffness – if they deflect equally, as they are likely to do, because of the floor's action in transferring the force.

The strength of a wall is relative to its section modulus $Z = bd^2/6$, and the stiffness of a wall is relative to its second moment of area, $I = bd^3/12$.

In the crosswall structure shown in Figure 14.20:

Wall x has a Z value proportional to $3^2 = 9$
Wall y has a Z value proportional to $6^2 = 36$
(Wall y is four times as strong as wall x)



Figure 14.19 Vertical cantilever action



Figure 14.20 Typical example of cantilever stiffness



Figure 14.21 Plan of walls of differing lengths parallel to wind direction

Wall x has an I value proportional to $3^3 = 27$
Wall y has an I value proportional to $6^3 = 216$
(Wall y is eight times as stiff as wall x)

Since the walls are tied together by floor slabs, they are likely to deflect equally – thus wall y will carry eight times the wind force of wall x.

Walls of Differing Length and Axes to the Wind

The distribution of wind forces, particularly on tall slender crosswall structures, between walls of differing stiffnesses may need consideration. Some of the main points are illustrated below.

In Figure 14.21, the floor plan of a block of flats shows walls of differing length (and, therefore, stiffness) and of differing positions in relation to the wind. The main wind force would be resisted by walls 1, assisted by walls 2, with some help from walls 3, and little help from walls 4. An experienced designer would probably, at first, check only the effect of walls 1 and 2 in resisting wind, and then, if they were inadequate, consider the assistance of walls 3. He would be likely to ignore the minimal effect of walls 4 in resisting the wind forces. The use of walls 1 only, would necessitate a long span for the plate action of the roof or floors.



Figure 14.22 Structural forms of varying stiffness

Walls of Differing Section

When external or corridor walls are bonded into crosswalls, they change the shape of a crosswall from a simple rectangle into a T-, I- or Z-section. This can give the crosswall increased stiffness and hence increased stability.

In Figure 14.22, the I- and Z-sections are stiffer than the T-section, which in turn, is stiffer than the rectangular section.

14.2.4 Openings in Walls

Intuitively, it can be seen that, in Figure 14.23, wall (a) is stiffer than wall (b) which, in turn is stiffer than wall (c). The gable wall (d) with small, widely spaced windows, may be considered to act similarly to wall (a) if the openings are relatively small. However, if the windows are deepened, the wall approaches the condition of wall (c).

Only rarely do the calculations become very complex. However, if they do, or if the designer is in any doubt as to the stiffness of the walls or structure, he or she should either refer to one of the many computer programs on the market, or carry out a model test. If a computer is used, the designers should satisfy themselves that the program is suitable and well founded, and that the results of the analysis are reasonable.

14.2.5 Typical Applications

School Classroom Blocks

These are not normally more than four storeys high, and a typical plan shape is shown in Figure 14.24.

The crosswalls usually need to be 215 mm thick to carry the load. Gable and external side walls are normally in 305 mm cavity brickwork. However Part E, 2003 of The Building Regulations is not specific about the acoustic requirements but refers the designer to *The Acoustic Design of Schools*,



Figure 14.23 Building forms of varying stiffness



Figure 14.24 Typical classroom block layout

DfES, published by The Stationery Office, in order to determine suitable resistance to noise for various uses and locations in school buildings. The external and corridor walls, together with the staircase, are normally more than adequate to provide longitudinal stability.

In many cases, the long floor spans are most economically formed in precast, prestressed concrete units, seated 100 mm minimum onto the walls. To give some continuity and resistance to the negative moments which will occur in practice (even though, in theory, the units are 'simply' supported) it is advisable to employ an rc insitu infill over the wall support. This will assist in preventing a floor slab collapse should a crosswall be removed by accidental damage (see Figure 14.25). Note that it is necessary to comply with the Building Regulation covering progressive collapse for all educational buildings (see Chapter 8).

Where wide-span units are used to provide a fair-faced soffit, the insitu infill should still be provided (see Figure 14.26).

The alternative spans loaded condition, and the resulting bending moments and eccentricity of loading induced into



Figure 14.25 Insitu concrete infill over supporting wall for precast concrete floors



Figure 14.26 Insitu concrete infill for wide-span concrete floor units



Figure 14.27 Typical bedroom block layout

the walls due to deflection of the floor units and rotation at the supports, are rarely critical. Nevertheless, the effect of eccentricity on the bearing stresses should be taken into account. The reinforcement in the infill tends to reduce the effect of eccentricities and distribute the uneven stresses. (Note that many school buildings were erected in the late 1950s to early 1970s using high alumina cement in the precast floor units. All these buildings had to be investigated and, as far as the authors' experience and knowledge are concerned, none of the walls showed any distress due to eccentric loading.)

Figure 14.27 shows a typical basic floor plan of a bedroom block. Many buildings of this type are five to ten storeys high, and need to be checked for accidental damage under Building Regulation Part A. Floors are usually insitu continuous concrete slabs. Where the external side walls and the corridor walls are loadbearing, the floor slabs may span two ways. Some minor increase in reinforcement is all that is usually necessary to cope with the accidental damage provisions.

Crosswalls usually need to be 215 mm thick minimum in order to carry the load but specifically to provide sound insulation. It is not uncommon to return the ends of the crosswalls, at their junctions with the external and corridor walls, to improve their stability.

Crosswall structures can, of course, be built much higher than ten storeys. However, as with all high-rise construction, the costs tend to increase faster than the increase in height.

Low- to Medium-rise Flats (up to Six Storeys)

A typical floor plan is shown in Figure 14.28.

The demand for high-rise flats (which were more suited to cellular construction) has waned, and there is now more interest in medium-rise blocks. These are a hybrid form of the classroom and bedroom blocks, discussed earlier, in that they tend to comprise a mixture of 215 mm and 102.5 mm crosswalls depending on the usage of any room and whether it is a separating wall between each flat or unit. The party walls, spaced at about 12 m centres, need to be



Figure 14.28 Typical low to medium rise flats layout

215 mm thick to comply with The Building Regulations, and the intermediate crosswalls which do not fall under type E2 of Part E of The Building Regulations can be 102.5 mm thick. Corridor walls and external walls are generally of masonry construction, subject to the same Building Regulation requirements as the party walls, and are also usually 215 mm minimum thickness, and are used structurally for longitudinal stability.

Floors are nearly always of concrete construction. Timber floors are generally only used in domestic housing.

14.2.6 Elevational Treatment of Crosswall Structures

Long side walls pierced by hole-in-the-wall windows can be visually dull. There are many ways of overcoming this – for example by using decorative brickwork and/or by modelling the elevation (see Figure 14.29).



Figure 14.29 Typical elevational treatment of crosswall structures

14.2.7 Podiums

A common objection to the use of crosswall construction is that the ground floor planning requirements demand more open spaces than crosswalls permit. Typical examples are reception areas and restaurants in hotels, car parking for flats, recreation areas and shops in student hostels. But the floors above, with regular wall layouts, are ideal for crosswall construction.

Frequently, there is no need to frame the whole structure, merely because of the ground floor planning requirements. A different structural form can be used for the ground storey, and a common solution to the problem is to form a podium with steel, concrete or masonry columns supporting a concrete deck, as shown in Figure 14.30. Depending on the load from the crosswalls, the deck can be of plate or waffle slab construction, diagrid or T beam.

The deflection of the deck under the crosswalls should be assessed, even though clay brickwork often has an inherent flexibility that enables it to adjust to the deflection of a concrete beam. Blockwork is not so adaptable. If the deflection is of such magnitude as to cause the masonry to crack, a flexible joint should be included at the deck/wall junction and the lower courses should be reinforced, as shown in Figure 14.31. The flexible joint must not, of course, affect the loadbearing capacity of the wall.

14.3 Spine Construction

Spine construction can be used on buildings of rectangular plan shape where crosswalls are either too restrictive on planning, circulation, etc., or where they cannot be lined up due to different functional requirements at each floor level. Typical examples of the first category are hospital ward blocks, storage buildings and office blocks. Buildings in the second category are much rarer – and when they do occur, it is often only because the designer will not accept the planning discipline of crosswall construction.

In many cases, the solution to these problems is to eliminate the crosswalls and to use the external side walls and the corridor walls or a spine wall as the main loadbearing elements, as shown in Figure 14.32.



Figure 14.30 Podium type structure



Figure 14.31 Detail of base of crosswall supported across a reinforced concrete slab



Figure 14.33 Example of building with inadequate lateral stability



Figure 14.32 Spine wall construction



Figure 14.34 Plate action of floor

The depth from the external wall to the spine or corridor wall is usually limited to 8 m, which is about the economic limit for precast prestressed concrete floor units. If economic factors are not restrictive (which is unusual), the floor spans could be wider. Many buildings do not really need a floor span greater than 7 m or 8 m. Office workers seated at distances of more than, say, 6 m from the external windows will need permanent artificial lighting, air-conditioning and expensive service runs for heating, etc. People, naturally, like to be able to see out of a window and to use it to control their physical environment. Some designers consider that 5 m should be the maximum distance of a work space from an external wall.

There are two main structural problems in the design of spine structures:

(a) the provision of lateral stability,
(b) many structures must be resistant to progressive collapse following accidental damage.

14.3.1 Lateral Stability

The building shown in Figure 14.33 clearly has inadequate lateral stability from wind forces, and it is necessary to introduce structural elements to resist them. This can be done externally or internally. In both cases, the floor must act as a horizontal plate, or wind girder, to transfer the wind forces to the lateral elements resisting the wind as shear walls (see Figure 14.34).

Internal Loadbearing Elements

These are commonly the walls around staircases, lift wells and vertical service ducts. Elements such as gable walls, fire barriers, and the occasional partition wall, can also be used, as shown in Figure 14.35.

There is rarely a problem in providing lateral walls of sufficient strength to resist the wind forces, but there can be difficulty in providing the plate action of the floor if it is not



Figure 14.35 Walls providing lateral stability



Figure 14.36 Fin walls providing lateral stability

of insitu concrete. If the floor is constructed of prestressed precast concrete beams, a reinforced concrete topping will be necessary.

External Elements

Fin walls can be used to counteract the lateral wind forces. If the wind forces are appreciable, the fins may need post-tensioning (see Chapter 15). The advantage of using fin walls as vertical cantilevers resisting the wind force, is that they considerably reduce the need for the floor to act as a plate, although the use of a robust floor plate in this type of building would be better practice. A plan and section of a possible fin structure are shown in Figure 14.36.

14.3.2 Accidental Damage

All buildings should be constructed such that they are robust, but most buildings, other than single-occupancy domestic units, must be designed to satisfy the requirements for preventing disproportionate collapse in accordance with Part A of The Building Regulations. Among the checks that are undertaken are by:

(a) a portion of the external or spine walls being removed;
(b) a portion of the lateral internal walls being removed;
(c) a fin being removed;
(d) a section of the floor being removed.

A method of checking and designing against accidental damage is dealt with in Chapter 8 and in the worked example in this chapter.

14.4 Cellular Construction

Of all structural masonry forms, cellular construction is the most resistant to lateral loads and accidental damage, and was used to a limited extent for high-rise flats in the 1960s. Despite the decline in high-rise construction, it is still a most valuable structural form for flats, student hostels, etc. Even below six storeys, it is still worthwhile to carry out a cost exercise to determine its economic viability (see Figure 14.37).

The technique was pioneered by the Swiss engineer, Haller, who built some spectacular high-rise blocks in Basle, Berne and Zurich. A number were built in the UK during the boom years of high-rise flat construction. However, the method did not achieve the wide popularity of the precast concrete structures – due both to government encouragement of system building, and the lack of experience of many engineers in structural masonry design. Certainly, there was no sound technical reason for the neglect of masonry construction – it was cheaper to build, more satisfactory in use, and required less maintenance than the concrete systems. Some of the system-built blocks are now causing tremendous maintenance problems due to lack of cover, leaking and inadequate joints, condensation, etc., and their vulnerability to accidental damage was tragically demonstrated in the Ronan Point disaster.

The basic 'egg crate' form (see Figure 14.38) provides stiffness in two directions at right angles, and is therefore highly resistant to wind forces. Lifts, stairs and service ducts are located at the centre of the plan, with housing units around the perimeter (see Figure 14.39). In study/bedroom blocks, the central portion can also house bathrooms, toilets and kitchens. Typical flat layouts are shown in Figure 14.39, with the main walls in heavy outline.



Figure 14.37 Cellular construction



Figure 14.38 Plan of cellular construction



Figure 14.39 Typical flat layouts providing cellular construction

14.4.1 Comparison with Crosswall Construction

The function of a building tends to dictate its structural form. School classroom and hotel bedroom blocks are usually long rectangular buildings, and appropriate to crosswall construction. Tall, or tower, blocks of residential accommodation are often square on plan and therefore well suited to cellular construction.

In crosswall structures, it is the crosswalls that mainly carry the load, while the longitudinal walls (corridor and external side walls) serve to provide stability along the longitudinal axis. In cellular construction, all the walls carry the load and provide resistance to lateral forces on both axes.

Floors in cellular structures are nearly always of insitu concrete and, because of the two-way spanning possibilities and the shorter spans, tend to be more economical than in crosswall or other structural forms (see Figure 14.40).

14.4.2 Envelope (Cladding) Area

The cost of a building is affected by its ratio of envelope to floor area – the smaller the ratio, the lower the cost of the envelope. Figure 14.41 shows the favourable ratio for cellular structures compared with rectangular structures.



Figure 14.40 Typical floor construction in cellular structure



Figure 14.41 Comparison of cellular construction with rectangular construction

14.4.3 Robustness

Cellular construction is probably the most robust of all structural forms. If Ronan Point had been built in this form, with properly bonded intersections instead of apparently inadequately tied concrete panels, it would have been extremely unlikely to have collapsed, and the 'incident' would have been localised.

As noted earlier, the form is highly resistant to lateral loading and, because of the commonly symmetrical form, it is resistant on both axes. Since it is relatively massive – compared, for example, with steel frames with glass external cladding and lightweight internal partitions – there is far less likelihood of unacceptable vibration in tower blocks due to severe wind gusting. The authors know of no case of noticeable vibration in a multi-storey cellular masonry structure – although there is evidence of such action in other materials. The inherent stiffness of the structural form makes it particularly useful in areas subject to high winds and foundation movement.

14.4.4 Flexibility

Reference has already been made to the relative ease of making alterations to masonry structures to suit changing functional requirements. Cellular structures are no exception and, because of the multiplicity of walls, they are often easier to alter than other structural forms. The designer must, of course, take the same care to ensure that the alterations do not overstress the structure.

14.4.5 Height of Structure

Very tall structures can be built using cellular construction. Apart from the cost, the main factor affecting the height is stability under wind loading. A simple calculation shows that a 20 m square block, 15 storeys (40 m) high has a generous factor of safety against overturning from the wind forces. A detailed check must, of course, be made to see that the structure has adequate stiffness (see Figure 14.42).

14.4.6 Masonry Stresses

Since the load is shared by all the walls, the stresses tend to be lower than in other structural masonry forms – which makes cellular construction particularly suitable for high-rise buildings, and when considering lateral loads on external walls. The wall thicknesses need to meet Building Regulation requirements for fire, sound and thermal insulation, party walls, etc., and are often greater than the



loading

walls $8(20 \times 2.4 \times 0.215 \times 20\ \text{kN/m}^3) = 1651$

$+ 5(20 \times 2.4 \times 0.103 \times 20\ \text{kN/m}^3) = 494$

floors $13(20 \times 20 \times 3\ \text{kN/m}^2) = \dfrac{15\,600}{17\,745}$

stability $M = 17\,745 \times 10 = 177\,450$ kN m

wind $M = 40 \times 20 \times 20 \times 1\ \text{kN/m}^2 = 16\,000$ kN m

Figure 14.42 Simple calculation for overturning of tall structure subjected to wind load

thickness required to carry the loads. Calculations show that, quite often, the most heavily stressed wall under imposed and wind loading (the external wall on the leeward face) needs only to be a normal 305 mm cavity wall.

14.4.7 Foundations

The foundations of cellular structures tend to be cheaper than those for other structural forms. The loads are spread over more walls, more uniformly, and at closer spacings. Contact pressures, therefore, are generally lower. On soils of good bearing capacity, it is not uncommon to merely thicken the ground floor slab under the internal walls.

14.5 Column Structures

Masonry columns are scarcely a new structural form, and modern masonry column structures are simply a development of an old technique. For example, many medieval cathedrals are basically column structures in which the lateral thrust from the roof is resisted by flying buttresses. When, in a modern column structure, the columns are not adequate to resist the lateral thrust from the wind, the restraint can be provided by shear walls, fins, etc.

Use

Masonry column structures are mainly used for buildings whose functions require large open spaces, such as warehouses, department stores and, occasionally, open-plan offices.

The spacing of the column grid is usually a compromise between the client's preferences, cost and engineering feasibility. The closer the spacing, the cheaper the structure, but the greater the loss of spatial freedom. As so often happens with concrete structures, the client tends to want a grid spacing of 12 m, but eventually settles for about 7.5 m.

Floors

Most column structures have insitu concrete floors, of either plate or waffle slab construction to eliminate the inconvenience of beams which reduce headroom. The floors must act as horizontal plates to transfer the lateral wind thrusts to shear walls.

14.5.1 Advantages

It may appear odd to use masonry columns in a structure when so much insitu concrete is used in the floors and foundations. Masonry columns are chosen for:

(a) Speed of Erection

It is quicker to build a masonry column than an insitu concrete column, or to fabricate, erect, plumb and fire-protect a steel column. To ensure continuity of the masonry labour force, it is usually advisable to use masonry construction for the external cladding, shear walls, etc.

(b) Economy

Masonry columns are generally cheaper than alternative materials. Admittedly, economy is rarely a major consideration, since the cost of the columns is only a minor part of the total construction costs.

(c) Durability

Corners of columns are easily chipped and damaged in warehouses, etc. The corners of concrete columns can be rounded off by using $^1/_4$ round bead fillets in the shuttering, and the fire protection cladding to steel columns can be strengthened by adding steel angles at the corners. Both methods add to costs. Radiused bricks or bull-nosed bricks are not expensive and are usually readily available.

(d) Aesthetics

Since the columns are likely to be heavily stressed, engineering or high-strength facing bricks are often required. Both categories are available in a wide range of colours and textures, and are likely to be far more visually attractive then encased steelwork or plastered concrete.

14.5.2 Cross-sectional Shape

Square and rectangular columns are the cheapest and simplest to build since they only involve four corners (and thus four plumbing lines), do not require specially shaped bricks, and are easily bonded. However, there are sometimes structural or aesthetic advantages in using other sections.

(a) Cruciform

These give higher lateral resistance in two directions. No guidance is given in BS 5628 on the slenderness ratio or section modulus of such sections. However, the authors suggest that the radius of gyration of the section be determined, related to a square section of equal radius of gyration, and the thickness of the square section taken as the effective thickness of the cruciform section. The section modulus can be determined from first principles, in the

same way as the section modulus of cruciform sections in other materials.

(b) I Sections

Similar effectiveness and methods apply to I sections. A further advantage of this section is that services can be run up the faces of the webs.

(c) Hollow Square, Rectangular or Circular Sections

These have the advantages of a high second moment of area and section modulus, but require a larger overall cross-sectional area. They are particularly useful as structural and permanent shuttering to reinforced concrete columns. Care must be exercised in grouting up each column lift to ensure that all mortar droppings are removed from the surface of the previously poured grout.

14.5.3 Size

With masonry columns, there is less need to maintain the same profile all the way up the structure – as there is with concrete (to reduce shuttering cost) or with steelwork (to simplify connections). Nevertheless, to avoid complications in standard details, fixings, etc., it is advisable to keep the number of changes of section to a minimum. This can be achieved by using high-strength masonry in the lower storeys (perhaps, with the addition of reinforcement) and lower-strength masonry in the upper storeys to produce an economical balance.

Typical floor-to-floor heights for offices are about 3–4 m, for department stores around 5 m and for warehouses 4–6 m. Grid spacings are generally from 5–7 m in both directions. Thus the size of the columns can vary enormously since it depends on their height, load (dependent on the grid spacing and the use of the structure) and the strength of the masonry. It is not difficult to reduce the cross-section of a column by adding reinforcement, if this is economically worthwhile.

Depending on location, availability of tradesmen, time and other factors such as Construction Design and Management (CDM) issues, it is worth considering the use of masonry columns instead of steel or concrete columns.

14.6 Design Procedure

The design procedure for multi-storey masonry structures is similar to that for other structural materials and is as follows:

(1) Layout. Wall positions should be chosen to suit the function of the building. This is usually the architect's responsibility, but the engineer should certainly advise in this regard, and on the types and direction of floor spans and roofs, joint locations, restraint considerations, etc. All too frequently, the two professions – architects and engineers – do not confer at an early enough stage in the creative process.
(2) Wall thicknesses should be chosen to comply with:
  (a) Building Regulations (fire resistance, acoustic and thermal requirements, etc.),
  (b) material dimensions (215 or 102.5 mm brickwork, 100, 140 or 215 mm blockwork),
  (c) serviceability needs,
  (d) estimated trial section for load carrying.
(3) Check required thickness against trial section thickness for load carrying.
(4) Preliminary appraisal of liability to accidental damage (span of floors, returns to walls, etc.).
(5) Determine dead, imposed and wind loadings, and worst combination.
(6) Determine stresses in masonry elements.
(7) Choose masonry and mortar strengths.
(8) Check for 'column action' or overstressing of areas of wall in external walls with large window or other openings, internal walls with large door openings or service access, particularly corridor walls with clerestorey lights.
(9) Check upper storey (or storeys) for flexural tensile stress under minimum axial loading.
(10) Check for stability.
(11) Check again for accidental damage.
(12) Add straps and ties, where necessary.
(13) Check details (end bearing stresses, stresses around service holes, etc.).

14.7 Example 1: Hotel Bedrooms, Six Floors

Basic Data (see Figure 14.43)

Overall height	15.0 m
Floor-to-floor height	2.50 m
Span of floors	3.0 m
Overall length	30.0 m
Overall width	20.5 m
Density of masonry	20 kN/m^3
Density of reinforced concrete	24 kN/m^3

The floor and roof construction is of reinforced insitu concrete slabs supported by loadbearing masonry. Precast concrete floors were not chosen in this example because insitu floors tend to give greater rigidity to the structure when it has to be designed to meet accidental damage loadings. Furthermore, on such relatively short spans, insitu concrete slabs tend to be more economical than precast, and a suitable bearing onto thin crosswalls is achieved more easily. It should be noted that this example has been worked with a 125 mm thick slab. This is likely to be too thin to meet sound requirements in accordance with Part E of The Building Regulations for the separating walls between each specific room/unit.

14.7.1 Characteristic Loads

Roof

Dead loads, G_k,

125 mm rc slab = 24 × 0.125	= 3.0 kN/m^2
lightweight screed to falls	1.0 kN/m^2
(average) allow	= 4.0 kN/m^2

Imposed load, Q_k (BS 6399, Part 1) = 0.75 kN/m^2



ground floor plan



general floor plan



section A-A

Figure 14.43 Layout for Example 1

Floors

Dead loads, G_k,

125 mm rc slab = 24×0.125	$= 3.0\ kN/m^2$
partitions, allow	$1.0\ kN/m^2$
finishes and services, allow	$0.3\ kN/m^2$
allow floor screed	$1.0\ kN/m^2$
	$= 5.3\ kN/m^2$

Imposed load, Q_k (BS 6399, Part 1) = $2.0\ kN/m^2$

Wind Loading

The choice of the characteristic wind load for design purposes is covered in BS 6399, Part 2, 1997, and is outside the scope of this example. Assume that the maximum characteristic wind pressure, W_k, is 0.894 kN/m^2. Also assume that the roof is flat and that $C_{pi} = +0.2$ or -0.3 and $C_{pe} = +1.0$.

14.7.2 Design of Internal Crosswalls

Having decided on the basic design parameters and loadings, the designer can now go on to design the structure itself. It should be remembered that careful consideration must be given to the location of any joints within the concrete slabs and masonry walls, since these will affect the overall stability of the structure.

Loading

The self-weight of the masonry must be added to the above in obtaining the total design load. For a trial section, try a 102 mm thick wall. At position A, the characteristic load = height × thickness × density = $15.0 \times 0.102 \times 20 = 30.6$ kN/m run due to the masonry.

Assume $\gamma_f = 1.4$ for dead loads or 0.9 as appropriate, 1.6 for imposed loads (from clause 22, BS 5628).

Therefore, at A (see Table 14.1) the total design load

$= 1.4(91.5 + 30.6) + 1.6(0.6 \times 32.25)$
$= 170.9 + 30.96$
$= 201.85$ kN/m run

Now assuming that the floor slab, if built into the wall, provides enhanced resistance to lateral movement, then the effective height of the wall (clause 28.3.1.1, BS 5628) may be taken as $0.75 \times 2500 = 1875$.

Table 14.1

Position	Characteristic dead load, G_k, kN/per metre run due to floors and roof	Characteristic imposed load, Q_k, kN/per metre run	Imposed load reduction factor (%) (Table 2, BS 6399, Part 1)
Roof	$3 \times 4 = 12$	$3 \times 0.75 = 2.25$	0
5th floor	$12 + 3 \times 5.3 = 27.9$	8.25	10
4th floor	43.8	14.25	20
3rd floor	59.7	20.25	30
2nd floor	75.6	26.25	40
1st floor	91.5	32.25	40



Figure 14.44 Eccentricity check for Example 1

The effective thickness of a half brick wall is the actual thickness = 0.102 m.

Therefore, slenderness ratio = 1.875/0.102 = 18.4.

Check the maximum eccentricity at first floor level (see clause 31, BS 5628) – assume the loading given in Figure 14.44 for the calculation of the eccentricity.

The resultants R_1 and R_2 are assumed to act at one-third of the depth of the bearing area from the loaded faces of the wall, i.e. $(102/2) \times 1/3 = 17$ mm in from the face.

Now $R_1 = (1.4 \times 5.3 \times 3/2) + (1.6 \times 0.6 \times 2 \times 3/2)$
$= 11.13 + 2.88$
$= 14.01$ kN/m run

and $R_2 = (0.9 \times 5.3 \times 1.5)$
$= 7.1$ kN/m run

The load in the wall above the first floor level may be assumed to be axial and

$= 0.9(75.6 + 12.5 \times 0.102 \times 20)$
$= 91$ kN/m run

Considering a 1 m length of wall and taking moments about face P, let R be the distance to the resultant of R_1, R_2 and the axial load:

$(91 \times 0.051) + (14.01 \times 0.017) + (7.1 \times 0.085)$
$= (91 + 14.01 + 7.1)R$

Therefore $R = 0.049$

Therefore, eccentricity at the top of the wall = 0.051 – 0.049
= 0.002 m

Now, thickness, t = 0.102, therefore eccentricity (as a proportion of t) = $0.002/0.102 = 0.0196t$.

So, from Table 7, BS 5628 (see Table 5.15), β is unchanged for values of eccentricity up to $0.05t$, and thus the resultant eccentricity even under the work loading conditions at first floor level has no effect on the β value. Hence, β = 0.76.

14.7.3 Partial Safety Factor for Material Strength (Table 4, BS 5628 – see Table 5.11)

Case (a)

Manufacturing and construction control, both special: $\gamma_m = 2.5$.

Case (b)

Manufacturing and construction control, both normal: $\gamma_m = 3.5$.

Note: Normally, the designer would use only one value of γ_m. In this example, two cases are used for comparison purposes only.

14.7.4 Choice of Brick in the Two Design Cases, at Ground Floor Level

Case (a)

$$\text{Design strength} = \frac{\beta t f_k}{\gamma_m} \quad \text{per m run}$$

Design load = 202 kN/m run, $\beta = 0.76$, $t = 102$ mm, $\gamma_m = 2.5$

Design strength ≥ design load

Therefore

$$f_k \text{ required} = \frac{202 \times 2.5 \times 10^3}{0.76 \times 102 \times 1.15 \times 10^3} = 5.66 \text{ N/mm}^2$$

where the factor 1.15 in the denominator is the stress increase from clause 23.1.2 for narrow brick walls.

Assuming a mortar designation (iii) (1 : 1 : 6) (from Table 2(a), BS 5628 – see Table 5.4), bricks with a compressive strength of 20 N/mm^2 are required.

Case (b)

$$f_k \text{ required} = \frac{202 \times 3.5 \times 10^3}{0.76 \times 102 \times 1.15 \times 10^3} = 7.93 \text{ N/mm}^2$$

Bricks with a compressive strength of 35 N/mm^2 set in a mortar designation (iii) would be required. The strength of brick can be reduced at higher levels, normally at every third floor.

14.7.5 Choice of Brick in the Two Design Cases, at Third Floor Level

$$\text{Design load} = 1.4(43.8 + 15.3) + 1.6(0.8 \times 14.25)$$
$$= 101 \text{ kN/m run}$$

It should be noted that, as before, the eccentricity of loads under the worst condition is still less than $0.05t$ and thus β is 0.76 as previously calculated.

Case (b)

$$f_k \text{ required} = \frac{101 \times 3.5 \times 10^3}{0.76 \times 102 \times 1.15 \times 10^3} = 3.96 \text{ N/mm}^2$$

Bricks with a compressive strength of 15 N/mm^2 set in a designation (iii) mortar would be satisfactory (manufacturing and construction control both normal) for both cases.

It may be noted that common bricks are normally at least 20 N/mm^2 crushing strength.

14.7.6 Design of Gable Cavity Walls to Resist Lateral Loads Due to Wind

Assume clay bricks are used for the inner and outer leaves. A critical design case occurs in the top storey of a building under lateral loading, because the compression in the wall from the dead loads is small, and the wind can cause uplift on the roof, further reducing the compressive load. Walls under high lateral loading and low compressive load (particularly when the walls are used as mere cladding to a steel or concrete frame) are more likely to fail due to flexural tensile cracking, rather than axial compressive crushing or buckling.

14.7.7 Uplift on Roof

From clause 22, BS 5628, $\gamma_f = 0.9$ for dead load
and $= 1.4$ for wind load

Design dead load $= 0.9 \times 4 = 3.6$ kN/m^2

Design wind load (uplift) $= 1.4 \times 0.89(1 + 0.2)$
$= 1.5$ kN/m^2

Therefore, net dead load, contributing to compressive load in the walls,

$= 3.6 - 1.5 = 2.10$ kN/m^2

14.7.8 Design of Wall

There are three general methods for the design of walls under lateral loading mentioned in BS 5628, and definitive guidance is not provided as to which method should be used in a given case. The three methods are as follows:

(1) Effective Eccentricity Method

Clause 36.8 covers the lateral strength of axially loaded walls and columns from consideration of the effective eccentricity, and using β factors.

(2) Arching – Horizontal or Vertical

Clause 36.8 also mentions design using the formula:

$$q_{lat} = \frac{8tn}{h^2 \gamma_m}$$

(3) Designing on the Basis of a Cracked or Uncracked Section

By assessing moments or using the method for panel walls in BS 5628.

By implication, methods (1) and (2) above, are normally used where the axial loads are high in relation to the lateral loads. In the top storey axial loads are low, so that there is little thrust to resist the arching effect. Also, the moment is



Figure 14.45 Bending moment coefficients for walls subject to wind load in Example 1

high in relation to the axial load, so that the effective eccentricity is high, giving a large capacity reduction (i.e. the β value from BS 5628, Table 7 is very small – see Table 5.15). Thus method 3 should be adopted.

Wall ties of the vertical twist type should be provided in accordance with Table 6 of BS 5628 – see Table 6.2 (i.e. 2.5 ties per m^2). Therefore, both leaves may be treated as acting together, but not as a homogeneous section.

14.7.9 Calculation of Design Wall Moment

Assume that the wall behaves as a slab spanning continuously over supports provided by the floors (see Figure 14.45).

Design moment occurs at top floor level (see Figure 14.46)

$= 1.25 \times (2.5)^2 \times 0.107$
$= 0.84$ kN m/m length

14.7.10 Resistance Moment of Wall (Figure 14.46)

Assume:

(1) Clay bricks used in both leaves, with water absorption 7%, in designation (iii) mortar, i.e. $f_{kx} = 0.5$ N/mm^2.
(2) Special construction control, i.e. $\gamma_m = 2.5$.



Figure 14.46 Position of maximum design moment in walls for Example 1

(3) The total resistance moment is the sum of the resistance moments of the two individual leaves, i.e. fZ, where $f = g_d + f_{kx}/\gamma_m$.

This design method assumes that flexural tensile resistance can be developed and relied upon at this level.

Design dead load in inner leaf at position of maximum moment due to the net dead load from the roof, and a storey height of 102 mm thick brickwork

$= (2.1 \times 3/2) + (0.9 \times 2.5 \times 0.102 \times 20) = 3.15 + 4.59$
$= 7.74$ kN/m run

Therefore

$$g_d = \frac{7.74 \times 10^3}{102 \times 10^3} = 0.076 \text{ N/mm}^2$$

Design dead load outer leaf = 4.59 kN/m run

Therefore

$$g_d = \frac{4.59 \times 10^3}{102 \times 10^3} = 0.045 \text{ N/mm}^2$$

$$Z = \frac{1000 \times 102^2}{6} = 1.734 \times 10^6 \text{ mm}^3$$

$$\text{Total resistance moment} = \left(\frac{0.5}{2.5} + 0.076\right) \times 1.734 \times 10^6 + \left(\frac{0.5}{2.5} + 0.045\right) \times 1.734 \times 10^6$$
$$= 0.48 + 0.42$$
$$= 0.9 \text{ kN m/m}$$

The resistance moment is greater than the design moment, thus the wall is satisfactory at this level. At other levels, where the compressive dead load is higher, there is less risk of flexural tensile failure of the bed joints, and the governing factor in design is the axial compressive, rather than the flexural, strength of the wall.

14.7.11 Overall Stability Check

(1) Stability in* y *Direction (see Figure 14.47)

This is provided by the gable walls and by crosswalls 1 to 18, at 3 m centres. These walls are deep (8 m and 9 m, in the direction of the wind) and, by inspection, the building is rigid in the y direction. Overturning of the structure as a whole is not a problem for a building of this height and with these proportions. The additional stresses due to the wind on the crosswalls are very small (see Figure 14.48). For the method of calculation, see (2) (below) on the stability in x direction.

(2) Stability in* x *Direction

The wind is taken by the two corridor walls and the two external walls. For simplicity in this example, it is assumed that the load is shared equally by the four walls. Since the resulting stresses are likely to be low, this approximation is not unreasonable, although a more accurate analysis would



Figure 14.47 Plan of structure for overall stability check, Example 1



Figure 14.48 Elevation on shear walls in Example 1

be to share the load in proportion to the relative stiffnesses of the walls providing the stability. Consider the two corridor walls each consisting of five shorter walls. The walls may be assumed to act as vertical cantilevers, each wall taking an equal proportion of the total wind load. It will be assumed that the floors are relatively flexible and are not able to transfer flexural shears, hence the assumed deflected shape is as shown in Figure 14.49.

If the floors were made rigid and able to transfer the flexural shears, a much higher lateral load could be carried or, for the same load, the stress due to lateral loading would be much lower.

A critical design case for the wall is at its mid-height, between ground and first floor level. There are two cases to consider:



Figure 14.49 Deflection of corridor walls providing stability in the x direction in Example 1



Figure 14.50 Plan on single section of corridor wall in Example 1

Case (a)

Dead + wind load acting, $\gamma_f = 0.9$ on dead load and $\gamma_f = 1.4$ on wind load, and flexural tensile stresses are considered.

$$\text{MR on section} = W_k \times \gamma_f \times \frac{h^2}{2} \times \frac{\text{breadth of building}}{\text{no. of shear walls} \times \text{no. of walls}}$$

$$= 1.25 \times \frac{15^2}{2} \times \frac{20.5}{4} \times \frac{1}{5}$$

$$= 144 \text{ kN m}$$

Design axial load acting:

due to self-weight of masonry

$$= 0.9 \times 15 \times 0.102 \times 20 = 27.5 \text{ kN/m}$$

due to design dead load from roof and five floors in 1 m wide corridor area

$$= 0.9(4 + 5.3) \times 5 \times 0.5 = \underline{13.7 \text{ kN/m}}$$

$$= 41.2 \text{ kN/m}$$

Total design axial load over 5 m long wall $= 5 \times 41.2 = 206$ kN

Wall properties (Figure 14.50)

$$A = 102 \times 5000 \quad = 51 \times 10^4 \text{ mm}^2$$

$$Z = \frac{102 \times 5000^2}{6} = 425 \times 10^6 \text{ mm}^4$$

$$\text{Design MR} = \left(\frac{f_{kx}}{\gamma_m} + g_d \right) Z$$

Using 20 N/mm^2 clay bricks in designation (iii) mortar with water absorption less than 7%, then $f_{kx} = 0.5$ N/mm^2.

Assume special construction control, $\gamma_m = 2.5$, for flexural design, and special construction and manufacturing control, $\gamma_m = 2.5$, for compression design.

Therefore

$$\text{Design MR} = \left(\frac{0.5}{2.5} + \frac{206 \times 10^3}{5.1 \times 10^5} \right) \times \frac{425 \times 10^6}{10^6} = 256.7 \text{ kN m}$$

This is greater than the design moment = 144 kN m

Case (b)

The wall should also be checked for compressive buckling failure. Possible load combinations are ($1.4G_k$ and $1.4W_k$) or ($1.2G_k$; $1.2Q_k$ and $1.2W_k$). In this case, the former will give the worst design condition. Check at mid-span of wall.

$$\text{Design stress due to dead load} = \frac{1.4(4 + (5.3 \times 5)) \times 0.5 \times 10^3}{10^3 \times 102}$$

$$= 0.21 \text{ N/mm}^2$$

Design stress due to ow masonry

$$= \frac{1.4 \times 13.75 \times 0.10 \times 20 \times 10^3}{1000 \times 102} = 0.38 \text{ N/mm}^2$$

Total axial compressive stress due to dead loads

$$= 0.21 + 0.38$$
$$= 0.59 \text{ N/mm}^2$$

The flexural compressive stress $= M/Z$

$$\text{The design bending moment} = 1.25 \times \frac{13.75^2 \times 20.50 \times 1}{2 \times 4 \times 5}$$

$$= 121.12 \text{ kN m}$$

Therefore

$$\text{flexural compressive stress} = \frac{121.12 \times 10^6}{425 \times 10^6} = 0.285 \text{ N/mm}^2$$

14.7.12 Eccentricity of Loading

Design moment on wall = 121.12 kN m

$$\text{Design axial load on wall} = \frac{0.6 \times 5000 \times 102}{10^3} = 306 \text{ kN}$$

$$\text{Eccentricity} = \frac{121.12}{306} = 0.396 \text{ m}$$

i.e. $0.08b$ (see Figure 14.51).

The slenderness ratio, SR, as previously calculated = $(2500/102) \times 0.75 = 18.4$. Hence, $\beta = 0.72$.

Therefore

$$\text{maximum design strength} = \frac{\beta f_k \times 1.15}{\gamma_m}$$

$$= \frac{0.72 \times 5.8 \times 1.15}{2.5}$$

$$= 1.92 \text{ N/mm}^2$$

This is greater than the sum of the design load stresses and bending stresses = 0.59 + 0.29 = 0.88 N/mm^2.

Hence, the wall is satisfactory.

14.7.13 Accidental Damage

Section 5 of the Code covers accidental damage, and Chapter 8 has explained its requirements in detail. The partial safety factors, γ_f, to be used are given in clause 22(d) as follows:

$0.95G_k$ or $1.05G_k$
$0.35Q_k$ ($1.05Q_k$ where the building is used predominantly for storage)
$0.35W_k$

Values of γ_m for materials may be taken as half the values given in Table 4 of BS 5628 (see Table 5.11).



Figure 14.51 Eccentricity of loading on single section of corridor wall in Example 1

This example is for a Class 2B building, i.e. one of five storeys or more. Table 12 of the Code gives three options for detailing and designing the structure to withstand accidental damage (see Table 8.1). It is considered that the option of vertical and horizontal elements, unless protected, proved removable one at a time without causing disproportionate collapse, would be adopted here in conjunction with the provision of horizontal ties.

Crosswalls Removed

The normal span of concrete floor is in the *x* direction. If, say, crosswall CH is removed, the slab can be designed to span – using increased distribution steel if necessary – in the *y* direction from the spine walls to an edge beam spanning from B to D. In addition the slab will also tend to hang in catenary action between walls BJ and DG (see Figure 14.52).



Figure 14.52 Part plan of Example 1 for checking disproportionate collapse provision

Gable Wall Removed

BS 5628 states that for walls without vertical lateral supports the whole length of external walls must be considered removable, while for similar internal walls only 2.25*h* need be considered as the removable length. The Building Regulations do not differentiate between internal and external walls but limit the removable length to 2.25*h* for all walls. It seems, to the authors, particularly harsh to consider, say in a spine wall structure of 30 m or more in length, the possibility of an incident capable of removing such a disproportionate length of external wall. However without sufficient evidence to justify this feeling it is anticipated that designers will need to meet this requirement.

Having assessed the removable length of gable wall, consideration can now be given to the alternative means of support for the structure following its removal. If the length removed is not excessive, consideration may be given to composite action of the masonry over acting with the floor slab immediately above the removed length of wall. This, together with the arching effect of the masonry to spread the loads over to either side of the removed length of wall, may be all that is necessary with the additional reinforcement, if any, being added peripherally in the insitu floor slab. A more complex analysis might consider two adjacent floor slabs acting as the flanges of deep I beams with the spine walls between them acting as the webs of the same beams. These composite sections may be used to cantilever from the last crosswall and could support, at the end of the cantilever, a similar I-shaped composite beam utilising the gable wall as the web. Hence, a framework of composite beams is provided, and reinforced accordingly, to support the structure over (see Figure 14.53).

It may well be the case that, at the lower levels of a load-bearing brickwork structure, there is enough compressive dead load from above to enable the wall to withstand a lateral force of 34 kN/m^2 and thus it is a protected member as defined in clause 37.1.1 of the Code.

14.8 Example 2: Four-storey School Building

Design an internal crosswall to resist vertical loading in a four-storey school-type building, shown in Figure 14.54. Overall height is 12 m. This building is a Class 2B structure



Figure 14.53 Floors and crosswalls providing composite section

for disproportionate collapse rules and is likely to be designed with horizontal ties, to BS 5628, Part 1, and checked for element removal as Example 1.

14.8.1 Characteristic Loads

Roof

Dead loads, G_k,

precast concrete units = 3.6 kN/m^2
screed to falls, allow 1.4 kN/m^2
= 5.0 kN/m^2

Imposed load, Q_k = 0.75 kN/m^2

Floors

Dead loads, G_k,

precast concrete units = 4.8 kN/m^2
screed finishes, allow 1.2 kN/m^2
= 6.0 kN/m^2

Imposed load, Q_k = 3.0 kN/m^2

14.8.2 Design of Wall at Ground Floor Level

Reduction in imposed load: four floors = 30%.

Roof + Floors

Design dead load

$= 1.4(5 + 6 + 6 + 6)$ $= 32.2$ kN/m^2

Design imposed load

$= 1.6(0.75 + 3 + 3 + 3) \times 0.7 = 10.9$ kN/m^2
$= 43.1$ kN/m^2

Design load per m run $= 43.1 \times 7/2 = 151$ kN/m

Walls

Characteristic load per m run due to masonry self-weight (brickwork density 20 kN/m^3):

$20 \times 12.0 \times 0.215$	= 52 kN/m
Design load, 52×1.4	= 72 kN/m
Therefore, total design load, n_w	= 72 + 151
	= 223 kN/m
Effective height	$= 0.75 \times 3.0$
	= 2.25 m
Effective thickness	= 0.215 m
SR: 2.25/0.215 = 10.5 and e_x	= 0 to 0.5t
Reduction factor for slenderness, β = 0.96	

Vertical load resistance per metre is given by $\beta t f_k/\gamma_m$.

Therefore, required minimum characteristic strength of masonry $f_k = \gamma_m n_w/\beta t$.

Case (a)

Manufacturing and construction control both special, $\gamma_m = 2.5$.

$$f_k \text{ required} = \frac{2.5 \times 223 \times 10^3}{0.97 \times 215 \times 10^3} = 2.7 \text{ N/mm}^2$$



Figure 14.54 Plan on school building Example 2



Figure 14.55 Plan on office block Example 3

Assume mortar designation (iii) and standard format bricks.

Common brick (20 N/mm^2) should give ample strength ($f_k = 5.8$ N/mm^2 > 2.7 N/mm^2 required).

Case (b)

Manufacturing and construction control both normal, γ_m = 3.5.

$$f_k \text{ required} = \frac{3.5 \times 223 \times 10^3}{0.9 \times 215 \times 10^3} = 3.7 \text{ N/mm}^2$$

Again use a common brick (20 N/mm^2) set in designation (iii) mortar.

14.9 Example 3: Four-storey Office Block

14.9.1 Column Structure for Four-storey Office Block

A simplified plan of a brick column structure is shown in Figures 14.55 and 14.56. Although the structure is mainly open-plan, a number of internal walls and partitions have been omitted for clarity. This building is a Class 2A structure for disproportionate collapse requirements and as such will require horizontal tying only. The basic T-shaped plan, the staircase, lift wells and service cores, the internal partitions and the plate action of the floor slab and beams would make for a robust structure. Wind forces are transferred to the gable and internal shear walls by the plate action of the floors and roof.



Figure 14.56 End elevation Example 3

The external gable walls are 305 mm cavity walls, the shear walls and walls to staircases, lifts, etc., are 215 mm solid walls, and the columns are 330 mm square in the upper storey, and 440 mm square below this.

The columns and the shear walls may be designed as follows.

14.9.2 Characteristic Loads

Roof

Trussed timber roof, $G_k = 1.25\ kN/m^2$

Imposed load, $Q_k = 0.75\ kN/m^2$

Floor

Precast beam and pot floor with structural screed,
$G_k = 4.9\ kN/m^2$

Partitions, $G_k = 1.0\ kN/m^2$
$= 5.9\ kN/m^2$

Imposed load, $Q_k = 2.5\ kN/m^2$

Wind Loading

Assume that the maximum characteristic wind pressure, W_k, is 0.8 kN/m^2 and that the wind uplift on the roof is 1.0 kN/m^2.

Before proceeding with the design of the structure as a whole, the designer should consider carefully the location of joints, and the like, since these will affect the stability and strength of the structure. In this example, it has been assumed that the floors act as a plate to transfer the wind load to the shear walls which are designed as vertical cantilevers to resist the lateral loading. Therefore, it may be assumed that there is no wind loading on the columns.

14.9.3 Design of Brick Columns

The first step in the design is to rationalise the number of load cases to be considered since, in general, each column will have a different load. By inspection of Figure 14.55, the column marked P will be one of the most heavily loaded, and this example will show the design of column P from ground floor to roof level. The design of other columns is performed in a similar manner. The second step is to calculate the design loadings for the selected groups of columns (see Table 14.2).

14.9.4 Loading on Column P

The dead load of the masonry must be added to the above in obtaining the total design axial load.

Assume the characteristic density of the brickwork = 20 kN/m^3.

Therefore, characteristic dead load at A due to brick column above

$= 20 \times 0.33^2 \times 4 \times 3.5$
(density × area × height)
$= 30\ kN$

assuming brick columns are 330 mm × 330 mm.

Design Load at Ground Floor (A)

For this combination of loading, $\gamma_f = 1.4$ for dead loads and 1.6 for imposed loads (clause 22, BS 5628). Therefore:

$$\text{Design load at A} = (1.4 \times 409) + (1.6 \times 0.7 \times 178) + (1.4 \times 30)$$
$$= 573 + 199 + 42$$
$$= 814\ kN$$

Slenderness Ratio of Column

The effective height of the column is the actual height between lateral supports, therefore, h_{ef} = 3.50 m. Assume for a trial section a 330 × 330 brick column constructed of standard format facing bricks with a compressive strength of 35 N/mm^2, laid in a designation (iii) mortar. The least lateral dimension is 330 mm therefore, slenderness ratio = 3.5/0.33 = 10.6.

Characteristic Compressive Strength of Brickwork, f_k

The value of $f_k = 8.5\ N/mm^2$ (Table 2(a), BS 5628 – see Table 5.4 – for 35 N/mm^2 compressive strength facing bricks in designation (iii) mortar).

The area of the brick column is 0.11 m^2 and clause 23.1.1 of BS 5628 states that, where the horizontal cross-sectional area of a column is less than 0.2 m^2, the characteristic compressive strength should be multiplied by the factor (0.70 + 15*A*) where *A* is the horizontally loaded cross-sectional area of the column. In this case the area reduction factor = 0.7 + (1.5 × 0.11) = 0.865.

Calculation of β Value for Design

First determine the eccentricity of the loading (see clause 31, BS 5628) (see Figure 14.57).

The resultants R_1 and R_2 are assumed to act at one-third of the depth of the bearing area from the loaded face of the column, i.e. (330/2) × (1/3) = 55 mm in from the face.

Now

$$R_1 = \left(1.4 \times 5.9 \times \frac{3.6}{2} \times 6\right) + \left(1.6 \times 2.5 \times \frac{3.6}{2} \times 6\right)$$
$$= 89.21 + 43.2 = 132.41\ kN$$

Table 14.2

Position	Characteristic dead load due to floors and roof (kN)	Characteristic imposed load (kN)	Imposed load reduction factor (Table 2, BS 6399, Part 1) (%)
Roof	6 × 3.6 × 1.25 = 27	6 × 3.6 × 0.75 = 16	0
3rd floor	27 + (6 × 3.6 × 5.9) = 154	16 + (6 × 3.6 × 2.5) = 70	10
2nd floor	282	124	20
1st floor	409	178	30



Figure 14.57 Eccentricity calculation for column in Example 3

and

$$R_2 = 89.21 \text{ kN}$$

The load in the column just above the first floor may be assumed to be axial and

$$\begin{aligned} &= (1.4 \times 282) + (1.6 \times 0.8 \times 124) \\ &\quad + (1.4 \times 20 \times 0.33^2 \times 3 \times 3.5) \\ &= 395 + 159 + 32 \\ &= 586 \text{ kN} \end{aligned}$$

Taking moments about face N, let R be the distance to the resultant of R_1 and R_2 and the axial load

$$\left(586 \times \frac{0.33}{2}\right) + (132.41 \times 0.055) + (89.21 \times 0.275)$$

$$= (586 + 132.41 + 89.21)R$$

Therefore $R = 0.159$ m from face N.

Therefore, eccentricity at the top of the column = 0.33/2 – 0.159 = 6.3×10^{-3} m = 6.3 mm = 0.02t.

Hence, for slenderness ratio of 10.6 and eccentricities up to 0.05t (Table 7, BS 5628 – see Table 5.15), by interpolation, $\beta = 0.958$.

Design Vertical Load Resistance of Column

Design vertical load resistance

$$= \frac{\beta b t f_k}{\gamma_m} \times \text{area reduction factor}$$

Now assume the manufacturing and construction controls are both special, therefore, $\gamma_m = 2.5$ (Table 4, BS 5628 – see Table 5.11).

Design vertical load resistance

$$= \frac{0.958 \times 330 \times 330 \times 8.5 \times 0.865}{2.5}$$

$$= 307 \text{ kN}$$

This is less than the required vertical load resistance of 814 kN. Hence, the column section designed is inadequate.

Increase Trial Column Size

Try a 440 mm square brick column constructed of standard format bricks with a compressive strength of 50 N/mm^2 laid in designation (iii) mortar.

$f_k = 10.6$ N/mm^2

(Table 2(a), BS 5628 – see Table 5.4)

$$\begin{aligned} \text{Area reduction factor} &= 0.7 + (1.5 \times 0.44^2) \\ &= 0.99 \end{aligned}$$

$$\begin{aligned} \text{Design load} &= 814 \text{ kN} + \text{extra load due to} \\ &\quad \text{increased size of column} \end{aligned}$$

$$\begin{aligned} \text{Extra column load} &= (0.44^2 - 0.33^2) \times 4 \times 3.5 \times 20 \\ &= 23.7 \text{ kN} \end{aligned}$$

$$\begin{aligned} \text{Design load} &= 814 + 23.7 \\ &= 837.7 \text{ kN} \end{aligned}$$

By comparison with 330 mm square column, β will be 1.0 for 440 mm square column.

Vertical load resistance of 440 mm square column

$$= \frac{1 \times 440^2 \times 10.6 \times 0.99}{2.5} = 812 \text{ kN}$$

This is just less than the design load of 814 kN. The minimum required characteristic strength of the masonry is:

$$= \frac{2.5 \times 837.7 \times 10^3}{0.99 \times 440^2}$$

$$= 10.92 \text{ N/mm}^2$$

From Figure 1 of BS 5628, the required compressive strength of bricks laid in designation (iii) mortar = 58 N/mm^2, in a 440 × 440 column. If it is not possible to obtain facing bricks of this strength, then the use of engineering bricks should be considered, or the column could be reinforced.

Design of Column between 1st and 2nd Floor Levels

Assume a 440 mm × 440 mm column.

$$\begin{aligned} \text{Design vertical load} &= (1.4 \times 282) + (1.6 \times 0.8 \times 124) \\ &\quad + (3 \times 3.5 \times 20 \times 0.44^2 \times 1.4) \\ &\quad \text{(see Figure 14.58)} \\ &= 395 + 158 + 57 \\ &= 610 \text{ kN} \end{aligned}$$

The eccentricity of loading in the column should be recalculated at each level but will be assumed to be zero for this case also.

Minimum required compressive strength of masonry

$$f_k = \frac{2.5 \times 610 \times 10^3}{0.99 \times 440^2}$$

$$= 7.95 \text{ N/mm}^2$$

From Figure 1 of BS 5628, the required compressive strength of bricks is 33 N/mm^2 in designation (iii) mortar. Facing bricks can be obtained with this strength for use in a 440 mm × 440 mm brick column.



Figure 14.58 Elements providing lateral stability in Example 3



Figure 14.59 Elements providing lateral stability in Example 3

The design of the brick columns at higher levels is performed in a similar manner, and the section may be reduced, or the brick strength varied, as required, to suit both architectural and economic consideration.

Simplified Design for Lateral Loading Due to Wind

By inspection of the plan, the structure appears to be rigid and robust with many crosswalls, and the stresses induced in the structure due to lateral loading are small.

Consider wind loading on the south elevation. The main elements resisting the loading are shown in Figure 14.58.

As in the previous shear wall design example, the structure will be assumed to behave as a vertical cantilever under lateral loading. Hence, the deflected shape is as shown in Figure 14.59.

The total design bending moments should be shared between the shear walls in proportion to their stiffnesses, and the designs of the individual walls should then proceed using the principles demonstrated in design example 8 in Chapter 11. A careful check should be made at all floor levels, particularly in the uppermost storey, as the dead loading available to eliminate flexural tensile stresses is considerably reduced.

15 Reinforced and Post-tensioned Masonry

In the preceding chapters, discussion has been largely confined to the basic principles and assumptions underlying the design of plain structural masonry – ordinary bricks or blocks and mortar construction. However, in that it is strong in compression and relatively weak in tension, the structural application of plain masonry tends to be restricted to walls, columns, arches and other elements carrying mainly compressive loads. When plain structural masonry elements are subjected to lateral loading, from wind or retained earth and other causes, they need thickening or a change in geometric shape to resist the resulting tensile stresses. In short, the material's relatively low tensile strength tends to govern the design. As a result, its high compressive strength is often partly wasted.

As most engineers know, concrete – which is also strong in compression but weak in tension – is commonly either reinforced with steel to carry the tensile stresses, or prestressed to eliminate them. Similar principles can be applied to the design of structural masonry (see Figure 15.1) with corresponding gains in the extension of its field of application.



Figure 15.1 Column stresses under various load combinations



Figure 15.2 Similar construction in reinforced and post-tensioned concrete applied to masonry

Such an obvious concept is not new. In fact, the reinforcing of brickwork long preceded the reinforcing of concrete. In about 1820, Sir Marc Brunel reinforced the brick shafts of the Wapping to Rotherhithe tunnel. At the turn of the twentieth century, Sir Alexander Brebner used reinforced brickwork in India, and his example was followed in the 1920s and 1930s in Japan and other countries subject to earthquakes. Since the Second World War, there has been an increasing application of the technique in the USA.

Nevertheless, and despite these historical precedents, the development of reinforced and prestressed masonry has lagged far behind reinforced and prestressed concrete. This is hardly surprising. Research on the subject, technical papers, codes of practice, design guides, etc. have only really been available in the past 40 years to assist the engineer. However practically no engineering student receives any instruction in the subject during their studies.

The recent revisions of BS 5628, Part 2 and the design guides, etc., should enable the engineer to use reinforced and prestressed masonry to its full potential. There is no doubt, in the authors' minds, that industry and society as a whole are missing out on a valuable and worthwhile technique of construction, in that reinforced and post-tensioned masonry maintain all the advantages set out in Chapter 2, including speed, simplicity and economy, see Figure 15.2.

15.1 General

15.1.1 Design Theory

Being based on limit state principles, the design philosophy for reinforced and prestressed masonry is exactly the same as for plain masonry. Reference is made to BS 8110, *The structural use of concrete*, which is also based on limit state principles. This is not because there is any direct relationship between masonry and concrete (see section 15.1.2), but because of the progress that has been made in the research and development of reinforced and prestressed concrete and the similarity of the results arising from the lesser research into reinforced and prestressed masonry.

The assessment of loadings and member forces is made in exactly the same way as for plain masonry. Specific recommendations now exist for reinforced and prestressed masonry and the analysis of sections is generally based on the methods given in BS 5628, Part 1 for plain masonry, together with those in BS 5628, Part 2, 2000, *Structural use of reinforced and prestressed masonry*.

15.1.2 Comparison with Concrete

Because masonry is analogous to concrete, some engineers tend to consider them as almost identical materials in design terms. They are not – and the analogy can be taken too far.



Figure 15.3 Reinforced masonry examples

Unlike concrete, masonry – brickwork particularly – is not homogeneous or isotropic. Concrete shrinks as it matures and brickwork expands, and this affects bond strength and creep losses. Cracking on the tensile face of reinforced concrete members will be spread along the face, and the cracks are likely to be minute. Cracking on the tensile face of a reinforced masonry member will be concentrated on the mortar joints, and the cracks may well be larger.

While the bulk of concrete is reinforced, only some is prestressed. It would certainly appear likely that, with further experience, the reverse situation will occur in masonry. Reinforcing concrete is generally simpler than prestressing it. Quite the opposite applies to most masonry. Prestressed concrete usually calls for high stresses needing sophisticated stressing equipment, high-strength materials, complicated duct installation, high-tensile steel tendons and careful site supervision. On the other hand, post-tensioned brickwork is concerned with relatively low stresses, requiring an almost rudimentary technique using everyday materials and methods. However, there is considerable scope for reinforcing hollow blockwork where the section may be treated as reinforced concrete complying with the advice in BS 8110.

Although it is true that masonry and concrete are not identical, nevertheless they are sufficiently alike to enable some similar design concepts of reinforcing and prestressing to apply. On the other hand, they are sufficiently different as to require different design methods, detailing and construction. The designer *must* be aware of these differences, and must not blindly apply the methods and techniques of insitu or precast concrete to masonry.

15.1.3 Applications

Reinforced masonry has been used to enable walls to act as beams, lintels and cantilevers, with the reinforcement in the bed joints, i.e. horizontal reinforcement – see Figure 15.3.

It was, and still is, used for vertical members subject to lateral loading, such as retaining walls. One of its most common, economical and simplest uses is in grouted cavity construction (see Figure 15.4).

Another use, and one likely to continue, is to enhance the loadbearing capacity of brick columns when there are restrictions on their cross-sectional area. In the limited amount of prefabricated brickwork built in recent years, reinforcement has often been added to cope with the erection and handling stresses. In addition to being a useful and economical alternative to concrete, brickwork can also be effectively used in association with it. There are occasions



Figure 15.4 Reinforced grouted cavity wall



Figure 15.5 Plan on reinforcement in pockets in masonry walls



Figure 15.6 Possible composite action between rc footing and masonry wall

when it can act compositely with concrete, for example in retaining and balcony walls (see Figure 15.5).

Some engineers have appreciated the fact that a relatively thin reinforced concrete footing to a wall can result in a composite beam, where the masonry wall forms the compression flange and the rc footing the tensile flange (see Figure 15.6). This has led to worthwhile savings in foundation costs, particularly on soils subject to significant differential settlement.

Brickwork has been increasingly used in recent years as a veneer to rc cladding panels, where it can act as a permanent shutter and provide an attractive mask to the often unacceptable face of concrete. Too often, however, the compressive strength of the brickwork has been neglected, resulting in a less economical design than was possible. The use of an unstressed brickwork veneer is considered by some to be structurally 'dishonest' and makes inefficient use of the material.



Figure 15.7 Prestressed masonry example

15.1.4 Prestressing

Of the two techniques of prestressing i.e. pre-tensioning and post-tensioning, the former method has been most widely used in concrete, particularly in precast units. In structural masonry, however, post-tensioning has so far been found to be the most successful, and certainly the simplest method. Briefly, the procedure is to anchor one end of a high-tensile steel bar and build the masonry around it – leaving a space for grouting up, if felt necessary. On completion of building the masonry, a plate is placed over the end of the rod – which is threaded – to act as a load-dispersal anchorage. A nut is then screwed on, and tightened up to the required post-tensioning stress with a torque spanner (see Figure 15.7).

Prestressed concrete sections are more structurally efficient if the section has a high section modulus/cross-sectional area ratio, Z/A, as in an I- or T-beam, and the same principle applies to prestressed masonry. The post-tensioning of diaphragm walls (I-sections) and fin walls (T-sections) shows great potential for tall walls subject to high lateral loading and low axial loading.

15.1.5 Methods of Reinforcing Walls

Masonry can be constructed with reinforcement incorporated in pockets in the face of the wall, in vertical holes inside the wall and in the voids of cavity construction (see Figure 15.8).

In the case of walls 2, 3 and 4, shuttering is not necessary and the void can be filled as the work proceeds. As far as simplicity is concerned, walls 2 and 4 are generally much easier and quicker to construct than walls 1 and 3 – wall 2 has the simplest bond. From the construction point of view, the Quetta bond wall is usually expensive and slow.

Methods of filling around the reinforcement must be considered (see Figure 15.9). If grouting is used, then difficulties of keeping the void clear of mortar droppings and projections and keeping the brickwork adequately tied to resist hydrostatic pressure, and of preventing air being trapped below the grout, all become very real problems. Generally, the simplest, most successful and economical method is to fill the void with a suitable quality mortar as



Figure 15.8 Methods of reinforcing walls



Figure 15.9 Methods of filling in grouted cavity walls

the work proceeds, and to make the bricklayers aware of the need for complete filling of the void to ensure adequate bond and protection against corrosion.

The designer must be very aware of the problems at the design detail stage, and should make adequate adjustments to suit the methods and likely quality of construction. If grouting is chosen for a particular situation, then lifts with vent holes, to prevent air locks and to monitor the filling, can help considerably – as can clear communications to site operatives, and good supervision.

To summarise:

(a) complicated details should be avoided wherever possible;
(b) shuttering should be reduced to a minimum;
(c) hydrostatic head should be reduced to a minimum;
(d) bonding should be kept simple;
(e) the majority of the work should be kept under direct control of the bricklayer.

The designer should make allowances for the effects the above points may have on the expected quality. For example, if the bond of the mortar to rods is expected to be reduced, the stresses used in the design should be reduced and lap lengths increased accordingly. If corrosion could be a problem due to the expected quality of workmanship, non-ferrous metal or galvanised steel should be used and, again, the stresses adjusted to suit these materials and any possible loss of bond (see also section 15.1.8).

15.1.6 Composite Construction

As mentioned earlier, composite construction is another form of reinforced masonry. Generally, a shallow reinforced concrete beam is designed for two basic conditions. First, as a member to support the temporary condition of the first lifts of wet masonry. Second, and after the masonry has cured and acts with the beam, to support compositely the loads likely to be applied. This method of construction can prove to be very simple and economical to construct, particularly at foundation and floor slab levels where reinforced concrete is frequently already being used.

The principles of design for composite constructions are similar to those for reinforced masonry, and careful attention should be paid to the points summarised in section 15.1.5. Again, the designer should keep the details simple. He should also consider carefully the differential movements of the two materials, and the temporary construction loading (see Figure 15.10), and the final loading including suitable allowance for openings and damp proof courses, which may affect the composite action.

15.1.7 Economics

Even using the results of detailed cost surveys, it is notoriously difficult to quantify cost savings. However, the authors' experience suggests that structural masonry can show 10% savings in building costs and, by reinforcing or post-tensioning, these savings can often be further increased.

Savings in construction time tend to be between 10% and 30%, depending on the type of structure. Reinforcing and post-tensioning add little to the time-saving implications of structural masonry – their main value lies in widening its scope, increasing its range of application and in making it an even better and more economical alternative to other structural materials.

15.1.8 Corrosion of Reinforcement and Prestressing Steel

Since clay bricks, calcium silicate bricks, concrete blocks and mortar are porous, understandable concern has been expressed about the possibility of corrosion in reinforcing steel and post-tensioning rods. There are a number of buildings, in various countries, where careful detail, good workmanship and proper supervision have shown that the problem can be solved. In reinforced masonry walls and columns, the rods should have the minimum cover given in section 15.1.9, and the bed and perpend joints should be completely and properly filled with dense and durable mortar. When reinforcement is placed in the cavity of a cavity wall, or the core of a hollow column or fin, the void should be fully grouted up with a well-designed cement grout. In post-tensioned diaphragm and fin walls, a 'belt-and-braces' approach can be adopted by using a larger rod than necessary, to allow for the loss of cross-sectional area due to corrosion, and by reducing the risk of corrosion, by coating the rod with a bitumen paint and wrapping it in a proprietary waterproof tape. Alternatively, stainless steel rods can be used. Although these are currently about four times the cost of high-tensile steel rods, the extra cost per m^2 of the completed wall is not usually significant.



Figure 15.10 Possible composite construction

15.1.9 Cover to Reinforcement and Prestressing Steel

Under no practical circumstances should masonry be regarded as providing cover to steel. Shortly after the Second World War when there was a famine of structural steelwork and a desperate shortage of timber for shuttering, a number of reinforced brickwork projects were built. The authors' extensive experience in surveying such structures showed that the major cause of failure was lack of cover to the reinforcement. In a survey at the Albert Dock, Liverpool, it was found that reinforcement provided with more than 500 mm of masonry cover had corroded to such an extent that it had cracked the massively thick brick walls.

The depth of cover depends on:

(a) the exposure situation,
(b) the type of masonry,
(c) the type of steel,
(d) the positioning of the reinforcement or prestressing bars.

(a) Exposure situation

BS 5628, Part 3, Table 11 gives the classification of exposure situations as sheltered, moderate shelter, severe and very severe. These classifications can be described as follows:

E1 Sheltered, i.e. internal work or behind surfaces protected by impervious coatings that can be inspected readily.
E2 Moderate shelter, i.e. buried masonry or masonry continually in contact with fresh water or external work subject to sheltered/moderate exposure.
E3 Severe – masonry exposed to freezing while wet, cycles of wetting and drying, heavy condensation as in swimming pools and laundries and external parts.
E4 Very severe – masonry exposed to salt, moorland or other contaminated water, corrosive fumes, or abrasion.

(b) Type of masonry

The less porous the masonry then the less the moisture will penetrate so that high strength bricks of low water absorption bedded in strong mortar give improved protection. Masonry or bricks with a water absorption greater than 10% or concrete blocks of lower density than 1500 kg/m^3 should be considered as being used in the next most severe exposure situation than actually occurs. BS 5628: Part 3. Table 13 provides further information on masonry unit types and suitability for particular locations.

(c) and (d) type of steel; positioning of reinforcement or prestressing bars

The type of reinforcement and minimum amount of protective coating which is recommended to be used for varying exposure situations and positioning of reinforcement are given in Table 15.1 (BS 5628, Part 2, Table 14).

15.1.10 Cover

(1) Stainless steel or steel coated with a minimum of 1 mm of austenitic stainless steel theoretically requires no cover for durability purposes. But obviously adequate cover is necessary to develop bond stress.
(2) Reinforcement, when placed in bedjoints, should have at the very least 15 mm cover on the exposed masonry face and the authors prefer to use stainless steel in such conditions.
(3) For grouted cavity and similar construction (including Quetta bond if this is used) the absolute minimum should be:
    (a) Carbon steel reinforcement in E1 situation – 20 mm mortar or grout.
    (b) Carbon steel reinforcement in E2 situation – 20 mm concrete.
    (c) Galvanised steel reinforcement – 20 mm mortar or concrete.

These minimum covers must be increased depending on the exposure situation and grade of concrete as shown in Table 15.2 (Table 15, BS 5628, Part 2).

The Code recommends that prestressing tendons positioned in open voids, not filled with mortar or concrete, should

Table 15.1 Selection of reinforcement for durability

Exposure situation	Minimum level of protection for reinforcement, excluding cover	
	Located in bed joints or special clay units	Located in grouted cavity or Quetta bond construction
E1	Carbon steel galvanised following the procedure given in BS 729 Minimum mass of zinc coating 940 g/m^2	Carbon steel
E2	Carbon steel galvanised following the procedure given in BS 729 Minimum mass of zinc coating 940 g/m^2	Carbon steel or, where mortar is used to fill the voids, carbon steel galvanised following the procedure given in BS 729 to give a minimum mass of zinc coating of 940 g/m^2
E3	Austenitic stainless steel or carbon steel coated with at least 1 mm of stainless steel	Carbon steel galvanised following the procedure given in BS 729. Minimum mass of zinc coating 940 g/m^2
E4	Austenitic stainless steel or carbon steel coated with at least 1 mm of stainless steel	Austenitic stainless steel or carbon steel coated with at least 1 mm of stainless steel

Notes: In internal masonry other than the inner leaves of external cavity walls, carbon steel reinforcement may be used.
Prefabricated bed joint reinforcement is not generally available with a mass of zinc coating of 940 g/m^2

Table 15.2 Minimum concrete cover for carbon steel reinforcement

Exposure situations	Thickness of concrete cover (mm)				
	Concrete grade				
	30	35	40	45	50
	Minimum cement content (kg/m^3)				
	275	300	325	350	400
	Maximum free water /cement ratio				
	0.65	0.6	0.55	0.5	0.45
E1[a]	20	20	20[b]	20[b]	20[b]
E2	—	35	30	25	20
E3	—	—	40	35	25
E4	—	—	—	60[c]	50

[a] Alternatively, 1 : 0 to 1/4 : 3 : 2 cement : lime : sand : 10 mm nominal aggregate mix may be used to meet exposure situation E1, when the cover to reinforcement is 15 mm minimum

[b] These covers may be reduced to 15 mm minimum provided that the nominal size of aggregate does not exceed 10 mm

[c] Where the concrete infill may be subjected to freezing while wet, air entrainment should be used



Figure 15.11 Post-tension rod installation



Figure 15.12 Potential problem in reinforced cavity wall



Figure 15.13 Grouting in reinforced masonry beam

be given a minimum mass of zinc coating of 940 g/m^2. Since there is some possibility of the coating suffering micro-cracking in tensioning the tendons, the authors prefer to rely on the 'paint and wrap' process discussed in section 15.1.8.

15.2 Choice of System

The authors have designed many structures using post-tensioned and/or reinforced masonry, and the reasons for choosing either method in any particular situation have varied – as, indeed, have the economic conditions existing at the time of construction. For each scheme, the choice is essentially a matter for the designer's judgement. There are no hard and fast rules. Nevertheless, the aim of all design should be to achieve simple, safe and economical details and, bearing this in mind, several general points emerge which should help to guide the reader towards a satisfactory decision.

Vertically post-tensioned masonry is generally simpler than vertically reinforced masonry from both the construction and supervision points of view, and particularly when a cavity is to be maintained.

Protection for post-tensioning rods can be more easily provided and relied upon. Rods can be galvanised, painted and wrapped above the foundation anchorage, without any worries over loss of bond stress at these levels, and with the simplest of supervision. Rods can easily be inspected for protection, and can be checked for tension simply by applying a torque spanner to the nut after post-tensioning (see Figure 15.11). Reinforcement, on the other hand, relies upon bond which, in turn, relies upon adequate compaction of the grout or mortar. Reinforcing steel also requires adequate cover to prevent corrosion (this is absolutely vital to walls exposed to driving rain). These requirements can be very difficult to achieve, supervise and check (Figure 15.12).

For horizontal members, however, post-tensioned sections generally become more difficult, and details less simple, while reinforced masonry becomes more reliable from the point of view of achieving a satisfactory bond and a properly grouted cross-section (see Figure 15.13).

Again, the need to give adequate protection to the reinforcement should be stressed. This cannot be over-emphasised and, where cover to bars is minimised in attempts to support masonry which is forming, say, the soffit shutter for the grout, the bars should either be made of non-ferrous metal, or be protected by galvanising or by other means.

All too often, there is a tendency for engineers to introduce secondary reinforcement into locations which later result in problems of bursting, due to corrosion, when the omission of such reinforcement would have produced a suitable and reliable detail. This is very apparent in many existing



Figure 15.14 Reinforced masonry in balcony construction

reinforced concrete buildings, and must be avoided in the next generation of structures.

Provided that the above points are watched, reinforced masonry is often suitable for horizontal members. Particularly, of course, when a masonry finish is required.

Thus to summarise the situation, post-tensioning is generally better for vertical conditions, and reinforcement for horizontal work. Occasions do arise, however, where the balance of advantage is only marginal. For example, both reinforced and post-tensioned masonry can prove to be very economical for balcony walls and retaining walls (see Figure 15.14).

Fundamentally, masonry is a 'walling' material and it is likely therefore, that greater use will be made of post-tensioned masonry than reinforced. Since cracking, due to bending (possibly causing durability problems), is more likely to occur in reinforced masonry than post-tensioned masonry, designers may tend to opt for the latter.

The principal use of both techniques is in members resisting large bending moments. However, if we consider large compressive loads, post-tensioning would tend to reduce the wall's ability to resist such loads, whereas reinforcement would improve the wall's strength in compression (see Figure 15.15).

Reinforcement and post-tensioning can be exploited in the construction of precast masonry panels, which require added tensile strength to resist handling stresses.

Similar conditions arise in areas subject to mining subsidence, in that the most critical condition for the masonry



Figure 15.15 Reinforced masonry subjected to heavy direct load



Figure 15.16 Foundation settlement in mining areas



Figure 15.17 Post-tensioned panel use in mining areas

is the effect of the tensile stresses, which can be produced in direct form and in bending (see Figure 15.16).

The stresses can be reduced, and the masonry's resistance improved, by jointing the walls in short lengths and post-tensioning the resulting panels to increase the compression on the bed joints – thereby increasing the joint's resistance to applied tensions. Horizontally, the bonding of the masonry provides a greater resistance than the weaker bed joints and, generally, the panel size is restricted to maintain the stresses within acceptable limits (see Figure 15.17).

15.3 Design of Reinforced Brickwork

15.3.1 Partial Factors of Safety

Loadings

Partial factors of safety on ultimate loadings and details of the various load combinations to be considered are all as for plain masonry. Details of the various values are given in Chapter 5. Partial factors of safety for serviceability limit state are given in Table 5.1.

Materials

The partial safety factors for masonry in compression, $\gamma_{m'}$ have been reduced in BS 5628, Part 2 from those recommended in Part 1 and only 'special' category of workmanship is considered appropriate. The revised values are given in Table 15.3 and partial safety factors for steel, bond and shear are given in Table 15.4.

Table 15.3 Partial safety factors, γ_{mm}, for strength of reinforced masonry in direct compression and bending ultimate limit state (BS 5628, Part 2, Table 7)

Category of manufacturing control of structural units	Value of γ_{mm}
Special	2.0
Normal	2.3

Note: When considering accidental loading the above values may be halved

Table 15.4 Partial factor of safety on materials – ultimate and accidental damage limit states (BS 5628, Part 2, Table 8)

	Limit state	
	Ultimate	Accidental damage
Steel, γ_{ms}	1.15	1.0
Bond between mortar/ grout and steel, γ_{mb}	1.5	1.0
Shear strength of masonry, γ_{mv}	2.0	1.0

15.3.2 Strength of Materials

In order to analyse reinforced masonry the characteristic strengths of the various materials used must be determined. The properties of both the masonry and the reinforcement must be determined, in addition to the properties of the combined materials.

Properties of Masonry

The characteristics compressive, f_k, strength of the masonry is determined in exactly the same way as previously for plain masonry (details are given in Chapter 5 as is the capacity reduction factor).

Properties of Reinforcement

The characteristic tensile strengths, f_y, of reinforcement for various types of steel are given in the appropriate British Standards. Some values are given in Table 15.5.

The characteristic compressive strength of steel is taken as less than the characteristic tensile strength, and is taken as $0.83 \times f_y$.

15.3.3 Design for Bending: Reinforced Masonry

The design loading on a particular structural element is determined from the combination of the characteristic loadings from the relevant codes of practice and the partial factors of safety appropriate to the case being considered.

In the case of elements subject to bending, for example beams and retaining walls, the following points should be

Table 15.5 Characteristic tensile strength of reinforcement

Designation	Nominal sizes (mm)	Characteristic tensile strength, f_y (N/mm^2)
Hot rolled steel bars BS EN 10080 (NAD)	all	250
Hot rolled deformed high yield steel BS EN 10080 (NAD)	all	460
Cold worked steel bars BS EN 10080 (NAD)	all	460
Hard drawn steel wire	12	485



Figure 15.18 Effective depth and effective span



Figure 15.19 Effective depth and effective span

used in assessing the design loads, as illustrated in Figures 15.18 and 15.19.

Effective Span

The effective span of a simply supported member should be taken as the lesser of the distance between the centres of bearing or the clear distance between supports plus the effective depth.

The effective span of a continuous member should be taken as the distance between centres of supports.

The effective span of a cantilever should be taken as its length to the face of the support plus half its effective depth, except where it forms the end of a continuous beam where the length to the centre of the support should be used.

15.3.4 Lateral Stability of Beams

To ensure lateral stability a simply supported or continuous beam should be so proportioned that the clear distance

Table 15.6 Limiting slenderness ratios for walls and beams

(a) Walls

End condition	Ratio
Simply supported	35
Continuous	45
Cantilever with up to 0.5% reinforcement[a]	18

(b) Beams

End condition	Ratio
Simply supported	20
Continuous	26
Cantilever with up to 0.5% reinforcement[a]	7

[a] The percentage of reinforcement should be based on the gross cross-sectional area of the brickwork. For higher percentages of reinforcement special consideration should be given to deflection.

between lateral restraints does not exceed $60b_c$ or $250b_c^2/d$, whichever is the lesser, where b_c = breadth of compression face and d = effective depth. For cantilevers with lateral restraint provided only at the support, the clear distance from the end of the cantilever to the face of the support should not exceed $25b_c$ or $100b_c^2/d$ whichever is the lesser. For walls reinforced to resist lateral loading the slenderness ratios should be limited to the values given in Table 15.6 (BS 5628, Part 2, Tables 9 and 10 respectively).

15.3.5 Design Formula for Bending: Moments of Resistance for Reinforced Masonry

As in reinforced concrete the amount of reinforcement is designed so that the section fails in compressive crushing of the masonry at the same bending moment as the reinforcement fails in tension, i.e. a balanced section. If less reinforcement is used the section is under-reinforced and the section fails in tension, often with excessive deflection. If more reinforcement is used the section is over-reinforced and the section fails, catastrophically, in compression of the masonry. To prevent such explosive failure the Code aims to under-reinforce sections slightly.

Similar assumptions are made in reinforced masonry design as in reinforced concrete, viz:

(a) plane sections remain plane,
(b) tensile strength of masonry is ignored,
(c) compressive stress distribution is rectangular over the compression zone of magnitude f_k/γ_{mm}.

In addition the following assumptions are recommended by the Code:

(d) the maximum strain in the outermost compression fibre at failure is 0.0035,
(e) the stress in the steel does not exceed the values given in Table 15.5 and the stress–strain relationship is taken from Figure 15.20,
(f) the span to effective depth, d, ratio is not less than 1.5.

The stress and strain distributions are shown in Figure 15.21, where

A_s = cross-sectional area of primary reinforcing steel
b = width of section
d = effective depth
f_k = characteristic compressive strength of masonry
f_y = characteristic tensile strength of reinforcing steel
γ_{mm} = partial safety factor for strength of masonry
γ_{ms} = partial safety factor for strength of steel

$$z = \text{lever arm} = d\,\frac{(1 - 0.5A_s f_y \gamma_{mm})}{bdf_k\gamma_{ms}}$$

and $\geqslant 0.95d$

$$T = \frac{A_s \times f_y}{\gamma_{ms}} \qquad C = \frac{f_k}{\gamma_{mm}} \times b \times d_c$$

The design moment of resistance, M_d, of a singly reinforced rectangular masonry member, considering the reinforcement:



Figure 15.20 Short-term design stress–strain curve for reinforcement



Figure 15.21 Stress and strain distributions

$$M_d = \frac{A_s f_y z}{\gamma_{ms}} \quad \text{and} \quad \frac{0.4 f_k b d^2}{\gamma_{mm}}$$

Since z depends on the area of A_s it can be difficult to use this formula, and the Code gives a more convenient method using Q, a moment of resistance factor,

$$M_d = Q\,bd^2$$

Q depends on the lever arm factor, c, which is equal to z/d, and equals $2c(1-c)\,f_k/\gamma_{mm}$.

The Code gives a useful graph, see Figure 15.22, and Table 15.7 (BS 5628, Part 2, Table 11) relating Q, c and $f_k\gamma_{mm}$.

The simplest method for designing a balanced section is to consider the strain diagram in Figure 15.21 where:

$$\frac{d_c}{0.0035} = \frac{d}{0.0035 + 0.0031}$$

$$d_c = d\frac{0.0035}{0.0066}$$

$$= 0.53d$$

$$M_d = \frac{f_k}{\gamma_{mm}} \times b \times d_c \times \left(d - \frac{d_c}{2}\right)$$



Figure 15.22 Moment of resistance factor Q

Table 15.7 Values of the moment of resistance factor, Q, for various of f_k/γ_{mm} and lever arm factor, c

	Values of Q (N/mm^2)														
f_k/γ_{mm} c	1	2	3	4	5	6	7	8	9	10	11	12	13	15	20
0.95	0.095	0.190	0.285	0.380	0.475	0.570	0.665	0.760	0.855	0.950	1.045	1.140	1.235	1.425	1.900
0.94	0.113	0.226	0.338	0.451	0.564	0.677	0.790	0.902	1.015	1.128	1.241	1.354	1.466	1.692	2.256
0.93	0.130	0.260	0.391	0.521	0.651	0.781	0.911	1.042	1.172	1.302	1.432	1.562	1.693	1.953	2.604
0.92	0.147	0.294	0.442	0.589	0.736	0.883	1.030	1.178	1.325	1.472	1.619	1.766	1.914	2.208	2.944
0.91	0.164	0.328	0.491	0.655	0.819	0.983	1.147	1.310	1.474	1.638	1.802	1.966	2.129	2.457	3.276
0.90	0.180	0.360	0.540	0.720	0.900	1.080	1.260	1.440	1.620	1.800	1.980	2.160	2.340	2.700	3.600
0.89	0.196	0.392	0.587	0.783	0.979	1.175	1.371	1.566	1.762	1.958	2.154	2.350	2.545	2.937	3.916
0.88	0.211	0.422	0.634	0.845	1.056	1.267	1.478	1.690	1.901	2.112	2.323	2.354	2.746	3.168	4.224
0.87	0.226	0.452	0.679	0.905	1.131	1.357	1.583	1.810	2.036	2.262	2.488	2.714	2.941	3.393	4.524
0.86	0.241	0.482	0.722	0.963	1.204	1.445	1.686	1.926	2.167	2.408	2.649	2.890	3.130	3.612	4.816
0.85	0.255	0.510	0.765	1.020	1.275	1.530	1.785	2.040	2.295	2.550	2.805	3.060	3.315	3.825	5.100
0.84	0.269	0.538	0.806	1.075	1.344	1.613	1.882	2.150	2.419	2.688	2.957	3.226	3.494	4.032	5.376
0.83	0.282	0.564	0.847	1.129	1.411	1.693	1.975	2.258	2.540	2.822	3.104	3.386	3.669	4.233	5.644
0.82	0.295	0.590	0.886	1.181	1.476	1.771	2.066	2.362	2.657	2.952	3.247	3.542	3.838	4.428	5.904
0.81	0.308	0.616	0.923	1.231	1.539	1.847	2.155	2.462	2.770	3.078	3.386	3.694	4.001	4.617	6.156
0.80	0.320	0.640	0.960	1.280	1.600	1.920	2.240	2.560	2.880	3.200	3.520	3.840	4.160	4.800	6.400
0.79	0.332	0.664	0.995	1.327	1.659	1.991	2.323	2.654	2.986	3.318	3.650	3.982	4.313	4.977	6.636
0.78	0.343	0.686	1.030	1.373	1.716	2.059	2.402	2.746	3.089	3.432	3.775	4.118	4.462	5.148	6.684
0.77	0.354	0.708	1.063	1.417	1.771	2.125	2.479	2.834	3.188	3.542	3.896	4.250	4.605	5.313	7.084
0.76	0.365	0.730	1.094	1.459	1.824	2.189	2.554	2.918	3.283	3.648	4.013	4.378	4.742	5.472	7.296
0.75	0.375	0.750	1.125	1.500	1.875	2.250	2.625	3.000	3.375	3.750	4.125	4.500	4.875	5.625	7.500
0.74	0.385	0.770	1.154	1.539	1.924	2.309	2.694	3.078	3.463	3.848	4.233	4.618	5.002	5.772	7.696
0.73	0.394	0.788	1.183	1.577	1.971	2.365	2.759	3.154	3.548	3.942	4.336	4.730	5.125	5.913	7.884
0.72	0.403	0.806	1.210	1.613	2.016	2.419	2.822	3.226	3.629	4.032	4.435	4.838	5.242	6.048	8.064

Substituting for d_c:

$$M_d = \frac{f_k}{\gamma_{mm}} \times b \times 0.53d\left(d - \frac{0.53d}{2}\right) = 0.39\,\frac{f_k b d^2}{\gamma_{mm}}$$

for high yield steel:

$$M_d = 0.36\,\frac{f_k b d^2}{\gamma_{mm}}$$

When the span/depth ratio is less than 1.5 the lever arm may be taken as $^2/_3d$ and not greater than $0.7 \times$ span.

Walls with Reinforcement Concentrated Locally, such as Pocket Type and Similar Walls

The thickness of the flange, t_f, should be taken as the thickness of the masonry but not greater than $0.5d$.

The width of the flange (Figure 15.23) should be taken as the least of:

(a) the width of the pocket (or rib) + $12 \times t_f$,
(b) c/c of the pockets,
(c) one-third the height of the wall.



Figure 15.23 Flange width

M_d is determined as in section 15.3.5, but not greater than:

$$M_d = \frac{f_k}{\gamma_{mm}}[bt_f(d - 0.5t_f)]$$

When the centres of the pockets or ribs exceed 1 m, the wall's ability to span horizontally, mainly as an arch, should be checked (see section 6.6.3). At the ends of the wall, movement joint or other discontinuity, when there could be inadequate restraint for the 'arch' thrust, stiffened pockets in ribs should be provided.

Locally Reinforced Hollow Blockwork

It is unreasonable to expect hollow blockwork to provide the same flange width as solid masonry and the Code advises a restriction on the width to 3 × thickness of the blockwork.

15.3.6 Design Formula: Shear Stress

The behaviour of reinforced masonry members to flexural shear forces is more complex than when subjected to bending moments. The flexural shear resistance is influenced by many factors including the span-to-depth ratio of the member and the type of loading. The design for shear resistance is thus based more on past experience than exact analysis.

The shear stress may be assumed to be

$$v = \frac{V}{bd}$$

where

V = shear force due to design loads
b = width of section
d = effective depth (for flanged members the wall thickness between pockets and ribs when this is less than the effective depth).

The equation assumes a uniform distribution of shear stress across the section. This is, of course, a simplification of a complex phenomenon, and restrictions based on empirical data are placed on the characteristic shear strength of masonry, f_v.

When v is less than (f_v/γ_{mv}), no shear reinforcement is necessary, although, as in reinforced concrete beam design, the inclusion of nominal links in beams may be considered.

$$v \not> \frac{2.0}{\gamma_{mv}}\ \text{N/mm}^2$$

When v is greater than f_v/γ_{mv}, shear reinforcement should be provided so that:

$$\frac{A_{sv}}{S_v} \geq \frac{b(v - f_v/\gamma_{mv})\gamma_{ms}}{f_y}$$

where

A_{sv} = cross-sectional area of reinforcing steel resisting shear force
S_v = spacing of shear reinforcement (links or bent-up bars), provided that the spacing does not exceed $0.75d$.

Shear reinforcement for masonry is usually provided by links only and not by bent-up bars. There is little experience or empirical data on the action of bent-up bars in masonry and there are practical site difficulties in building them in.

It should be noted that the value of f_v for reinforced masonry differs from that given for plain masonry in section 6.11.1, and the Code, in clause 7.4.1.3, advises:

(a) f_v for beams and walls = 0.35 N/mm², when reinforcement is bedded in mortar designation (i) and (ii).

(b) For simply supported beams and cantilevers when the reinforcement is bedded in mortar and where the ratio of the shear span to effective depth is less than 2

$$\left(\text{shear span, } a = \frac{\text{maximum design bending moment}}{\text{maximum design shear force}}\right) f_v$$

may be increased by $2d/a_v$

where a_v = distance from face of support to nearest edge of a principal load.

The increase, over 0.35 N/mm², is limited to 0.7 N/mm².

(c) For simply supported beams or cantilever walls when the reinforcement is set in concrete grout and where a/d is 6 or less, f_v may be increased by a factor $[2.5 - 0.25(a/d)]$. This increase is limited to 1.75 N/mm².

(d) For other reinforced sections when the reinforcement is placed in pockets, cores or cavities and filled with a concrete grout, f_v may be obtained from the equation:

$$f_v = 0.35 + 17.5\rho\ \text{N/mm}^2$$

where $\rho = A_s/bd$
This increase is limited to 0.7 N/mm²

(e) For prestressed sections, $f_v = 0.35 + 0.6\ g_B$ N/mm² but not greater than 1.75 N/mm², where g_B = design load (including prestress) per unit area acting at right angles to the bed joint.

(f) For simply supported prestressed beams or cantilevers, where a/d is less than 6, f_v may be increased as in (c) above.

15.3.7 Shear Reinforcement

Shear reinforcement in the form of links is designed on the basis of the truss analogy (as explained in many text-books on reinforced concrete). The vertical tie force to be provided by the reinforcement must be greater than, or equal to, the shear force across the section less the resistance provided by the member itself. The spacing of links when required, should not exceed $0.75d$ to ensure that links will pass through any potential failure plane (see Figure 15.24), i.e. tensile force, $T \geq V$.

The tensile force provided by the reinforcement

$$= A_{sv}\frac{f_y}{\gamma_{ms}}$$

i.e. area of bars × design stress, where f_y is the characteristic strength of the shear reinforcement. Therefore



Figure 15.24 Behaviour of shear links

$$A_{sv}\frac{f_y}{\gamma_{ms}}+\frac{f_v}{\gamma_{mv}}\times bd\geq V$$

but $V=v_h bd$, therefore

$$A_{sv}\frac{f_y}{\gamma_{ms}}+\frac{f_v}{\gamma_{mv}}\times bd\geq v_h bd \qquad (15.1)$$

Links will be provided at centres less than the effective depth, therefore, several ties will become effective and the contribution of the reinforcement will be increased according to the ratio of the link spacing to the effective depth. Therefore, number of ties or links $=d/S_v$, where S_v = spacing of links.

Therefore equation (15.1) becomes:

$$\frac{d}{S_v}\times A_{sv}\times\frac{f_y}{\gamma_{ms}}+\frac{f_v}{\gamma_{mv}}\times bd\geq v_h bd$$

Hence

$$\frac{A_{sv}}{S_v}\geq\frac{bd\left(v_h-\dfrac{f_v}{\gamma_{mv}}\right)}{d\dfrac{f_y}{\gamma_{ms}}}$$

$$\geq\frac{b\left(v_h-\dfrac{f_v}{\gamma_{mv}}\right)}{f_y}\gamma_{ms} \qquad (15.2)$$

15.3.8 Design Formula: Local Bond

It is essential that the reinforcement provided in a flexural member is able to act with the mortar/grout/concrete. Referring to Figure 15.25, it has previously been established that the change in tensile force in the reinforcement between AB and CD is given by T_0-T_1 and that this may be expressed as $(M_0-M_1)/l_a$.



Figure 15.25 Shear stress distribution

This change in tensile force is balanced by the shearing stresses in the surrounding mortar/grout. The forces must be transmitted between steel and mortar or grout via the adhesion between the two. That is to say, the strength of the adhesive bond between the two must be greater than or equal to the change in force. The strength of the adhesion may be defined as the product of the bond stress and the contact area between steel and mortar grout, i.e.

$$(f_{bs}/\gamma_{mb})\times\delta L\times\pi\,\text{Dia}$$

where

f_{bs} is the characteristic local bond strength
γ_{mb} is the partial factor of safety (see Table 15.2)
δL is the length of bar being considered (see Figure 15.25)
Dia is the diameter of the bar.

π Dia may be replaced by Σu, where Σu is the sum of perimeters of the bars providing the tensile reinforcement, i.e. strength of adhesive bond is $(f_{bs}/\gamma_{mb})\times\delta L\times\Sigma u$.

Thus the total design adhesion must be greater than or equal to the design force to be transferred, i.e.

$$\frac{f_{bs}}{\gamma_{mb}}\times\delta L\times\Sigma u\geq\frac{M_0-M_1}{l_a}$$

Rearranging this becomes:

$$\frac{f_{bs}}{\gamma_{mb}}\geq\frac{M_0-M_1}{\delta L\times\Sigma u\times l_a}$$

But, as before, $(M_0-M_1)/\delta L$ is equal to the rate of change in bending, which in turn is equal to the shear force V, as explained earlier. Thus

$$\frac{f_{bs}}{\gamma_{mb}}\geq\frac{V}{\Sigma u\times l_a} \qquad (15.3)$$

As before, with the shear stress, this is generally expressed as:

$$\frac{f_{bs}}{\gamma_{mb}}\geq\frac{V}{\Sigma u\times d} \qquad (15.4)$$

The Code omits discussion of local bond, but the authors are of the opinion that designers should consider local bond.

15.3.9 Characteristic Anchorage Bond Strength, f_b

The characteristic anchorage bond strength, f_b, between mortar and steel is given in Table 5 of BS 5628 Part 2.

The detailing of reinforcement should generally follow the guidance given in BS 8110, but adjusted as necessary to take account of the differences in materials and construction.

15.3.10 Design for Axial Loading

The design loadings are determined in the normal manner. When determining the design strength, the effective height

or length of an element should be as defined in BS 5628, Part 1.

Effective Thickness

The effective thickness should be as defined in BS 5628, Part 1, clause 28.4. For grouted cavity walls the effective thickness should be taken as the actual thickness.

Design Formula for Axial Loading

The design vertical axial strength of a reinforced masonry element, where the slenderness ratio does not exceed 12, is simply the combination of the vertical axial strength of the masonry in compression, as determined for unreinforced masonry, plus the vertical axial strength in compression of the reinforcement. Where the slenderness ratio exceeds 12, the column is subject to bending, references to BS 5628, Part 2 should be made. The capacity reduction factor is applied to account for slenderness effects as with plain masonry.

Design vertical axial strength = β (compressive strength of masonry + compressive strength of reinforcement), where β is the capacity reduction factor based on the slenderness ratio as determined from BS 5628, Part 1, clause 28.

$$\text{Compressive strength of masonry} = f_k \times \frac{A}{\gamma_{mm}}$$

where

f_k = characteristic compressive strength of masonry
A = cross-sectional area
γ_{mm} = partial safety factor for masonry.

$$\text{Compressive strength of reinforcement} = 0.83 f_y \times \frac{A_s}{\gamma_{ms}}$$

where

f_y = characteristic compressive strength of masonry
A_s = cross-sectional area
γ_{ms} = partial safety factor for steel reinforcement.

Thus design vertical axial strength,

$$N_d = \beta \left(\frac{f_k A}{\gamma_{mm}} + \frac{0.83 f_y A_s}{\gamma_{ms}} \right) \qquad (15.5)$$

(See section 15.7.)

15.4 Example 1: Design of Reinforced Brick Beam

Reinforced brickwork beams are required to span 3.0 m, spaced at 3.0 m centres supporting a concrete floor as shown in Figure 15.26. The bricks have a compressive strength of 20 N/mm^2.

Masonry Stresses

Characteristic compressive strength of masonry, f_k, using standard format bricks in designation (ii) mortar = 6.4 N/mm^2.

Characteristic shear strength, $f_v = 0.35$ N/mm^2.

Steel Strength

Characteristic tensile strength using hot-rolled deformed high yield steel = 460 N/mm^2.

Partial Factors of Safety

Loads: dead load + imposed load, combination

Design dead load $= 0.9G_k$ or $1.4G_k$
Design imposed load $= 1.6Q_k$

Materials:

For brickwork in compression and shear, assume special manufacturing and construction control, $\gamma_{mm} = 2.0$.

Bond between mortar and steel:

bricks, $\gamma_{mb} = 1.5$ ultimate limit state.

Density of brickwork = 20 kN/m^3.

Loading

Characteristic dead load:

150 mm rc floor	$24 \times 0.15 =$	3.6 kN/m^2
50 mm screed	$24 \times 0.05 =$	1.2 kN/m^2
Partition allowance	=	1.0 kN/m^2
	=	5.8 kN/m^2
Design dead load	$1.4 \times 5.8 =$	8.1 kN/m^2
Characteristic imposed load	=	1.5 kN/m^2
Design imposed load	$1.6 \times 1.5 =$	2.4 kN/m^2
Total design load	$8.1 + 2.4 =$	10.5 kN/m^2
Design UDL on beam	$10.5 \times 3 =$	31.5 kN/m^2
Design dead load due to self-weight of beam (estimated)	=	8.5 kN/m^2
	=	40.0 kN/m^2



Figure 15.26 Details for Example 1

Beam is simply supported

$$\text{Design bending moment} = \frac{40 \times 3^2}{8} = 45 \text{ kN m}$$

$$\text{Maximum design shear force, } V, = \frac{40 \times 3}{2} = 60 \text{ kN}$$

Effective depth, d, required to provide a moment of resistance equal to this value: $M_d = Qbd^2$. Therefore

$$d = \sqrt{\left(\frac{M_d}{Qb}\right)}$$

for γ_{mm} = 2.0 and f_k = 6.4 N/mm^2, since M_d = 0.375 $(f_k/\gamma_{mm})bd^2$ as a maximum value (0.375 is the average value between 0.39 for mild steel and 0.36 for high yield steel, see section 15.3.5).

Take b = 327 mm, then

$$d \text{ required} = \sqrt{\left(\frac{45 \times 10^6}{0.375 \times \frac{6.4}{2} \times 327}\right)}$$

$$= 338 \text{ mm}$$

Depth required to resist shear without shear reinforcement:

In accordance with section 15.3.6(d),

$$f_v = 0.35 + 17.5\rho$$

where $\rho = \frac{A_s}{bd} = \text{(say)}\ \frac{339}{327 \times 800} = 0.0013$ (assume 3T12 bars).

Hence, $f_v = 0.35 + (17.5 \times 0.0013) = 0.37$ N/mm^2

Design shear strength, $v_h = (0.37/2.0) = 0.185$ N/mm^2

$$d \text{ required} = \frac{V}{v_h b}$$

$$= \frac{60 \times 10^3}{0.185 \times 327}$$

$$= 992 \text{ mm}$$

Therefore provide shear reinforcement and try 327 wide × 900 deep overall beam, which is a multiple of the height of one brick course and gives an effective depth of 790 mm, i.e. allowing one course of brickwork plus 25 mm cover plus half bar diameter (see Figure 15.27).

Moment of tensile resistance

$$M_{rs} = \frac{A_s f_y l_a}{\gamma_{ms}}$$

Therefore, area of reinforcement required:

$$A_s = \frac{M\gamma_{ms}}{f_y l_a}$$

Estimating the lever arm l_a as 0.90d,

$$A_s = \frac{45 \times 10^6 \times 1.15}{460 \times 0.90 \times 790} = 137 \text{ mm}^2$$

Use two T12 bars (226 mm^2).



Figure 15.27 Shear link construction in Example 1

Check Value of Lever Arm

The actual value of the lever arm is now calculated to ensure that the value assumed before in the calculation of A_s was reasonable.

$$l_a = d\left[1 - \left(\frac{A_s f_y}{\gamma_{ms}}\right)\left(\frac{\gamma_m}{1.5 f_k}\right)\left(\frac{0.58}{bd}\right)\right]$$

$$= d\left[1 - \frac{226 \times 460 \times 2.0 \times 0.58}{1.15 \times 1.15 \times 6.4 \times 327 \times 790}\right]$$

$$= 0.95d$$

This is greater than the assumed value and is therefore satisfactory.

Check Percentage of Reinforcement in Grouted Void

There is a maximum practical percentage of reinforcement which can be accommodated in the grout void which may be assumed to be 4% of the grouted area.

$$\text{Reinforcement percentage} = \frac{226}{100 \times 150}$$

$$= 1.5\% \text{ of the grouted area}$$

This is acceptable.

Shear Links

Flexural shear strength, f_v = 0.37 N/mm^2

Design shear load, V = 60 kN

$$\text{Design shear stress, } v_h = \frac{V}{bd} = \frac{60 \times 10^3}{327 \times 790}$$

$$= 0.23 \text{ N/mm}^2$$

$$\text{Design shear strength} = \frac{f_v}{\gamma_{mv}} = \frac{0.37}{2.0}$$

$$= 0.185 \text{ N/mm}^2$$



Figure 15.28 Position of shear links in double Flemish bond brickwork beam 1½ bricks thick

Thus design shear strength is less than design shear stress. Links should normally be provided unless the design shear strength is greater than the applied design shear stress.

Positioning of Links

According to the type of bonding, continuous vertical mortar joints occur at intervals. At these positions 8 mm diameter bars could be accommodated (if necessary the corners of the adjacent bricks could be removed to provide more space). Figure 15.28 shows that continuous joints suitable for accommodating links occur at 225 mm centres. Links would not be required where the shear stress was less than the shear strength. Where links are provided but not calculated to provide a specific shear value, they are termed nominal links.

Design of links

$$\frac{A_{sv}}{S_v} \geq \frac{b\left(v_h - \dfrac{f_v}{\gamma_{mv}}\right)\gamma_{ms}}{f_y}$$

i.e.

$$\frac{A_{sv}}{S_v} \geq \frac{327(0.23 - 0.185)1.15}{250}$$

$$\frac{A_{sv}}{S_v} \geq 0.068$$

This is provided by R8 links at 225 mm centres.

Local Bond

Characteristic local bond strength, f_{bs} = 2.8 N/mm^2 for grade C30 concrete.

$$\text{Design local bond strength} = \frac{2.8}{1.5} = 1.87\ \text{N/mm}^2$$

$$\text{Local bond stress} = \frac{V}{\Sigma u \times d}$$

$$= \frac{60 \times 10^3}{2\pi \times 12 \times 790} = 1.0\ \text{N/mm}^2$$

Design local bond stress < design local bond strength.

15.5 Example 2: Alternative Design for Reinforced Brick Beam

For use when the depth of the beam is to be restricted. Beam depth is arrived at as follows: consider what shear reinforcement it is possible to get in the beam; calculate minimum depth based on shear resistance thus obtained. This gives a smaller depth than the first method. The first part of the calculation is as before.

Depth Required to Resist Shear

According to the type of bonding, continuous vertical mortar joints occur at intervals. At these positions, 8 mm diameter links could be accommodated in the joint (if necessary the corners of the adjacent bricks could be removed to provide more space). Figure 15.28 shows that, for a beam

built in double Flemish bond, suitable locations for links occur at 225 mm centres. Assuming then that R8 shear links at 225 mm centres will be used, a suitable depth of beam can be calculated.

Minimum depth required, using R8 shear links at 225 mm centres:

$$\frac{A_{sv}}{S_v} \geq \frac{b\left(v_h - \frac{f_v}{\gamma_{mv}}\right)\gamma_{ms}}{f_y}$$

where

$A_{sv} = 2 \times 50.3$ (R8 link)
$S_v = 225$ mm
$b = 327$ mm
f_v assume this approach yields a depth less than 750 mm; therefore the lower value of f_v must be used, i.e. 0.35 N/mm^2
$\gamma_{mv} = 2.0$; $f_v/\gamma_{mv} = 0.175$ N/mm^2
$\gamma_{ms} = 1.15$
$f_y = 250$ N/mm^2 for mild steel.

Therefore

$$\frac{50.3 \times 2}{225} \geq \frac{327(v_h - 0.175)1.15}{250}$$

$$\frac{50.3 \times 2 \times 250}{225 \times 327 \times 1.15} + 0.175 \geq v_h$$

$$v_h \leq 0.472 \text{ N/mm}^2$$

$v_h = V/bd$, where $V = 60$ kN and $b = 327$ mm, therefore

$$d = \frac{60 \times 10^3}{327 \times 0.472}$$

$$= 389 \text{ mm}$$

Minimum effective depth	= 389 mm
$\frac{\text{bar diameter}}{2}$, say,	= 10 mm
cover	= 25 mm
1 course of brickwork below	= 75
Overall depth of beam	= 499 mm

The nearest size greater than this figure, which is also a multiple of the height of one brick course, is 525 mm (giving an effective depth of 415 mm), see Figure 15.29. Use 327 wide × 525 overall deep beam.

It can be seen that the designer has great scope to design a suitable beam for many different visual circumstances and within certain limits can vary the design to achieve a desired depth.

Ultimate Compressive Moment of Resistance of Beam

$$M_d = Rbd^2$$
$$= 1.0 \times 327 \times 415^2$$
$$= 56.3 \text{ kN m}$$



Figure 15.29 Beam section in example 2

(Design bending moment = 45 kN m, which is less than the moment of resistance.)

Ultimate moment of tensile resistance:

$$M_{rs} = \frac{A_s f_y l_a}{\gamma_{ms}}$$

Area of reinforcement required:

$$A_s = \frac{M\gamma_{ms}}{f_y l_a}$$

Estimating l_a as $0.80d$

$$A_s = \frac{45 \times 10^6 \times 1.15}{460 \times 0.80 \times 415}$$

$$= 339 \text{ mm}^2$$

Use 2 T16 bars (provides 402 mm^2).

Check Value of Lever Arm

The actual value of the lever arm is now calculated to ensure that the value assumed above in the calculation of A_s was reasonable:

$$l_a = d\left[1 - \left(\frac{A_s f_y}{\gamma_{ms}}\right)\left(\frac{\gamma_m}{1.15 f_k}\right)\left(\frac{0.58}{bd}\right)\right]$$

$$= d\left[1 - \frac{402 \times 460 \times 2.0 \times 0.58}{1.15 \times 1.5 \times 6.4 \times 327 \times 415}\right]$$

$$= 0.86d$$

This is greater than the assumed value and is therefore satisfactory.

Local Bond

Characteristic local bond strength, $f_{bs} = 2.1$ N/mm^2

Design local bond strength $= \frac{2.1}{1.5} = 1.4$ N/mm^2

Design local bond stress $= \frac{V}{\Sigma u \times d}$

$$= \frac{60 \times 10^3}{2\pi \times 16 \times 415} = 1.44 \text{ N/mm}^2$$

Slight overstress, but say okay.



Figure 15.30 Wall section Example 3



Figure 15.31 Soil pressures Example 3

15.6 Example 3: Reinforced Brick Retaining Wall

The retaining wall shown in Figure 15.30 is to be constructed in two leaves of brickwork, the outer leaf being thicker than the inner, with a 100 mm cavity to take the reinforcement, which is to be grouted after construction. Design height = 1.8 m.

The loading on the wall will include a particularly severe surcharge as indicated in the design calculations.

In accordance with BS 5628, Part 3, Table 13, special quality bricks in designation (i) mortar are to be used. To comply with the requirement of special quality, use bricks having a water absorption not greater than 7%, and crushing strength, say 27.5 N/mm^2. The wall retains dry sand to a depth of 1.8 m. Assume manufacturing and construction control both special, therefore $\gamma_m = 2.0$.

Characteristic compressive strength of bricks of 27.5 N/mm^2 crushing strength in designation (i) mortar, $f_k = 9.2$ N/mm^2.

Characteristic flexural strength of bricks having a water absorption less than 7% in designation (i) mortar f_{kx} = 0.7 N/mm^2.

Design Load

Retained material, fine dry sand:

Angle of internal friction = 30°

Density = 17 kN/m^3

$$q_1 = k_1 \times \text{density} \times h$$

where $k_1 = \dfrac{1 - \sin 30°}{1 + \sin 30°} = 0.33$

Allow 1 m surcharge to allow for surcharge loading at high level.

Characteristic horizontal pressure due to retained material behind wall:

at top $= 0.33 \times 17 \times 1 = 5.6$ kN/m^2
at base, $q_1 = 0.33 \times 17 \times 2.8 = 15.7$ kN/m^2

Design load= $Q_k \times \gamma_f$
(where γ_f is 1.2 for earth or water load)

Design load (top) = $5.6 \times 1.2 = 6.72$ kN/m^2
(base) = $15.7 \times 1.2 = 18.9$ kN/m^2

(See Figure 15.31.)



Figure 15.32 Plan on reinforcement position in wall in Example 3

Overturning Moment

$$\frac{6.72 \times 1.8^2}{2} = 10.9 \text{ kN m}$$

$$12.18 \times \frac{1.8}{2} \times \frac{1.8}{3} = \underline{6.6 \text{ kN m}}$$

$$\text{Total} = 17.5 \text{ kN m}$$

Try the Following Section

Note that the width of the grouted cavity shown here (100 mm) is the minimum practical width to ensure sufficient cover to the reinforcement. The use of galvanised reinforcement should also be considered depending on the required life of the wall.

Effective depth (see Figure 15.32):

$$d = 215 + \frac{100}{2} = 265 \text{ mm}$$

$$M_d = Qbd^2$$

therefore $Q = \dfrac{17.5 \times 10^6}{1000 \times 265^2} = 0.249$

For $f_k = 9.2$ N/mm^2 and $\gamma_{mm} = 2.0$, $c = 0.95$ (see Figure 15.22).

$$A_s = \frac{M_A \gamma_{ms}}{f_y l_a}$$

$$f_y = 460 \text{ N/mm}^2$$

$$l_a = 0.95d$$

Therefore

$$A_s = \frac{17.5 \times 10^6 \times 1.15}{460 \times 0.95 \times 265}$$

$$= 174 \text{ mm}^2/\text{m}$$

Use T12s at 300 mm centres.

This reinforcement is vertical reinforcement and some longitudinal bars should be provided to tie these together for ease of construction. Therefore, provide T10 bars longitudinally at 600 mm vertical centres.

Check Shear

$$V = 6.72 \times 1.8 + 12.18 \times \frac{1.8}{2}$$
$$= 12.1 + 11.0$$
$$= 23.1 \text{ kN}$$

$$f_v = 0.35 + 0.0008 = 0.351 \text{ N/mm}^2$$

$$\text{Design shear strength} = \frac{f_v}{\gamma_{mv}} = \frac{0.351}{2.0} = 0.176 \text{ N/mm}^2$$

$$\text{Shear stress} = v_h = \frac{23.1 \times 10^3}{1000 \times 265} = 0.087 \text{ N/mm}^2$$
$$< 0.176 \text{ N/mm}^2$$

Clause 8.2.5.2 of the Code allows a reduction in the design shear stress if inclined bars are used in retaining walls. This is not applicable in this example.

Check Local Bond

$$\text{Characteristic local bond strength, } f_{bs} = 2.8 \text{ N/mm}^2$$
$$\gamma_{mb} = 1.5$$
$$\text{Design local bond strength} = \frac{f_{bs}}{\gamma_{mb}} = 1.87 \text{ N/mm}^2$$
$$\text{Design local bond stress} = \frac{V}{\Sigma u \times d}$$
$$= \frac{23.1 \times 10^3}{12\pi \times \frac{1000}{300} \times 265}$$
$$= 0.71 \text{ N/mm}^2$$
$$< 1.87 \text{ N/mm}^2$$

The main vertical reinforcement must, of course, be bonded into the concrete base. A concrete base should now be designed, its size being such as to give a suitable factor of safety against overturning and sliding (see Figure 15.33). This is beyond the scope of this book.



Figure 15.33 Reinforced concrete base and drainage for wall in Example 3

15.7 Example 4: Column Design

Calculate the area of reinforcement required for the column shown in Figure 15.34 subject to the loading shown (see section 15.3.10).

$$\text{Slenderness ratio } \frac{h_{ef}}{t_{ef}} = \frac{7000}{440} = 16$$

therefore $\beta = 0.83$.

Design vertical axial strength

$$N_d = \beta\left(f_k \frac{A}{\gamma_{mm}} + 0.83 f_y \frac{A_s}{\gamma_{ms}}\right)$$

Design vertical axial strength, $N_d \geq$ applied design load $(1.4G_k + 1.6Q_k) = (1.4 \times 300) + (1.6 \times 180) = 708$ kN.

Therefore

$$708 \text{ kN} \leq \beta\left(f_k \frac{A}{\gamma_{mm}} + 0.83 f_y \frac{A_s}{\gamma_{ms}}\right)$$

If A_s required is the area of reinforcement required

$$A_s \text{ required} \geq \left(\frac{708}{\beta} \times 10^3 - \frac{f_k A}{\gamma_{ma}}\right) \frac{\gamma_{ms}}{0.83 f_y}$$

Substituting for γ_{mm}, etc., and assuming high yield steel reinforcement,

$$A_s \text{ required} \geq \left(\frac{708 \times 10^3}{0.83} - \frac{6.4 \times 440^2}{2.3}\right) \times \frac{1.15}{0.83 \times 460}$$
$$\geq 946 \text{ mm}^2$$



Figure 15.34 Details for column in Example 4



Figure 15.35 Post-tensioned brickwork fin wall under vertical and horizontal load

Adopt four No. T20 diameter bars which give an area of 1260 mm^2.

Links should be provided in accordance with the recommendations of BS 8110.

15.8 Design of Post-tensioned Brickwork

15.8.1 General

In order to introduce the idea of post-tensioned masonry in a little more detail, and before considering specific aspects of design and design examples, it may be of value to first briefly consider its use in a particular application – post-tensioned fin walls.

As discussed earlier, because of masonry's low resistance to tensile stresses, it is often advantageous when high bending moments and/or uplift forces have to be resisted in locations of low gravitational loads to incorporate a material which is good in resisting tensile stresses. This can either be in the form of reinforcement to resist the tensile stress, or post-tensioned rods to create additional compressive stress in the masonry to cancel out the excessive flexural tensile stress. In many cases, it is more economical to post-tension than to reinforce and, in the case of fin walls, and other applications, experience to date favours the use of post-tensioning.

Simplified Design Philosophy

Consider a section of a brick fin wall of cross-sectional area, A, and section modulus, Z, resisting a compressive load, P, and a bending moment, M (see Figure 15.35).

For the normal stress condition, the stress in the extreme fibres = $(P/A \pm M/Z)$ for an uncracked section. For a normal section under combined bending and compression, in a typical fin wall situation, it would be the allowable flexural tensile stress which would limit the resistance moment. Therefore it is $(P/A - M/Z)$ which is critical, and not $(P/A + M/Z)$. It follows that increasing (P/A) improves the critical condition by reducing the flexural tensile stress when the bending moment, M, is applied. Thus where possible, it is logical to make use of the remaining allowable compressive stress by increasing P by post-tensioning with an applied force, T, so that when the bending moment is applied the resulting flexural tensile stress is below the allowable limit.



Figure 15.36 Location of post-tensioning rod in wall

A check must also be made for the combination of $(P/A + M/Z)$, plus the post-tensioning stress in the brickwork to check the maximum combined compressive stress against the allowable value.

Location of Post-tensioning Rods

The post-tensioning rod should be located within the critical section so that M is also reduced by the eccentricity of the rod (see Figure 15.36), but regard must be given to the effect of this eccentricity at the other critical section for the reverse applied bending moment induced by the eccentric post-tensioning force.

The resulting stress at the tensile face of the section shown in Figure 15.36 would now be

$$\frac{P}{A} - \frac{M}{Z} + \frac{Te}{Z}$$

giving a much reduced flexural stress. The effect of the post-tensioning is, therefore, to reduce the section size required to resist the combined bending and direct loading condition.

It should be noted that, depending on the location of the rods, there may be a change in the strain due to bending, which may affect the post-tensioning force. As with prestressed concrete design to BS 8110, pending further research, this may be ignored.

Method and Sequence of Construction

The foundations are cast with the post-tensioning rods anchored in. The masonry wall is then constructed, leaving



Figure 15.37 Construction method of post-tensioned wall



Figure 15.38 End anchorage in post-tensioned wall

suitable voids around the rods. At the top of the wall, the threaded upper ends of the rods are allowed to project. When the masonry has cured, a plate is placed over the upper end of each rod on the top of the wall. Nuts are screwed onto the threads and tightened down to a predetermined torque using a calibrated torque spanner. The threads must be kept clear of foreign matter and be lubricated to give a calculable force in the rod when the torque is applied. For high levels of prestress, hydraulic jacks are used as in prestressed concrete.

On completion of the post-tensioning, voids can, if required, be filled with a slurry grout, in which case they should be constructed with vent holes up the height of the wall. The amount of grout should be predetermined by calculation so as to provide a check that the voids have been completely filled. However, in most cases, the voids are left ungrouted – the rods being protected above the foundation anchorage by a tape and paint product such as 'Denso' (see Figure 15.37).

The method of corrosion protection should be chosen to suit the exposure conditions and the stress condition in the rods. It should be noted, however, that where the anchorage of a rod relies upon bond stress, any protective coating that is likely to slip under load must not be used within the designed length of anchorage (see Figure 15.38).



Figure 15.39 Anchorage of roof beams at top of wall

At the location of beam bearings, it is often convenient to use the post-tensioning rods as an anchorage for the roof beams (see Figure 15.39).

High Walls in Post-tensioning Construction

In high walls, post-tensioning rods should be jointed in order to restrict the projecting length to a manageable amount. The length should be determined from consideration of

the bar diameter, the possibility of temporary support from scaffolding, etc., and the likely wind exposure during construction. The joints must be of sufficient strength to resist the forces involved, should be simple to construct, and adequately protected against corrosion. Bottle connectors or welded joints are suitable.

On very high or multi-storey buildings, where temporary stability of the post-tensioned wall becomes more critical if the total post-tensioning is left until completion of the brickwork, a phased sequence of the post-tensioning can be operated as the work progresses. For example, at preset levels within the height of the wall, the rods can be post-tensioned as the brickwork reaches each level, leaving a projection of threaded rod onto which an extension sleeve can be fixed to continue the rod to the next stage. Alternatively, a number of rods can be used, relating the necessary height of each rod to the design condition and curtailing it at a suitable level. This will result in rods which curtail at various heights up the wall. Post-tensioning of the rods as the wall reaches the curtailment level will give added stability to the wall as the work progresses to the next height. The addition of loading on a previously post-tensioned section may reduce the post-tensioning in that section by changing the strain in the rod. This effect should be considered when using this technique (see Figure 15.40).

15.8.2 Post-tensioned Masonry: Design for Flexure

In reinforced masonry in bending, the lack of tensile strength is overcome by providing reinforcement to resist the tensile stresses. Another solution to this problem is to provide sufficient precompression within the member so that the net tensile stresses, when flexural stresses are combined with this compressive stress, are very small or zero. For masonry it is considered that, under the application of working loads, the combined flexural tensile stress should be limited to zero.

Post-tensioning, as applied to masonry, is basically the addition of compressive axial loading, which may or may not be applied eccentrically, to reduce the flexural tensile stresses set up in the member due to bending. By applying the axial loading eccentrically, for example in a member subject to lateral loading from one direction only, flexural tensile and compressive stresses may be induced in reverse to those set up under the application of the working lateral load. The combination of axial loading with the applied lateral loading produces an increase in the total compressive stress which the masonry is more able to accommodate and a reduction in the tensile stresses (see Figures 15.41 and 15.42).

The applied force and its eccentricity may be varied to produce design stresses within the allowable limits of the tensile and compressive strengths of the masonry.

The simple basic idea of post-tensioning is made complicated, as far as the design is concerned, by the natural properties of the materials involved which may cause changes in the applied force after its application. The initial applied force may be reduced by losses or increased by gains which may occur due to any or all of the following:



Figure 15.40 Typical detail for tall post-tensioned fins



Figure 15.41 Stresses produced using concentric position of prestressing force



P = applied post-tension force and own weight plus vertical load
A = area of section
M = applied bending moment
Z = section modulus

Figure 15.42 Stresses produced using eccentric position of prestressing force

(a) moisture movements in the masonry,
(b) relaxation of the post-tensioned steel,
(c) elastic deformation of the masonry,
(d) friction,
(e) natural growth of clay brickwork,
(f) creep of brickwork and blockwork,
(g) thermal movement.

These are the main factors influencing losses or gains in the post-tensioning force as applied, in its simplest form, to masonry.

The stresses must therefore be checked for the conditions appertaining when the post-tensioning force is initially applied and then again after all or most of the losses have occurred. If gains are expected, which is generally less likely, allowance for this should be made in assessing the stresses applicable at any particular design stage and the strength assessments, which are described in the following pages, must be adjusted accordingly.

As the flexural tensile stresses are eliminated (or reduced to nominal acceptable amounts) owing to the application of the load to be supported, an elastic analysis is appropriate. The design is therefore based on design strengths using the appropriate partial safety factors and capacity reduction factors where applicable.

15.8.3 Design Strengths

The basic characteristic compressive strength of masonry, f_k may be increased to allow for:

(a) the permanence of the strength requirement,
(b) flexural compressive stresses as opposed to axial compressive stresses.

The partial loss of post-tensioning force, which commences immediately after its application, may be taken to constitute a temporary force prior to the losses and a permanent force after losses. The magnitude of the total losses allowed for in the design is approximately 20%, which will be discussed later in this chapter, and it is therefore considered reasonable to increase the characteristic compressive strength of the masonry by 20% to accommodate the short-term duration of this loading condition.

The percentage increase on the characteristic compressive strength, to take account of its application as a flexural compressive strength, should vary depending on the ratio of axial to flexural compressive stress being applied. If the applied stress is wholly axial, f_k should not be increased at all. If the applied stress is wholly flexural, it is considered reasonable to increase f_k to $1.5f_k$ as is used in reinforced masonry design. A sliding scale of increase factors should be devised from research on the basis of the principles described and possibly incorporating a unity factor relating actual and allowable stresses for both axial and flexural loading. In the absence of such a scale it is proposed that a global figure of $1.25f_k$ should be adopted for general situations, with adjustments made to this figure, at the discretion of the designer, when extreme cases are considered.

Care should be exercised in assessing the stress condition at all critical stages of loading for each different type of element to be analysed. For example, consider the following two totally differing elements described briefly as:

Case (1): Masonry beam, spanning horizontally and supporting predominantly dead loads.
Case (2): Masonry wall panel, spanning vertically and supporting equal wind forces in either direction.

Case (1) element would most likely be post-tensioned eccentrically to induce the reverse stress diagram to that of the working loads. Hence, the situation prior to losses would be that of a temporary strength requirement limited by the flexural compressive stress on one side of the stress block and zero flexural tensile stress on the other side. It is considered reasonable to limit the design flexural compressive strength in this situation to $1.20 \times (1.25f_{ki}/\gamma_{mm})$ in which both increase allowances have been exploited and f_{ki} is the characteristic compressive strength of the masonry at the age at which the post-tensioning is applied.

For the same element, the next loading stage to be analysed is after all losses are assumed to have taken place and the applied load added (including removal of props from



Figure 15.43 Stresses arising at stages in prestressing and loading

beneath the beam). This is now the permanent working state for this element and the reversed stress diagram should now limit the design flexural compressive stress to $1.25f_k/\gamma_{mm}$, in which only the flexural aspect of the increase is exploited and the masonry is assumed to have gained its full characteristic compressive strength value of f_k. The stress diagrams for these loading situations on case (1) element are shown in Figure 15.43.

The application of the capacity reduction factor, β, to these strength limitations is applicable in certain circumstances and is discussed in the worked examples which follow.

Consider now case (2) element in which the post-tensioning force would be most effective if applied concentrically to have an equal effect on the flexural tensile stresses from each direction of wind loading. The situation prior to losses would be that of a temporary strength requirement for axial compressive stresses only and shows as a rectangular stress block in which the design compressive strength is limited to $1.2\beta f_{ki}/\gamma_{mm}$. After losses and under the application of the wind loading the situation could be considered as that of a more permanent strength requirement limited by the flexural compressive stress on one side of the stress block and zero flexural tensile stress on the other side. In this instance for solid walls the design flexural compressive stress may be limited to $1.25f_k/\gamma_{mm}$, and the capacity reduction factor, β, is applied inversely to the actual stress resulting from the axial load only, as it is considered inappropriate to apply it to the flexural compressive stress in solid walls.

Hence, the design equation is written as:

$$f_{ubc} + \frac{f_{uac}}{\beta} \leq \frac{1.25f_k}{\gamma_{mm}}$$

where

f_{ubc} = design flexural compressive stress
f_{uac} = design axial compressive stress
β = capacity reduction factor
f_k = characteristic compressive strength
γ_{mm} = partial safety factor on materials.

For geometric profiles, such as the fin or diaphragm wall, where under certain conditions the whole of the stressed area can buckle under the combined flexural and axial compressive loading, the factor should be applicable in the normal way and the design equation in this situation may be written as:

$$\text{Actual combined stress} \leq \frac{1.25\beta f_k}{\gamma_{mm}}$$

While the application of the wind loading is described as a more permanent strength requirement, it could equally be argued that wind loading is of a particularly temporary nature and thus, a temporary strength allowance could be considered.

The compressive strength requirement may, however, be dominated by the post-tensioning force which is now a more permanent load and it is therefore recommended that the temporary nature of the wind load is ignored so far as stress increases are concerned. In addition, its temporary nature is catered for in the allocation of partial safety factors (γ_f) for loads for differing load combinations.

With this element, a third and more critical loading situation requires analysis, this being the more common permanent working state of the wall, in which the post-tensioning has been affected, losses have occurred but no wind loading is applied. This loading situation is similar to that which occurred before the anticipated losses. Hence, the design compressive stress is limited to $\beta f_k/\gamma_{mm}$ and shows as a rectangular stress block.

The stress diagrams for each of these three loading situations are shown in Figure 15.44.

15.8.4 Steel Stresses

The maximum initial stress in the post-tensioning rods should be limited to 70% of the normally applicable design strength of f_y/γ_{ms}, in which γ_{ms} has been given in Table 15.2 as 1.15. The purpose of this additional partial safety factor is to limit the stress relaxation in the steel which has a significant effect on the loss of post-tensioning force to be expected.

15.8.5 Asymmetrical Sections

Particular care is required when analysing asymmetrical sections such as the fin wall, as the section has two Z (section modulus) values. The appropriate Z value must be carefully selected for each level considered, for both directions of lateral loading and for both flexural tensile and flexural compressive stresses.



Figure 15.44 Stresses arising at stages in prestressing and loading

15.8.6 Losses of Post-tensioning Force

For most applications of post-tensioning to masonry as presented here, it is considered that 20% losses in the post-tensioning force due to all of the various factors may be assumed. (This excludes losses due to elastic contraction, which are eliminated in post-tensioning.) A more accurate figure could only be determined by a programme of research into the various effects. The need for a more accurate figure is debatable, bearing in mind the quality control and practicalities of construction, and that the 20% figure has proved satisfactory over a considerable period. In particularly specialised applications with very strict quality control, it may be considered worthwhile to determine a more accurate figure. However, more research is required with regard to gains of post-tensioning force in clay brickwork due to the long-term expansion noted earlier, and little is understood about this phenomenon in relation to post-tensioning.

Assessment of Losses

(a) Creep and moisture movements

When loading is applied to masonry, there is an instantaneous shortening due to contraction from compressive forces which is termed the elastic deformation, and then a further deformation which is time-dependent and known as creep. Much research has been undertaken into creep in concrete. However, relatively little has been done with regard to masonry. The mechanism of creep in masonry appears to be similar to that of concrete, although there are important differences.

Moisture causes various reversible and irreversible movements in masonry clay. Bricks undergo a comparatively small and reversible expansion and contraction due to wetting and drying. A much larger and irreversible expansion occurs immediately after firing. Most of this expansion occurs within the first seven days for the majority of units, continuing at a decreasing rate for about six months, when a limiting value is reached. In addition to these two types of movement, there appears to be, in some clay bricks, a much longer-term permanent expansion movement, possibly related to moisture movements within the bricks. The longer-term expansion may be greater than the contraction due to creep, thus clay brickwork can expand or 'grow' after the initial elastic compression. Thus in the long term, there may be no net losses in the post-tensioning force due to creep and moisture movements but, in some cases, a possible effective gain. This increase may cause problems of cracking and local crushing around bearing plates, etc., and should be considered in the design.

The effect of creep should also be considered, as the two effects cannot reasonably be assumed to counteract one another. Figures for moisture and thermal movements in brickwork are given in various Brick Development Association (BDA) publications as well as in Appendix 3 and additional information on the behaviour of the particular type of brick or block should be obtained from the manufacturer.

Concrete brickwork and blockwork do not generally 'grow' with age but rather are more likely to shrink fairly rapidly. The total shrinkage may not, however, have taken place when the units are built into a post-tensioned wall and the shrinkage which may yet be to follow will constitute losses in the post-tensioning force. Values of anticipated total shrinkage of concrete units are given and discussed in Appendix 3.

Creep for brickwork of (1.5 × the elastic deformation) is given in the Code, and this results in a higher percentage loss found in research and practice of 10–15%. In concrete blockwork the Code recommends (3.0 × elastic deformation). Designers should exercise their judgement in using this value or perhaps 30% less.

(b) Relaxation of post-tensioned steel

The amount of relaxation or creep of steel depends on the quality of the steel, and also the stress level within the steel. Detailed information on this subject is available from specialist manufacturers of various proprietary bars. Figures for the maximum relaxation after 1000 hours duration are given in various British Standards, and these are based on a 70% stress level. However, bars larger than those required for the designed loads are often provided in post-tensioned brickwork to allow for possible corrosion. It is thus less likely that bars will be stressed to their maximum stress levels. The losses due to relaxation may be assumed to decrease from about 8% at the 70% stress level down to 0% at the 50% stress level. An appropriate figure for the losses should be assessed from the above for any particular application, depending on the stress level within the bars.

(c) Elastic deformation of masonry

The instantaneous elastic deformation of the masonry will, for all practical purposes, be taken up during the stressing of the bars and no compensating calculations are necessary for this in the assessment of losses in the post-tensioning force but would be necessary for the similar situation in pre-tensioning work. The amount of this elastic deformation may be determined from an elastic method of analysis with a modular ratio based on Young's modulus for masonry given by the following assumption that:

$$E_m \text{ for } E_b \text{ and } E_m = 0.9 f_k \text{ kN/mm}^2$$

where E_m = modulus of elasticity of masonry.

E_m has been found to vary on site from 0.7 to 1.1 f_k kN/mm^2, and where it is essential for accurate design purposes to determine E_m, then it is advisable to conduct a test on site.

(d) Friction

Frictional losses occur at the stressing stage and will be concerned mainly with tightening down of the bearing plates which transfer the stress from the bars into the masonry. It is recommended that a torque wrench be used when tightening down the nuts. The manufacturers of such wrenches are generally able to advise on the reduction for any friction losses, and it is usually unnecessary to make a specific allowance in the calculation of post-tensioning forces. It should be noted, however, that the information provided by the torque wrench manufacturer will relate to certain specific conditions prevailing when the torque is applied. Such conditions are likely to include the type of thread and the lubrication quality, i.e. lightly oiled, of the thread on both the rod and the nut, as well as the surface condition of the spreader plate against which the nut is turned. It is vital that these conditions are provided and, during the construction of the wall, adequate protection of the threads must be maintained to ensure this. Similar guidance may be obtained from practising hydraulic jack manufacturers.

15.8.7 Bearing Stresses

The post-tension force in the bars is applied to the masonry, generally, by means of steel plates bearing on the top of the wall. The compressive force, applied locally at these points, then disperses into the remainder of the element. The relatively high local bearing stresses should thus be checked to ensure that the loading is applied over a sufficiently large area to avoid local over-stressing. This may be calculated by the methods given in Chapter 10, which relate to BS 5628, Part 1, clause 34, for the ultimate limit state.

15.8.8 Deflection

In general, post-tensioned masonry should comply with the slenderness ratio requirements for plain masonry, and this should limit deflections to acceptable values. Deflections may, however, need to be considered in more detail in the case of cantilevered walls, and also where the post-tensioning force is applied eccentrically. In such cases, an elastic analysis should be undertaken to determine the deflection at working load to be compared with acceptable values based on particular requirements for each application.

15.8.9 Partial Safety Factor on Post-tensioning Force

The partial safety factor for loads, γ_f, is applicable, to some degree, to the post-tensioning force. The values given in BS 5628 for γ_f have been determined statistically for dead, superimposed and wind loadings. No research has been carried out to determine, statistically, the appropriate γ_f values for the post-tensioning operation and an assessment of the likely variable factors must be made by the designer in order to arrive at a reasonable combination of extreme values. In the absence of any other values it is proposed that the values already determined for dead loadings should be used for application to post-tensioning force calculations.

15.9 Example 5: High Cavity Wall with Wind Loading

The 225 mm thick cavity wall shown in Figure 15.45 is to be constructed in two leaves of brickwork comprising bricks with a minimum compressive strength of 20 N/mm^2 and a water absorption of 9% set in a designation (ii) mortar. The partial safety factor for material will be taken as 2.0; the characteristic wind load will be taken as 0.9 kN/m^2 and the characteristic wind uplift will be taken as 1.0 kN/m^2. There are no internal walls offering support to the external wall. The density of the masonry will be taken as 19.0 kN/m^3 and the characteristic superimposed roof load will be taken as 0.75 kN/m^2. The plain cavity wall can be shown, by calculation, using the design principles given in Chapter 11, to be unstable, hence, post-tensioning will be introduced to provide the additional strength required.

Stresses should be checked for the following conditions:

(a) After losses (or gains)

These may occur in the post-tensioning force due to the factors discussed in section 15.8.6:

- *flexural tensile stresses*: with the wall subject to dead plus wind loading only (this condition also determines the magnitude of the post-tensioning force required).
- *flexural compressive and axial compressive stresses*: with the wall subject to the various combinations of dead plus superimposed, dead plus wind, and dead plus superimposed plus wind loadings.

(b) Before losses

- *axial compressive stresses*: with the wall subject to dead plus superimposed loads only. In this situation, where wind loading may be applied as both suction and pressure, the post-tensioning force will be applied concentrically on the wall. It will be assumed that the post-tensioning force will not be applied until the masonry has achieved its characteristic strength. If the force should be applied before fourteen days, allowance must be made in the calculations for the strength available for a particular loading situation and in the assessment of any additional losses which may be expected as a result.



Figure 15.45 Typical section

For each of the above loading situations, the dead loading should be considered as comprising both the dead loading of the wall and roof slab together with the applied post-tensioning force.

The most economical design for the wall would utilise the roof slab as a prop to the head of the wall and the upper anchorage of the post-tensioning rod will be made through a spreader plate placed on top of the roof slab as shown in Figure 15.46.

This detail would have the added advantage of ensuring that the post-tensioning force was shared equally between the two leaves of the wall and the stiffness of the slab may be assumed to place the force into each leaf with zero eccentricity. High-yield steel rods will be used for the post-tensioning.

15.9.1 Capacity Reduction Factor, β

The wall is, for the major part of its life, subject to axial loading (dead plus post-tensioning plus superimposed) only, and only intermittently is it subject also to the lateral wind loadings which generally dictate the most onerous design cases. Hence, the effect of buckling under axial loading must be considered and is based on the capacity reduction factor, β, as derived from the slenderness ratio of the wall and the eccentricity of the loading.

$$\text{Slenderness ratio} = \frac{\text{effective height}}{\text{effective thickness}}$$

$$= \frac{0.75 \times 3600}{{}^{2}/_{3}\,(102.5 + 102.5)}$$

$$\text{SR} = 19.9$$

Eccentricity of load, e_x = 0 to 0.05t as previously stated, although consideration should be given to the possibility of eccentricity of the dead and superimposed roof loads which may result from rotation of the slab at the bearing due to its deflection at mid-span. The net eccentricity for this example will be assumed to lie within 0 and 0.05t for each leaf. Hence, capacity reduction factor, β = 0.70 (from BS 5628, Part 1, Table 7 – see Table 5.15).

For solid and cavity walls the capacity reduction is applicable only to the axial compressive stresses, whereas for geometric wall profiles, such as the fin or diaphragm wall, the capacity reduction factor is applicable to both axial compressive and flexural compressive stresses (as discussed in section 15.8.3) as was the case for the design of plain fin and diaphragm walls covered in Chapter 13.



Figure 15.46 Detail at top of wall Example 5

15.9.2 Characteristic Strengths

Masonry

Characteristic compressive strength, $f_k = 6.4\ \text{N/mm}^2$

Characteristic flexural compressive strength, $f_{kx} = 1.25 \times 6.4 = 8.0\ \text{N/mm}^2$

Characteristic flexural tensile strength = limited to zero

Steel

Characteristic tensile strength, $f_y = 460\ \text{N/mm}^2$

15.9.3 Design Strengths (after Losses)

$$\text{Design compressive strength (at base)} = \frac{1.15 f_k}{\gamma_{mm}}$$

(1.15 narrow wall factor)

$$= 1.15 \times \frac{6.4}{2.0}$$

$$= 3.68\ \text{N/mm}^2$$

Design compressive strength (in wall height)

$$= \frac{1.15 \beta f_k}{\gamma_{mm}}$$

$$= 1.15 \times \frac{0.70 \times 6.4}{2.0} = 2.58\ \text{N/mm}^2$$

$$\text{Design flexural compressive strength} = \frac{1.15 f_{kx}}{\gamma_{mm}}$$

$$= 1.15 \times \frac{8.0}{2.0}$$

$$= 4.60\ \text{N/mm}^2$$

Design flexural tensile strength = limited to zero

15.9.4 Section Modulus of Wall

For a cavity wall, tied with vertical twist type wall ties in accordance with BS 5628, the section modulus of the wall may be taken as the sum of the section moduli of the individual leaves.

Hence

$$Z = \frac{2 \times 1000 \times 102.5^2}{6} = 3.47 \times 10^6\ \text{mm}^3$$

15.9.5 Design Method

The design method adopted for this example is to calculate the theoretical flexural tensile stress which would be likely to develop as a result of the lateral loading and in the absence of any post-tensioning force. An axial compressive stress is then applied by way of the post-tensioning force and in addition to the existing axial stress from the minimum vertical loading, to eliminate the theoretical flexural tensile stress previously calculated. Checks are then carried out to establish that the wall specified can support the applied vertical and lateral loading as well as the post-tensioned force for the various design conditions prevailing.

15.9.6 Calculation of Required Post-tensioning Force

The wall will be considered to act as a propped cantilever in that the post-tensioning force will be calculated to ensure that the wall section at its base does not 'crack' (tensile stresses are limited to zero) and the bending moment diagram for the wall is as shown in Figure 15.47.



Figure 15.47 Bending moment diagram in wall under wind load Example 5

For the loading condition dead plus wind only, the applicable partial safety factors for dead and wind loads are 0.9 and 1.4 respectively. Hence, the design bending moments are calculated as:

$$\text{at base level, } M_b = \frac{\gamma_f W_k h^2}{8}$$

$$= \frac{1.4 \times 0.9 \times 3.6^2}{8} = 2.0\ \text{kN m}$$

$$\text{at } {}^3/_8 h \text{ level, } M_w = \frac{9 \gamma_f W_k h^2}{128}$$

$$= \frac{9 \times 1.4 \times 0.9 \times 3.6^2}{128} = 1.15\ \text{kN m}$$

Characteristic Dead Load, G_k

roof slabs	$= 0.15 \times 24 \times 2$	$= 7.20\ \text{kN/m}$
roof finishes		$= 5.00\ \text{kN/m}$
ow wall	$= 2 \times 0.102 \times 19 \times 3.6 = 13.95\ \text{kN/m}$	
		$= 26.15\ \text{kN/m}$

$$\text{At } {}^3/_8 h \text{ level, } G_k = 7.2 + 5.0 + \left(13.95 \times \frac{3}{8}\right)$$

$$= 17.43\ \text{kN/m}$$

Characteristic Wind Uplift

$$= 1.0 \times \frac{4}{2} = 2.0\ \text{kN/m}$$

Net Design Dead Load

$$(\gamma_f \times G_k) - (\gamma_f \times \text{wind uplift}) = (0.9 \times 26.15) - (1.4 \times 2.0)$$
$$= 20.74\ \text{kN/m}$$

The design dead load will be considered to be shared equally by the two leaves of the cavity wall hence, the axial compressive stress due to the design dead load:

$$g_d = \frac{20.74 \times 10^3}{2 \times 102 \times 1000} = 0.10\ \text{N/mm}^2$$

Theoretical flexural tensile stress (in the absence of the application of the post-tension force) equals:

$$g_d - \frac{M_A}{Z}$$

where

M_A = design bending moment per leaf
Z = section modulus per leaf
g_d = axial compressive stress from dead-wind uplift.

$$\text{Theoretical flexural tensile stress} = 0.10 - \frac{2.0 \times 10^6 \times 0.5}{3.47 \times 10^6 \times 0.5}$$

$$= -0.48 \text{ N/mm}^2$$

Hence, a design post-tensioning stress of +0.48 N/mm^2 should be provided to eliminate this theoretical flexural tensile stress and these processes are shown in Figure 15.48, in which all the stresses are shown in N/mm^2.

In order to achieve a minimum design post-tensioning stress of 0.48 N/mm^2, a characteristic post-tensioning stress of $0.48/\gamma_f$ should be provided by the post-tensioning force in the rods, where γ_f would be taken as 0.9 as discussed in section 15.8.9. Hence, the characteristic post-tensioning stress = 0.48/0.9 = 0.53 N/mm^2.

The spacing of the post-tensioning rods, the force required per rod, the torque required to produce that force and the local bearing stresses will be considered later in this example. The next stage of the design process is to consider the effect of these compressive stresses on the wall section provided to ensure that stability is maintained.

15.9.7 Consider Compressive Stresses: After Losses

Owing to the variations in the factors for partial safety on loading, it is not immediately obvious which combination of loading (dead plus superimposed, dead plus wind, dead plus superimposed plus wind) may produce the most onerous design condition. The three loading cases stated above should therefore be considered individually taking account of the capacity reduction factor, β, where applicable.



Figure 15.48 Stresses under loading conditions Example 5

Case (a) Dead Plus Superimposed

$$\text{Design axial stress, } f_{uac} = \left[\frac{(\gamma_f G_k) + (\gamma_f Q_k)}{\text{area}}\right] + \text{post-tensioning stress}$$

where

G_k = characteristic dead load = 26.15 kN/m
Q_k = characteristic superimposed load
γ_f = partial safety factors for loads; for this loading combination γ_f = 1.4 and 1.6 for G_k and Q_k respectively.

Hence

$$f_{uac} = \frac{(1.4 \times G_k) + (1.6 \times Q_k)}{2 \times 102.5 \times 1000} + \text{post-tensioning stress}$$

$$= \frac{(1.4 \times 26.15) + (1.6 \times 0.75 \times 2)}{2 \times 102.5 \times 1000} + (\gamma_f \times \text{characteristic post-tensioning stress})$$

$$= 0.191 + (1.4 \times 0.53)$$
$$= 0.933 \text{ N/mm}^2$$

in which the partial safety factor for loads of 1.4 has been applied to the characteristic post-tensioning stress of 0.53 N/mm^2 calculated earlier to give the design post-tensioning stress for this situation.

$$\text{Design strength in span of wall} = \frac{1.15\beta f_k}{\gamma_{mm}} = \frac{1.15 \times 0.70 \times 6.4}{2.0}$$

$$= 2.58 \text{ N/mm}^2$$

As the design strength of 2.58 N/mm^2 exceeds the design axial stress of 0.933 N/mm^2, the wall is acceptable for this loading condition.

Case (b) Dead Plus Wind

Design axial stress, f_{uac}, at base level

$$= \left(\frac{\text{design dead load} - \text{design wind uplift}}{\text{area}}\right) + \text{post-tensioning stress}$$

$$= \left[\frac{(\gamma_f G_k) - (\gamma_f \times \text{wind uplift})}{\text{area}}\right] + (\gamma_f \times 0.53)$$

$$= \left[\frac{(1.4 \times 26.15) - (1.4 \times 2.0)}{2 \times 102.5 \times 1000}\right] + (1.4 \times 0.53)$$

$$= 0.166 + 0.742$$
$$= 0.908 \text{ N/mm}^2$$

Design axial stress, f_{uac}, at $^3/_8h$ level

$$= \left[\frac{(1.4 \times 17.43) - (1.4 \times 2.0)}{2 \times 102.5 \times 1000}\right] + (1.4 \times 0.53)$$

$$= 0.106 + 0.742$$

$$= 0.848 \text{ N/mm}^2$$

$$\frac{f_{uac}}{\beta} = \frac{0.848}{0.70} = 1.211 \text{ N/mm}^2$$

The lateral wind loading produces the design bending moments shown in Figure 15.47. Design flexural stress, $f_{ubc} = \pm M_A/Z$ (compressive and tensile).

Combined design stress =

(i) at base level = $f_{uac} + f_{ubc}$

(ii) at $^3/_8h$ level = $\left(\frac{f_{uac}}{\beta}\right) + f_{ubc}$

(i) At base level

$$f_{ubc} = \pm\frac{2.0 \times 10^6}{3.47 \times 10^6} = \pm 0.6 \text{ N/mm}^2$$

$$\text{Combined design stress} = 0.908 \pm 0.6$$

$$= +1.508 \text{ N/mm}^2$$

$$\text{or } +0.308 \text{ N/mm}^2$$

(ii) At $^3/_8h$ level

$$f_{ubc} = \pm\frac{1.15 \times 10^6}{3.47 \times 10^6} = \pm 0.33 \text{ N/mm}^2$$

$$\text{Combined design stress} = \frac{0.848}{0.7} \pm 0.33$$

$$= +1.541 \text{ N/mm}^2$$

$$\text{or } +0.881 \text{ N/mm}^2$$

The stress diagrams for this loading situation at the critical levels considered are shown in Figure 15.49 (all stresses are shown in N/mm^2).

$$\text{Design strength of wall} = \frac{1.15 \times 1.25 f_k}{\gamma_{mm}}$$

$$= \frac{1.15 \times 1.25 \times 6.4}{2.0}$$

$$= 4.60 \text{ N/mm}^2$$

The design strength exceeds the combined design stresses hence, the wall is acceptable for this loading condition.

Case (c) Dead plus Superimposed plus Wind

Design axial stress, f_{uac} at base level

$$= \left[\frac{(\gamma_f G_k) - (\gamma_f \times \text{wind uplift}) + (\gamma_f Q_k)}{\text{area}}\right]$$

$$+ \text{post-tensioning stress}$$

$$= \left[\frac{(1.2 \times 26.15) - (1.2 \times 2.0) + (1.2 \times 1.5)}{2 \times 102.5 \times 1000}\right] + (\gamma_f \times 0.53)$$

$$= 0.151 + (1.2 \times 0.53)$$

$$= 0.787 \text{ N/mm}^2$$



Figure 15.49 Stresses under dead plus wind load Example 5

Design axial stress, f_{uac}, at $^3/_8h$ level

$$= \left[\frac{(1.2 \times 17.43) - (1.2 \times 2.0) + (1.2 \times 1.5)}{2 \times 102.5 \times 1000}\right]$$

$$+ (1.2 \times 0.53)$$

$$= 0.099 + 0.636$$

$$= 0.735 \text{ N/mm}^2$$

$$\frac{f_{uac}}{\beta} = \frac{0.735}{0.70} = 1.05 \text{ N/mm}^2$$

$$\text{Design } M_b \text{ at base level} = \frac{\gamma_f W_k h^2}{8} = \frac{1.2 \times 0.9 \times 3.6^2}{8}$$

$$= 1.75 \text{ kN m}$$

$$\text{Design } M_w \text{ at } ^3/_8h \text{ level} = \frac{9\gamma_f W_k h^2}{128} = \frac{9 \times 1.2 \times 0.9 \times 3.6^2}{128}$$

$$= 0.98 \text{ kN m}$$

(i) At base level

$$f_{ubc} = \pm\frac{1.75 \times 10^6}{3.47 \times 10^6} = \pm 0.5 \text{ N/mm}^2$$

$$\text{Combined design stress} = 0.787 \pm 0.5$$

$$= +1.287 \text{ N/mm}^2$$

$$\text{or } +0.287 \text{ N/mm}^2$$

(ii) At $^3/_8h$ level

$$f_{ubc} = \pm\frac{0.98 \times 10^6}{3.47 \times 10^6} = \pm 0.282 \text{ N/mm}^2$$



Figure 15.50 Stresses under dead plus superimposed plus wind Example 5

$$\text{Combined design stress} = \frac{0.735}{0.70} \pm 0.282$$

$$= +1.332 \text{ N/mm}^2$$

$$\text{or } +0.768 \text{ N/mm}^2$$

The stress diagrams for this loading situation at the critical levels considered are shown in Figure 15.50.

The design strength of 4.60 N/mm^2 calculated earlier again exceeds the combined design stresses and the wall is acceptable for this loading condition.

15.9.8 Consider Compressive Stresses: Before Losses

Dead plus superimposed load only will be considered.

$$\text{Design axial stress, } f_{uac} = \left[\frac{(1.4G_k) + (1.6Q_k)}{\text{area}}\right]$$

$$+ \text{ post-tensioning stress before losses}$$

The design post-tensioning stress will be increased by 20% in anticipation of that amount of loss, hence:

$$f_{uac} = \left[\frac{(1.4 \times 26.15) + (1.6 \times 1.5)}{2 \times 102.5 \times 1000}\right] + \frac{1.4 \times 0.53}{0.8}$$

$$= 0.191 + 0.927$$

$$= 1.118 \text{ N/mm}^2$$

$$\text{Design strength of wall before losses} = \frac{1.20\beta(1.15f_{ki})}{\gamma_{mm}}$$

where f_{ki} is the characteristic compressive strength of the masonry at the age at which the post-tensioning is applied.

In this example it will be assumed to have achieved its full characteristic strength, i.e. f_k (based upon the 28-day test). Hence

$$\text{Design strength before losses} = \frac{1.20\beta(1.15f_{ki})}{\gamma_{mm}}$$

$$= \frac{1.20 \times 0.70 \times 1.15 \times 6.4}{2.0}$$

$$= 3.09 \text{ N/mm}^2$$

The design strength before losses exceeds the design axial stress, hence the wall is acceptable for this loading condition.

15.9.9 Design of Post-tensioning Rods

The characteristic post-tensioning stress required, to be provided in the brickwork by the post-tensioning rods, is 0.53 N/mm^2.

This is the equivalent of $0.53 \times 2 \times 102.5 \times 1000 = 108$ kN per m run of wall. To allow for 20% losses in the post-tensioning force, the initial equivalent load = 108/0.8 = 135 kN per m run.

In order to limit relaxation of the steel and hence minimise the losses, the stress in the post-tensioning rods is limited to

$$\frac{0.7f_y}{\gamma_{mm}} = \frac{0.7 \times 460}{1.15} = 280 \text{ N/mm}^2$$

$$\text{Steel area required per m} = \frac{135 \times 10^3}{280}$$

$$= 480 \text{ mm}^2 \text{ per m run}$$

High yield bars of 25 mm diameter placed at 900 mm centres (which provide an area of 546 mm^2 per m) will be used.

Torque to Provide Rod Tension

Considerable variation exists in the recommendations, given by manufacturers and suppliers of torquing equipment, for the calculation of torque requirements.

The amount of tension induced by a particular torque is dependent on numerous factors, the two most significant being the pitch and type of the thread and the coefficients of friction between the contact surfaces of nuts, bolts and spreader plates, etc. This latter aspect is largely dependent on the type and quality of the original finish to these components and the degree of lubrication and general protection during the construction of the works prior to the post-tensioning.

The calculation provided below is based on a general engineering formula derived from test research and utilises lightly oiled, metric threads with self-finish nuts and bolts and a hardened washer between the nut and the spreader plate.

$$\text{Torque required} = \frac{\text{bolt tension} \times \text{bolt diameter}}{5}$$

$$\text{Bolt tension (in kgf)} = \frac{135 \times 10^3}{9.81} \text{ per m run of wall}$$

$$= \frac{135 \times 0.9 \times 10^3}{9.81} \text{ per rod at 900 centres}$$

$$= 12\,385 \text{ kgf per rod}$$

$$\text{Torque required} = \frac{12\,385 \times 0.025}{5}$$

$$= 61.9 \text{ kgf m}$$

Spreader Plate Design

$$\text{Maximum design force per rod} = 135 \times \gamma_f$$
$$= 135 \times 1.4$$
$$= 189 \text{ kN}$$

$$\text{Design compressive strength of wall} = \frac{1.5 \times 1.15 \times 6.4}{2.0}$$

$$= 5.52 \text{ N/mm}^2$$

in which a 1.5 strength increase factor has been incorporated to take account of the local bearing condition of the spreader plate on the brickwork.

$$\text{Area of spread required} = \frac{189 \times 10^3}{5.52}$$

$$= 34\,239 \text{ mm}^2$$

$$\text{Length of spread along two leaves} = \frac{34\,239}{2 \times 102}$$

$$= 168 \text{ mm}$$

Allowing for a 45° dispersion of load from the spreader plate through the rc slab, as shown in Figure 15.51, a 150 mm long × 100 mm wide × 12 mm thick spreader plate would be suitable.



Figure 15.51 Spreader plate

15.10 Example 6: Post-tensioned Fin Wall

A warehouse measuring 27 m × 46 m on plan and 10 m high, as shown in Figure 15.52, is to be constructed in load-bearing brickwork using fin wall construction for its main vertical structure. The planning requirements are for the fins to be as small as possible, hence post-tensioning of the fins is proposed to provide for this requirement. The wall panels between fins will be of normal 255 mm (min) cavity construction and there are no internal walls within the building. The roof construction and detailing will be assumed to provide an adequate prop to the head of the wall and will similarly ensure stability of the structure by transferring this propping force to the gable shear walls. The type of brick to be used throughout will have a compressive strength of 30 N/mm^2 and a water absorption of 10%. The partial safety factor for materials may be assumed as 2.3. The fin profile to be used is reference 'E' from Table 13.1 and the various dimensions and properties may be obtained from that table and Figure 15.52.

15.10.1 Design Procedure

The design procedure is similar to that used for the previous example but consideration must be given to the fin profile being asymmetrical. The post-tensioning force was positioned concentrically in the previous example because the section is symmetrical and the wind loading (suction and pressure) in each direction could be assumed to be of a similar magnitude. For the asymmetrical fin wall profile, with similar wind loading, the stresses at the extreme edges



Figure 15.52 Layout for Example 6

of the fin and flange would differ considerably owing to the two values of section modulus Z_1 and Z_2. Hence, the post-tensioning force is applied eccentrically, in this situation, to make the maximum use of the eliminating compressive stress at each of the extreme edges.

Figures 15.53 and 15.54 show the theoretical stresses which may occur in the wall, in the absence of the post-tensioning force, for wind suction and wind pressure loadings respectively. For each direction of wind loading, a theoretical flexural tensile stress may be calculated, for the extreme edges of either fin or flange and at either base level or at maximum span moment level, as applicable.

Having established the maximum theoretical flexural tensile stress at each of the extreme edges, an eccentric post-tensioning force may be calculated to eliminate these stresses. The basic theory of this process is indicated in Figure 15.55 in which f_{t1} and f_{t2} are the maximum theoretical flexural tensile stresses at the extreme edges of the fin and flange respectively.

In Figure 15.55,

P = design post-tensioning force
A = area of effective fin section (from Table 13.41)
e = eccentricity of P about neutral axis (NA)
Z_1 = minimum section modulus (from Table 13.41)
Z_2 = maximum section modulus (from Table 13.41).

The design should then proceed to check that the compressive (combined axial and flexural) stresses which result are acceptable in the same manner as for the previous example.

15.10.2 Design Post-tensioning Force and Eccentricity

Figure 15.55 represents the design post-tensioning force as P and its eccentricity, about the neutral axis (NA) of the



Figure 15.53 Theoretical stresses under wind suction



Figure 15.54 Theoretical stresses under positive wind load



Figure 15.55 Application of eccentric post-tensioning force

section, as e. The stresses at each of the extreme edges may be expressed as:

$$f_{t1} = \frac{P}{A} + \frac{Pe}{Z_1} \tag{15.6}$$

and

$$f_{t2} = \frac{P}{A} - \frac{Pe}{Z_2} \tag{15.7}$$

A pair of simultaneous equations may be written from equations (15.6) and (15.7) to solve for P and e as follows:

Multiply (15.6) throughout by Z_1 and (15.7) throughout by Z_2 giving:

$$f_{t1}Z_1 = \frac{PZ_1}{A} + Pe \tag{15.8}$$

$$f_{t2}Z_2 = \frac{PZ_2}{A} - Pe \tag{15.9}$$

adding (15.8) to (15.9) gives:

$$(f_{t1}Z_1) + (f_{t2}Z_2) = \frac{P}{A}(Z_1 + Z_2)$$

Hence

$$P = \frac{[(f_{t1}Z_1) + (f_{t2}Z_2)]A}{Z_1 + Z_2} \tag{15.10}$$

The value of P calculated in equation (15.10) can now be substituted into equation (15.7) to calculate the value of e.

Equation (15.7) transposed gives:

$$e = \left(\frac{P}{A} - f_{t2}\right)\frac{Z_2}{P} = \left(\frac{1}{A} - \frac{f_{t2}}{P}\right)Z_2 \tag{15.11}$$

15.10.3 Characteristic Strengths

For the materials given in Example 15.6, the following properties may be obtained from BS 5628.

Masonry

Characteristic compressive strength, $f_k = 7.6\ \text{N/mm}^2$

Characteristic flexural tensile strength (failure plane parallel to bed joints) $= 0.4\ \text{N/mm}^2$

Characteristic flexural tensile strength (failure plane perpendicular to bed joints) $= 1.1\ \text{N/mm}^2$

Characteristic flexural compressive strength, $1.25f_k = 9.5\ \text{N/mm}^2$

Steel

Characteristic tensile strength, $f_y = 460\ \text{N/mm}^2$

15.10.4 Loadings

The following data will be assumed to have been provided for the calculation of the design loadings:

(a) Wind loads

Dynamic wind pressure, q $= 0.74\ \text{kN/m}^2$
Characteristic wind loads:
suction on leeward face, W_{k1} $= 0.56\ \text{kN/m}^2$
pressure on windward face, $W_{k2} = 0.81\ \text{kN/m}^2$
gross wind uplift on roof, W_{k3} $= 0.39\ \text{kN/m}^2$

(b) Dead and superimposed loads

Characteristic superimposed load, $Q_k = 0.75\ \text{kN/m}^2$
Characteristic dead load, G_k $= 0.60\ \text{kN/m}^2$

The wall panel is assumed to have been checked as being adequate to span horizontally between fins spaced at 3.80 m centres.

For the loading combination, dead plus wind, the partial safety factors for loads may be taken as 0.9 and 1.4 or 1.4 and 1.4 for dead and wind loads respectively.

Design wind loads per fin

Case (1) suction

Design wind load $= 3.8 \times 1.4 \times 0.56$
$= 2.98\ \text{kN/m}$ height of fin wall

Case (2) pressure

Design wind load $= 3.8 \times 1.4 \times 0.81$
$= 4.31\ \text{kN/m}$ height of fin wall

Case (3) uplift

Design wind load $= 1.4 \times 0.39$
$= 0.55\ \text{kN/m}^2$

Dead load – roof uplift $= (0.9 \times 0.6) - (1.4 \times 0.39)$
$= 0.54 - 0.55$
$=$ zero (say)

Hence, only the own weight of the masonry can be considered in providing resistance to the flexural tensile stresses.



Figure 15.56 Bending moment diagram

15.10.5 Design Bending Moments

The wall will be designed, taking advantage of the prop provided by the roof plate, as a propped cantilever. Unlike the plain fin wall, there should not normally be any requirement to adjust the bending moment diagram from the propped cantilever proportions as the post-tensioning force can be made sufficiently large to avoid this. The design bending moment diagram is as shown in Figure 15.56. Hence, the design bending moments are:

Case (1) suction

(a) At $^3/_8h$ level, $M_w = \dfrac{9 \times 2.98 \times 10^2}{128} = 21 \text{ kN m}$

(b) At base level, $M_b = \dfrac{2.98 \times 10^2}{8} = 37.3 \text{ kN m}$

Case (2) pressure

(a) At $^3/_8h$ level, $M_w = \dfrac{9 \times 4.31 \times 10^2}{128} = 30.3 \text{ kN m}$

(b) At base level, $M_b = \dfrac{4.31 \times 10^2}{8} = 53.9 \text{ kN m}$

15.10.6 Theoretical Flexural Tensile Stresses

Case (2) suction

(a) At $^3/_8h$ level:

Axial compressive stress due to ow

$$= \frac{0.9 \times 19 \times 3.75}{1000} = +0.064 \text{ N/mm}^2$$

Theoretical flexural stresses, $\pm \dfrac{M_w}{Z_1}$

$$= \pm \frac{21 \times 10^6}{0.061 \times 10^9} \quad = \pm 0.344 \text{ N/mm}^2$$

Theoretical flexural tensile stress $= -0.280 \text{ N/mm}^2$

(b) At base level:

Axial compressive stress due to ow

$$= \frac{0.9 \times 19 \times 10}{1000} = +0.171 \text{ N/mm}^2$$

Theoretical flexural stresses, $\pm \dfrac{M_b}{Z_2}$

$$= \frac{37.3 \times 10^6}{0.12 \times 10^9} \quad = \pm 0.310 \text{ N/mm}^2$$

Theoretical flexural tensile stress $= -0.139 \text{ N/mm}^2$

Case (3) pressure

(a) At $^3/_8h$ level:

Axial compressive stress due to ow

$$= \text{as case (1)} \quad = +0.064 \text{ N/mm}^2$$

Theoretical flexural stresses, $\pm \dfrac{M_w}{Z_2}$

$$= \pm \frac{30.3 \times 10^6}{0.12 \times 10^9} = \pm 0.253 \text{ N/mm}^2$$

Theoretical flexural tensile stress $= -0.189 \text{ N/mm}^2$

(b) At base level:

Axial compressive stress due to ow

$$= \text{as case (1)} \quad = +0.171 \text{ N/mm}^2$$

Theoretical flexural stresses, $\pm \dfrac{M_b}{Z_1}$

$$= \pm \frac{53.9 \times 10^6}{0.061 \times 10^9} = \pm 0.884 \text{ N/mm}^2$$

Theoretical flexural tensile stress $= -0.713 \text{ N/mm}^2$

By inspection of these theoretical flexural tensile stresses, cases (2b) and (2a) give the most onerous values of f_{t1} and f_{t2} respectively for the calculation of the required post-tensioning force and its eccentricity, i.e.

$$f_{t1} = 0.713 \text{ N/mm}^2$$
and $$f_{t2} = 0.189 \text{ N/mm}^2$$

15.10.7 Calculations of P and e

From section 15.10.2, equation (15.10),

$$P = \frac{[(f_{t1}Z_1) + (f_{t2}Z_2)]A}{Z_1 + Z_2}$$

From section 15.10.2, equation (15.11)

$$e = \left(\frac{1}{A} - \frac{f_{t2}}{P}\right) Z_2$$

where

$f_{t1} = 0.713 \text{ N/mm}^2$
$f_{t2} = 0.189 \text{ N/mm}^2$
$A = 0.46 \times 10^6 \text{ mm}^2$ (from Table 13.1)
$Z_1 = 0.061 \times 10^9 \text{ mm}^3$ (from Table 13.1)
$Z_2 = 0.12 \times 10^9 \text{ mm}^3$ (from Table 13.1).



Figure 15.57 Effective fin section Example 6

Hence

$$P = 168 \text{ kN} \quad \text{and} \quad e = 124 \text{ mm}$$

15.10.8 Spread of Post-tensioning Force

The area, A, used in the above equations for the calculations of P and e is the effective area of the effective fin section, which is based on a flange width of 1971 mm. The spacing of the fins for this example is 3800 mm leaving a central length of wall, 1829 mm long, which was not taken into account in calculating P and e. The effective fin section is shown in Figure 15.57.

It may be argued that the effect of the post-tensioning force will spread into this central, 1829 mm long, area and therefore account of it should be included in the calculation of P and e. However, whatever effect P may have on this central area should be compensated for by a larger effective section giving higher section moduli, Z_1 and Z_2. In the absence of any research work to investigate this phenomenon it is considered that a reasonable and safe solution would be provided by considering the post-tensioning force to be effective over the area of the effective section only.

15.10.9 Characteristic Post-tensioning Force P_k

In order to achieve a minimum design post-tensioning force of 168 kN, a characteristic post-tensioning force of $168/\gamma_f$ should be provided in the rods, where γ_f would be taken as 0.9 as discussed in section 15.8.9.

Hence, characteristic post-tensioning force, $P_k = 168/0.9 = 187$ kN.

This force is now used to check the design compressive stresses in the wall and to establish the size of the post-tensioning rods.

15.10.10 Capacity Reduction Factors, β

At the base of the wall it will be assumed that a raft foundation has been provided which is able to provide full buckling restraint to both the fin and the flange depending upon the particular direction of wind loading. It may be noted that a more robust raft foundation may be necessary for the post-tensioned fin wall than for the same section of plain fin wall.

In Wall Span

The calculation of the relevant capacity reduction factors follows the same design basis as was used for the plain fin wall design example given in Chapter 13.

Case (1) suction

(maximum combined compressive stress in flange:)

$$\text{Slenderness ratio, SR} = \frac{2 \times \text{outstanding length of flange}}{\text{effective cavity wall thickness}}$$

$$= \frac{2 \times 822}{{}^{2}/_{3}(2 \times 102.5)}$$

$$= 12$$

The eccentricity of the compressive stress in the flange of the fin wall may be taken to be 0 to $0.05t$, hence $\beta = 0.93$.

Case (2) pressure

(maximum combined compressive stress at end of fin:)

Slenderness ratio, SR

$$= \frac{\text{distance between points of contraflexure}}{\text{actual thickness of fin}}$$

$$= \frac{7500}{327}$$

$$= 23$$

The eccentricity of this compressive stress may again be taken as 0 to $0.05t$, hence, $\beta = 0.58$.

15.10.11 Check Combined Compressive Stresses

The critical loading condition will be either case (a) dead plus wind (where the partial factors of safety for loads are $1.4G_k$ and $1.4W_k$) or case (b) dead plus superimposed plus wind (where the partial safety factors for loads are $1.2G_k$, $1.2Q_k$ and $1.2W_k$).

Characteristic Vertical Loads in Fin

Case (a) dead plus wind

Roof wind uplift cancels out roof dead load hence, only own weight of brickwork applicable for this loading case.

G_k, at $^3/_8h$ level $= 9.19 \times 3.75 = 34.46$ kN

G_k, at base level $= 9.19 \times 10.0 = 91.90$ kN

Case (b) dead plus superimposed plus wind

$$Q_k = 0.75 \times 3.8 \times \frac{27}{2} = 38.48 \text{ kN}$$

G_k, at $^3/_8h$ level = as case (a) $= 34.46$ kN

G_k, at base level = as case (a) $= 91.90$ kN

Characteristic Wind Loads per Fin

Case (1) suction $= 3.8 \times 0.56 = 2.128$ kN/m of height
Case (2) pressure $= 3.8 \times 0.81 = 3.078$ kN/m of height

Design Bending Moments

Case (a) dead plus wind ($1.4W_k$)

Case (1) suction:

$$M_w, \text{ at } {}^3/_8h \text{ level} = \frac{9\gamma_f W_k h^2}{128}$$

$$= \frac{9 \times 1.4 \times 2.128 \times 10^2}{128}$$

$$= 20.95 \text{ kN m}$$

$$M_b, \text{ at base level} = \frac{9\gamma_f W_k h^2}{8}$$

$$= \frac{1.4 \times 2.128 \times 10^2}{8}$$

$$= 37.24 \text{ kN m}$$

Case (2) pressure:

$$M_w, \text{ at } {}^3/_8h \text{ level} = \frac{9\gamma_f W_k h^2}{128}$$

$$= \frac{9 \times 1.4 \times 3.078 \times 10^2}{128}$$

$$= 30.30 \text{ kN m}$$

$$M_b, \text{ at base level} = \frac{\gamma_f W_k h^2}{8}$$

$$= \frac{1.4 \times 3.078 \times 10^2}{8}$$

$$= 53.86 \text{ kN m}$$

Case (b) dead plus superimposed plus wind ($1.2W_k$)

Case (1) suction:

$$M_w, \text{ at } {}^3/_8h \text{ level} = 20.95 \times \frac{1.2}{1.4} = 17.95 \text{ kN m}$$

$$M_b, \text{ at base level} = 37.24 \times \frac{1.2}{1.4} = 31.9.1 \text{ kN m}$$

Case (2) pressure:

$$M_w, \text{ at } {}^3/_8h \text{ level} = 30.30 \times \frac{1.2}{1.4} = 25.97 \text{ kN m}$$

$$M_b, \text{ at base level} = 53.86 \times \frac{1.2}{1.4} = 46.16 \text{ kN m}$$

Combined Compressive Stresses for Case (1) Suction

Case (a) dead plus wind loading – at base level

Design axial stress due to own weight, $G_k = +\frac{\gamma_f G_k}{A}$

$$= +\frac{1.4 \times 91.9 \times 10^3}{0.46 \times 10^6} \qquad = +0.280 \text{ N/mm}^2$$

Design axial stress due to post-tension force, $P_k = +\frac{\gamma_f P_k}{A}$

$$= +\frac{1.4 \times 187 \times 10^3}{0.46 \times 10^6} \qquad = +0.598 \text{ N/mm}^2$$

Design flexural stresses due to post-tensioning force,

$$P_k = +\frac{\gamma_f P_k e}{Z_1}$$

$$= +\frac{1.4 \times 187 \times 10^3 \times 124}{0.061 \times 10^9} = +0.532 \text{ N/mm}^2$$

or $$= -\frac{\gamma_f P_k e}{Z_2}$$

$$= -\frac{1.4 \times 187 \times 10^3 \times 124}{0.12 \times 10^9} = -0.270 \text{ N/mm}^2$$

Design flexural stresses due to applied moment $= +\frac{M_b}{Z_1}$

$$= +\frac{37.24 \times 10^6}{0.061 \times 10^9} \qquad = +0.610 \text{ N/mm}^2$$

or $$= -\frac{M_b}{Z_2}$$

$$= -\frac{37.24 \times 10^6}{0.12 \times 10^9} \qquad = -0.310 \text{ N/mm}^2$$

Hence:

Maximum combined compressive stress $= +2.02$ N/mm^2
Minimum combined compressive stress $= +0.298$ N/mm^2

Case (b) dead plus superimposed plus wind loading – at base level

Design axial stress due to G_k and $Q_k = +\frac{\gamma_f G_k + \gamma_f Q_k}{A}$

$$= +\frac{(1.2 \times 91.9) + (1.2 \times 38.48)}{0.46 \times 10^3} = +0.341 \text{ N/mm}^2$$

Design axial stress due to post-tensioning force, $P_k = +\frac{\gamma_f P_k}{A}$

$$= +\frac{1.2 \times 187 \times 10^3}{0.46 \times 10^6} \qquad = +0.488 \text{ N/mm}^2$$

Design flexural stresses due to post-tensioning force,

$$P_k = +\frac{\gamma_f P_k e}{Z_1}$$

$$= +\frac{1.2 \times 187 \times 10^3 \times 124}{0.061 \times 10^9} \qquad = +0.456 \text{ N/mm}^2$$

or $$= +\frac{\gamma_f P_k e}{Z_2}$$

$$= -\frac{1.2 \times 187 \times 10^3 \times 124}{0.12 \times 10^9} \qquad = -0.232 \text{ N/mm}^2$$

Design flexural stresses due to applied moment $= +\frac{M_b}{Z_1}$

$$= +\frac{31.91 \times 10^6}{0.061 \times 10^9} \qquad = +0.523 \text{ N/mm}^2$$

or $$= -\frac{M_b}{Z_2}$$

$$= -\frac{31.91 \times 10^6}{0.12 \times 10^9} \qquad = -0.266 \text{ N/mm}^2$$

Hence:

Maximum combined compressive stress = +1.808 N/mm^2
Minimum combined compressive stress = +0.331 N/mm^2

Case (a) dead load plus wind loading at 3/sh level

Design axial stress due to own weight, $G_k = +\frac{\gamma_f G_k}{A}$

$$= +\frac{1.4 \times 34.46 \times 10^3}{0.46 \times 10^6} \qquad = +0.105 \text{ N/mm}^2$$

Design axial stress due to post-tension force, $P_k = +\frac{\gamma_f P_k}{A}$

$$= +\frac{1.4 \times 187 \times 10^3}{0.46 \times 10^6} \qquad = +0.598 \text{ N/mm}^2$$

Design flexural stresses due to post-tension force,

$$P_k = +\frac{\gamma_f P_k e}{Z_1}$$

$$= +\frac{1.4 \times 187 \times 10^3 \times 124}{0.061 \times 10^9} = +0.532 \text{ N/mm}^2$$

or $$= -\frac{\gamma_f P_k e}{Z_2}$$

$$= -\frac{1.4 \times 187 \times 10^3 \times 124}{0.12 \times 10^9} = -0.270 \text{ N/mm}^2$$

Design flexural stresses due to applied moment $= -\frac{M_w}{Z_1}$

$$= -\frac{20.95 \times 10^6}{0.061 \times 10^9} \qquad = -0.343 \text{ N/mm}^2$$

or $$= +\frac{M_w}{Z_2}$$

$$= +\frac{20.95 \times 10^6}{0.12 \times 10^9} \qquad = +0.175 \text{ N/mm}^2$$

Hence:

Maximum combined compressive stress = +0.892 N/mm^2
Minimum combined compressive stress = +0.608 N/mm^2

Case (b) dead plus superimposed plus wind loading at 3/sh level

Design axial stress due to G_k and $Q_k = +\frac{\gamma_f G_k + \gamma_f Q_k}{A}$

$$= +\frac{(1.2 \times 34.46) + (1.2 \times 38.48)}{0.46 \times 10^3} = +0.190 \text{ N/mm}^2$$

Design axial stress due to post-tension force $P_k = +\frac{\gamma_f P_k}{A}$

$$= +\frac{1.2 \times 187 \times 10^3}{0.46 \times 10^6} \qquad = +0.488 \text{ N/mm}^2$$

Design flexural stresses due to post-tension force,

$$P_k = +\frac{\gamma_f P_k e}{Z_1}$$

$$= +\frac{1.2 \times 187 \times 10^3 \times 124}{0.061 \times 10^9} \qquad = +0.456 \text{ N/mm}^2$$

or $$= -\frac{\gamma_f P_k e}{Z_2}$$

$$= -\frac{1.2 \times 187 \times 10^3 \times 124}{0.12 \times 10^9} \qquad = -0.232 \text{ N/mm}^2$$

Design flexural stresses due to applied moment $= -\frac{M_w}{Z_1}$

$$= -\frac{17.95 \times 10^6}{0.061 \times 10^9} \qquad = -0.294 \text{ N/mm}^2$$

or $$= +\frac{M_w}{Z_2}$$

$$= +\frac{17.95 \times 10^6}{0.12 \times 10^9} \qquad = +0.150 \text{ N/mm}^2$$

Hence:

Maximum combined compressive stress = +0.840 N/mm^2
Minimum combined compressive stress = +0.596 N/mm^2

Combined Compressive Stresses for Case (2) Pressure

Case (a) dead plus wind loading – at base level

Design axial stress due to own weight,
G_k = as case (1) = +0.280 N/mm^2

Design axial stress due to post-tension force,
P_k = as case (1) = +0.598 N/mm^2

Design flexural stresses due to post-tension force,
P_k = as case (1) = +0.532 N/mm^2
or = as case (1) = –0.270 N/mm^2

Design flexural stresses due to applied moment $= -\frac{M_b}{Z_1}$

$$= -\frac{53.86 \times 10^6}{0.061 \times 10^9} = -0.883 \text{ N/mm}^2$$

or $$= +\frac{M_b}{Z_2}$$

$$= +\frac{53.86 \times 10^6}{0.12 \times 10^9} = +0.449 \text{ N/mm}^2$$

Hence:

Maximum combined compressive stress = +1.057 N/mm^2
Minimum combined compressive stress = +0.527 N/mm^2

Case (b) dead plus superimposed plus wind loading – at base level

Design axial stress due to G_k and
Q_k = as case (1) = +0.341 N/mm^2

Design axial stress due to post-tension force,
P_k = as case (1) = +0.488 N/mm^2

Design flexural stresses due to post-tensioning force,
P_k = as case (1) = +0.456 N/mm^2
or = as case (1) = −0.232 N/mm^2

Design flexural stresses due to applied moment $= -\frac{M_b}{Z_1}$

$$= -\frac{46.16 \times 10^6}{0.061 \times 10^9} = -0.757 \text{ N/mm}^2$$

or $$= +\frac{M_b}{Z_2}$$

$$= +\frac{46.16 \times 10^6}{0.12 \times 10^9} = +0.385 \text{ N/mm}^2$$

Hence:

Maximum combined compressive stress = +0.982 N/mm^2
Minimum combined compressive stress = +0.528 N/mm^2

Case (a) dead load wind loading at 3/8h level

Design axial stress due to own weight
G_k = as case (1) = +0.105 N/mm^2

Design axial stress due to post-tension force,
P_k = as case (1) = +0.598 N/mm^2

Design flexural stresses due to post-tensioning force,
P_k = as case (1) = +0.532 N/mm^2
or = as case (1) = −0.270 N/mm^2

Design flexural stresses due to applied moment $= +\frac{M_w}{Z_1}$

$$= +\frac{30.30 \times 10^6}{0.061 \times 10^9} = +0.497 \text{ N/mm}^2$$

or $$= -\frac{M_w}{Z_2}$$

$$= -\frac{30.30 \times 10^6}{0.12 \times 10^9} = -0.253 \text{ N/mm}^2$$

Hence:

Maximum combined compressive stress = +1.732 N/mm^2
Minimum combined compressive stress = +0.180 N/mm^2

Case (b) dead plus superimposed plus wind loading at 3/8h level

Design axial stress due to G_k and
Q_k = as case (1) = +0.190 N/mm^2

Design axial stress due to post-tension force,
P_k = as case (1) = +0.488 N/mm^2

Design flexural stresses due to post-tensioning force,
P_k = as case (1) = +0.456 N/mm^2
or = as case (1) = −0.232 N/mm^2

Design flexural stresses due to applied moment $= +\frac{M_w}{Z_1}$

$$= +\frac{25.97 \times 10^6}{0.061 \times 10^9} = +0.426 \text{ N/mm}^2$$

or $$= -\frac{M_w}{Z_2}$$

$$= -\frac{25.97 \times 10^6}{0.12 \times 10^9} = -0.216 \text{ N/mm}^2$$

Hence:

Maximum combined compressive stress = +1.560 N/mm^2
Minimum combined compressive stress = +0.230 N/mm^2

The two most critical design cases, for wind suction and wind pressure are shown in Figure 15.58 to demonstrate the method of stress calculations on the preceding pages. It would be more obvious to the experienced designer that a number of the preceding design cases did not require calculation to arrive at the two critical conditions stated.

15.10.12 Design Flexural Compressive Strengths of Wall: After Losses

At base level, where $\beta = 1.0$ by inspection,

$$\text{Design flexural compressive strength} = \frac{1.25 f_k}{\gamma_{mm}}$$

$$= \frac{1.25 \times 7.6}{2.3}$$

$$= 4.13 \text{ N/mm}^2$$

At 3/8h level, where $\beta = 0.58$ by calculation,

$$\text{Design flexural compressive strength} = \frac{1.25 \beta f_k}{\gamma_{mm}}$$

$$= \frac{1.25 \times 0.58 \times 7.6}{2.3}$$

$$= 2.40 \text{ N/mm}^2$$

Comparison of the design flexural compressive strengths with the previously calculated combined compressive stresses shows that the wall is acceptable for all loading cases considered this far.

15.10.13 Check Overall Stability of Wall

The wall will be checked for overall stability, both before and after losses in the post-tensioning force, for the loading combination of dead plus superimposed plus post-tensioning force.



Figure 15.58 Critical design cases for wind suction and wind pressure Example 6

Consideration has already been given to local stability of the fin and flange in the design of flexural compressive strengths. In this design check consideration is given to buckling of the section as a whole.

As was discussed in Chapter 13, in the design of the plain fin wall, it is questionable whether the narrow flange of the T profile is able to offer full resistance to buckling about the axis perpendicular to the flange. The robustness of the fin section in comparison to the relatively flimsy flange section suggests that local instability of the flange would occur before it was able to develop its full apparent stiffness about that axis. Hence, it is proposed that the actual thickness of the fin, 327 mm for this example, should be used to give a safe design, pending research into the buckling properties of such composite sections.

The effective height of the wall may be taken as $0.85h$ on the basis of full lateral restraint being provided at base level, partial lateral restraint at roof level and additional unquantified restraint from the contribution of the flange. The combination of $0.85h$ for the effective height and the fin thickness for the effective thickness about that axis is considered to provide a safe design basis and one which it would be expected to improve upon following a programme of suitable research work.

$$\text{Slenderness ratio, SR} = \frac{0.85 \times 10.0 \times 10^3}{327}$$

$$= 26$$

The eccentricity of the loading about this axis may be taken as zero.

Hence, from BS 5628, Table 7 (see Table 5.15), $\beta = 0.45$.

Design strength of wall, after losses:

$$= \frac{\beta f_k}{\gamma_{mm}} = \frac{0.45 \times 7.6}{2.3} = 1.49\ \text{N/mm}^2$$

Design strength of wall, before losses:

$$= \frac{1.2\beta f_k}{\gamma_{mm}} = \frac{1.2 \times 0.45 \times 7.6}{2.3} = 1.79\ \text{N/mm}^2$$

where $f_{ki} = f_k$, for this example.

Design stress in wall, after losses:

$$= \frac{1.4G_k + 1.6Q_k + 1.4P_k}{A}$$

$$= \frac{(1.4 \times 122.68) + (1.6 \times 38.48) + (1.4 \times 187)}{0.46 \times 10^3}$$

$$= 1.076\ \text{N/mm}^2$$

where

G_k = ow masonry = 91.90 kN

plus, roof dead load $= 0.6 \times 3.8 \times \frac{27}{2}$ = 30.78 kN

= 122.68 kN

The design strength after losses exceeds the design stress, hence, the wall is acceptable for this loading condition.

Design stress in wall, before losses:

$$= \frac{1.4G_k + 1.6Q_k + (1.4P_k/0.8)}{A}$$

$$\frac{(1.4 \times 122.68) + (1.6 \times 38.48) + (1.4 \times 187/0.8)}{0.46 \times 10^3}$$

$$= 1.22 \text{ N/mm}^2$$

where P_k is made initially 20% greater than the design value of 187 kN in anticipation of 20% losses.

The design strength before losses exceeds the design stress, hence, the wall is acceptable for this loading condition.

The stiffness of the fin about the other axis is considerably greater although the effect of the post-tensioning force is eccentric.

The net eccentricity of G_k, Q_k and P_k may be calculated by taking moments of these loads and forces about the flange face

$$\frac{(122.68 \times 301) + (38.48 \times 301) + (187 \times 425)}{122.68 + 38.48 + 187}$$

$$= \frac{127.99 \times 10^3}{348.16}$$

$$= 368 \text{ mm from flange face}$$

hence, net eccentricity of G_k, Q_k and P_k about neutral axis of section:

$$e = 301 - 368 = 67 \text{ mm}$$

Expressed in terms of the length of the fin the eccentricity

$$e = 0.075 \times 890$$

This small net eccentricity related to the considerable stiffness of the fin about this axis, compared with the design strengths calculated for the previous axis of buckling, indicates that the section will not be critical, from the point of view of overall stability, about this axis.

15.10.14 Design of Post-tensioning Rods

As for Example 5 the design stress in the yield rods will be limited to

$$\frac{0.7f_y}{\gamma_{ms}} = \frac{0.7 \times 460}{1.15} = 280 \text{ N/mm}^2$$

The post-tensioning force required before losses:

$$= \frac{187}{0.8} = 233.75 \text{ kN}$$

$$\text{Steel area required} = \frac{233.75 \times 10^3}{280} = 835 \text{ mm}^2$$

This will be provided by two high-yield rods each of 25 mm diameter positioned as shown in Figure 15.59 to give an equivalent eccentricity of 124 mm.

The design of the torque required for the rods and the spreader plate should follow similar principles to those given for Example 5.



Figure 15.59 Details of position of post-tensioning rods Example 6

15.11 Example 7: Post-tensioned Brick Diaphragm Retaining Wall

The retaining wall design in Example 3 (see section 15.6) as a reinforced brick wall will now be designed as a post-tensioned diaphragm wall. The wall is 2 m high and is to be constructed with facing bricks with a crushing strength of 27.5 N/mm^2 and a water absorption of 8% set in a designation (i) mortar. A density of 19 kN/m^3 will be assumed. The same surcharge loading will be included.

For this retaining wall, bending from the retained earth occurs in one direction only and therefore an eccentric post-tensioning force will be applied to counteract this bending. A section through the wall is shown in Figure 15.60.

15.11.1 Design Procedure

The design procedure is broadly similar to that used for the design of the post-tensioned fin wall in Example 6. The stress diagrams representing the design process are shown in Figure 15.61.

The design equations for the required post-tensioning force and its eccentricity may then be derived as follows:

$$\frac{P}{A} + \frac{Pe}{Z_1} = f_t$$

$$\frac{P}{A} - \frac{Pe}{Z_2} = -f_c$$



Figure 15.60 Post-tensioning rods as reinforcement in foundation Example 6



Figure 15.61 Stress diagrams for Example 7

but $Z_1 = Z_2$ for a diaphragm wall, hence:

$$\frac{PZ}{A} + Pe = f_t Z$$

$$\frac{PZ}{A} - Pe = -f_c Z$$

Adding

$$\frac{2PZ}{A} = (f_t - f_c)Z$$

Rearranging

$$P = (f_t - f_c)\frac{A}{2}$$

This is the minimum value of P necessary to produce the required post-tensioning stress. The corresponding value of its eccentricity, e, may now be calculated by substituting P into one of the original equations thus:

$$\frac{P}{A} + \frac{Pe}{Z} = +f_t$$

$$\frac{Pe}{Z_1} = f_t - \frac{P}{A}$$

$$e = \left(f_t - \frac{P}{A}\right)\frac{Z}{P}$$

$$e = \left(\frac{f_t}{P} - \frac{1}{A}\right)Z$$

This equation provides the eccentricity corresponding to the minimum value of P already calculated. The eccentricity may be found to be larger than can be accommodated within the trial section selected. In such a case, the maximum value of e which can be accommodated should be inserted into the latter equation and a revised value of P obtained. This revised value of P will be larger than that originally calculated.

When the required post-tensioning force and its eccentricity have been calculated, the maximum combined stresses (axial plus flexural) should be checked. The section must also be checked to ensure that no flexural tensile stresses are developed before losses of the post-tensioning force and also the overall stability of the wall when subject to the post-tensioning force alone.

Finally, the moments and stresses in the rc foundation should be considered. However, this aspect of the design is outside the scope of this book.

15.11.2 Design Loads

The retained material will be assumed to comprise fine dry sand with an angle of internal friction of 30° and a density of 17 kN/m^3. Adequate land drainage will be assumed to have been provided to ensure no build-up of water pressure. A surcharge above the retained sand, equivalent to 1.0 m depth of retained material, will also be applied. Hence, from Rankine's formula:

earth pressure at any level = $k_1 \times$ density $\times$ height

$$\text{where } k_1 = \frac{1 - \sin\theta}{1 + \sin\theta} = 0.33$$



Figure 15.62 Pressure diagram Example 7

$$\text{Pressure at top of wall} = 0.33 \times 17 \times 1.0 = 5.6\ \text{kN/m}^2$$

$$\text{Pressure at base of wall} = 0.33 \times 17 \times 2.8 = 15.7\ \text{kN/m}^2$$

$$\text{Own weight of masonry} = \frac{19 \times 2}{10^3}$$

$$= 0.038\ \text{N/mm}^2 \text{ at base level}$$

The partial safety factors for dead and retained loads are each 1.4 and 1.2 respectively, when checking combined compressive stresses, and 0.9 and 1.2 respectively when checking for the theoretical flexural tensile stresses.

Design superimposed loads:

at top of wall $= 1.2 \times 5.6 = 6.72\ \text{kN/m}^2$
at bottom of wall $= 1.2 \times 15.7 = 18.84\ \text{kN/m}^2$

The design loading diagram is shown in Figure 15.62.

Hence, design bending moment at base level, maximum

$$= \left(6.72 \times 2 \times \frac{2}{2}\right) + \left(12.12 \times \frac{2}{2} \times \frac{2}{3}\right) = 21.52\ \text{kN m}$$

Minimum design dead load stress at base level

$$f_c = 0.9 \times 0.038 = 0.0342\ \text{N/mm}^2$$

Design shear force at base level, maximum

$$= (6.72 \times 2) + \left(12.12 \times \frac{2}{2}\right) = 25.56\ \text{kN/m}$$

15.11.3 Trial Section

There are three dimensional variables which require consideration in order to arrive at a trial section for fuller analysis, these being:

(a) the overall depth of the wall, D,
(b) the thickness of the wall flanges, T, and spacing of the cross-ribs, B_r,
(c) the thickness of the cross-ribs, t_r.

(a) Overall depth, D

There is limited guidance which can be given for a reasonable assessment of the overall depth. Experience and familiarity with the design processes will indicate to the designer the benefits of a deeper wall section which is required to be balanced against space requirements, quantity of walling materials and the effect on the size of the post-tensioning rods and magnitude of the post-tensioning force. Greater depth of section will also assist in resisting shear forces which can be critical and are considered in the third of the three dimensional variables. For this example, the overall depth, D, will be taken as 558 mm.

(b) Flange Thickness, T and Cross-rib Spacing, B_r

The wall flange, on the earth face, is required to support the earth and transfer its pressure to the cross-ribs by spanning horizontally between the cross-ribs. It is considered unreasonable that the maximum pressure, at the base of the wall, should be taken as the load to be supported on the horizontal span and there is likely to be considerable resistance provided by the foundation, and the flange will tend to cantilever for a certain height rather than span horizontally. Figure 15.63 shows the design pressure diagram with the loading, assessed by the authors, as being that appropriate to the horizontal span of the flange.



Figure 15.63 Earth pressure diagram



Figure 15.64 Bending moment diagram for flange Example 7

The bending moment diagram for the design of the flange is shown in Figure 15.64 in which the design bending moment intensity has been estimated as $\gamma_f Q_k B_r^2/15$ and occurs, as shown, at the intersection of the flange with the face of the cross-rib.

$$\text{Maximum } M = \frac{\gamma_f Q_k B_r^2}{12}$$

$$\text{Design } M = \frac{\gamma_f Q_k B_r^2}{15} \text{ (estimated)}$$

$$= \frac{14.47 B_r^2}{15} = 0.965 B_r^2$$

$$\text{Design MR} = \frac{f_{kx} Z}{\gamma_m} = \frac{1.5 \times 1.0 \times 0.102^2 \times 10^3}{2.5 \times 6}$$

$$= 1.04 \text{ kN m}$$

Design MR = design M, therefore $1.04 = 0.965 B_r^2$, hence

$$B_r = \sqrt{\left(\frac{1.04}{0.965}\right)}$$

$$= 1.04 \text{ m} = \text{maximum span of flange}$$

but the horizontal shear resistance is generally the most significant factor in assessing the size and centres of the cross-ribs in a retaining wall design.

Hence, to suit an acceptable bonding arrangement the cross-ribs will be spaced, for trial purposes, at 675 mm centres which is obviously within the capacity of the span of the flange as designed above.

(c) Cross-rib Thickness, t_r

This may be assessed from a consideration of the horizontal shear force from the retained material, which has been calculated previously as 25.56 kN/m at base level.

Shear force per cross-rib, $V = 25.56 \times 0.675 = 17.25$ kN.

The maximum horizontal shear stress occurs on the centroid of the overall section and may be derived from the formula:

$$v I_h = \frac{V A_1 \bar{y}}{I_{na} t_r}$$

where

v_h = horizontal shear stress
V = applied horizontal shear force
A_1 = half the cross-sectional area (as shown hatched in Figure 15.65)
$\bar{y}$ = distance from neutral axis to centroid of area A_1 (see Figure 15.65)
I_{na} = second moment of area about neutral axis
t_r = thickness of cross-ribs.

For this example:

V = 17.25 kN per cross-rib
A_1 = 0.107 m^2
$\bar{y}$ = 0.178 m
$I_{na} = 8.07 \times 10^{-3}$ m^4
t_r = 0.215 m (assessed for trial purposes).

Hence

$$v_h = \frac{17.25 \times 0.107 \times 0.178}{8.07 \times 10^{-3} \times 0.215} \text{ kN/m}^2$$

$$= 0.189 \text{ N/mm}^2$$

Shear resistance = f_v/γ_{mv}, where $f_v = 0.35 + 0.6 g_B$ (for this example BS 5628, Part 2). The unknown factor in this equation, at this stage of the design process, is the value of g_A, which is the summation of the own weight of the masonry plus the post-tensioning force. However, a minimum post-tensioning force required to provided the horizontal shear



Figure 15.65 Section dimensions

resistance may be calculated and later checked against the minimum post-tensioning force applied to eliminate the theoretical flexural tensile stress due to bending. The larger of the two forces calculated should then be used in the design.

$$v_h = \frac{0.35}{\gamma_{mv}} + \frac{0.6g_B}{\gamma_{mm}}$$

therefore

$$0.189 = \frac{0.35}{2.0} + \frac{0.6g_B}{2.0}$$

therefore

$$g_B = 0.047\ \text{N/mm}^2$$

But

$$g_B = g_d + \text{design post-tensioning stress}$$

and

$$g_d = \frac{0.9G_k}{A} = \frac{7.32 \times 10^3}{0.214 \times 10^6}$$

$$= 0.034\ \text{N/mm}^2$$

where $G_k = 0.214 \times 19 \times 2 = 8.132\ \text{kN/cell} = 12.05\ \text{kN/m}$

Hence

$$g_A = 0.034 + \text{design post-tensioning stress}$$
$$0.047 - 0.034 = \text{design post-tensioning stress}$$
$$0.013 = \text{design post-tensioning stress}$$

The design post-tensioning stress varies across the section owing to its eccentricity, however the maximum value of horizontal shear occurs where the design post-tensioning stress has its average value.

Hence:

$$\text{design post-tensioning force} = 0.013 \times A$$
$$= 0.013 \times 0.214 \times 10^3$$
$$= 2.78\ \text{kN per cross-rib}$$
$$= 4.12\ \text{kN/m (small pre-stress force to satisfy shear)}$$

At this stage, the design post-tensioning force calculated is that applicable only to the development of horizontal shear resistance. The trial section derived is shown in Figure 15.66 and this section will now be used to check masonry stresses and to design the post-tensioning rods.



Figure 15.66 Trial section

15.11.4 Calculate Theoretical Flexural Tensile Stresses

$$f_t = \frac{0.9G_k}{A} - \frac{M_b}{Z}$$

$$= \frac{10.85 \times 10^3}{0.317 \times 10^6} - \frac{21.52 \times 10^6}{42.82 \times 10^6}$$

$$= 0.034 - 0.50$$

$$f_t = -0.466\ \text{N/mm}^2 \quad \text{and} \quad f_c = +0.034\ \text{N/mm}^2$$

Hence an eccentric post-tensioning force to produce stresses on $f_c = -0.034$ N/mm^2 and $f_t = +0.466$ N/mm^2 is required.

15.11.5 Minimum Required Post-tensioning Force Based on Bending Stresses

$$P = (f_t - f_c)\frac{A}{2}$$

where

$f_t = 0.466\ \text{N/mm}^2$
$f_c = -0.034\ \text{N/mm}^2$
$A = 0.317 \times 10^6\ \text{mm}^2/\text{m}$

hence

$$P = (0.466 - 0.034)\frac{0.317 \times 10^6}{2} = 68\ \text{kN/m}$$

The minimum post-tensioning force required to eliminate the theoretical flexural tensile stresses (68 kN/m) is greater than that required to ensure adequate shear resistance (5.07 kN/m) as calculated in section 15.11.3. The higher value of the two is adopted for subsequent calculations. It is first necessary to determine the eccentricity at which the post-tensioning force should be placed. This is given by the equation:

$$e = \left(\frac{f_t}{P} - \frac{1}{A}\right)Z$$

where $Z = 42.82 \times 10^6$ mm^3, hence

$$e = \left(\frac{0.466}{68 \times 10^3} - \frac{1}{0.317 \times 10^6}\right) \times 42.82 \times 10^6$$

$$= 158\ \text{mm}$$

The maximum practical eccentricity which can be provided in a wall section 558 mm deep is:

$$e_{max} = \left(\frac{558}{2} - 102 - \frac{\text{rod diameter}}{2}\right)$$

$$= \left(177 - \frac{\text{rod diameter}}{2}\right)$$

Allowing for a 20 mm rod, say, maximum practical eccentricity = 160 mm.

The required eccentricity is just within this limit, hence, by placing the calculated force, 68 kN/m, at an eccentricity of 158 mm, both the bending and shear stresses are limited to acceptable values.

If the calculation had indicated that an eccentricity greater than 150 mm were required, then it would have been necessary to use an increased post-tensioning force at reduced eccentricity. The new force required would be determined by substituting the maximum practical value of e in the formula:

$$P = \frac{f_t}{(1/A) + (e/Z)}$$

15.11.6 Characteristic Post-tensioning Force, P_k

In order to achieve a minimum design post-tensioning force of 68 kN/m, a characteristic post-tensioned force, P_k of $68/\gamma_f$ should be provided in the rods, where γ_f would be taken as 0.9 as discussed in section 15.8.9.

Hence, characteristic post-tensioning force $P_k = 68/0.9 = 75.56$ kN/m. This force is now used to check the design compressive stresses in the wall and to establish the size of the post-tensioning rods.

15.11.7 Capacity Reduction Factors

The overall stability of the wall section and the local stability of the flanges (leaves) will be checked under combined axial and flexural loading.

(a) Overall Stability

Effective height, $h_{ef} = 2h = 2 \times 2 = 4000$ mm
Effective thickness, t_{ef} = actual thickness = 558 mm

(*Note:* The effective thickness for diaphragm walls was discussed in Chapter 13.)

$$\text{Slenderness ratio, SR} = \frac{4000}{558} = 7.2$$

Eccentricity of dead load plus characteristic post-tensioning force:

$$\text{effective eccentricity} = \frac{P_k e}{P_k + \text{design dead load}}$$

$$= \frac{75.56 \times 0.158}{75.56 + 10.85}$$

$$= 0.138\ \text{m}$$

$$\frac{\text{effective eccentricity}}{t_{ef}} = \frac{138}{558}$$

$$= 0.247$$

Hence, for SR = 7.2 and $e_x = 0.247t$, from BS 5628, Part 1, Table 7, $\beta = 0.57$ (see Table 5.15).

(b) Local Stability

The flange (leaf) is restrained against buckling by the cross-ribs which may be taken to constitute enhanced resistance to lateral movement. Hence

$$\text{Slenderness ratio, SR} = \frac{h_{ef}}{t_{ef}} = \frac{0.75 \times 675}{102.5} = 4.9$$

The combined axial and flexural stresses may be considered to be applied to the flange with zero eccentricity for the purpose of the calculation of β.

Hence for SR = 4.9 and $e_x = 0$, from BS 5628, Part 1, Table 7, β = 1.0 (see Table 5.15).

15.11.8 Check Combined Compressive Stresses

Consider the wall subject to dead loading plus post-tensioning force only – before losses. In anticipation of 20% loss of post-tensioning force, the characteristic post-tensioning force, P_k, should initially be increased by 20%, hence:

$$\text{Post-tensioning before losses} = \frac{75.56}{0.8} = 94.5 \text{ kN/m}$$

$$\text{Design post-tensioning force before losses} = \gamma_f \times 94.5 = 132.3 \text{ kN/m}$$

where $\gamma_f = 1.4$, i.e. load factor for dead loads.

$$\text{Maximum design dead load} = 1.4G_k = 1.4 \times 12.05 = 16.87 \text{ kN/m}$$

Maximum flexural compressive stress due to post-tensioning force, P_k

$$= \frac{P}{A} + \frac{Pe}{Z}$$

$$= \frac{132.3 \times 10^3}{0.317 \times 10^6} + \frac{132.3 \times 10^3 \times 158}{42.82 \times 10^6}$$

$$= 0.417 + 0.488$$

$$= 0.905 \text{ N/mm}^2$$

Minimum flexural compressive stress due to post-tensioning force

$$= \frac{P}{A} - \frac{Pe}{Z}$$

$$= 0.417 - 0.488$$

$$= -0.071 \text{ N/mm}^2$$

i.e. tension.

Axial stress due to maximum design dead load

$$= \frac{16.87 \times 10^3}{0.317 \times 10^6} = 0.053 \text{ N/mm}^2$$

Combined stresses due to G_k and post-tensioning force:

$$\text{Maximum combined stress} = 0.053 + 0.905 = 0.96 \text{ N/mm}^2$$

$$\text{Minimum combined stress} = 0.053 - 0.071 = -0.018 \text{ N/mm}^2$$

$$\text{Design strength before losses} = 1.2\left(\frac{1.25\beta f_{ki}}{\gamma_{mm}}\right) = 1.2\left(\frac{1.25 \times 1.0 \times 9.2}{2.0}\right) = 6.90 \text{ N/mm}^2$$

in which the wall is assumed to have achieved its full characteristic compressive strength at the time that the post-tensioning is carried out, hence, $f_{ki} = f_k$; also the capacity reduction factor relates to the local stability of the flange in this instance and the effect on the overall stability will be checked in due course.

By inspection the design strength far exceeds the combined compressive stress, hence, the wall is acceptable for this loading condition.

The reserve of strength available in this example before losses indicates that there is no need to check for the same loading condition after losses.

Consider stability of overall wall section under dead loading plus post-tensioning force after losses.

$$\text{Design axial load} = (\gamma_f G_k) + (\gamma_f P_k) = (1.4 \times 12.05) + (1.4 \times 75.56) = 122.65 \text{ kN/m}$$

$$\text{Design axial stress} = \frac{122.65 \times 10^3}{0.317 \times 10^6} = 0.387 \text{ N/mm}^2$$

$$\text{Design strength of wall} = \frac{\beta f_k}{\gamma_{mm}} = \frac{0.57 \times 9.2}{2.0} = 2.62 \text{ N/mm}^2$$

in which the effect of the eccentricity of the post-tensioning force has been taken into account in the calculation of β.

The design strength exceeds the design stress, hence the wall is acceptable for this loading condition.

Consider the wall subject to dead loading plus superimposed loading plus post-tensioning force.

$$\text{Axial stress due to } G_k = \frac{\gamma_f G_k}{A} = \frac{1.4 \times 12.05 \times 10^3}{0.317 \times 10^6} = +0.053 \text{ N/mm}^2$$

Maximum flexural stress due to post-tensioning force, P_k

$$= \frac{\gamma_f P_k}{A} + \frac{\gamma_f P_k e}{Z}$$

$$= \frac{1.4 \times 75.56 \times 10^3}{0.317 \times 10^6} + \frac{1.4 \times 75.56 \times 10^3 \times 158}{42.82 \times 10^6}$$

$$= +0.724 \text{ N/mm}^2$$

Minimum flexural stress due to post-tensioning, P_k

$$= \frac{\gamma_f P_k}{A} + \frac{\gamma_f P_k e}{Z}$$

$$= 0.333 - 0.390 = -0.057 \text{ N/mm}^2$$

i.e. tension.

Flexural stress due to applied moment

$$= \pm\frac{M_b}{Z} = \frac{21.52 \times 10^6}{42.82 \times 10^6} = \pm 0.503 \text{ N/mm}^2$$

Hence:

Maximum combined compressive stress = +0.499 N/mm^2
Minimum combined compressive stress = +0.274 N/mm^2

The stress diagrams for this working condition are shown in Figure 15.67.

$$\text{Design strength of wall} = \frac{1.25\beta f_k}{\gamma_{mm}}$$

$$= \frac{1.25 \times 1.0 \times 9.2}{2.0}$$

$$= 5.75 \text{ N/mm}^2$$

The design strength exceeds the combined stress, hence the wall is acceptable for this loading condition.



Figure 15.67 Stress diagram for dead plus superimposed plus post-tension loading Example 7

Check minimum combined stress in which γ_f for dead and post-tensioning force = 0.9.

$$\text{Axial stress due to } G_k = \frac{\gamma_f G_k}{A} = \frac{0.9 \times 12.05 \times 10^3}{0.317 \times 10^6}$$

$$= 0.034 \text{ N/mm}^2$$

Maximum flexural stress due to post-tensioning force, P_k

$$= \frac{\gamma_f P_k}{A} + \frac{\gamma_f P_k e}{Z}$$

$$= \frac{0.9 \times 75.56 \times 10^3}{0.317 \times 10^6} + \frac{0.9 \times 75.56 \times 10^3 \times 158}{42.82 \times 10^6}$$

$$= 0.215 + 0.251 = 0.466 \text{ N/mm}^2$$

Minimum flexural stress due to post-tensioning force, P_k

$$= 0.215 - 0.251 = -0.036 \text{ N/mm}^2$$

$$\text{Flexural stresses due to applied moment} = \pm\frac{M_b}{Z}$$

$$= \pm 0.503 \text{ N/mm}^2$$

Minimum combined compressive stress

$$= 0.034 + 0.466 - 0.503 = \text{zero N/mm}^2$$

Hence, no tensile stresses are developed.

15.11.9 Check Shear between Leaf and Cross-rib

Another critical section for checking shear stresses is in the vertical plane at the junction of the cross-ribs and the leaves, as shown in Figure 15.68.

$$\text{Shear stress, } v_h = \frac{VA_2\bar{y}}{I_{na}t_r}$$

where

V = design shear force = 17.25 kN/cross-rib
A_2 = area of leaf = $102.5 \times 675 = 0.069 \times 10^6$ mm^2
$\bar{y} = 177 + \frac{102}{2} = 228$ mm
I_{na} = moment of inertia = 8.07×10^9 mm^4
t_r = thickness of cross-rib = 215 mm.

Hence

$$v_h = \frac{17.25 \times 10^3 \times 0.069 \times 10^6 \times 228}{8.07 \times 10^9 \times 215}$$

$$= 0.156 \text{ N/mm}^2$$

The cross-ribs are assumed to be half-bonded into the leaf at alternate courses as shown in the bonding diagram (Figure 15.69). For shear failure to occur at the junction of the cross-rib with the leaf, the bonded bricks would need to snap.

$$\text{Shear strength of a fully bonded wall} = \frac{f_v}{\gamma_{mv}}$$

There appears to be some uncertainty in the Code about the value of f_v which is given as 0.7 N/mm^2 in Part 1 of the Code (vertical shear: vertical direction, see Figure 6.34) and



Figure 15.68



Figure 15.69 Bonding details

up to a maximum value of 1.75 N/mm^2 in Part 2 of the Code (see section 15.3.6(e)) depending on the level of prestress. The authors consider it prudent to use a maximum value of 0.7 N/mm^2, hence:

$$f_v = 0.7\ \text{N/mm}^2$$

$$\gamma_{mv} = 2.5$$

Therefore

$$\text{Shear strength} = \frac{0.7}{2.5} = 0.28\ \text{N/mm}^2$$

The effect of the half-bonding shown in Figure 15.69 is uncertain but will result in the above shear strength being reduced by anything up to half of the calculated value.

$$\text{Shear strength of half-bonded wall} = \frac{0.28}{2}$$

$$= 0.14\ \text{N/mm}^2$$

which falls short of the applied shear stress of 0.156 N/mm^2.

This shortfall can be accommodated by the introduction of flat metal shear ties, as shown in Figure 15.69, placed in the lower courses only up to the course level at which the applied shear stress has reduced to that of the shear resistance of the half-bonded wall – estimated to be at fourth or fifth course up from base. The horizontal shear stress has already been shown to be acceptable in section 15.11.3.

15.11.10 Design of Post-tensioning Rods

Post-tensioning force required = 94.5 kN/m before losses. One post-tensioning rod per cell of the diaphragm wall will be used, hence

$$\text{Post-tensioning force per cell} = 94.5 \times 0.675$$

$$= 63.79\ \text{kN}$$

$$\text{Design strength of rods} = \frac{0.7 f_y}{\gamma_{ms}}$$

$$= 280\ \text{N/mm}^2$$

$$\text{Area of rod required per cell} = \frac{63.79 \times 10^3}{280}$$

$$= 228\ \text{mm}^2$$

One high yield post-tensioning rod of 20 mm diameter (area provided = 315 mm^2) will be used in each cell of the diaphragm wall.

The remainder of the rod design should follow similar principles to the previous two examples. A capping beam will be provided to spread the post-tensioning force throughout the wall section.

16 Arches



Figure 16.1 Typical arch

Brick arches were built in Egypt more than 5000 years ago. They are one of the oldest and most attractive structural forms.

Since arches are basically required to resist compressive forces they are well suited to masonry construction. There have been, in the past, exciting developments from the arch to the vault and the dome. They have been economical, durable and aesthetically pleasing – and almost forgotten by modern engineers. A revival in their use would be invaluable in developing countries with indigenous supplies of stone, brick and local masons. They would also be useful in developed countries in areas where the visual environment needs something more attractive than a plain steel or concrete beam bridge. To give some idea of their potential, a simple masonry arch can easily span 20 m or more. The common terms used in arch design are depicted in Figures 16.1–16.5 and may be useful to the engineer in discussions with architects and builders and in the production of working drawings.



Figure 16.2 Arch coursing



Figure 16.3 Arch terms



Figure 16.4 Brick ring types



Figure 16.5 Square and skew arch plans

16.1 General Design

The following discussion deals, for simplicity, with an arch ring unconnected with a spandrel wall – which could be considered as a wall with an arch 'cut out'; or a narrow arch with spandrels on both faces which could be considered similar to a U-shaped section.

Most masonry arches are considered to be 'fixed' arches, i.e. there are no hinges, and they are not considered to be capable of resisting tensile stresses. The downward load on the arch creates lateral and compression thrusts in the arch span (see Figure 16.6), which pushes the masonry units against each other and compresses them, and in turn the arch thrusts against the abutments.

If the line of the thrust is on the centre of the arch, the arch ring is under uniform compressive stress (see Figure 16.7)



Figure 16.6 Loading and thrust in an arch



Figure 16.7 Uniform compressive stress



Figure 16.8 Non-uniform compressive stress

As will be seen later, the line of the thrust does not always pass along the centre line of the arch, and the arch is not then in uniform compressive stress (see Figure 16.8).

The compressive stress on the arch due to P, is P/bd, i.e. P/A, and the stress due to the moment Pe, is Pe/Z.

The total stress, then, is

$$f = \frac{P}{A} \pm \frac{Pe}{Z}$$

Z for a rectangular section $= bd^2/6$, and $A = bd$.

At the limit, for no tension (see Figure 16.9):

$$f = 0 = \frac{P}{A} - \frac{Pe}{Z}$$

$$\text{therefore} \quad \frac{P}{A} + \frac{Pe}{Z}$$



Figure 16.9 No tension condition in arch



Figure 16.10 Middle third in the arch

$$\text{therefore} \quad e = \frac{Z}{A} = \frac{bd^2/6}{bd} = \frac{d}{6}$$

Provided that the line of thrust does not pass outside a distance $(d/6)$ either side of the centre line of the arch, no tension stresses will develop. This, of course, is the well-known 'middle third' rule (see Figure 16.10).

In fact, the line of thrust can lie outside the middle third, tensile stresses can develop and cracks can occur. The line of thrust can move to the edge of the arch ring and a 'hinge' will develop, but the arch will not necessarily collapse. This will be discussed later – for simplicity the design of the fixed arches with no tension will be discussed first.

16.1.1 Linear Arch

The linear arch (see Figure 16.11) is analogous to a steel cable, and a consideration of the behaviour of the cable will clarify the behaviour of an arch.

A force diagram is drawn, for the cable shown in Figure 16.11, from which the funicular polygon can be constructed which shows the magnitude of the forces in the cable. The value of P depends upon the magnitude of the horizontal reaction, H. As H increases the sag in the cable lessens, but the tension in the cable increases. The force diagram (using the well-known Bow's notation) enables the value of the tension force in the cable to be determined.

If the point loads, W_1, W_2, etc., are replaced by the own weight of the cable, the cable takes up the shape of a



Figure 16.11 Funicular polygon



Figure 16.12 Linear arch



Figure 16.13 Arch rise and thrust relationship



Figure 16.14 Parabolic arch and uniformly distributed load

catenary curve. When a cable is loaded with a uniformly distributed load, the deflected shape forms a parabola. (It should be noted that the own weight alone of a cable does not produce a uniformly distributed load.) If the steel cable, shown in Figure 16.11, is replaced by a series of short steel rods pin-jointed at their connections at load points W_1, W_2, W_3, etc., and then inverted, the rods would be the same as in the cable, and have the same vertical and horizontal components. The inverted funicular polygon is known as a linear arch (see Figure 16.12).

The horizontal thrust at the abutments of the arch, and the compression in the rods, depend not only on the magnitudes of W_1, W_2, etc., but also on the rise of the arch (in the same way as the sag in the cable depended on a horizontal pull at its supports) and on the magnitude of the loads (see Figure 16.13). Roman arches were nearly always semicircular, so that the rise was half the span. Many experts were alarmed when Brunel built the Maidenhead Bridge with a span of 38 m and a rise of only 8 m. The bridge apparently now carries ten times the load Brunel envisaged.

Similarly, if the arch is uniformly loaded, its most efficient shape is parabolic (see Figure 16.14). In some cases in practice, the line of thrust is near enough for design purposes to the arc of a circle.



Figure 16.15 Position and magnitude of P in an arch under uniformly distributed load

Changes in the magnitude of the thrust, H, affect the magnitude of the compression force, P. It will also alter its position within the arch ring.

In a uniformly loaded arch, P is assumed to act horizontally at the crown (top) of the arch and in the centre of the arch ring (see Figure 16.15(a)).

The value of P is calculated (admittedly crudely) by cutting through the arch at the crown and taking moments about A, assuming A to act as a pin joint, when:

$$P \times r = W_1 \times x_1 + w_2 \times x_2 + w_3 \times x_3$$

(see Figure 16.15(b)).

This assumes that there is no restraining moment at A, but this error gives the maximum possible value of P and is therefore on the safe side.

Since the theory of fixed arches is based on assumptions of doubtful validity, in practice (see below) many engineers think it prudent to determine the linear arch which lies nearest to the line of the arch. This will be explained in later examples. From experience, it has been found that graphical analysis of trial sections is more satisfactory, certainly for spans up to 15 m, than the questionable and tedious mathematical analyses. It gives too, a better 'feel' of the structure and forces to the designer.

16.1.2 Trial Sections

A number of Victorian engineers derived formulae for trial sections for brickwork based on experience, and some testing, and examples of these are given below (for S, R and D, see Figure 16.16).

Rankine: $D = \sqrt{(0.12R)}$

Trautwine: $D = 0.27 + 0.33\sqrt{\left(\frac{S}{2} + R\right)}$



Figure 16.16 Trial section dimensions



Figure 16.17 Typical arch for rule of thumb application

Depuit: $D = \sqrt{(0.074S)}$ (for segmental arches)

$D = \sqrt{(0.13S)}$ (for semi-circular arches)

Sejourne: D (for ellipses)

$$= 0.15 \left(\frac{4}{3 + \dfrac{2 \times \text{rise}}{S}} \right) [3.28 + \sqrt{(3.28S)}]$$

D(for semi-circular) $= 0.15\ [3.25 + \sqrt{(3.28S)}]$

Hurst: $D = 0.4\sqrt{R}$

These formulae are based on Imperial measurements, and would need conversion to SI units.

If the foregoing 'rules' are applied to a semi-circular arch of 50 foot span (therefore, $R = 25$ ft and rise = 25 ft), the results are surprisingly consistent:

Rankine:	$D = 2.45$ ft	Average = 2.39 ft (approximately 0.8 m)
Trautwine:	$D = 2.58$ ft	
Depuit:	$D = 2.55$ ft	
Sejourne:	$D = 2.4$ ft	
Hurst:	$D = 2.0$ ft	

With better bricks, stricter control of workmanship, and a greater understanding of structural behaviour, the trial section could be reduced. The 'rules' were based on relatively thick arches supporting massive earth filling. The influence of the rolling imposed loads from horses and carts was negligible (see Figure 16.17).

Many Victorian masonry arches over railways and canals, built to carry horse-drawn carts and carriages, had to be checked before the D-Day invasion in the Second World War to determine whether they were capable of supporting the massive loadings from tanks and artillery. Practically all of them were more than adequate.

16.1.3 Mathematical Analysis

Professor Pippard (*Journal of the Institution of Civil Engineers*, Jan. 1939) stated that the 'middle third' rule was unduly pessimistic and suggested the use of the 'middle half'. In later work, he found that the thrust could pass not just outside the middle half, but outside the arch ring without the arch collapsing.

Professor Hardy Cross (of moment distribution fame) found on concrete arches (University of Illinois, Bulletin No. 203) that half the total stress in the arch was due to its own dead weight. He later went on to say: 'Some of the problems of arch analysis, however, cannot be solved by either rational or empirical methods alone. They are problems in probability in which the range of uncertainty of certain fundamental variables is a matter for observation, but the probable uncertainty in the results consequent upon accidental combination of these variable can scarcely be determined by experiments.' This view may now be outdated, but good research, applied with appropriate partial factors of safety, would be valuable to practising engineers.

The mathematical analysis of masonry arches has, at times, attracted mathematicians and structural theorists. The resulting highly complex mathematics have not been acceptable to many practising designers, perhaps because the assumptions made by the analysis do not occur in practice. Typical assumptions and the authors' rejection of the analyses are given below:

The Abutments do not Move

In practice the abutments can be subject to the following movements:

(a) Spread of the abutments

The arch will thrust against the abutments causing them to spread apart (see Figure 16.18). The arch will crack at the crown and springings and form a statically determinate three-pinned arch (as distinct from the assumed fixed arch). The hinges would show up as haircracks in the mortar joints, and the line of thrust would pass through the hinge points. The arch, acting as a three-pinned arch would still be safe and stable, provided the compressive resistance of the masonry is not exceeded.

(b) 'Squashing' together of the abutments

The pressure from retained earth and excessive surcharge loading can push the abutments together and reduce the span of the arch. Again, the arch could crack and form a three-pinned arch, as shown in Figure 16.19.



Figure 16.18 Spread of arch abutments



Figure 16.19 Squashing of arch abutments

(c) Differential settlement of the abutments

It is rare in practice for both abutments to settle by exactly the same amount. Even minute differential settlements would distort many mathematical analyses. The most thorough soil surveys, investigations and analyses only give estimates of settlement.

Arches are very stable structures and are not over-sensitive to foundation movement. Clare Bridge at Cambridge, for example, is appreciably distorted due to movement of the abutment, which took place a long time ago. It is still standing and is still safe.

The Arch is Elastic

Masonry, while at low stresses can act elastically, even though it is not an elastic material.

The Arch does not Change its Profile

The elements of the arch can contract due to compression forces, creep action, shrinkage of the mortar (or concrete blocks), etc. These contractions will shrink the arch and cause it to sag. The sagging would in most cases, be minute, and can in practice be ignored.

The elements of the arch can expand due to moisture and thermal movement, expansion of bricks, chemical changes, etc. These expansions will 'lengthen' the arch and cause it to rise. Again the rise would generally be minute and of little practical consequence.

Arches, as any other structural member, are rarely built to an exact profile. There are the normal construction tolerances and small imperfections. Arch formwork will deform slightly during construction of the arch. Mortar joints and masonry units have permissible tolerances, setting out even, if possible, to accuracies of 1 in 100 000 is not 'accurate'.

The Material is Homogeneous and Isotropic

Arches are made of masonry and mortar which have different properties. Mortar does not glue the masonry together, but helps to transfer the compressive load from one masonry unit to another uniformly, and not just at the high points. Masonry does not have an orthogonal ratio of unity.

The Loading is Uniform

When the dead loads and superimposed loadings are uniform, the arch has its highest compressive stresses. The worst case for tensile stresses is usually when only one half of its span is subject to superimposed load (see Figure 16.20). If the superimposed load is sufficiently excessive, four hinges could form and a collapse mechanism develop.

Changes of profile, span, length, etc., which will happen, have a very significant effect on complex mathematical analyses and very little effect on practical design or strength and stability of the arch. Masonry, like steel and reinforced concrete, has sufficient elasticity to withstand small structural movements without damage.

Mathematical analysis is, of course, invaluable to the engineer when it allows him to design safe and economical structures, and the above comments should not be regarded as denigrating analysis but as helping to give a sense of proportion. The simple graphical analysis should produce a safe arch. Some mathematical analysis may result in a thinner arch, which would make for extra economy. However, it should be appreciated that much of the cost of arch bridges is independent of the thickness of the arch. For example, the costs of the abutments, temporary centring formwork, road slab, filling and spandrels are hardly affected by whether the arch is three rings or four rings thick.

Most masonry designers would have more confidence in design tolerance based on extensive study of the structural behaviour of actual masonry arches, than those based on theoretical assumptions.

One of the simplest analyses (and in the opinion of the authors, one of the best) is probably that of Professor Heyman of Cambridge, in his excellent book, *Equilibrium of Shell Structures*. This deals with an arch of minimum thickness supporting its own weight only, and the depth of the calculated arch must be increased for trial section analyses to carry further dead load and any imposed loading. He has produced two graphs to determine the



Figure 16.20 Loading to provide worst tensile stresses in arch

thickness of the arch and horizontal component of the abutment thrust.

16.2 Design Procedures

(1) Choose rise (between 1/4 to 1/2 span).
(2) Choose shape (preferably parabolic or arc of a circle).
(3) Choose trial section.
(4) Carry out graphical analysis.
  (a) Divide the arch and the filling above into a number of segments, such as A, B, C, D, E (see Figures 16.21 and 16.22).
  (b) Determine the dead load of the arch, filling and imposed load on each segment. Take both cases of imposed loading, i.e. whole span loaded and from abutment to crown only loaded.
  (c) Treat the distributed load as a series of point loads, W_1, W_2, etc.
  (d) Calculate the thrust H_z at crown by taking moments about X:

$$H_z \times r = W_1 \times X_1 + W_2 \times X_2 + W_3 \times X_3 + \text{etc.}$$

  (for this calculation, assume that H_z is horizontal and that the moment at the crown is zero, i.e. a three-pinned arch).
  (e) Plot the force diagram, using Bow's notation (see Figure 16.23).
  (f) Draw the line of thrust on the arch profile thus:
    (i) Start at crown of arch and plot the horizontal thrust line acting through the centre of the depth of the arch ring.
    (ii) Through space A, draw line parallel to ao (i.e. horizontal thrust line H_z) changing slope at 'a' and becoming parallel to bo.



Figure 16.21 Division of arch into segments



Figure 16.23 Force diagram

    (iii) Continue line parallel to bo through space B and change slope at b to become parallel to co, and so on.
  (g) The resulting line, known as the line of resultant thrust, is checked to determine whether it passes outside the middle third of the depth of the arch ring.
(5) Check stresses at the critical locations on the arch ring using the procedure given in the following examples.
(6) Check 'cracked section' analysis if unacceptably high tensile stresses are indicated in operation (5).
(7) Redesign as necessary; note that if the line of resultant thrust is shown, in operation (4g), to be considerably outside the middle third of the depth of the arch ring, it is likely that the shape of the arch will require adjustment and operations (1) to (4) should be repeated for the new arch profile.
(8) Having established a suitable arch profile, and checked the stress levels in operations (5) and (6), choose masonry unit and mortar strength.

16.3 Design Examples

The following design examples will simply relate loads to stresses and will not be presented in 'limit state' terms. It is considered that this will provide the designer with a clearer picture of the mechanics of arch design and will highlight the need for experienced judgement and adjustment of the trial section.

16.3.1 Example 1: Footbridge Arch

Segmental brick arch of 10 m span and 2 m rise will be assumed to be 330 mm deep and is subject to various loading conditions (see Figure 16.24).

The arch has been divided into ten segments each of equal length (equal length segments were chosen merely to



Figure 16.22 Division of arch into segments – uniformly distributed load



Figure 16.24 Arch profile for Example 1

simplify the calculations and this is not a pre-requisite of the process). The mass of each segment is then calculated and a density of 23.5 kN/m^3 has been assumed for the masonry in each of the following examples.

Calculate Mass of Arch Segments

Volume of each segment

Segment A(A_1) $0.70 \times 1.0 = 0.70$ m^3
Segment B(B_1) $0.72 \times 1.0 = 0.72$m^3
Segment C(C_1) $0.80 \times 1.0 = 0.80$ m^3
Segment D(D_1) $0.94 \times 1.0 = 0.94$ m^3
Segment E(E_1) $1.18 \times 1.0 = 1.18$ m^3

Hence, using a density of 23.5 kN/m^3,

Mass A(A_1) $= 0.70 \times 23.5 = 16.45$ kN
Mass B(B_1) $= 0.72 \times 23.5 = 16.92$ kN
Mass C(C_1) $= 0.80 \times 23.5 = 18.80$ kN
Mass D(D_1) $= 0.94 \times 23.5 = 22.09$ kN
Mass E(E_1) $= 1.18 \times 23.5 = 27.73$ kN

Case (1): Dead Loading only

Having determined the mass of each segment, moments of the masses are taken about the point X at the base of the arch. The summation of these moments is equated to the moment of the thrust, acting at the point Z at the crown of the arch. In this example the thrust is thus shown to be 105 kN as follows.

Take moments about X:

Mass A $= 16.45 \times 4.5 =$ 74.03
Mass B $= 16.92 \times 3.5 =$ 59.22
Mass C $= 18.80 \times 2.5 =$ 47.00
Mass D $= 22.09 \times 1.5 =$ 33.14
Mass E $= 27.73 \times 0.5 =$ 13.87
Total $= 227.26$ kN m

$$H_z \times 2.165 = 227.26$$
$$H_z = 105.0 \text{ kN}$$

The base line of the force diagram can now be plotted to a suitable scale with a horizontal line ao representing the thrust H_z in magnitude and direction (see Figure 16.25). From point 'a' the mass of each segment is plotted on a vertical line with a–b representing the mass of segment A, b–c representing the mass of segment B, etc., until point x is reached. The lines of thrust in each segment are now established by connecting point o to each of the points b, c, d, e and x. Line xo represents the resultant reaction at the base of the arch.



Figure 16.25 Force diagram for dead load only for Example 1

The forces from the force diagram are now transferred to the arch profile following the procedure given earlier in operation (4f). The line of resultant thrust is symmetrical about the centre line of the arch for this symmetrical loading condition. By inspection of the line of resultant thrust there appears to be a potential problem near to the springing point where the thrust line is touching the edge of the arch ring (see Figure 16.24). Hence, the thrust has a large eccentricity and tensile stresses within the arch ring may be excessive. However, the thrust at the crown was assumed to be applied on the centre of the depth of the arch ring and it is likely that if this were moved upwards to the edge of the middle third of the depth of the arch ring, the stress levels at this location would still be acceptable. In doing so the line of resultant thrust at the springing point would move nearer to the centre line of the arch, thus reducing the effect of its eccentricity. The line of thrust will, of course, take its own course in practice and the object of the design process is to set out a theoretical line of thrust and adjust it until a situation is reached where all stresses are within acceptable limits. This may not necessarily be the most

efficient line for the thrust to take, in that stress levels in some zones of the arch ring may be disproportionately higher than in other zones. However, the design will have demonstrated that the section is adequate. In adjusting the point of application of the thrust at the crown, the assumptions made at the outset will be incorrect, i.e. the dimensions used to calculate the reactions will differ slightly and there will now be a bending moment at the crown where zero moment was assumed for the calculation of the reactions. However, it is considered that, provided stresses are checked throughout and shown to be acceptable, these errors may be ignored and the suggested design method should produce a safe and satisfactory solution.

Cases (2) and (3): Dead plus Superimposed Loading

Case (2) is based on a crowd superimposed loading of 4 kN/m in addition to the dead loads as calculated for case (1). The horizontal thrust H_z for this loading case is calculated to be 128.14 kN and the line of resultant thrust is shown in Figure 16.26, having been plotted from the force diagram shown in Figure 16.27.

Similarly for case (3) loading, where the superimposed load is increased to 8.0 kN/m, the relevant arch and force diagrams are shown in Figures 16.28 and 16.29 respectively.

The calculation of stresses within the masonry will be dealt with in Example 2.



Figure 16.26 Load and segments for dead and superimposed loading Example 1(case 2)



Figure 16.27 Force diagram for dead and superimposed loading Example 1(case 2)



Figure 16.28 Load and segments for dead and superimposed loading Example 1(case 3)



Figure 16.29 Force diagram for dead and superimposed loading Example 1(case 3)

16.3.2 Example 2: Segmental Arch Carrying Traffic Loading

A circular arch has been selected which, from experienced judgement, provides the most suitable profile to support the heavier loading involved. The span of the arch is 10.0 m and the rise will be made 4.0 m, almost semi-circular. The loading information and arch profile is shown in Figure 16.30 and the thickness of the masonry will be taken as 1.0 m.

The design procedure is similar to that used for the previous example and for convenience the arch has been divided into ten equal segments.

Case (1): Dead plus Superimposed Loading

Calculate thrust, H_z, at crown

	Dead Load (kN)	Superimposed load (kN)	Total load (kN)
Segment A	25.4	16.4	41.8
Segment B	38.5	16.4	54.9
Segment C	54.1	16.4	70.5
Segment D	73.8	16.4	90.2
Segment E	98.7	16.4	115.1
Total (excluding 40 kN point load) =			372.5



Figure 16.30 Arch profile for Example 2

Total vertical reaction at X = 372.5 + 20.0 = 392.5 kN

(where 20 kN = half centre point load).

Take moments about X:

$$\begin{aligned}\text{Mass A} &= 41.8 \times 4.5 = 188.10\\ \text{Mass B} &= 54.9 \times 3.5 = 192.15\\ \text{Mass C} &= 70.5 \times 2.5 = 176.25\\ \text{Mass D} &= 90.2 \times 1.5 = 135.30\\ \text{Mass E} &= 115.1 \times 0.5 = 57.55\end{aligned}$$

$$\text{Half point load} = 20.0 \times 5.0 = \underline{100.00}$$

$$\text{Total} = 849.35 \text{ kN m}$$

$$H_z \times 4.24 = 849.35$$

$$H_z = 200 \text{ kN}$$

1 Plot force diagram

The force diagram, shown in Figure 16.31, may now be plotted. The one difference in the setting out of the force diagram is the need to provide an inclined thrust at the crown to generate a vertical component equal and opposite to the point load applied at the centre of the span. Half the point load has been assumed to influence each half of the symmetrical profile. Hence line ao is inclined by the introduction on the force diagram of the 20 kN external force, z–a.

The forces are now transferred back to the arch profile shown in Figure 16.32 and once again the initial commencement point is at the centre of the depth of the arch at the crown. By inspection, a logical adjustment of this line of resultant thrust would be to raise the point of application of the thrust at the crown which would very likely result in the thrust line being contained within the arch depth throughout its length. However, the calculation of stresses in the masonry will be carried out using the line of thrust shown in Figure 16.32 based upon the thrust magnitudes given in the force diagram (Figure 16.33).



Figure 16.31 Force diagram dead plus superimposed loading Example 2

Calculate masonry stresses

For convenience, as numerous repetitive calculations are required, the masonry stresses may be computed in tubular form as shown in Table 16.1.

The stresses shown in Table 16.1 should now be compared with those allowable for the selected bricks and mortar using the basic principles given in Chapter 11. It is already evident that high tensile stresses exist at location G and a 'cracked section' analysis will almost certainly have to be carried out at this location.

Case (2): Dead plus Partial Superimposed Loading

Figure 16.32 shows the same arch with superimposed loading on one half only of the arch span.



Figure 16.32 Load and segments for dead and partial superimposed loading Example 2

Table 16.1 Masonry stresses (two typical locations, F and G, are considered)

	Point F	Point G
Thrust, *p*	213.0 kN	342 kN
Bending moment, *M*	*anticlockwise* 54.9 × 0.5 = 27.45 70.5 × 1.5 = 105.75 90.2 × 2.5 = 225.50 115.1 × 3.5 = 402.85 200.1 × 4.13 = 826.00 Total = 1587.55 kN m	*anticlockwise* 115.1 × 0.5 = 57.55 200 × 2.445 = 489.00 Total = 546.55 kN m
	clockwise 392.5 × 4.0 = 1570.0 kN m	*clockwise* 392.5 × 1.0 = 392.5 kN m
	imbalance 1587.55 – 1570 = 17.55 kN m	*imbalance* 546.55 – 392.5 = 154.05 kN m
Calculated eccentricity, *e* *e* = *M*/*P*	$\frac{17.55 \times 10^6}{213.0 \times 10^3}$	$\frac{154.05 \times 10^6}{342 \times 10^3}$
Eccentricity scaled from drawing	120 mm	410 mm
P/*A*	$\frac{213 \times 10^3}{480 \times 10^3}$ = 0.444 N/mm^2	$\frac{342 \times 10^3}{480 \times 10^3}$ = 0.713 N/mm^2
M/*Z*	$\frac{17.55 \times 10^6}{38.4 \times 10^6}$ = 0.457 N/mm^2	$\frac{154.05 \times 10^6}{38.4 \times 10^6}$ = 4.012 N/mm^2
Maximum stress $\frac{P}{A} + \frac{M}{Z}$	0.444 + 0.457 = +0.901 N/mm^2 (compressive)	0.713 + 4.012 = + 4.725 N/mm^2 (compressive)
Minimum stress $\frac{P}{A} - \frac{M}{Z}$	0.444 – 0.457 = –0.013 N/mm^2 (tensile)	0.713 – 4.012 = –3.299 N/mm^2 (tensile)



Figure 16.33 Force diagram for dead and partial superimposed loading Example 2

The design procedure is the same and the force diagram, for the full span since the loading is asymmetrical, is shown in Figure 16.33.

Calculate thrust H_z at crown

	Dead load (kN)	Superimposed load (kN)	Total load (kN)
Segment A	25.4	16.4	41.8
Segment B	38.5	16.4	54.9
Segment C	54.1	16.4	70.5
Segment D	73.8	16.4	90.2
Segment E	98.7	16.4	115.1
Segment A_1	25.4	0	25.4
Segment B_1	38.5	0	38.5
Segment C_1	54.1	0	54.1
Segment D_1	73.8	0	73.8
Segment E_1	98.7	0	98.7
Total (excluding 40 kN point load) =			663 kN

Total vertical reaction at X, $V_x = 372.0$ kN
Total vertical reaction at Y, $V_y = 331.0$ kN

SV = 0 $V_x + V_y = 703$ kN (16.1)
SH = 0 $H_x - H_y = 0$ (16.2)

Hence

$$0 = 4.24H_x + (41.8 \times 0.5) + (54.9 \times 1.5) + (70.5 \times 2.5) + (90.2 \times 3.5) + (115.1 \times 4.5) - (5.0V_x)$$

$$0 = (4.24H_x) + 1113.3 - (5.0V_x) \quad (16.3)$$

and

$$0 = 4.24H_y + (25.4 \times 0.5) + (38.5 \times 1.5) + (54.1 \times 2.5) + (73.8 \times 5) + (98.7 \times 4.5) - (5.0V_y)$$

$$0 = (4.24H_y) + 908.2 - (5.0V_y) \quad (16.4)$$

Now adding (16.3) + (16.4)

$$0 = 4.24(H_x + H_y) + 2021.5 - 5(V_x + V_y) \quad (16.5)$$

and substituting (16.1) into (16.5) gives

$$0 = 4.24(H_x + H_y) + 2021.5 - 3513$$

Therefore $H_x + H_y = 352.2$ kN (16.6)
and $H_x - H_y = 0$ (16.2)
hence $H_x = H_y = 176.1$ kN

Vertical component of thrust at crown, V_z

To left of Z:

$$V_x - 372.5 - 40 - V_z = 0$$
$$V_z = 40.5 \text{ kN}$$

Check to right of Z:

$$V_y - 290.5 + V_z = 0$$
$$V_z = 40.5 \text{ kN}$$

Horizontal component of thrust at crown, H_z

Taking moments about X

$$0 = (40 \times 5.0) + (115.1 \times 0.5) + (90.2 \times 1.5) + (70.5 \times 2.5) + (54.9 \times 3.5) + (41.8 \times 4.5) - (V_z \times 5.0) - (4.24H_z)$$
$$4.24H_z = 949.35 - 202.5$$
$$H_z = 176.1 \text{ kN}$$

16.3.3 Example 3: Repeat Example 2 using a Pointed Arch

For the same loading and dimensional criterion as Example 2, a pointed arch will now be analysed to demonstrate its unsuitability.

Case (1): Dead plus Superimposed Loading

Figure 16.34 shows the arch profile and the line of resultant thrust for case (1) loading (dead plus superimposed).

Calculate thrust, H_z, at crown

Take moments about X:

Segment A = $(25.4 + 16.4) \times 4.5 = 188.10$
Segment B = $(38.5 + 16.4) \times 3.5 = 192.15$
Segment C = $(54.1 + 16.4) \times 2.5 = 176.25$
Segment D = $(73.8 + 16.4) \times 1.5 = 135.30$
Segment E = $(98.7 + 16.4) \times 0.5 = 57.55$
Point load = $40.0/2 \times 5.0 = 100.00$
Total = 849.35 kN
$H_z \times 4.24 = 849.35$
$H_z = 200.00$ kN



Figure 16.34 Arch profile for Example 3



Figure 16.35 Force diagram for dead and superimposed loading Example 3

The force diagram, shown in Figure 16.35, may now be plotted in the same manner as for Example 2. By inspection of the line thrust, a considerable eccentricity exists at approximately quarter span indicating that the profile of the arch is not as suitable as the circular arch analysed in the previous example.

Case (2): Dead plus Partial Superimposed Loading

Figure 16.36 shows the same arch profile with the superimposed loading on only half of the span and the revised line of resultant thrust which, clearly, is an even more critical design condition than that produced from the case (1) loading previously calculated.

The force diagram, shown in Figure 16.37, once again covers the full span owing to the asymmetrical loading.

The calculation of V_x, V_y, V_z, H_x, H_y and H_z follows the same procedure as for Example 2 and, in fact, gives identical values, i.e.

$V_x = 372$ kN $\quad V_y = 331$ kN $\quad V_z = 40.5$ kN
$H_x = 176.1$ kN $\quad H_y = 176.1$ kN $\quad H_z = 176.1$ kN



Figure 16.36 Load and segments for dead and partial superimposed loading Example 3



Figure 16.37 Force diagram for dead and partial superimposed loading Example 3

Appendix 1 Materials

A1.0 Introduction

The previous specifications for masonry units, i.e. BS 3921 *Specification for Clay Bricks*; BS 6073–1 *Specification for Precast Concrete Masonry Units*; BS 187 *Specification for Clay and Calcium Silicate (sandlime and flintlime) Bricks*; BS 6649 *Specification for Clay and Calcium Silicate Modular Bricks*; have been replaced with BS EN 771, Part 1 *Clay Masonry Units*; BS EN 771, Part 2 *Calcium Silicate Masonry Units*; BS EN 771, Part 3 *Aggregate Concrete Masonry Units (Dense and lightweight aggregates)*; BS EN 771, Part 4 *Autoclaved Aeroated Concrete Masonry Units*.

BS EN 771 is a performance standard unlike the previous British Standards. It does not specify unit sizes nor does it provide details of unit strength classes. The unit sizes and strength values are to be provided by the manufacturer along with other properties such as type of unit, dimension and tolerance, configuration, gross and net density and tolerances, compressive strength and others. BS EN 771 specifies the number and types of tests to be undertaken on units in order to produce this information. Each part of BS EN 771 specifies units as either Category I or Category II masonry units. Category I masonry units are those with a declared compressive strength with a probability of failure to reach this strength of less than 5%. Category II units are those which do not satisfy this criterion.

BS EN 771 states that a manufacturer may use a classification system to specify the properties of masonry units, provided that the system is based only on single properties included within BS EN 771 and does not constitute a barrier to trade. BS EN 771 does however permit details of classification systems in current use to be given in informative national annexes. Annexes in BS EN 771 can be normative or informative, normative being part of the standard and therefore part of any compliant requirement while informative annexes are provided to give guidance to professionals and are not part of any compliant requirement.

A1.1 Clay Masonry Units (Clay Bricks)

BS EN 771–1 *Specification for Clay Masonry Units* supersedes BS 3921 (*Specification for Clay Bricks*) which will be withdrawn in January 2005. This appendix is therefore based generally on BS EN 771–1.

A1.1.1 Sizes

BS EN 771–1 does not specify standard sizes for clay masonry units since it has been prepared to encompass all clay bricks and blocks available throughout Europe.



Figure A1.1 Brick dimensions

The standard clay brick of worksize 215 mm × 102.5 mm × 65 mm will still be available in the UK. This is the actual size of the brick. However, as bricks are laid in mortar, it is convenient to consider the size of the brick plus its share of the mortar joints. This measurement is termed the coordinating size under BS EN 771–1. As a 10 mm joint is normal, the coordinating size becomes 225 mm × 112.5 mm × 75 mm, as illustrated in Figure A1.1.

Although there is only one British Standard size of brick, some manufacturers also produce modular bricks to meet the needs of dimensional coordination. These sizes are given in BS 4729: 2004. Coordinating format sizes are as follows:

2M $200 \times 100 \times 100$ mm
$200 \times 100 \times 75$ mm

3M $300 \times 100 \times 100$ mm
$300 \times 100 \times 75$ mm

As bricks are made from clay, which is fired in kilns at very high temperatures, some variation in size is to be expected. Such differences are not generally significant in large areas of brickwork, but may be so in smaller elements. Problems can arise if two different suppliers are used for the opposite leaves of a cavity wall, in that there may be difficulties in tying the two leaves together.

A1.1.2 Classification

Low density (LD) units comprise clay masonry units with a gross dry density of less than or equal to 1000 kg/m^3 for use

on protected masonry. High density (HD) units comprise all clay masonry units for use in unprotected masonry or clay units with a gross dry density greater than 1000 kg/m^3 for use in protected masonry.

BS EN 771–1 specifies requirements and properties for each of the LD and HD units in terms of:

- *Dimensions and tolerances* – Methods for determining these values which must be declared by the manufacturer.
- *Configuration* – BS EN 771–1 shows general examples of LD units which tend to be perforated units. The manufacturer should declare the shape of the masonry unit and the direction and percentage of voids. This shall also include the minimum thickness of shells and webs and the area of grip holes, where provided.
- *Density* – The manufacturer shall declare the gross dry density of the units, as well as the net dry density of the units.
- *Compressive strength* – The mean compressive strength shall be declared by the manufacturer. Compressive strength in BS EN 771–1 is to be provided by the manufacturer with respect to the orientation of the clay masonry units as tested, the methods of bedding the units and whether any voids are fully fitted with mortar.

Variety

The masonry industry traditionally in the UK generally uses three types or varieties of clay bricks, which are:

(a) *Common*: Any brick for general building work, but not specifically chosen for its attractive appearance.
(b) *Facing*: Any brick specially made or selected for its appearance.
(c) *Engineering*: A brick having a dense and strong semi-vitreous body conforming to defined absorption and strength limits (unlike common or facing bricks which only have a minimum strength requirement, and no particular absorption limits).

Quality

(a) *Internal*: Bricks for internal use only. Internal quality bricks may require protection during construction in winter.
(b) *Ordinary*: Less durable than special quality bricks, but normally durable on the external face of a building above dpc level.
(c) *Special quality*: Durable in conditions of severe exposure where they may be liable to be wet and frozen, e.g. below dpc level, retaining walls, etc.

Type

Six types are defined:

(a) *Solid*: Having holes not exceeding 25% of the brick's volume, or frogs not exceeding 20% (a frog is illustrated in Figure A1.1).
(b) *Perforated*: Having holes in excess of 25% of the brick's volume, provided the holes are less than 20 mm wide or 500 mm^2 in area with up to three hand holds within the 25% total.
(c) *Hollow*: Having holes in excess of 25% and larger than defined in (b).
(d) *Cellular*: Having holes closed at one end which exceed 20% of the volume of the brick.
(e) *Special shapes*.
(f) *Standard specials*.

Note that the classifications of variety, quality and type are not related. For example, a common brick could be of internal quality or special quality, and could be of a solid type or cellular. Thus due to the permutations of variety, quality and type, plus the added variables of colour and texture, the range of bricks available is extremely wide. Designers should always take advantage of the wide choice available, and exercise care in selecting exactly the right brick for the job in hand. By far the majority of cases of unsatisfactory performance in use are attributable to an incorrect choice of brick.

Many other terms, either traditional and/or relating to manufacturing processes are still sometimes used to describe particular kinds of bricks. These, however, do not provide a sufficiently accurate description for design engineering purposes.

A1.1.3 Strength and Durability

From the structural viewpoint, the main classification of a brick is according to its compressive strength. The strength must, of course, be maintained for the required design life. So, the durability of a brick is just as important as its compressive strength, the latter of which is not necessarily an index of durability. Bricks having a compressive strength of over 48.5 N/mm^2 are usually durable, but there are bricks approaching this value which decay rapidly if exposed to frost in wet conditions. Conversely, there are many weaker bricks which are more durable. Durability should always be checked with the manufacturer.

It should also be remembered that walls are required to fulfil many other functions than that of providing resistance to direct compression loading and, for some of these purposes, the compressive strength of a particular brick is not necessarily the prime consideration.

Strength

The compressive strength of a brick relates to the characteristic strength value which may be used for design in accordance with BS 5628. The strength requirements for bricks, as set out in BS 3921, Table 4, are not reproduced in BS EN 771. However it is anticipated that the classification system can still be used in the UK (see Table A1.1 of this appendix). The National Annexe gives guidance on classification of traditional UK engineering bricks.

Due to the effect of the mortar, there is no direct relationship between the compressive strength of a particular brick and the strength of a wall built with it. Obviously though, a wall built with bricks of high compressive strength will have a greater loadbearing capacity than an identical wall built with bricks of lower compressive strength.

Table A1.1 Classification of bricks for use in loadbearing brickwork (BS 3921, now superseded)

	Class	Minimum average compressive strength (N/mm^2)
Engineering	A	69.0
	B	48.5
Loadbearing brick for brickwork designed to BS 5628	15	103.5
	10	69.0
	7	48.5
	5	34.5
	4	27.5
	3	20.5
	2	14.0
	1	7.0

Durability

Having considered the strength of bricks, and in order to ensure that their design strength is maintained, the question of durability must be considered. The main factors which can cause problems with bricks and brickwork are sulphate attack, frost attack and crystallisation of soluble salts.

Clay bricks may contain sulphates derived from either the original clay or its reaction with the sulphur compounds from the fuel used in firing. Sulphates may also be present in mortars, soils, gypsum plasters and polluted atmospheres.

In persistently wet conditions, sulphates react slowly with tricalcium aluminate – a constituent of Portland cement and hydraulic lime – causing it to expand, and thus bring about cracking or spalling of the mortar joints and, possibly, spalling of the bricks themselves. Sulphate attack is liable to occur in brickwork which remains wet for long periods, e.g. below dpc level, and parapets above roof level.

Thus it is important to ensure the best possible protection by: (a) a correct choice of brick; (b) correct detailing practice. Regarding the first of these provisions, maximum acceptable levels of sulphate content for bricks to be used in exposed situations are recommended in National Annexe to BS EN 771–1. In addition, resistance to attack can be further reduced by the use of fairly rich mortar mixes (see Tables A1.4 and A1.5). Brickwork which suffers sulphate attack will expand, and the provision of joints in the work can reduce the resulting problems. However bricks prone to sulphate attack should be used with caution and in particular damp environments should be avoided. Sulphate attack can also occur from contact with sulphate soils and fills and chimneys subject to certain flue gases. Further information on this aspect is provided in Appendix 3.

The resistance of a particular type of brick to frost attack is best measured by prolonged exposure to the conditions likely to be met in use. Special quality bricks as defined in Table A1.1, should have performed satisfactorily for three years under similar conditions to those occurring in use. A critical condition arises in situations where bricks may be frozen while saturated. As in the case of sulphate attack, sound detailing and a correct choice of brick are required. It is also particularly important that work in the course of construction should be protected, since sections not specifically designed for high resistance to frost may easily become saturated and then frozen.

The crystallisation of soluble salts in bricks often causes a white deposit, known as efflorescence, to appear on the surface of brickwork. While not being particularly harmful in general, efflorescence is unsightly. Occasionally, though, it can lead to the decay of underfired bricks, if the salts crystallise out beneath the faces.

The liability to efflorescence depends on the soluble salt content of the bricks (see BS 3921, and refer to manufacturers' data) and on the wetting and drying conditions. Again, the risks can be substantially reduced by sound detailing and the correct choice of brick to suit the exposure conditions.

A1.1.4 Testing

The allowance in BS 3921 of up to 25% of holes in a solid brick is omitted from BS EN 771–1. The manufacturer is only required to provide details of among others, compressive strength and percentage of voids.

A method of testing the crushing strength of clay bricks is described in BS EN 772–1.

A1.2 Calcium Silicate Units (Bricks)

Calcium silicate (sand–lime and flint–lime) bricks should conform to the requirements of BS EN 771–2. Although, in the past, they were mainly used for non-loadbearing work, improvements in manufacturing techniques accompanied by an increase in compressive strength make them suitable for loadbearing masonry.

Although possessing broadly similar functional properties to clay bricks, they have different movement characteristics, and the manufacturer's advice should be sought on the spacing of movement joints (see also Appendix 3).

As in the case of clay bricks, BS EN 771–2 is a performance standard unlike the previous British Standards. It does not specify unit sizes nor does it provide details of unit strength classes. The unit sizes and strength values are to be provided by the manufacturer along with other properties such as type of unit, dimension and tolerance, configuration, gross and net density and tolerances, compressive strength and others. BS EN 771 specifies the number and types of tests to be undertaken on units in order to produce this information. Each part of BS EN 771 specifies units as either Category I or Category II masonry units. Category I masonry units are those with a declared compressive strength with a probability of failure to reach this strength of less than 5%. Category II units are those which do not satisfy this criterion.

BS EN 771 states that a manufacturer may use a classification system to specify the properties of masonry units,

provided that the system is based only on single properties included within BS EN 771 and does not constitute a barrier to trade. BS EN 771 does however permit details of classification systems in current use to be given in informative national annexes. Annexes in BS EN 771 can be normative or informative, normative being part of the standard and therefore part of any compliant requirement, while informative annexes are provided to give guidance to professionals and are not part of any compliant requirement.

A1.3 Concrete Bricks

Concrete bricks are now included under BS EN 771–3 for concrete units.

A1.4 Stone Units (Stonework)

Stone masonry should comply with the requirements of BS EN 771, Parts 5 and 6, maufactured and natural stone units respectively. Because of its high initial cost and the expense of skilled labour, stonework is rarely used structurally in industrialised countries, except in conservation areas, and is mainly restricted to facing veneers on prestige buildings. However, it could still be an economical proposition in developing countries with adequate indigenous supplies of good stone and experienced masons.

A1.5 Concrete Units (Blocks and Bricks)

Concrete bricks and blocks are produced in a great variety of sizes, and are generally described in BS 2028, BS 1364, and BS 1180. BS EN 771–3 makes no differentiation between bricks and blocks but includes all concrete masonry elements under this one specification.

A1.5.1 Sizes

Sizes are not specified in BS EN 771–3. However the National Annexe provides typical coordinating sizes and work sizes. The work size is the size of the block itself. The 'concrete block' sizes specified in BS 2028 and BS 1364 are provided in Table A1.2, but please note that although the previous classification, i.e. Types A–C have been included, classification is not included in BS EN 771–3 and cannot be specified as this could constitute a barrier to trade.

It can be seen that there is a very wide and confusing variety of standard block sizes. Not altogether surprisingly, the current trend is for manufacturers to reduce their range of standard sizes – the blocks at the larger end of the scale tending to be discarded.

Ideally, the sizes should be such as to facilitate ease of handling, with regard to health and safety, e.g. issues of manual lifting. The larger solid blocks can and do exceed the maximum manual lifting weight of 20 kg. In addition, the thicker blocks tend to be difficult to grasp, unless provided with special hand grips. On the other hand, however, the economics of manufacturing require the largest possible units to be produced by the blockmaking machines. Thus the actual sizes of the blocks tend to be a compromise between these conflicting requirements.

Table A1.2 Range of concrete block sizes (previously BS 2028 and BS 1364, and generally conforming to National Annexe to BS EN 771–3)

Block	Length and height (mm)		Thickness (mm)
	Co-ordinating size	Work size	Work size
Type A	400 × 100	390 × 90	75, 90, 100
	400 × 200	390 × 190	140 and 190
	450 × 225	440 × 215	75, 90, 100, 140 190 and 215
Type B	400 × 100	390 × 90	75, 90, 100
	400 × 200	390 × 190	140 and 190
	450 × 200	440 × 190	75, 90, 100, 140
	450 × 225	440 × 215	190 and 215
	450 × 300	440 × 290	
	600 × 200	590 × 190	
	600 × 225	590 × 215	
Type C	400 × 200	390 × 190	60 and 75
	450 × 200	440 × 190	
	450 × 250	440 × 215	
	450 × 300	440 × 290	
	600 × 200	590 × 190	
	600 × 225	590 × 215	

While it is slower to lay blocks than bricks, since they are larger than bricks, the rate of walling production is not necessarily adversely affected.

A1.5.2 Classification

BS EN 771–3 gives more of a performance specification for concrete units, rather than detailed descriptions of their manufacture. Thus virtually any suitable materials may be used, provided the blocks meet the specifications.

A1.5.3 Density

The three types, A, B and C, previously stated in British Standards have now been omitted from BS EN 771–3 which only requires the manufacturer to specify the gross and net density of each particular unit.

A1.5.4 Form

BS EN 771–3 does not differentiate between solid, hollow or cellular units. The manufacturer only needs to specify these properties for each particular unit.

A1.5.5 Strength

The strength of concrete units is determined by compressive testing – the method being described in BS EN 772–1. The specified compressive strengths for Types A and B are provided in Table A1.3, although it must be stated that this is for comparison only as Types A and B cannot be specified under BS EN 771–3.

A1.5.6 Durability

As with brickwork, one of the main requirements to ensure durability is correct construction detailing. Correctly

Table A1.3 Compressive strengths of concrete blocks Type A and Type B

	Minimum compressive strength	
Block type and designation	Average of ten blocks (N/mm^2)	Lowest individual block (N/mm^2)
A(3.5)	3.5	2.8
A(7)	7.0	5.6
A(10.5)	10.5	8.4
A(14)	14.0	11.2
A(21)	21.0	16.8
A(28)	28.0	22.4
A(35)	35.0	28.0
B(2.8)	2.8	2.25
B(7)	7.0	5.6

detailed blockwork is generally durable, whatever the type of block.

The durability of concrete blocks is comparable to that of good concrete. If suitable joints are provided to cope with thermal and moisture movements, as described in Appendix 3, serious deterioration is unlikely.

The appearance of blockwork, particularly if open-textured blocks are used, can be marred by the effects of pollution. A problem of algae growth on the face of blockwork, during construction, has been encountered by the authors, but such effects are unlikely to affect the strength of blockwork.

A1.6 Mortars

The role of the mortar between the bricks or blocks used in a structural element is very important and complex. There are requirements to be met by the mortar, both in the freshly made and hardened states. During construction, it must be easily workable – it must be spread easily and remain plastic long enough to enable lining and levelling of the units. It must also retain water, so that it does not dry out and stiffen too quickly with absorbent units. It must then harden in a reasonable time to prevent squeezing out under the weight of the units laid above. On completion of the day's work, the mortar must have gained sufficient strength to resist frost.

When hardened, in the finished structure, the mortar must transfer the compressive, tensile and shear stresses between adjacent units, and it must be sufficiently durable to continue to do so. However, while adequate strength is essential, only the weakest mortar consistent with the strength and durability of the bricks or blocks should be used. When a suitably matched mortar is used, any cracking from thermal or other movements will occur at the joints. Cracks in the mortar tend to be smaller and easier to repair than cracks in the masonry units. In any case, the use of a stronger mortar does not necessarily produce a stronger structural element, because mortar strength is not directly related to the strength of the masonry built with that mortar.

For any particular strength of unit, there is an optimum mortar strength, and a stronger mortar will not increase the strength of the brickwork or blockwork. Particular care is needed when choosing a mortar for use with the lower strength blocks to ensure that it is of sufficiently low strength to confine any cracking to the joints. On the other hand, richer mortars, which develop strength quickly enough to resist frost, are obviously to be preferred for winter working in that, if a lean mortar is specified, additional precautions will be required.

Masonry should be laid on a *full* bed of mortar and, if bed joints are raked out for pointing, allowance must be made in the design for the decreased width as well as the resulting loss of strength.

A1.6.1 Constituents

Mortars generally consist of sand and water in combination with one or more of the following:

(a) lime
(b) Portland cement
(c) sulphate-resisting Portland cement
(d) masonry cement
(e) high alumina cement
(f) plasticisers or other additives
(g) pigments.

Portland cement, in one or other of its several forms, is the principal binding agent in mortars. It is used because of its comparatively rapid strength gain and quick setting rate. Very high strengths are obtainable from cement : sand mortars, e.g. 1 : 3 cement : sand, but these are not generally required except for very exposed conditions, such as below dpc level or in retaining walls.

Lime is normally added to mortars to improve their workability and bonding properties, although this does result in some loss of strength. Probably the most commonly used mix is a 1 : 1 : 6 cement : lime : sand, which is suitable for most applications.

As an alternative to lime, plasticisers, which entrain air into the mortar, are often used to improve workability. Lime requires special handling, and the use of plasticisers can show economies in labour and material costs. Among other things, the entrainment of air is also claimed to improve frost resistance. However, the entrainment of air bubbles inevitably reduces the strength of the mortar. This can be a difficult problem to control on site, in that plasticisers are often added by the masons themselves, somewhat indiscriminately. For this reason, and others such as the effects on wall ties, reinforcement, and the long-term weakening of the mortar, care should be taken to obtain up-to-date and reliable information before considering the use of any plasticiser or similar additive.

Note that frost inhibitors based on calcium chloride, or calcium chloride itself, should never be used, since these cause long-term weakening of the mortar and excessive corrosion of wall ties and reinforcement.

Masonry cement consists of Portland cement with the addition of a very fine mineral filler and an air-entraining agent. Masonry cement should be used with caution. The

Table A1.4 Mortar mixes (proportions by volume)

		Mortar designation	Type of mortar (proportion by volume)			Mean compressive strength at 28 days (N/mm^2)	
			Cement : lime : sand	Masonry cement : sand	Cement : sand with plasticiser	Preliminary (lab) tests	Site tests
↑ Increasing strength	↓ Increasing ability to accommodate movement, e.g. due to settlement, temperature and moisture changes	(i)	1 : 0 to 1/4 : 3	–	–	16.0	11.0
		(ii)	1 : 1/2 : 4 to 4 1/2	1 : 2 1/2 to 3 1/2	1 : 3 to 4	6.5	4.5
		(iii)	1 : 1 : 5 to 6	1 : 4 to 5	1 : 5 to 6	3.6	2.5
		(iv)	1 : 2 : 8 to 9	1 : 5 1/2 to 6 1/2	1 : 7 to 8	1.5	1.0
			Increasing resistance to frost attack during construction →				
			← Improvement in bond and consequent resistance to rain penetration				

Note: Direction of change in properties is shown by the arrows

presence of the mineral filler reduces strength, and the comments above on the use of plasticisers also apply.

High alumina cement should not be used.

A.1.6.2 Choice of Mortar

Tables A1.4 and A1.5, reproduced from *BRE Digest 160*, give guidance on the selection of particular mortars for various applications. To avoid any confusion on site, the number of different mixes to be used on any one project should be kept to a minimum. It is also worth noting that the extra cost of making a good mortar is an insignificant proportion of the total cost of a wall. There is little point – indeed it is a false economy – in trying to produce a cheap inferior mortar.

A1.6.3 Proportioning and Mixing

Mortar is usually mixed on site in small batches, and strict control must be kept on the quality. Positive measures should be taken to ensure that only the specified materials are used and are mixed in the correct proportions. Where large areas of structural masonry are being constructed, weigh batching should be employed.

Allowance must be made for the increase in volume and weight of the sand when it is damp – whatever method is used for gauging the proportions of the mix. On large contracts, consideration should be given to the production of several trial mixes so as to ensure the quality of the mortar.

If weigh batching is not justified by the quantity of the work, gauge boxes should be used. These should be filled level to the top in order to provide the correct mix proportions.

Lime and sand, termed the 'coarse stuff', may be obtained ready mixed for delivery to the site. However, as mixing is done off the site, some degree of control is lost. The use of coarse stuff is preferable to mixing cement, lime and sand dry, because the bulking of the sand can be allowed for, and the lime becomes more plastic when soaked overnight. The previous standard BS 4721 *Specification for Ready Mixed Lime : Sand Mortar*, gave mix proportions for use when batching by volume was employed. This has now been replaced by BS EN 998–2, which, as all other BS EN specifications, is not prescriptive and does not include prescribed mixes. However BS EN 998–2 specifies mortar strengths in classes M1, M2.5, M5, M10, M15, and M20, where the compressive strength of each is 1, 2.5, 5, 10, 15, and 20 N/mm^2 respectively. Table A1.4 is reproduced from BS 4721 for guidance and comparison only.

Where a range of sand contents is given, the larger quantity should be used for sand that is well graded and the smaller for coarse or uniformly fine sand.

Because damp sands bulk, the volume of damp sand used may need to be increased. For cement : lime : sand mixes, the error due to bulking is reduced if the mortar is prepared from lime : sand coarse stuff and cement in appropriate proportions; in these mixes 'lime' refers to non-hydraulic or semi-hydraulic lime and the proportions given are for lime putty. If hydrated lime is batched dry, the volume may be increased by up to 50% to get adequate workability.

A1.6.4 Testing

As noted earlier, the properties of freshly mixed and hardened mortar are both very important in ensuring that the design requirements are met. Various testing methods are dealt with in the various parts of BS EN 1015. Samples of the mortar are taken on site and prisms or cubes are prepared, similar to those taken for the testing of concrete.

Table A1.5 Selection of mortar groups

	Type of brick			
	Clay		Concrete and calcium silicate	
Early frost hazard[a]	No	Yes	No	Yes
Internal walls	(v)	(iii) or (iv)[b]	(v)[c]	(iii) or plast (iv)[b]
Inner leaf cavity walls	(v)	(iii) or (iv)[b]	(v)[c]	(iii) or plast (iv)[b]
Backing to external solid walls	(iv)	(iii) or (iv)[b]	(v)	(iii) or plast (iv)[b]
External walls; outer leaf of cavity walls:				
– above damp proof course	(iv)[d]	(iii)[d]	(iv)	(iii)
– below damp proof course	(iii)[e]	(iii)[b,e]	(iii)[e]	(iii)[e]
Parapet walls; domestic chimneys:				
– rendered	(iii)[f,g]	(iii)[f,g]	(iv)	(iii)
– not rendered	(ii)[h] or(iii)	(i)	(iii)	(iii)
External free-standing walls	(iii)	(iii)[b]	(iii)	(iii)
Cills; copings	(i)	(i)	(ii)	(ii)
Earth-retaining (back filled with free draining material)	(i)	(i)	(ii)[e]	(ii)[e]

[a] During construction, before mortar has hardened (say 7 days after laying) or before the wall is completed and protected against the entry of rain at the top
[b] If the bricks are to be laid wet, a plasticiser may improve frost resistance (see also section A1.6.1)
[c] If not plastered use group (iv)
[d] If to be rendered, use group (iii) mortar made with sulphate-resisting cement
[e] If sulphates are present in the groundwater, use sulphate-resisting cement
[f] Parapet walls of clay units should not be rendered on both sides; if this is unavoidable, select mortar as though not rendered
[g] Use sulphate-resisting cement
[h] With special quality bricks, or with bricks that contain appreciable quantities of soluble sulphates

Six 100 mm × 25 mm × 25 mm prisms or six 75 mm or 100 mm cubes should be prepared on site for every 150 m^2 of wall, using any one designation of mortar, or for every storey of the building, whichever is the more frequent. Specimens should be stored and tested in accordance with BS 4551.

Half of the site samples should be tested at 7 days. The average strength should exceed two thirds of the appropriate 28-day strength given in Table 5.3.

When the site samples are tested at the age of 28 days, the mortar will be deemed to pass if the average of the six values obtained from three 100 mm × 25 mm × 25 mm prisms or the average of the values obtained from three cubes exceeds the appropriate site values given in Table 5.3.

The results are then compared with the values specified for the work, in order to determine whether the mortar is acceptable.

Chemical analysis of mortar can be made, and is useful for the following purposes:

(1) Assessment of the efficiency of mixing and the accuracy of batching on sites, in mixing plants and laboratories.
(2) Analysis of recently placed mortar for assessment of compliance with specification requirements, and the investigation of failures.
(3) Analysis of old mortars for the investigation of failures and, in the case of very old mortars, for assessing their type and chemical composition.

Chemical analysis may thus be used to provide a further check if compressive testing of cubes is producing low results. It should be remembered, however, that all such testing methods have limitations, especially when applied to a material of the nature of mortar. Test results should only be used as a guide, and not as a final judgement, depending, of course, on the size and nature of the work involved.

Appendix 2 Components

In determining the suitability of any structural components, it is first essential to consider the purpose for which they are to be used, the practicality of construction, the control over workmanship, and the life expectancy of the material in relation to the life requirements of the structure. In loadbearing masonry, there are a number of components, and care should be exercised in their choice and specification.

A2.1 Wall Ties

Wall ties are used mainly to tie together unbonded leaves of masonry, and there are a number of different types and qualities. In cases where the component is required to tie the leaves across the cavity, and to provided some interaction between them, a traditional vertical twist tie is most suitable. However the fishtail ends of these ties produce a risk of cuts on site and should not be specified. The manufacturers have produced a range of alternative safety ties, although it should be noted that these are generally less robust than the traditional vertical twist tie. In locations where differential movements are to be expected between the leaves, and little interaction is required, a more flexible type of tie is desirable.

In special circumstances, where high shear resistance is required across the tied joint, purpose-designed shear ties may be necessary.

In all cases, durability in relation to the severity of the corrosive environment is an important factor that merits close attention. As far as possible, the environment should be controlled, and thought should be given to the corrosive effects of building materials – particularly calcium chloride (see Appendix 1, A1.6.1) and certain colouring agents, the use of which should be avoided wherever possible.

In some locations, such as junctions where restraint is required but an unbonded joint is desirable, tie bars or standard bed joint reinforcement can be used to provide the necessary tie action. In external walls, or where required by Building Regulations, stainless steel or suitable non-ferrous ties should be used.



Figure A2.1 British Standard types of wall ties

Standard wall ties should conform to the requirements of BS EN 845, Part 1, and maximum centres for spacing should be in accordance with BS 5628, or a lesser figure to suit the design conditions. Minimum embedment should also comply with BS 5628. Examples of various ties are shown in Figure A2.1. The authors recommend that butterfly ties are only used in minor structures.

A2.2 Damp Proof Courses

The purpose of damp proof courses is to form a barrier to cut off the movement of dampness from an external source to the building fabric. But, through necessity, they sometimes have to be located where structural forces must also be transferred, and care is needed to ensure that the chosen membrane can transfer these forces. Two common examples are:

(a) horizontal dpc to prevent vertical movement of moisture, located in a position where high compression, shear and bending stresses are to be resisted;
(b) vertical dpc to prevent horizontal movement of moisture from outer to inner leaves of brickwork, located in a position where vertical shear forces are to be resisted.

Thus a dpc must not squeeze out under vertical loading, nor slide under the horizontal loading.

Damp proof courses can be made from a wide variety of materials such as bitumen felt, metals, slate, plastic, brick, etc., and the choice must be based on the required performance related to the material's proven performance. Bitumen felt type dpcs, for example, are usually the least expensive but suffer from poor resistance to compressive forces and can, therefore, squeeze out under load. They can also be damaged by careless workmanship. On the other hand, the flexibility of felt or plastic dpcs can be of great importance where movements such as mining settlement, etc., are to be expected. A brick dpc can be very advantageous in providing resistance to tensile stresses at a critical cross-section, a property which few other membranes can provide. Brick dpcs are formed by specially selected engineering bricks (see Appendix 1, A1.1.2) built in a number of bonded courses to provide an impermeable barrier. These are generally less effective at resisting the movement of moisture compared to the membrane alternatives. Some typical horizontal dpcs are shown in Figure A2.2.

A2.3 Fixings

Components for providing fixings in brickwork are numerous, and the designer should be prudent when selecting



Figure A2.2 Some typical alternative damp proof courses

from manufacturers' catalogues. They can be very expensive, and the designer should carefully consider the type, sizes and costs of the various products available before specifying. Samples of fixings should be available in the design office for inspection, since, often, a component that appears in a catalogue to be a lightweight and economical fixing can be very disappointing in reality. In other cases, the designer may become aware of a weakness in the fixing, or see a practical construction problem related to the proposed use.

The forces to be taken on fixings must be considered since, if the masonry in the area around the fixing is weaker than that of the fixing itself, local failure of the masonry could occur. Particular care is needed for connections on the upper course of lightly loaded walls, and in locations where uplift forces are being resisted. Wherever possible, fixings should be located under similar conditions to that of the test specimen on which the manufacturer's performance data are based, otherwise additional testing or allowance for the differences will be made.

As with other components, the durability of fixings must be considered in the light of the expected environment. The choice of fixing materials must be compatible with other materials in the locality if problems such as electrolytic action, etc., are to be avoided.

A2.4 Brick Bonds

Although the bonding of masonry units is a technique rather than a component, it was nevertheless felt appropriate to discuss it in this appendix.

For loadbearing walls, properly bonded masonry is essential. For single-leaf masonry, and ordinary cavity walling, stretcher bond is the only choice available without the use of snap headers. This can create engineering problems if not taken into account at an early stage in the design (see Figure A2.3).

With thicker, solid walls, there appears to be little difference in the structural performance of the various standard bonds that have been used for many years. For walls of double leaf thickness and over, English bond is, perhaps, ideal. On the other hand, Flemish and its derivative English garden wall bond appear to give a similar structural performance under normal loading conditions and are, therefore, usually acceptable (see Figure A2.4).

Stretcher bonds on walls of double-leaf thickness or over require special consideration, and may necessitate the use of special shear ties.

There has been a move in recent years to construct walls with stack bonded masonry. This needs special consideration in order to replace the resulting loss of shear resistance caused by continuous perpend joints.



Figure A2.3 Effects of bonding masonry on lateral loading



stretcher bond (single leaf only)



English bond



Flemish bond



English garden wall bond

Figure A2.4 Some standard bonds

Appendix 3 Movement Joints

All materials move, and the designer must take account of the movements and make due allowance for them. Like other materials, the movement of masonry is caused by variations in the environmental conditions such as thermal changes, changes in moisture content, changes in loading conditions, chemical changes, foundation settlement, frost action, etc. (see Figure A3.1).

The causes of movement may operate singly, or in combination to supplement or oppose one another, and it is often very difficult to forecast precisely the movement that will occur in a particular situation. Nevertheless, the designer must try to anticipate the type and magnitude of movements, and the effect they are likely to have on the building.

If the movements act upon elements unable to contain the forces resulting from the movements, cracking is likely to occur. Where materials with different movement characteristics are bonded together, cracking is again likely to occur. Wherever possible, movement should be allowed to occur with minimum resistance, and carefully detailed movement joints should be provided to ensure that:

(a) the structural stability and performance of the jointed building is adequate,
(b) damage to the building and its finishes is kept within tolerable limits.

With all building materials, it is almost inevitable that some damage will occur, since the requirement to allow for movement frequently clashes with other needs – structural and non-structural – of the building. A compromise of carefully considered joints which control the damage within acceptable limits should be the designer's aim.

Where care is not taken, cracks and/or bulging may occur. In some situations, this can result in instability and become dangerous. In others it may be unsightly, and in some cases the condition deteriorates from the ingress of moisture into cracks and/or from the loosening of wall ties. Some typical failure conditions are shown in Figures A3.2 and A3.3.

Restraints which aggravate cracking may arise from the wall being fixed to, or built tightly around, some rigid unyielding feature at its ends; from some fixture to the wall; or where the wall incorporates materials of dissimilar properties. Cracking is most likely to occur at weakened sections, where the vertical or horizontal section of the wall changes abruptly (see Figure A3.4).

Correctly located and detailed control joints, taking into account restraints, the movement characteristics of the masonry, and any differential movements with other materials, will help to mitigate the detrimental effects of movement. Assessment of the likely locations of cracking needs particular care, in that a badly located joint might still allow critical cracking to occur at a more susceptible position.



Figure A3.1 Environmental conditions



Figure A3.2 Masonry expansion



Figure A3.3 Masonry contraction



Figure A3.4 Restraint to masonry movement

A3.1 Movement due to Thermal Expansion and Contraction

The major problems caused by thermal expansion and construction of masonry occur on long walls which are subjected to large variations in temperature, such as external walls exposed to sun and frost, walls around boilerhouses or refrigeration plants, etc. In the case of internal walls subjected to a reasonably constant temperature, there are a few problems, even on long walls, unless they are connected to other materials which are moving differentially, e.g. shrinking of blockwork at the time the expansion of the brickwork is occurring.

Particular care should be taken in the design of thin walls exposed directly to the sun, where surface wall temperatures may rise to 50°C (120°F). Such temperatures can give rise to bending as well as expansion of the wall, due to the thermal gradient through the wall thickness.

Extract from BS 5628, Part 3, 2001, Appendix B

> The theoretical free movement due to thermal effects, which is reversible, is equal to the temperature range multiplied by the appropriate coefficient of linear thermal expansion (see figure B1). However, the movement that actually occurs within a wall after construction depends not only on the range of the temperature but also on the initial temperature of the masonry units when laid. This will vary according to the time of year and the exact conditions during the construction period, and, in some cases, how soon after manufacture the masonry units are used, i.e. when they come straight from the kiln or curing chamber. Thus, in order to determine the potential free movement that could occur in a wall, some estimate of the initial temperature and the likely range of temperature should be made.
>
> This potential free movement then needs to be modified to allow for the effect of restraints.

Table A3.1 Linear thermal movement of masonry units and mortar (BS 5628, Part 3, 2001, Appendix B4, Table B1)

Material	Coefficient of linear thermal expansion (°C)
Fired-clay masonry units[a]	4 to 8 $\times 10^{-6}$
Concrete masonry units[b]	7 to 14 $\times 10^{-6}$
Calcium silicate masonry units	11 to 15 $\times 10^{-6}$
Mortars	11 to 13 $\times 10^{-6}$

[a] Thermal movement of fired-clay masonry units depends on the type of clay

[b] Thermal movement of concrete masonry units depends on the type of material and the mix proportions

> Table B1 indicates typical ranges for coefficients of linear thermal expansion. Some estimate of the actual value for the particular material being used should be made. In many instances, this information can be obtained from manufacturers. (*See Table A3.1.*)
>
> The longitude coefficient of thermal movement of masonry may be taken to be the same as that of the constituent masonry units.
>
> Expansions in the vertical direction may be determined by summing the values obtained by multiplying the dimensions of the masonry units and the mortar by the respective coefficients of linear thermal expansion. It should be borne in mind that the magnitude of movement in the horizontal and vertical directions will differ where the coefficients for the mortar and masonry units are not the same and when the masonry units' height and length are unequal.

The unrestrained thermal movement of a wall may be estimated very approximately from the likely change in mean wall temperature and the coefficient of thermal expansion, which is often taken as 5×10^{-6} per °C for fired-clay brickwork in a horizontal direction, and may be up to one-and-a-half times this value for clay brickwork vertically, and for calcium silicate brickwork and concrete blockwork.

Thermal movements vertically in walls are generally reversible. However, horizontal movements are unlikely to be completely reversible since some form of restraint, particularly near the bottom of the wall, does tend to prevent the masonry from returning to its original length.

A3.2 Movement due to Moisture

A3.2.1 Fired Clay Units

Clay bricks expand and contract with increases or decreases in moisture content, and these movements are normally negligible. However, superimposed over these changes, there is a permanent moisture expansion which depends on the type of clay and the degree of firing. The rate of this permanent expansion decreases with time. It starts to occur during cooling in the kiln and, in many cases, up to 50% of the first two years expansion takes place during the first two days (see Table A3.2).

Table A3.2 Moisture expansion of fired-clay brickwork

Walls built of bricks made from	Expansion at constant temperature (%)			
	Total after 15 days	Rate per 10 days after 15 days[a]	Total after 300 days	Rate per 10 days after 300 days[a]
Glacial clay	0.015	0.0026	0.039	0.0004
Coal measure shale	0.014	0.0027	0.050	0.0008

[a] Covering the 5-day period either side of the 15- and 300-day period

Table A3.3 Expansions of fired-clay units resulting from changes in moisture content

Clay from which units were made	Irreversible expansion[a] (% calculated on original dry length) for bricks fired to average works temperature		Wetting movement[b] (%)
	From kiln hot to 2 days	From 3 days to 128 days	Generally less than 0.02 unless under-fired
Lower Oxford	0.03	0.03	
London stock	0.05	0.02	
London clay	0.02	0.03	
Keuper marl	0.03	0.03	
Weald clay	0.08	0.04	
Carboniferous shale	0.04	0.07	
Devonian shale	0.03	0.05	
Gault	0.02	0.01	

[a] The expansions quoted have been obtained from measurements made on unrestrained specimens. The bricks were removed from the furnace at 200°C, cooled in a desiccator and measured immediately they were cold

[b] Measured by the method that was described in BS 1257 *Methods of Testing Clay Building Bricks* (now withdrawn and replaced by BS EN 772)

The solution is to avoid using kiln-fresh bricks, and bricks manufactured from clays with an unusually high moisture movement, in critical locations (see Table A3.3).

A3.2.2 Concrete and Calcium Silicate Units

While fired-clay units expand after manufacture due to the increase in moisture content, concrete and calcium silicate units dry out and shrink (see Tables A3.4 and A3.5). If wetted, the units will expand again – but only part of the initial drying shrinkage is reversible. In addition, non autoclaved units are subject to a slow non-reversible carbonation shrinkage, and should be stored for at least 4 weeks at normal temperature (longer in cold weather), and exposed to the wind but protected from rain prior to use. Autoclaved concrete and calcium silicate products need only a sufficient storage period to allow them to cool, but they should be kept dry prior to and during construction – which can, at times, be very difficult. For units in locations where large variations in temperature and humidity are to be expected, special precautions are necessary. For example, for short-term variations, the use of plaster or render on both sides of the units can considerably reduce the effects. Reference to CP 211 and CP 221 is recommended for further information. It must be emphasised that the drying shrinkage of calcium silicate and concrete units can be a major problem, and requires particular care in design and construction.

Table A3.4 Moisture movement of concrete and calcium silicate masonry units (BS 5628, Part 3, 2001, Appendix B5, Table B2)

Material and type of masonry unit:	Shrinkage (as % of original dry length)
Autoclaved aerated concrete masonry units	0.04 to 0.09
Other concrete masonry units	0.02 to 0.06
Calcium silicate bricks	0.01 to 0.04

Note: These figures were obtained from tests carried out as described in BS 1881; Part 5. Note that these tests are now carried out in accordance with BS EN 772

Table A3.5 Shrinkage of mortars due to change in moisture content (BS 5628, Part 3, 2001, Appendix B5, Table B3)

Stage	Shrinkage (%)
Initial drying	0.04 to 0.10
Subsequent reversible movement	0.03 to 0.06



Figure A3.5 Sulphate attack example

A3.3 Movement due to Chemical Interaction of Materials (Sulphate Attack)

The causes and effects of sulphate attack were outlined in Appendix 1, section A1.1.3. One of the most damaging effects is expansion of the mortar. This can cause deformation of the masonry – a common example being domestic chimneys (see Figure A3.5).

In some cases, the condition can become dangerous. However, careful detailing and choice of materials in line with the recommendations of this appendix can prevent that situation arising. For example, for the chimney shown, the use of bricks with a low sulphate content, and a sulphate-resisting cement : sand mortar, plus the addition of a flue liner in the chimney would probably have prevented the occurrence.

A3.4 Differential Movement with Dissimilar Materials and Members

Where a wall has a concrete roof, floors or beams spanning onto it, consideration must be given to the potential effects of shrinkage and/or expansion of concrete. For example, a large concrete roof on a loadbearing clay brick structure will be subjected to drying shrinkage for the first few years of its life, together with some expansion and contraction due to the varying temperature range to which it will be exposed. At the same time, the clay bricks below will be subjected to moisture expansion and thermal effects. At certain times, therefore, the materials could be attempting to move in opposite directions and, unless precautions are taken, unsightly cracking will result (see Figure A3.6). To reduce the effect of this movement, certain details can be incorporated in the construction (see Figure A3.7).

At the end of a long run of beams seated on piers, there is a danger of vertical cracking in the piers, due to shrinkage of the concrete beams (see Figure A3.8). In those locations, a suitable padstone should be used, and a slip plane provided between the pad and the beam seating (see Figure A3.8).

With long runs of masonry built of concrete nibs, there is a danger of unsightly cracking, particularly at changes in direction and/or the end of runs – see the elevation in



Figure A3.6 Movement of dissimilar materials



Figure A3.7 Slip plane provision



Figure A3.8 (a) Shrinkage of concrete beam, (b) provision of slip plane

Figure A3.9. The detail should incorporate a slip plane between the nib seating and the first brick course, for example, a dpc membrane (see section in Figure A3.9). The masonry should also be jointed vertically, in accordance with the recommendations of this appendix, to reduce the amount of differential movement to an acceptable level.

Where a wall is built on a floor which may deflect significantly under load, the wall should be separated from the floor, including any screed, by a separating layer, and should be strong enough to span between the points of least deflection. This applies in particular to concrete block walls supported on concrete floors and beams, where relatively small deflections of the supporting members will result in the wall arching and cracking (see Figure A3.10).

It is not only when other members come into contact with masonry that differential movement occurs.



Figure A3.9 Slip plane in long runs of masonry



Figure A3.10 Walls supported on floors subject to deflection

For example, consider a cavity wall with concrete bricks for the internal leaf and clay bricks for the outer leaf (see Figure A3.11). The outer leaf will expand due to moisture movement and temperature changes, while the inner leaf will contract due to drying shrinkage and load strain. The changes in length will need to be considered since, in multi-storey work the build-up of vertical movement could cause buckling of the outer leaf and/or loosening of the wall ties. Joints should be incorporated to accommodate this movement, for example, by the introduction of a compression joint below a support slab at alternate or every third floor within the building (see Figure A3.11), the joint location and thickness being designed to absorb the anticipated movement without damage. If necessary, brick slip tiles can be adhered to the face of the concrete slab to achieve a continuous ceramic finish.

A3.5 Foundation Settlement

For foundations where differential settlement is within reasonable limits, and where the correct mortar mixes are used (see section A3.8), masonry structures are generally flexible enough to accommodate the movement without any detrimental effects. In locations where more severe settlements are likely, such as mining areas, large buildings should be jointed into smaller independent units where large strains and bending moments can be kept under control. For example, in areas of future mine workings, the smaller the unit the more economical the design of the foundations. On the other hand, the cost of providing the joints in the superstructure, and the problems of providing stability, will increase in proportion to the number of joints. It is important, therefore, to reach a reasonable compromise which, in mining areas, would generally be to limit the length of a unit to 20 m. Provided that the foundations and joints (see section A3.6) are then designed for the particular site conditions, in accordance with good practice, problems should not occur.



Figure A3.11 Cavity wall details

A3.6 Movement of Joints and Accommodation of Movement

In sections A3.1 to A3.5, movements due to changes in temperature, changes in moisture content, chemical interaction, dissimilar materials in contact with each other and foundation settlements have been discussed. In some cases, the solutions to the problems have also been considered. But the location and type of joint, which should be used, have not. The reason for this seeming omission is that while the causes of the various movements are different, there is, on most buildings, a need to accommodate a number of differing forms of movement. These movements may occur at different times, or at the same time; they may be additive, or they may cancel each other out. Joints designed for one form of movement may accommodate another. On the other hand, they may aggravate the problems in the building. The design of joints should, therefore, be based on assessment of all the movements likely in the particular building, and all the requirements that may be aggravated by the inclusion of joints.

This is probably best clarified by considering an example. A long block of four-storey flats is to be constructed in a mining area, mined by modern, deep, long-wall techniques. The flats are to be built in loadbearing brickwork. Clay bricks are to be used for the outer leaf of the external cavity walls and the loadbearing crosswalls, but concrete bricks will be used for the inner leaf of the external walls. Floors are to be insitu concrete construction.

Consideration for this building would be:

(a) to joint the length of flats into units less than 20 m long, in order to bring the ground strains resulting from the mining within acceptable limits that can be accommodated within, say, a 75 mm wide joint between units.
(b) to check that expansion and contraction from temperature changes are controlled by suitable expansion joints. This condition could normally be expected to be controlled within the joint provided for mining strain and, to check this, a calculation for the total mining strain plus the effects of expansion would need to be compared with the amount of strain that can be accommodated by the joint and the jointing materials.



Figure A3.12 Differential movements

(c) to check the effects of moisture movement, a combination of conditions must be considered, i.e. moisture movement and the movement of dissimilar materials. For example, the outer leaf of clay bricks will be expanding due to moisture expansion after firing, but the load strain on this leaf will partially cancel out this growth. At the same time, the inner leaf of concrete bricks will be contracting due to drying shrinkage and load strain (see Figure A3.12).

These movements will not only be occurring vertically, but will also have an effect horizontally where shrinkage of the concrete floor slab will be adding to the problem.

The typical floor plan and vertical sections shown in Figure A3.13 indicate how vertical control joints can be accommodated in the concrete brickwork, how horizontal control joints can be provided, and how the floor slab can be jointed to reduce the detrimental effects of shrinkage.

It should be noted that, since these joints affect the structural stability of the building, it is important that this is considered when locating them, and the effects of the weak zones within the building, since movement will occur in these areas. Having located the joints, a stability check should be made taking all the joints into account.

The jointing shown in Figure A3.13 is only provided as a typical example. It must be emphasised that, for any particular building, the joints must be specifically designed to suit the materials being used and the conditions to which the structure will be subjected.



Figure A3.13 Typical example of movement joints

A3.7 Jointing Materials and Typical Details

While each joint must be designed for the movement, or movements, to be accommodated, there are a number of general points to consider. Joints, which are required to accommodate expansion of the building or compressive ground strains, must be kept free from obstruction, and any compressible fillers must be capable of absorbing all of the strain.

Drying shrinkage, contraction and any other movement which could create tensile stresses in the masonry, need consideration if tensile cracks are to be avoided. A generous number of joints are always preferable to extending the spacing beyond that recommended.

It is, perhaps, surprising how many engineering designers keep the design stresses for the normal loading conditions well under control, but fail to keep the secondary stresses from movement within allowable limits. Thus quite often, a good basic design fails after construction, due to a lack of consideration of small details around the control joints, and/or lack of adequate site supervision in keeping debris out of the joints.

Some typical joint details are shown in Figure A3.14. Recommendations for materials for use in joints are provided in BS 5628, Part 3.



typical expansion joint in clay brickwork external cavity wall



typical control joint in sand lime bricks for drying shrinkage internal wall



typical shrinkage joint in suspended reinforced concrete slab

Figure A3.14 Typical construction joints



Figure A3.15 Vertical movement joint

Vertical joints for thermal and moisture movement are formed by butting the masonry units against a flexible separator, such as a patent compressible strip, polythene sheet, bituminous felt or plastic strips. U-shaped copper strips have been used very successfully for years, but these have become relatively expensive and many new and more economical types of filler are now on the market. The problems of sealing the joint has been eased by the use of polysulphide-based sealants manufactured to BS 4254. The joint must go right through, not only the structural elements, but also finishes such as plaster or screeds. Vertical joints should be about 12 mm thick, and spaced at 10–15 m for clay bricks, but should generally be reduced below 6 m for concrete blocks and bricks and for calcium silicate bricks (see Figure A3.15).

A3.8 Mortars in Assisting Movement Control

While specially designed joints are important in the control of movement and prevention of excessive damage, the designer must bear in mind that each mortar joint between the masonry units can be just as important in preventing critical damage.

In the past, when all mortar mixes tended to be weak, the mortar joints were the main control for movement – and they usually performed very well. Since the general use of stronger cement mortars and weaker bricks and blocks, the problems resulting from movements have increased. The majority of unsightly cracks in brickwork are those which pass through the bricks as well as the mortar joints. Many of these cracks would have remained unnoticed, and would have been less harmful, if a weaker mortar had been used, since the movement would have tended to disperse between the numerous mortar joints – leaving the masonry units undamaged. There is still a tendency to use too strong a mortar mix relative to the brick or block strength, and it cannot be over-emphasised that the mortar strength should generally be much weaker than the bricks or blocks. (See also Appendix 1, section A1.6.)

Appendix 4 Provision for Services

While the majority of service engineers would think twice about cutting a chase along a prestressed concrete beam, or cutting a hole through a steel column, they tend to think it much less serious when doing the same to structural masonry. This presented no problems in the past, when structural masonry was not of such slender construction, nor so highly stressed. However, modern masonry design calls for the same care and consideration as the prestressed beam and the steel column.

It is not difficult to make provision for services, provided that it is pre-planned. As far as possible, all service runs should be planned (see Figure A4.1) and coordinated by the design team before site work starts, and it should not be left to the services sub-contractors to cut runs indiscriminately in finished work.

The most common service provision is the cutting of chases for electrical conduits, etc. (Note that although chasing is still common practice it is specifically banned under Health and Safety legislation due to the dust generated.) If chases are cut horizontally, they obviously decrease the wall's effective thickness and cross-sectional area, and thus increase the stress in the wall and its tendency to buckle. If the stress would increase above the permissible limit, the chase should obviously not be allowed. However, even if the chase does not overstress the wall, and is allowable, care must be taken in forming it. A labourer banging away with a hammer and chisel, or pneumatic hammer, will not only cut the chase but may also shatter the surrounding masonry units and mortar. The chase must be gently sawn with a power saw – but see note above on dust.

Vertical chases may not appear to be such a problem, but most research carried out on test walls, loaded to destruction, shows that the walls split vertically (see Figure A4.2).

Where, for example, vertical chases are formed near doorways, they can produce isolated columns of masonry under



Figure A4.1 Typical elevation on wall showing building work details to be built in



Figure A4.2 Typical failure for wall subjected to compressive loading



Figure A4.3 Vertical chases

lintels and beams, so that the bearing stress is concentrated rather than dispersed through the wall (see Figure A4.3).

A vertical chase could then easily become a pre-formed crack. As with horizontal chases, vertical chases should be gently sawn, and only cut in walls or parts of walls which are not highly stressed.

Holes through walls to allow the passage of heating pipes, etc., should be formed during construction by leaving out masonry units and, if necessary, the joints around the holes should be reinforced and reduce the stress concentration (see Figure A4.4). The pipes, etc. passing through the pre-formed holes can be sleeved.

Vertical services can be routed through voids in hollow blocks and diaphragm walls, and through the cavities of cavity walls. However, such methods make access to the services difficult, and pre-planned service ducts in walls



Figure A4.4 Typical service hole details



Figure A4.5 Sectional plans on typical vertical service ducts

and room layouts, with proper access are more desirable for maintenance purposes (see Figure A4.5).

Openings through floor slabs for vertical ducts can be very useful for setting out on site, since they form check points for ensuring that the next lift of masonry on top of the slab lines up with the walls and columns already built below.

Index

absorption, 48, 50, 151, 160, 167, 170, 207
abutment, 294
  movement of, 297
acceptance limit, 27
accidental damage
  advantages of using masonry, 6
  building categories, 99
  building regulations, 99, 101, 194
  checking for (options), 101, 104, 108
  design for, 100
  direct tensile stress, 48, 105
  during construction, 99
  extent of, 99
  horizontal and vertical areas of collapse, 99
  horizontal ties, 105
  in multi-storey structures, 218, 223, 226, 235
  inadequate connections, 94
  influence of design and construction methods, 94
  influence of specialist sub-contractors, 94
  introduction to, 94
  lateral supports (definitions), 102
  limit of provision against, 98
  loadbearing elements, 102
  partial safety factors, 100, 104
  peripheral ties, 105
  primary and secondary damage, 99
  protected members, 103
  risk of, 94
  tie force, 104, 109
  vertical ties, 108
acoustic barriers, 1, 5, 130, 183, 219, 222
additives, 311
advantages, 4
  accidental damage, 5, 226
  aesthetics, 4
  capital and current energy requirements, 6
  combination with other materials, 7
  cost, 4
  diaphragm and fin walls, 179
  durability, 5, 16, 178, 186
  fire resistance, 5
  of column structures, 228
  repair and maintenance, 2, 6, 178, 226
  resistance to movement, 6
  sound insulation, 5
  speed of erection, 1, 3, 4, 118
  thermal insulation, 5
aesthetics, 4
air entrainment, 311
allowable flexural stresses
  compressive in fin wall design, 197
  tensile in fin wall design, 201
alternative construction techniques
  bonding, 26
approximate lever arm
  of diaphragm walls, 190, 206, 208
arches, 2, 115, 294
  abutment movement, 297
  buttress construction, 122
  Bow's notation, 295
  catenary, 296
  Depuit, 297
  design examples
    pointed road arch, 304
    segmental footbridge, 299
    segmental road arch, 301
  design procedure, 299
  economics, 2
  floors, 115
  footbridge design example, 299
  force diagram, 295, 300, 302
  foundations, 115
  funicular polygon, 295
  graphical analysis, 296, 299
  Hardy Cross, 297
  Heyman, 298
  Hurst, 297
  limit state design, 2
  line of thrust, 294, 295
  linear arch, 295
  Maidenhead bridge, 3, 296
  masonry stresses, 303
  mathematical analysis, 297
  middle third rule, 295, 299
  parabola, 296
  Pippard, 297
  pointed arch design example, 304
  Rankine, 297
  research, 2, 297
  segmental, 2, 299, 301
  Sejourne, 297
  semi-circular, 296
  spandrels, 294
  terminology, 294
  Trautwine, 296
  trial sections, 296
arching
  and joints, 61
  design examples, 59, 62
  lateral strength, 59
  methods of design, 147, 232
    horizontal arching, 60
    vertical arching, 58
  return walls to vertical arching, 62
areas of collapse – accidental damage
  horizontal and vertical, 99
asymmetrical sections
  in post-tensioned masonry, 267, 275
availability of materials and labour, 3, 7
axial loading
  basis of design, 18
  design examples, 124
  design formula – reinforced columns, 262
  diaphragm walls, 138, 213
  fin walls, 213

balustrade wall
  design of solid concrete block, 154
  design moment of resistance, 154
basis of design
  lateral loading, 47
  vertical loading, 18
beam
  bearing – design example, 140
  disadvantages, 8
  reinforced brick – design examples, 254, 257
bearing
  design example, 140
  local stresses, 45
  types, 43
  under plate in post-tensioning, 269, 275
bitumen felt dpc, 314
Blackwall tunnel, 3
blockwork, *see* concrete blocks and blockwork
bond (of reinforcement)
  local, 256
  partial factor of safety, 251
bonding
  alternative construction technique, 26
  characteristic strength, 21
  English, 315
  Flemish, 21, 315
  general, 315
  stretcher, 21, 315
Bow's notation, 299
box section, 2, 178
  effect of vertical dpm in diaphragm walls, 183
Brebner, Sir Alexander, 244

brick
bonds, 26, 315
calcium silicate, 309
cellular, 308
classification, 307, 310
clay, 307
common, 308
concrete, 310
crystallisation of soluble salts, 309
dpc, 314
durability, 309, 310
efflorescence, 439
engineering, 308
facing, 308
flint-lime, 309
frogged, 307
frost attack, 309
hollow, 308
internal, 308
loadbearing brick classification, 307
modular, 307
moisture expansion, 266, 317, 318
-on edge construction, 26
-on end construction, 26
ordinary quality, 308
perforated, 308
quality, 308
sand-lime, 309
shrinkage, 319
size, 307
solid, 308
special quality, 308
special shape, 308
standard format, 307
standard specials, 307
strength, 18, 308
sulphate attack, 309, 320
testing, 309
thermal expansion, 318
types, 308
water absorption, 48
Brick Development Association
nine-day house, 3
brickwork
characteristic compressive strength, 18
characteristic flexural strength, 48
characteristic shear strength, 71
orthogonal ratio, 49
Brunel
Isambard Kingdom, 3, 296
Sir Marc, 3, 244
buckling tendency, 12, 29, 34, 110, 124, 324
in diaphragm and fin walls, 178, 192, 196, 198, 202, 210
of shear walls, 71, 158
builders-work for provision of services, 216, 324
building categories, 99
building regulations, 99, 101, 219
butterfly wall ties, 56, 314

calcium chloride, 311
calcium silicate bricks, 309
shrinkage of, 319
thermal expansion of, 319
capacity reduction factor, 35, 38
calculation of, 36, 39
in columns, 37, 38, 136, 168
in diaphragm walls, 139, 209
in fin walls, 197
in post-tensioning, 267, 270, 289
in reinforced masonry, 257
in shear walls, 164
in solid wall design, 126, 150
capping beam, 11
construction of, 185
for diaphragm and fin walls, 181
category of building, 99
cavity walls, 34, 54, 110, 130
cavity thickness, 55
cavity ties, 55, 110, 314
cleaning cavities, 183
comparison with diaphragm walls, 146
design as cracked section, 155, 156, 159
design example – post-tensioned, 269
design of – grouted, 132
design of – ungrouted, 130, 154
design of – ungrouted with piers, 134
differing orthogonal ratios, 57
effective thickness, 34
flexural compressive stresses, 157
grouted, 57, 110, 130
in fin wall construction, 180, 191, 196
in multi-storey structures, 215, 321
in single-storey structures, 177
laterally loaded, 145, 154, 160
load share, 55
panel walls, 63, 160
perforated external, 170
resistance moment, 145, 155, 159
section modulus, 144
support conditions, 155
support of outer leaf, 56, 215, 321
thickened inner leaf, 145
cellular concrete blocks, 310
cellular construction, 1, 119, 214
in multi-storey structures, 119, 216
see also multi-storey structures
cements, 311
characteristic compressive strength, 18
bonding, 21
joint thickness, 21
of blockwork, 21
of brickwork, 21
of masonry, 21
of masonry units, 21
of mortar, 21
reinforced masonry, 257
standard of workmanship, 21
unit shape, 21
characteristic flexural strength of masonry
at dpc, 48
clay bricks, 48
orthogonal ratio, 49
characteristic loads, 18, 19
dead, 19
imposed, 19
wind, 19
characteristic shear strength
in diaphragm retaining wall, 291
increase for vertical loading, 72
of shear walls, 71
characteristic strength, 18, 19
and brick bonds, 21
calculation of, 19
chases, 216, 324
chevron walls, 112
chimneys, 116, 117
domestic – sulphate attack, 320
reinforced, 117
churches, 2, 123, 172
circular tube, 116, 123
cladding, 51, 63, 220
envelope area, 227
clay brick, 307
moisture expansion, 266, 317, 318
natural growth, 266
thermal expansion, 318
water absorption of, 48
coefficients of
shear stress in diaphragm walls, 205
thermal expansion, 318
trial section in diaphragm wall, 186, 206
trial section in fin wall, 192
collar jointed walls, *see* double leaf collar jointed walls
column and plate floor construction, 119
advantages, 228
cross-sectional shapes, 228
design example, 238
design procedure, 229
durability, 228
floor construction, 228
in multi-storey structures, 214, 228, 238
size and spacing of columns, 229
speed of erection, 229
uses in column structures, 228
see also multi-storey structures
columns, 1, 36, 114
capacity reduction factor, 37, 38, 136, 168, 257
column and plate floor, 214, 228
combined bending and axial load, 167
cross-sectional shapes, 229
cruciform, 114, 137, 167, 228
cruciform – combined loading, 167
definition, 36
design examples, 238
design of, 136, 165
design resistance moment, 167, 168, 169
design strength, 38, 136, 137
eccentric loading, 39, 41
effective height of, 36
effective thickness, 36
enhanced lateral support, 37
estimate size of, 136
flexural compressive stresses, 168, 169, 170
formed by openings, 37, 136
hollow circular, 115, 116, 229
hollow elliptical, 116, 123
hollow rectangular, 169, 229
of small plan area, 39, 115, 136

radius of gyration, 138, 167
reinforced, 245
slenderness ratio, 35, 137, 138, 168
solid rectangular, 168, 228
combined bending and axial loading
design basis, 48
design examples, 142
combined forms of construction, 120
combined slenderness and eccentricity, 40
components, 314
brick bonds, 315
damp proof courses, 314
fixings, 314
wall ties, 56, 314
composite construction, 116, 218, 246, 247
compression tube, 116, 123
compressive strength
bricks, 308
concrete blocks, 23, 310
factors affecting masonry, 19
mean compressive strength, 19
of masonry, 18
standard deviation, 19
compressive stress – design local, 44
concentrated loads, 43
design for, 140
design strength, 141
in diaphragm and fin walls, 185
pier at beam bearing, 142
spread of load, 43, 141
concrete blocks and blockwork
cellular, 310
characteristic compressive strength, 24
classification, 310
compressive strength of units, 23, 310
density, 310
design of filled hollow blocks, 25
design of solid, 129, 154
durability, 311
filled hollow blocks, 23
format, 310
handling for laying, 310
hollow blocks, 23, 310
shape of units, 21, 23
shrinkage, 319
sizes, 310
solid blocks, 23, 310
strength testing, 310
thermal expansion, 318
type A, 310
type B, 310
type C, 310
concrete bricks, 310
shrinkage of, 319
thermal expansion of, 318
construction control
normal, 27
special, 27
control joints, *see* movement joints
Conway bridge, 3
corrosion
of post-tensioning rods, 247, 249
of reinforcement, 247
of services, 182
of shear ties, 182
course stuff, 311
crack hinge (or plastic hinge), 188
cracked section, 48, 70, 142, 159, 172, 232
collar jointed walls, 152
diaphragm and fins, 188, 190, 197, 199, 206, 208
free-standing walls, 150, 152
moment of resistance, 51, 53
see also stability moment of resistance
creep in masonry, 266, 268
cross-ribs
centres of cross-ribs, 202, 286
in retaining walls, 286
of diaphragm walls, 2, 178, 182
shear resistance, 287, 291
shear ties, 182, 211
thickness of, 287
crosswalls, 1, 14, 70, 118, 222, 227
as shear wall – design of, 163
design examples, 229, 236
elevational treatment, 224
in multi-storey structures, 214, 219
see also multi-storey structures
cruciform columns, 114, 137, 167, 228

damp proof courses and membrane
bitumen felt, 314
brick, 314
for diaphragm and fin walls, 183, 188, 192
general, 314
horizontal, 314
metals, 314
plastic, 314
slate, 314
vertical, 314
deflection, 16
of cavity walls, 55
of post-tensioned masonry, 269
of precast concrete floors, 79
of roof prop, 190, 194, 202, 210
propping and tying, 74, 76
department stores, 1
Depuit, 297
design compressive strength
of columns, 38
of diaphragm walls, 138
of walls, 36
reinforced masonry, 257, 259
design load, 18
design of elements – combined bending and axial loading
balustrade walls, 154
columns, 165
comparison of cavity wall with diaphragm wall, 146
cruciform columns, 167
external cavity walls, 154
free-standing walls, 150
hollow rectangular columns, 169
method of design, 142
panel walls, 160
perforated external walls, 170
solid rectangular columns, 168
solid walls, 147
design of elements – vertically loaded
cavity walls – grouted, 132
cavity walls – ungrouted, 130
columns, 136
columns formed by openings, 136
concentrated loads, 140
design procedure, 124
diaphragm walls, 138
estimation of element size, 124
pier-stiffened solid walls, 134
principle of design, 124
solid columns, 137
solid walls, 124
design moment of resistance
collar jointed walls, 152
cracked sections, 53
diaphragm walls, 146, 190
free-standing walls, 63, 150
horizontally spanning, 51
of fin walls, 190
of shear walls, 164
reinforced masonry, 252
stability moment of resistance, 53, 62, 189
uncracked sections, 51
vertically spanning, 51
design philosophy, 10
architectural planning, 15
cantilevers, 13
capping beam, 11
comparison of brick and concrete structures, 15
comparison of wall properties, 12
essential building elements, 13
exploitation of cross-section, 10
foundations, 14
gable shear walls, 13
geometric sections, 13, 124
multi-storey structures, 15
podium construction, 15
post-tensioning, 11
propped cantilevers, 13
restraint, 11
strength of material, 10
T, I and L plan configurations, 15
uplift forces, 10
design strength, 18, 35
compressive strength of masonry, 18
of columns, 38, 136, 137
of reinforced masonry, 256
of wall ties, 182, 211
of walls, 36
post-tensioned masonry, 266
shear strength, 71
solid walls, 126, 129
diaphragm walls, 2, 11, 112, 178
approximate lever arm, 190, 209
architectural treatment, 181
capacity reduction factor, 139, 209
capping beams, 180, 182
cavity cleaning, 183
comparison with cavity walls, 146
comparison with fin walls, 179
comparison with solid walls, 139

diaphragm walls (*cont'd*)
damp proof courses and membranes, 183, 188
definition, 178
deflected roof prop, 302
depth, 204
design and construction details, 180
design bending moments, 188
design examples, 138, 207, 284
design for axial loading, 138, 214
design symbols, 191
disadvantages, 178
estimate wall thickness, 139
farm buildings, 212
foundations, 180, 184
in single-storey buildings, 177
mass-filled, 2, 112, 212
other applications, 212
plastic analysis, 188
post-tensioned, 284
principle tensile stress, 190
properties of sections, 204, 208
radius of gyration, 139
resistance moment, 146
retaining walls, 112, 212, 284
rib centres, 202
scaffolding, 185
services, 182
shear lag, 190
shear resistance of wall ties, 182, 211
shear stress coefficient, 205
slenderness ratio, 139, 209
sound and thermal insulation, 183
sound deflectors, 212
stability moment, 189, 190, 193, 196, 199, 206, 208
structural design, 139, 182
structural detailing, 183
capping beam, 185
foundations, 184
joints, 184
temporary propping, 185
wall openings, 185
trial section coefficients, 186, 206
trial section selection, 208, 286
with plate roof construction, 120
disadvantages, 7
beams and slabs, 8
control joints, 8
diaphragm and fin walls, 178
foundations, 8
increase in obstructed area, 7
isolated detail problems, 7
lack of education, 3, 7
large openings, 8
dispersion of load
at concentrated load bearings, 43, 141
available for arch thrust resistance, 58
docks
Albert Dock, 3
St Katherine's Dock, 3
double leaf collar jointed walls, 57, 110
design as cracked section, 152
design of, 134
free-standing walls, 152
moment of resistance, 152
requirements for, 57
wall ties, 153
double-leaf cavity walls, *see* cavity walls
double-triangle wall ties, 56, 314
durability, 5, 16, 178, 186
of column structures, 228
of concrete blocks, 311
of fixings (and compatibility), 315
of shear ties, 182

eccentric loading, 39, 235
combined with slenderness, 40
design in grouted cavity walls, 132
general conditions, 39
in columns, 39, 41
in plane of wall, 70
in solid walls, 127, 130
in walls, 40
eccentricity
effective, 57, 148
of post-tensioning rods, 263, 265, 276, 279
education, 3, 94
lack of, 3, 7, 244
effective depth
of reinforced brick beam, 258, 260
effective eccentricity
capacity reduction factor, 57
in solid walls – laterally loaded, 148
method of design, 57, 147
effective flange width
in fin wall design, 192, 196
effective height or length, 12, 28
determination of, 32
of columns, 36
of solid walls, 32, 126
use of partitions, 12
effective section
in fin wall design, 192, 193
effective span, 251
effective thickness, 12, 32, 124
in cavity piered walls, 35, 135
in cavity walls, 34
in reinforced masonry, 257
in solid piered walls, 34, 134
in solid walls, 34, 124
of columns, 36
efflorescence, 309
elastic
analysis of fin walls, 200
analysis of post-tensioned masonry, 266
analysis of shear walls, 71, 163
deformation of masonry, 266, 269
stresses, 16
elements
arches, 115
chevron (zig-zag) walls, 112
columns, 115
composite construction, 116
design of, 124, 142
diaphragm walls, 112
double-leaf cavity walls, 110
double-leaf collar jointed walls, 110
double-leaf grouted cavity walls, 110
faced walls, 111
fin walls, 113
horizontal reinforced masonry, 116
piered walls, 112
post-tensioned walls, 114
reinforced walls, 113
single-leaf (solid) walls, 110
veneered walls, 111
elimination of sub-contractors and suppliers, 2
elliptical tube columns, 116, 123
energy requirements, 1, ?
English
bond, 315
garden wall bond, 315
enhanced lateral support
of columns, 36
of walls, 29, 32
estimate (design size), 124
cavity walls (ungrouted), 131
columns, 136
columns formed by openings, 137
diaphragm walls, 139
grouted cavity walls, 133
pier-stiffened cavity walls, 135
pier-stiffened solid walls, 134
solid walls, 126, 128
expansion, 245, 318
coefficients, (remove this line)
see also movement

faced walls, 111
factor of safety, 16
see also partial factor of safety
factories, 1, 173
farm buildings, 212
filled hollow concrete blocks, 23
fin walls, 2, 11, 113, 178
allowable flexural compressive stress, 197
allowable flexural tensile stress, 201
architectural treatment, 181
capacity reduction factor, 197
capping beams, 180, 182
cavity cleaning, 183
comparison with diaphragm walls, 179
damp proof courses and membranes, 183, 188
definition, 178
deflection of roof prop, 194, 202
design and construction details, 180
design bending moments, 188
design examples, 194, 276
design procedure, 194
design symbols, 191
disadvantages, 178
effective flange width, 192, 196
effective section, 192, 193
elastic section, 192, 193
farm buildings, 212
for strengthening existing walls, 212
heavy axial loading, 213
in multi-storey structures, 213, 226
in single-storey structures, 177
interaction between leaves, 191

other applications, 212
'plastic' analysis, 188
post-tensioned fins, 212, 275
principle tensile stress, 190
properties of, 193
propped cantilever action, 180, 186, 188, 197
retaining walls, 212
scaffolding, 185
services, 182
shear lag, 190
size of, 181, 192
slenderness ratio, 197
sound and thermal insulation, 183
spacing of fins, 181, 191, 196
stability moment, 189, 190, 193, 196, 197, 199
structural design, 183, 193
structural detailing, 183
capping beam, 185
foundations, 184
joints, 184
temporary propping, 185
wall openings, 185
trial section coefficient, 186, 193, 196
with plate roof construction, 121
fire resistance, 5, 219
fixings
durability and compatibility, 314
general, 314
strength of, 314
flanges
flange length, 178, 179, 192
of diaphragm retaining wall, 286
of diaphragm walls, 178
of fin walls, 192, 196
Flemish bond, 21, 315
flexibility to alteration, 218
flexural strength
compressive, 53
tensile, 48
floors (restraint from)
abutting walls, 76, 87
bearing onto walls, 76, 87
footbridge arch, 299
force diagram
arch design examples, 299, 301, 304
in arch design, 295, 300, 302
forms
arch and buttress construction, 122
cellular construction, 119
chimneys, 116
column and plate floor construction, 120
combined forms, 120
compression tube construction, 123
crosswall construction, 118
diaphragm wall and plate roof construction, 120
fin wall and plate roof construction, 121
podium construction, 15, 217
spine wall construction, 121
foundations
diaphragms and fins, 180, 184
disadvantages, 8
multi-storey structures, 218
post-tensioning, remove this line
free-standing walls, 62, 147
balustrade walls, 154
chevron walls, 112
design examples, 63, 150, 152, 154
design of – collar-jointed, 152
design of – solid, 150, 152
design of – solid concrete block, 154
design as a cracked section, 152, 153
limiting dimensions, 62
moment of resistance, 63, 151
friction
losses in post-tensioned masonry, 266, 269
frost inhibitors, 311

gable walls, 14, 94
gains in post-tensioning force, 266
garages, 1
geometric sections, 124
diaphragm and fins, 178
flange width, 51
grouted cavity walls, 57, 110
brick and mortar strengths, 134
design of, 130
design strength, 132
eccentricity of load, 133
estimate wall thickness, 133
resultant load, 133
grouting in reinforced masonry, 245
growth, *see* natural growth of masonry
gymnasia, 2, 178

Haller, 226
halls of residence, 1
Hardy Cross, 297
Hartley, 3
Heyman, 298
high alumina cement, 311
holding down roofs
see tailing down of roofs
see strapping and tying
hollow blocks, 23, 310
horizontal
dpc, 314
girder, 13, 173, 180
movement, 76
reinforced masonry, 116, 257
stability of multi-storey structures, 215
ties in accidental damage, 105
hotel bedroom blocks, 1, 214, 217, 219, 223
design example, 229
houses – lateral restraint, 32
Hurst, 297

I section
effect of dpm in diaphragm walls, 183
industrial buildings, 1, 178
interaction with other materials, 7, 177
introduction, 1

joints
disadvantages, 8
for diaphragm and fin walls, 184
in arch method of design, 61
materials and details, 323
movement, 317
joist hangars, 76, 88 (hanger not hangar)

knife edge conditions, 53, 59, 174
diaphragm and fins, 190

labour, 3, 7
lateral loading
basis of design, 47
design lateral strength, 59
general, 51
on panel walls, 63
tensile and shear strength, 47
lateral stability
of reinforced masonry beams, 251
of walls, 29
lateral strength
in arch method of design, 58
lateral support
details, 36
enhanced, 29, 32, 36
in accidental damage design, 102
introduction, 28
loads to be resisted, 29
of columns, 36
of walls – horizontal, 29
of walls – vertical, 32
see also restraint
lift shafts and stair enclosures, 14
lime, 311
limit state design, 16, 18
of arches, (delete this line)
linear arch, 295
load
characteristic, 18, 19
concentrated, 43
design – introduction, 19
lateral, 51
share, 54, 191, 221
load bearing elements
in accidental damage design, 102
local bond
design formula, 256, 260, 262
losses
assessment of, 268
elastic deformation of masonry, 269
friction, 266
post-tensioning force, 266, 268
relaxation of post-tensioning steel, 268

Maidenhead bridge, 3
maintenance, 6, 178, 226
major axis
of columns, 42
manufacturing control
normal, 27
special, 27
masonry
cement, 311
in limit state design, 16
shape of units, 20
strength of masonry units, 20
mass filled diaphragm walls, 2, 112, 212

materials, 307
calcium silicate bricks, 309
clay bricks, 307
concrete blocks, 310
concrete bricks, 310
mortars, 311
stone masonry, 310
minor axis
of columns, 42
modular bricks, 22
moisture expansion, 266, 317, 318
moment of inertia
general, 55, 71, 124
of shear walls, 221
moment of resistance, *see* design moment of resistance
mortar
additives, 311
air entrainment
assistance in movement control, 323
calcium chloride, 311
chemical analysis, 313
choice, 312
constituents, 311
course stuff, 311
cubes, 313
frost inhibitors, 311
general, 311
high alumina cement, 311
in free-standing walls, 62
joint thickness, 21
lime, 311
masonry cement, 311
mixes, 312
mixing, 311
movement, 323
pigments, 311
plasticisers, 311
Portland cement, 311
proportioning, 312
quality control of, 16
ready-mixed, 311
sand, 311
selection, 313
shrinkage of, 319
sulphate-resisting Portland cement, 311, 320
sulphates in, 309
testing, 313
thermal expansion, 318
water, 311
movement
aggravation from restraint, 318
and mortars, 323
causes of, 317
chemical changes, 317
coefficients of thermal expansion, 318
concrete and calcium silicate bricks, 319
creep in masonry, 266
deflection of floor supporting wall, 320
differential, 320
dissimilar materials, 320
drying shrinkage, 319
due to moisture, 266, 317, 318
due to thermal expansion and contraction, 266, 317
fired clay bricks, 318
foundation, 317, 321
frost action, 317
natural growth of masonry, 266
resistance to, 6
sulphate attack, 320
movement joints
aggravation from restraints, 318
assessment of location, 318
assistance from mortars, 323
concrete floor slab/wall connection, 218
consideration of, 322
design of, 322, 323
dissimilar materials, 320
general, 8, 317, 322
in multi-storey buildings, 216
joint sealing, 323
materials and details, 323
shrinkage, 323
slip-plane, 320
multi-storey structures, 1, 2, 13, 213, 214
accidental damage, 218, 223, 226, 235
bedroom blocks, 223
choice of masonry materials, 219
column structure design example, 238
common problems to consider, 214
comparison of structural forms, 227
composite construction, 218
concrete roof slab/wall connection, 218
costs and saving, 214
crosswall design examples, 229, 236
crosswall elevational treatments, 224
envelope (cladding) area, 227
external cavity walls, 215, 220
fin walls, 226
flexibility, 218, 227
foundations, 218, 228
height parameters of cellular construction, 227
horizontal stability, 215, 220, 224, 225, 233
low/medium rise flats, 223
movement joints, 216
openings in shear walls, 22
podium construction, 217, 224
robustness of cellular construction, 227
school classroom blocks, 222, 236
services and builders-work requirements, 216
shear walls, 215, 221
spiral construction, 1, 118
structural forms
cellular, 214, 220
column, 214, 228, 238
crosswall, 214, 219
spine, 214, 224
varying brick and mortar strengths, 219
vertical alignment of walls, 217
vertical stability, 215, 220

narrow brick walls, 22, 59, 128
natural growth of masonry, 266
natural stone masonry, 25, 310
'normal control'
construction, 27
manufacturing, 27

openings
columns formed by, 37, 136
disadvantages, 8
in diaphragm and fin walls, 185
in shear walls, 222
open-plan offices, 1, 212
orthogonal ratio, 49, 66
design examples, 49, 162
differing ratios, 57
panel wall design, 161

panel walls, 50, 51, 63
bending moment coefficients, 66, 162
cavity walls, 63, 160
design methods, 64
design of double-leaf cavity, 160
edge support conditions, 64, 161
free-standing piered walls, 62
in multi-storey buildings, 220
limiting dimensions, 63, 162
load share
orthogonal ratio, 49, 66, 162
resistance moment, 162
strengths of wall ties, 69
parabola
in arches, 296
parapet walls, 62
partial factor of safety, 16, 18
acceptance limit, 27
accidental damage, 100, 104
construction control, 27
determination of, 20
for shear stresses, 72
on loads, 20
on materials, 27
on reinforcement, 250
on workmanship, 27
reinforcement masonry materials, 251
reinforced masonry – serviceability – on loads, 251
partitions
and accidental damage, 102
and effective length, 12
perforated external wall
assessment of mode of action, 170
design moments, 171
design of, 170
design resistance moment, 172
stability moments of resistance, 172
peripheral ties
in accidental damage designs, 105
permissible stress design, 16
philosophy, *see* design philosophy
piers, 2, 112
at concentrated load bearings, 142
see also fin walls
effect on slenderness of walls, 34
pier-stiffened cavity wall, 112
brick and mortar strength, 135
design of, 135
design strength, 134

effective thickness, 135
estimate thickness of, 135
in single-storey buildings, 177
reinforced, 112
pier-stiffened solid wall, 112
brick and mortar strength, 135
design of, 134
design strength, 134
effective thickness, 34, 135
estimate wall/pier configuration, 134
in single-storey buildings, 177
reinforced, 11
pigments, 311
Pippard, 297
plane of failure
parallel to bed joints, 49
perpendicular to bed joints, 49
plastic
analysis of diaphragms and fins, 188
dpc, 314
hinge, 188
materials such as masonry, 16
plasticiser, 16, 311
podium construction, 217, 224
Portland cement, 311
post-tensioned diaphragm walls, 3, 114, 186, 213, 246, 284
cross ribs shear resistance, 287, 291
design example, 284
design theory, 284
local stability, 289
overall stability, 289
trial section
cross-rib thickness, 287
depth, 286
flange thickness/cross-rib spacing, 286
post-tensioned fin walls, 3, 114, 186, 213, 246, 275
design example, 275
design theory for, 275
overall stability check, 282
spread of post-tensioning force, 279
post-tensioned masonry, 2, 244, 263
applications, 250
asymmetrical sections, 267, 276
bearing stresses under spreader plates, 269, 275
capacity reduction factor, 267, 270, 279, 289
choice of system, 249
comparison with concrete, 244
concrete blockwork, 3, 268
corrosion of post-tensioning steel, 247, 248, 264
creep of masonry, 266, 268
deflection, 269
design examples
cavity wall – wind loading, 269
diaphragm – retaining wall, 284
fin wall – wind loading, 276
design for flexure, 265, 269
design strengths, 265
design theory for, 244, 263, 284
eccentricity of rods, 263, 265, 276, 278
economics, 247
elastic analysis of, 266
elastic deformation of masonry, 266, 268, 269
friction, 266, 269
gains in post-tensioning force, 266, 268
grouting, 263
jointing of rods, 264
limitation of steel stress, 267
location of rods, 263
losses in post-tensioning force, 266, 268
method and sequence of construction, 263
moisture movements in masonry, 266, 268
natural growth of clay brickwork, 266, 268
overall stability, 282, 289
partial safety factor, 269
prestressing, 246
relaxation of steel, 266, 267, 268
research, 2, 268
shrinkage of concrete masonry, 268
simplified design philosophy, 263
slenderness ratio, 270, 279, 282
strengths adjusted to loading conditions, 266
temporary support, 265
thermal movement, 266, 268
torque, 246, 264, 269, 275
post-tensioned walls, 114, 147
in design philosophy, 11
in diaphragm and fin wall, 186, 213, 246, 276, 284
in single-storey buildings, 177
retaining walls, 284
school system buildings, 2
prefabrication, 3, 246, 250
prestressed masonry, 246
see also post-tensioned masonry
primary accidental damage, 99
principal tensile and stress
in diaphragm and fin walls, 190
progressive collapse, 2, 74, 94, 118
prop, 13, 173
deflection of roof, 190, 194, 202, 210
properties of sections
diaphragm walls, 204, 208
fin walls, 193
propped cantilever
design method, 69
in single-storey buildings, 69, 174
philosophy of, 13
principles of – for diaphragm and fin, 180, 186, 188, 197
propping – temporary, *see* temporary propping
protected member, 103

quetta bond, 246

radius of gyration, 12, 124, 138, 139, 167, 169, 213
random rubble masonry, 25, 310
Rankine, 297
ready-mixed mortars, 311
rectangular stress block, 53, 151, 153, 157
diaphragm and fins, 190, 198
reduction factor, *see* capacity reduction factor
reinforced masonry, 2, 244
applications of, 245, 250
Blackwall Tunnel, 3
characteristic compressive strength, 257
chimneys, 117
choice of system, 249
column design and formulae, 262
comparison with concrete, 244
composite construction, 116, 218, 246, 247
corrosion of reinforcement in, 247, 248, 249
depth required of brick beam, 258, 259
design examples
beams, 257
column axial loading, 262
retaining wall, 261
design formulae
axial loading, 257
local bond, 256, 260, 262
moment of resistance, 252, 258
shear reinforcement, 255
shear stress, 255
design theory for, 244, 250
economics of, 247
effective depth of brick beams, 258, 260
effective span, 251
effective thickness, 257
grouting, 245
history, 2
horizontally reinforced, 116
lateral stability of beams, 251
lever arm, 258, 260
limiting slenderness ratio for walls, 252
methods for, 245
partial safety factors, 250, 257
percentage of reinforcement, 252, 258
strength of materials, 251, 258
reinforced masonry walls, 113
limiting slenderness ratios, 252
methods of reinforcing, 246
retaining wall – design example, 261
reinforcement
around service holes, 325
characteristic tensile strength, 251
corrosion, 246
partial factors of safety, 250
shear reinforcement, 255
relaxation
of post-tension steel, 266, 268, 269
removal analysis
in accidental damage design, 104
repair and maintenance, 6, 218
research, 48, 266, 297, 324
resistance moment, *see* design moment of resistance and stability moment of resistance
resistance and stability moment of resistance

restraint, 28
aggravation to movement, 317
enhanced lateral support, 29, 32
from concrete floors, 32, 87
from trussed rafters, 32, 81–85
in houses, 32
of columns, 36
of external walls, 74
of fin walls, 199
of free-standing walls, 62
of outer leaf of cavity walls, 72, 215
reinforced masonry beams, 251
straps, 32, 48, 77–86
retaining walls, 2, 63, 112, 113, 213, 245
design example, post-tensioned diaphragm, 284
design example, reinforced, 261
diaphragm walls, 2, 112
fin wall, 212
robustness, 2, 94, 177
Ronan Point, 2, 74, 118
Rotherhithe Tunnel, 244

sand and water for mortar, 311
scaffolding
in diaphragm and fin walls, 185
school classroom blocks, 1, 119, 222
design example, 236
second moment of area, *see* moment of inertia
secondary accidental damage, 99
section modulus, 50, 112
of cruciform column, 167
of diaphragm walls, 205
of fin walls, 201
of hollow rectangular column, 169
of shear walls, 221
segmental arch, 2, 299, 301
Sejourne, 297
services
builders-work requirements, 216, 324
corrosion, 182
cutting chases in brickwork, 216, 324, 325
in diaphragm and fin, 182
in multi-storey buildings, 216
provision for, 324
reinforcement around service holes, 325
vertical alignment of walls, 217
shafts, 116, 123
shape
ratio, 130
unit, 21
shear
design of reinforced members, 255
force in diaphragm walls(flexural), 182, 211
force in fin walls (flexure), 192
forces on walls, 71
keying between wall and floor, 77
lag in diaphragm and fin walls, 190
partial factor of safety, 72
reinforcement, 255
resistance of wall ties, 182, 211
resistance to, 72
strength, 72
ties, corrosion of, 181
ties in diaphragm walls, 181, 211
walls, *see* shear walls
shear walls, 13, 71, 77, 97, 219
buckling tendency, 71
capacity reduction factor, 164
concrete block – design, 163
design resistance moment, 165
elastic analysis, 71, 163
flexural compressive stresses, 165
in diaphragm and fin walls, 180, 183
in multi-storey buildings, 221
load share, 221
openings in walls, 222
second moment of area, 221
section modulus, 221
walls of differing plan layout, 222
shell bedding, 26
shrinkage
and movement joints, 323
calcium silicate bricks, 319
concrete bricks and blocks, 319
in post-tensioned concrete masonry, 268
mortar, 319
single leaf walls, *see also* solid walls
design of, 124
walls, 110
single-storey buildings, 173
design considerations:
bending stresses, 173
combined bending moment diagram, 175
knife edge condition, 175
propped cantilever action, 69, 174
robustness, 177
roof action, 173
slenderness ratio, 177
stability moment of resistance, 69, 173
tailing down of roof, 176
vertical loads, 173
design procedure, 177
diaphragm walls, 177
fin walls, 177
height parameters of differing structural forms, 177
strapping and tying of, 73, 174, 176
slate dpc, 314
slenderness ratio, 18, 28, 124
columns, 36
combined effect with eccentricity, 40
diaphragm walls, 139, 209
fin walls, 197
limiting values for reinforced walls, 252
limiting values for walls, 28
piered walls, 34
post-tensioned walls, 270, 279, 283
solid walls, 126, 129, 149
solid concrete blocks, 23, 310
solid walls, 110, 147
balustrade walls, 154
brick and mortar strength required, 128, 129
capacity reduction factor, 126, 149
characteristic strength required, 128, 129, 149
comparison with diaphragm wall, 139
concrete block solid wall, 129
design loads and bending moments, 148
design of, 124, 126
design strength, 126, 129
eccentricity of load, 127, 130
effective eccentricity, 57, 148
effective height, 32, 127
effective thickness, 34, 124
estimate thickness, 126, 128
free-standing walls, 150, 151
in single-storey buildings, 177
narrow brick walls, 128
slenderness ratio, 126, 129, 149
sound deflectors
diaphragm wall, 212
sound insulation, 1, 5, 130, 219, 224
of diaphragm and fin walls, 183
spandrel, 294
special control
construction, 27
manufacturing, 27
speed of erection, 1, 4, 118, 214, 218, 247
BDA nine-day house, 3
spine walls, *see also* multi-storey structures, 1, 121
in multi-storey structures, 214, 224
spiral construction, 1, 118
sports halls, 1, 173, 178
spread of load, *see* dispersion of load
stability, 73, 94, 96
designer's responsibility, 96
of multi-storey structures, 215, 220, 233
of post-tensioned diaphragm wall, 289
of post-tensioned fin wall, 282
percentage of dead load applied laterally, 98
plate action of floors and roofs, 97
robustness of plan layout, 97
strapping and tying, 97
stability moment of resistance
for cavity walls, 156, 171
for diaphragm and fin, 189, 190, 193, 196, 199, 206, 208
for free-standing walls, 62, 151
general, 53, 62, 70, 173, 189
stair enclosures, *see* lift shafts and stair enclosures
standard deviation
compressive strength of masonry units, 19
standard format bricks
arches, (remove this line)
in diaphragm and fins, 178
size, 307
Stephenson, 3
stone masonry, 25, 310
strapping and tying, 73, 94, 98
and deflection of precast floors, 79
code requirements for straps, 79
design considerations for straps, 78
design example (complete building), 89–93

for horizontal movement, 76
for uplift, 73
illustrations of strapping, tying, propping, 80–88
in single-storey buildings, 174, 176
shear keying of walls to floors, 77
straps
bending value, 78
design considerations, 76
restraint, 32
strengths of, 78
strength, *see* characteristic
stretcher bond, 21, 315
structural forms, *see* forms
sulphate
attack, 309, 320
in mortar, 309
resisting cement, 311, 320
swimming pools, 2

T section, 15
moment of inertia graph, (omit this line)
neutral axis graph, (omit this line)
of fin walls, 2, 178, 191
properties, (omit this line)
tailing down of roofs, 48, 176
Telford, 3
temporary propping, 48
diaphragm and fin walls, 185
post-tensioned walls, 265
tensile strength
of reinforcement (characteristic), 251
tensile stress
direct, 48
direct in accidental damage design, 48, 105
theatres, 2, 173
thermal expansion
calcium silicate bricks, 319
clay bricks, 318
concrete blocks and bricks, 318
mortars, 318
thermal insulation, 5
of diaphragm and fins, 183
tie force, 104, 109
ties, *see* shear ties, wall ties and accidental damage
torquing, 246, 267
design torque required, 275
frictional losses, 265, 269
Trautwine, 296
trussed rafters
restraint from, 32, 81–85
tunnels, 116, 123

ultimate stress, 16
in arch method of design, 58
in diaphragm and fin walls, 190, 199
width of rectangular stress block, 53, 151, 153, 157
uncracked sectins
moment of resistance, 51
ungrouted cavity wall
brick and mortar strength, 130
design of
design strength
estimate wall thickness
uplift due to wind, 10, 48, 73, 77
in diaphragm and fins, 180
in multi-storey structures, 221, 232

vandal resistance, 178
vaults, (remove this line)
veneered walls, 111
vertical
alignment of walls, 217
dpc, 314
stability of multi-storey structures, 215
ties, in accidental damage, 108
twist, wall ties, 55, 80, 314
Victorian brick engineering, 3, 296

wall
balustrade, 154
bearings, 43
cavity, 110
chevron, 112
collar-jointed, 110
cross, 118
diaphragm, 112
double-leaf cavity, 110
double-leaf collar-jointed, 110
double-leaf grouted cavity, 110
faced, 111
fin, 113
free-standing, 62, 147
gable, 14
grouted cavity, 110
horizontal lateral support of, 29
joints, 317
lateral stability of, 29
mass-filled diaphragm, 112, 212
narrow brick, 22
narrow stone, 32, 440
of small plan area, 39
panel, 64
parapet, 62
partition, 12, 102
perforated external, 170
piered, 112
post-tensioned, 114
post-tensioned diaphragm, 284
post-tensioned fin, 275
random rubble, 25, 310
reinforced, 113
retaining walls, 3, 261, 284
return, 58
shear, 163, 221
single-leaf, 110
solid, 110
spine, 121, 214
ties, 314
veneered, 111
vertical lateral support of
zig-zag, 110
wall ties
butterfly, 56, 314
characteristic strength of, 69
corrosion, 181
design of in diaphragm walls, 182, 211
design of in wall panels, 69
diaphragm walls, (omit this line)
double-triangle, 56, 314
durability, 314
general, 54, 314
in collar-jointed walls, 152
selection of, 56
shear resistance, 182, 211
spacing, 56, 211
vertical twist, 55, 80, 314
Wapping – Rotherhithe Tunnel, 244
water absorption, 48, 50, 151, 160, 167, 170, 207
width of rectangular stress block, 53, 151, 153, 157
in arch method of design, 59, 61
in diaphragm and fin walls, 190, 198
workmanship
standard of, 27

Young's modulus, 55, 269

zig-zag walls, *see* chevron walls